november 1961
the
institute
of
radio
engineers

Proceedings of the IRE

UNIVERSITY OF ILLINOIS
LIBRARY
NOV 22 1961
CHICAGO

in this issue

THE CRYOSISTOR
A NEW SEMICONDUCTOR TETRODE
PULSED MASER LIGHT AMPLIFIER
INDUCTANCE IN SUPERCONDUCTORS
FREQUENCY SHIFT OF CRYSTALS
OPTICAL DOPPLER MEASUREMENTS
TIMING POTENTIALS OF LORAN-C
GROUND CONDUCTIVITY MAP FOR CANADA
TRANSACTIONS ABSTRACTS
ABSTRACTS AND REFERENCES



SURFACE-POTENTIAL CONTROLLED TRANSISTOR: page 1623

SPECIAL PULSE TRANSFORMERS TO YOUR REQUIREMENTS

The pulse units illustrated below show a few of the thousands of special types designed and produced by UTC, to customers' requirements. Range covered on special pulse units is from a few microwatts to 10 megawatts. Rectangular pulse shapes are deliberately shown exaggerated to clarify parameters.

Almost thirty years of pioneering in the design and production of transformers plus exhaustive life testing programs and rigid quality control measures guarantee components of the highest reliability in the industry. . . . You can stake YOUR reputation on UTC products.





25 KC pulse transformer, DO-T or DI-T configuration. Pulse width 60 μSec. Rise time less than 0.5 μSec. Secondary C.T. balance each side to within 1% to ground. MIL-T-27A, GR 4. Size: DO-T, 5/16 dia. x 13/32", wt. 1/10 oz.; DI-T, 5/16 dia. x 1/4", wt. 1/20 oz.

Special precision miniature pulse transformers. Designed in our standard stock mold to your specs. Checked and precisely adjusted in your tube or transistor blocking oscillator circuit. Sizes: 3/8 dia. x 3/8", 1 gram; 7/16 dia. x 7/16", 4 grams; 5/8 dia. x 5/8", 6 grams.





Ferrite core blocking oscillator transformer. 0.1 μSec. ±10% @ 200 KC PPS. 2 windings, rise time .01 μSec. Epoxy case. MIL-T-27A; 7/16 dia. x 1/4", .07 oz.





600 μSec. coupling transformer for printed circuit application. 3 windings, mu metal case for extreme shielding. Z=20 K Ω, 10 V. MIL-T-27A; standard UTC ML case; 7/16 x 31/64 x 7/16" h., .2 oz.





Toroidal pulse transformer, 150 V. 200 μSec. @ 400 PPS. Molded in epoxy. 3 windings, low leakage, less than 1 μSec. rise time; —40°C. to +85°C.; output voltage within 1%. MIL-T-27A; 1 3/8 sq. x 3/4"; 1.5 oz.



Output to 2J42 magnetron. Input 1300 V.-50 ohms. Output 6.5 KV to 1200 ohms and .6A. bifilar filament winding. .15 μSec., 1000 PPS. Trigger winding. MIL-T-27A GR 5; 1 1/2 x 2 1/2 x 2 3/4", 10 oz.





Output to Klystron, 5 μSec. pulses in groups of pulse trains at high rep rate. Droop 1% over pulse trains. 30 KV W.V., 43 KV hipot; —53°C. to +85°C.; MIL-T-27A; 4 1/4 x 5 x 6 3/4"; 11 1/2 lbs.





Sonar sine wave pulse output transformer. PP 4-65A's, 11-14 KC flat. Pri. 11 KV; 28 KV hipot. Spark gap protected. Sec. 1500 V. @ 800Ω, 60 millisec on, 6% duty cycle. MIL-T-27A; —65°C. to +85°C.; 6 x 6 x 8 1/2", 13 lbs.

Plus over 1,000 STOCK ITEMS with UTC High Reliability from your local distributor

write for catalog

UNITED TRANSFORMER CORP.

150 VARICK STREET, NEW YORK 13, N. Y.

PACIFIC MFG. DIVISION: 4008 W. JEFFERSON BLVD., LOS ANGELES 16, CALIF.

EXPORT DIVISION: 13 EAST 40th STREET, NEW YORK 16, N. Y. CABLES: "ARLAB"

VOLUME 49, NUMBER 11

November, 1961

published monthly by The Institute of Radio Engineers, Inc.

Proceedings of the IRE®

contents

Poles and Zeros 1613

M. W. Bullock, Director, 1961–1962 1614

Scanning the Issue 1615

PAPERS

The Cryosistor—A Field-Effect Controlled Impact Ionization Switch, *I. Melngailis and A. G. Milnes* 1616
A New Semiconductor Tetrode—The Surface-Potential Controlled Transistor, *C. T. Sah* 1623
Correction to "Statistical Analysis of Certain Binary Division Algorithms," *C. V. Freiman* 1634
The Pulsed Ruby Maser as a Light Amplifier, *P. P. Kisliuk and W. S. Boyle* 1635
Correction to "The Elimination of Intersymbol Interference by Input Signal Shaping," *I. Gerst* 1639
Inductance in Thin-Film Superconducting Structures, *Norman H. Meyers* 1640
Reduction of the Frequency-Temperature Shift of Piezoelectric Resonators by Mechanical Stress, *E. A. Gerber and M. H. Miles* 1650
Fundamental Limitations to Optical Doppler Measurements for Space Navigation, *R. H. Norton and R. L. Wildey* 1655
Timing Potentials of Loran-C, *R. H. Doherty, G. Hefley, and R. F. Linfield* 1659
A Provisional Ground Conductivity Map for Canada, *G. Clement Ireland* 1674

CORRESPONDENCE

Tunnel-Diode Series Resistance, *E. L. Bonin and J. R. Biard* 1679
Some Measurements on an Iris Beam Waveguide, *J. R. Christian and G. Goubau* 1679
Ionospheric Contributions to the Doppler Shift at VHF from Near-Earth Satellites, *William H. Guier* 1680
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 1681
Persistent-Current Memory Circuit, *W. C. Stewart, H. A. Owen, M. S. P. Lucas, and C. R. Vail* 1681
A *C*-Band Parametric Amplifier with Large Bandwidth, *B. T. Vincent, Jr.* 1682
Multiple Reflections of Microwaves Propagating Through a Semiconductor Medium, *H. Jacobs, F. A. Brand, J. D. Meindl, and R. Benjamin* 1683
Correlation Optical Radar, *M. Katzman and E. Frost* 1684
Unidirectional Lower Sideband Parametric Amplifier Without Circulator, *G. H. B. Thompson* 1684
One-Tunnel-Diode Flip-Flop HF Behavior, *Henry Guckel* 1685
Additional Information on "An Interaction Circuit for Traveling-Wave Tubes," *R. M. White, C. K. Birdsall, D. E. Chaffee, P. J. Crepeau, and I. Itzkan* 1686
Comments on "Design Theory of Optimum Negative-Resistance Amplifiers," *H. J. Carlin, L. I. Smilen, D. C. Youla, E. S. Kuh, and J. D. Patterson* 1687
Noise in Tunnel-Diode Mixers, *Shih-Fang Lo* 1688
Comments on "Tunnel-Diode Microwave Oscillators," *G. Fuller, G. W. H. Wooding, D. Sterzer, and D. E. Nelson* 1689
Gravitational Fields, *Jovan Djurić* 1689
The *gh*-Field Theory, *Jovan Djurić* 1690
X-Band Electronically-Variable Attenuator, *P. L. Fleming* 1690
A Method of Displaying Ultra-Fast Limit Cycles or Three-Parameter Trajectories, *William T. Rhoades* 1691
An Extension of Newtonian Relativity to Include Electromagnetic Phenomena, *Pascal M. Rapier* 1691
Maser Terminology, *William R. Mallory* 1692
Technique for Amplitude Modulating a Van Atta Radar Reflector, *William F. Bahret* 1692
Some Ladder Networks Representing Certain Transcendental Numbers—Classroom Note, *F. Reza* 1693
Performance Degradation of Linear FM-Pulse-Compression Systems Due to the Doppler Effect, *H. O. Ramp and E. R. Wingrove, Jr.* 1693
Doppler-Shift Effects in Space Propagation, *R. P. Haviland* 1694
Comment on Shot-Noise Smoothing Mechanism Proposed by LaRosa and Wilhelmsen, *C. A. Lee and A. Yariv* 1695
Vacuum-Tube Networks, *George D. O'Neill* 1695
Flow Graphs and Tapered Transmission Lines, *Frank M. Brown* 1696
Large Signal Interaction Between a Spiraling Electron Beam and the TE_{10} Rectangular Waveguide Mode, *W. L. Dickson, C. C. Johnson, and R. W. Grow* 1696

COVER

Shown on the cover is a three-dimensional diagram of the equipotential contours of the new surface-potential controlled transistor described on page 1623.

published monthly by The Institute of Radio Engineers, Inc.

Proceedings of the IRE®

continued

On Backward-Wave Oscillator Stabilization, *R. B. Clark and W. D. Comstock* 1697
Education and Creativity, *B. F. Miessner* 1697
A Simple Method for the Supervision of the Orbital Period of Artificial Satellites, *P. R. Arendt and L. H. Manamon* 1698
Comment on "A Theoretical Comparison of Average- and Spot-Noise Figure in Transistor Amplifiers," *Paul J. Bêneteau* 1699
The Directional Coupler Core of an Arbitrary, Lossless, Reciprocal 4-Port, *W. K. Kahn and R. L. Kyhl* 1699
Spectral Response of a Nonlinear Device, *William B. Ribbens* 1700
On a Mathematical Description of Noisy Measurement System Performance, *J. L. Hammond, Jr.* 1701
The Delta Function and the Fourier Integral, *A. W. McMurtrey* 1702
An Electronically Tunable Up-Converter, *George L. Matthaei* 1703
The Linearized Transfer Function of a Phase-Locked Loop Containing an IF Amplifier, *R. Lawhorn and C. S. Weaver* 1704
Infrared Fluorescence and Stimulated Emission of Nd^{+3} in $CaWO_4$, *L. F. Johnson and K. Nassau* .. 1704
Maser Oscillation Observed from HCN Maser at 88.6 kMc, *Dietrich Marcuse* 1706
High-Speed Silicon Computer Diodes as RF Switches, *R. E. Aitchison* 1707
Use of a Coherent Memory Filter in Spectral Measurements of Atmospheric Whistlers, *J. Capon and M. R. Weiss* 1707
Injection Efficiency in Double Diffused Transistors, *Melvin Klein* 1708
Antenna Size for a Space Vehicle, *C. S. Lorens* 1708
Input-Output Relationships for Multisampled Loop Systems, *George G. Lendaris* 1709

REVIEWS

Books:
"Adaptive Control Processes: A Guided Tour," by Richard Bellman, *Reviewed by L. A. Zadeh* 1712
"The Physical Theory of Transistors," by Leopoldo B. Valdes, *Reviewed by M. A. Clark* 1712
"An Introduction to the Principles of Communication Theory," by John C. Hancock, *Reviewed by Warren D. White* 1713
"Proceedings of URSI Thirteenth General Assembly," John P. Hagen, Ed., *Reviewed by E. C. Jordan* 1713
"The Antenna," by H. Thourel, *Reviewed by Seymour B. Cohn* 1713
"Antenna Engineering Handbook," Henry Jasik, Ed., *Reviewed by George Sinclair* 1714
"Electronic Circuits, Signals and Systems," by S. J. Mason and H. J. Zimmerman, *Reviewed by W. H. Huggins* 1714
Recent Books 1715
Scanning the TRANSACTIONS 1715

ABSTRACTS

Abstracts of IRE TRANSACTIONS 1716
Abstracts and References 1726

IRE NEWS AND NOTES

Current IRE Statistics 14A
Calendar of Coming Events and Authors' Deadlines 14A
Obituaries 15A
Program:
Seventh Conference on Magnetism and Magnetic Materials 16A
Professional Groups, Sections and Subsections 22A

DEPARTMENTS

Contributors 1710
IRE People 44A
Industrial Engineering Notes 35A
Meetings with Exhibits 8A
Membership 92A
News—New Products 96A
Positions Open 99A
Positions Wanted by Armed Forces Veterans 106A
Professional Group Meetings 32A
Section Meetings 36A
Advertising Index 161A

BOARD OF DIRECTORS, 1961
*L. V. Berkner, *President*
*J. F. Byrne, *Vice President*
Franz Ollendorff, *Vice President*
*S. L. Bailey, *Treasurer*
*Haraden Pratt, *Secretary*
*F. Hamburger, Jr., *Editor*
*Ernst Weber
Senior Past President
*R. L. McFarlan
Junior Past President

1961
C. W. Carnahan (R7)
B. J. Dasher (R3)
A. N. Goldsmith
*P. E. Haggerty
C. F. Horne
R. E. Moe (R5)
D. E. Noble
B. M. Oliver
J. B. Russell, Jr. (R1)

1961–1962
A. B. Bereskin (R4)
M. W. Bullock (R6)
A. B. Giordano (R2)
W. G. Shepherd
G. Sinclair
B. R. Tupper (R8)

1961–1963
E. F. Carter
L. C. Van Atta

*Executive Committee Members

EXECUTIVE SECRETARY
George W. Bailey

John B. Buckley, *Chief Accountant*

Laurence G. Cumming, *Professional Groups Secretary*

Joan Kearney, *Assistant to the Executive Secretary*

Emily Sirjane, *Office Manager*

ADVERTISING DEPARTMENT
William C. Copp, *Advertising Manager*

Lillian Petranek, *Assistant Advertising Manager*

EDITORIAL DEPARTMENT
Alfred N. Goldsmith, *Editor Emeritus*
F. Hamburger, Jr., *Editor*
E. K. Gannett, *Managing Editor*
Helene Frischauer, *Associate Editor*

EDITORIAL BOARD
F. Hamburger, Jr., *Chairman*
T. A. Hunter, *Vice Chairman*
E. K. Gannett
T. F. Jones, Jr.
J. D. Ryder
G. K. Teal
Kiyo Tomiyasu
A. H. Waynick

AUDITED PAID CIRCULATION ABC

PROCEEDINGS OF THE IRE, published monthly by The Institute of Radio Engineers, Inc., at 1 East 79 Street, New York 21, N. Y. Manuscripts should be submitted in triplicate to the Editorial Department. Correspondence column items should not exceed four double-spaced pages (illustrations count as one-half page each). Responsibility for contents of papers published rests upon the authors, and not the IRE or its members. All republication rights, including translations, are reserved by the IRE and granted only on request. Abstracting is permitted with mention of source.

Thirty days advance notice is required for change of address. Price per copy: members of the Institute of Radio Engineers, one additional copy $1.25; non-members $2.25. Yearly subscription price: to members $9.00, one additional subscription $13.50; to non-members in United States, Canada, and U. S. possessions $18.00; to non-members in foreign countries $19.00. Second-class postage paid at Menasha, Wisconsin, under the act of March 3, 1879. Acceptance for mailing at a special rate of postage is provided for in the act of February 28, 1925, embodied in Paragraph 4, Section 412, P. L. and R., authorized October 26, 1927. Printed in U.S.A. *Copyright © 1961 by The Institute of Radio Engineers, Inc.*

FILMISTOR® 'C'

METAL FILM RESISTORS OFFER 5 DISTINCT TEMPERATURE COEFFICIENTS TO MEET ALL CIRCUIT REQUIREMENTS

RUGGED END-CAP CONSTRUCTION FOR LONG TERM STABILITY

• • •

EXCEPTIONAL RESISTANCE TO MOISTURE AND MECHANICAL DAMAGE

• • •

SURPASS MIL-R-10509 PERFORMANCE REQUIREMENTS

Providing close accuracy, reliability and stability with low controlled temperature coefficients, these molded case metal-film resistors outperform precision wirewound and carbon film resistors. Prime characteristics include minimum inherent noise level, negligible voltage coefficient of resistance and excellent long-time stability under rated load as well as under severe conditions of humidity.

Close tracking of resistance values of 2 or more resistors over a wide temperature range is another key performance characteristic of molded-case Filmistor "C" Resistors. This is especially important where they are used to make highly accurate ratio dividers.

Filmistor "C" Resistors are automatically spiralled to desired resistance values by exclusive Sprague equipment. The metallic resistive film, deposited by high vacuum evaporation, bonds firmly to special ceramic cores. Noble metal terminals insure low contact resistance.

The resistance elements, complete with end caps and leads attached are molded in dense, high temperature thermosetting material to form a tough molded shell for maximum protection against mechanical damage, moisture penetration and repeated temperature cycling.

Filmistor "C" Resistors, in ⅛, ¼, ½ and 1 watt ratings, surpass stringent performance requirements of MIL-R-10509C, Characteristic C. Write for Engineering Bulletin No. 7025 to: Technical Literature Section, Sprague Electric Co., 235 Marshall Street, North Adams, Mass.

For application engineering assistance write:
Resistor Division, Sprague Electric Co.
Nashua, New Hampshire



SPRAGUE COMPONENTS

RESISTORS	INTERFERENCE FILTERS	HIGH TEMPERATURE MAGNET WIRE
CAPACITORS	PULSE TRANSFORMERS	CERAMIC-BASE PRINTED NETWORKS
MAGNETIC COMPONENTS	PIEZOELECTRIC CERAMICS	PACKAGED COMPONENT ASSEMBLIES
TRANSISTORS	PULSE-FORMING NETWORKS	FUNCTIONAL DIGITAL CIRCUITS

SPRAGUE®
THE MARK OF RELIABILITY

'Sprague' and '②' are registered trademarks of the Sprague Electric Co.

For some time now, AIL has been active in the areas of communication and reliability. The article below describes the essence of a paper presented at the 1961 International Convention of the IRE. The paper was one of the results of an AIL study on communications satellites. It presents, we believe, a novel approach to the problem of multichannel system reliability.

Pseudo-Redundancy in Communications Systems

AIL has developed a technique for increasing the reliability of multichannel communications systems without adding redundant components. This technique provides redundancy for sections of each communications channel without the need for complex decision-making circuitry, thus increasing system reliability (at least one channel operating) by as much as 50 percent.

The technique is particularly applicable to multichannel systems in which the post-amplifier sections are of the hard limiting type. When the cross-connection shown in Figure 1 is added, each post-amplifier section has two possible inputs and two possible outputs. The interconnection is located at the first limiting stage, and crossing signals are attenuated about 10db. Since each post-amplifier has adequate limiting, however, the normal output from each channel is almost unchanged.



FIGURE 1. TWO-CHANNEL SYSTEM WITH CROSS-CONNECTION

When only one input channel is operating, both channels have similar outputs. When both channels are operating, the attenuated crossover signals are effectively suppressed by the limiting post-amplifier and the normal straight-through signal is dominant at the output of each channel. Thus each post-amplifier serves as a redundant unit for the other, but only when the channel in which it normally operates is idle. Under normal conditions, interconnection will not disturb the communications capability of either channel.

The same technique can be used for amplitude-modulated communications systems, though a gain-controlled amplifier must be added. When both channels are operating in such a system, the crossover signals are effectively disconnected by AVC action.

For maximum system performance, bandwidths and channel frequencies must be carefully chosen to minimize intermodulation products. Figures 2 and 3 show the effect of frequency separation in a two-channel system where the amplitude of the input signal



FIGURE 2. EXPERIMENTAL RESULTS OF DUAL INTERCONNECTED CHANNELS



FIGURE 3. EXPERIMENTAL RESULTS OF DUAL INTERCONNECTED CHANNELS

to Channel A was held constant and the amplitude of the input signal to Channel B was varied. The bandwidth of the system was 10 Mc. In Figure 2, the frequency separation of the channels was 1.75 Mc; in Figure 3, the separation was 3.8 Mc. The nearest intermodulation products ($2f_1 - f_2$) fell outside the IF channel band-pass response for the conditions shown in Figure 3.

In an interconnected system a strong signal on one channel could assume control of both output channels. This can be avoided by designing the final stage of each preamplifier to begin limiting just as the normal signal is received. Thus, only the channel with the interfering signal is temporarily overpowered.

If intermodulation problems can be surmounted, the reliability of a multichannel system can be still further increased by cross-connecting each channel to the two adjacent channels, treating the system cyclically so that the last channel is considered adjacent to the first.

Figure 4 shows the improved reliability of the two-channel system of Figure 1 due to the cross-connection and consequent automatic time-sharing. The increase in reliability of a multichannel system with multiple cross-connections would be even greater. The same increase in reliability in the conventional approach to redundancy would require a considerable increase in the number of components.



FIGURE 4. PERCENT INCREASE IN RELIABILITY AS A FUNCTION OF TIME (AT LEAST ONE CHANNEL OPERATING)

A complete bound set of our fifth series of articles is available on request. Write to Harold Hechtman at AIL for your set.

CONTROL CUTLER-HAMMER AIL DIVISION
AIRBORNE INSTRUMENTS LABORATORY
DEER PARK, LONG ISLAND, NEW YORK

150,000 μF



*Powerlytic** Capacitors are packed with capacitance!

Designed specifically for applications requiring maximum capacitance in small physical size, Sprague Type 36D Aluminum Electrolytics find wide use in power supplies for digital computers, industrial controls, high-gain amplifiers, and allied equipment. Furnished in case sizes ranging from 1⅜" dia. x 2⅛" long to 3" dia. x 4⅝" long, Powerlytic Capacitors are available with capacitances which were previously impossible to obtain in the various case sizes.

Engineered for 65 C Operation

In Powerlytics, Sprague's many years of research, design, and production experience have produced a capacitor which allows the equipment designer maximum space economy for operating temperatures up to 65 C. This encompasses the great majority of applications in transistorized digital equipment and similar apparatus.

Outstanding Performance Characteristics

Powerlytic Capacitors have not only low ESR and low leakage currents but offer extremely long shelf life as well. Furthermore, they have the ability to withstand unusually high ripple currents.

Superior Seal and Safety Vents

Type 36D Powerlytics use the most reliable seal that Sprague has developed for aluminum electrolytic capacitors. This consists of crimping a beaded aluminum can onto a rubber gasket recessed in a rigid molded cover. Pressure-type safety vents employing silicone rubber are used on all case covers.

Choice of Terminal and Insulating Tube Styles

Tapped terminal inserts, often preferred for strap or bus bar connections, are available as well as solder lug terminals for use with permanently wired connections. In addition to the standard bare case, Powerlytic Capacitors may also be obtained with a new clear skin-tight plastic tube which adds very little to the bare case dimensions. They are also available with a Kraftboard tube.

Broad Range of Standard Ratings

Sprague's standard line of Powerlytic Capacitors includes 183 ratings covering capacitance values from 45 to 150,000 μF, in voltages from 3 to 450 WVDC. Each rating is the maximum capacitance available for a given case size.

• • •

For complete technical data on Type 36D Powerlytic Capacitors, write for Engineering Bulletin 3431 to Technical Literature Section, Sprague Electric Company, 235 Marshall Street, North Adams, Massachusetts.

*trademark

SPRAGUE COMPONENTS

CAPACITORS	INTERFERENCE FILTERS	HIGH TEMPERATURE MAGNET WIRE
TRANSISTORS	PULSE TRANSFORMERS	CERAMIC-BASE PRINTED NETWORKS
MAGNETIC COMPONENTS	PIEZOELECTRIC CERAMICS	PACKAGED COMPONENT ASSEMBLIES
RESISTORS	PULSE-FORMING NETWORKS	FUNCTIONAL DIGITAL CIRCUITS

SPRAGUE®
THE MARK OF RELIABILITY

'Sprague' and '®' are registered trademarks of the Sprague Electric Co.



Nearly two centuries ago, Karl Gauss, "Prince of Mathematicians," kept a diary which was destined to become one of the most significant documents in the history of mathematics.

In his diary Gauss jotted down the results of elaborate calculations that had led him to fundamental discoveries in mathematics. But he never published these discoveries, and many of them remained undisclosed during his lifetime.

It wasn't until almost 50 years after Gauss's death that his diary was found and published. Much time and talent, meanwhile, had been spent in duplicating Gauss's efforts. Mathematical progress had been needlessly slowed.

In contrast, today's scientists and engineers are alert to the importance of sharing their findings through publication. In fact, the number of definitive papers published in a scientific or technological field has become a sure sign of the creative effort in that field.

Bell Laboratories scientists and engineers publish more than 800 papers a year, reporting new observations and new thinking in the arts and sciences that serve communications. They have also authored more than 50 technical books, many of which have become standard works of reference. The steady stream of new information that comes out of Bell Laboratories again reflects the scope and depth of the creativity that works to improve Bell System communications.

BELL TELEPHONE LABORATORIES

World center of communications research and development

A CASE OF *Accuracy!*

The "COMMANDER" instruments described below have a 5-year accuracy guarantee. By using NBS or NRC reported values, total cumulative errors for a complete measurement system can be as low as ±.002%.

DAUPHINEE POTENTIOMETER TYPE 9144

ACCURACY ±.001%

A new 6-figure DC vernier potentiometer with a total measuring range of 2.101010V. *Accuracy is at least 10 x that of similar commercially available equipment.* Direct readout on 4 dials in increments of .1 μv (no slidewire). Thermal emf's less than .1 μv. Switch controlled ranges of x 1 & x .1. Contains 2 saturated standard cells in an internally thermostatted enclosure. Completely "Self-Checking." *May be used with equal facility and accuracy as a Saturated Standard Cell or Resistance Comparator — and for the calibration of .01% accurate potentiometers.*

The Type 9144 is an original design by Dr. T. M. Dauphinee of the National Research Council in Canada. All rights are protected by a United States patent application.

VOLT RATIO BOX TYPE 9700A

ACCURACY ±.005%

A volt ratio box similar to that used by the National Bureau of Standards as described by NBS Research Paper RP 1419. Self-heating and surface leakage negligible. Ranges: .15/.3/.45/.6/.75/1.5/3/4.5/6/7.5/15/30/45/60/75/150/300/450/600/750/900/1050/1200/1350/1500 V. (Type 9700 up to 750 V. only). Furnished in a thermostatted oil bath with a motor-driven impeller.

CONSTANT TEMPERATURE STANDARD CELL ENCLOSURE TYPE 9152 AND SATURATED STANDARD CELL TYPE 4305

ACCURACY ±.001%

Enclosure accommodates up to 4 cells and is air thermostatted at 30°C ± .01°C. Transistorized circuit. Operates on 110V/60 cps (Battery standby). Type 9152A holds 12 cells.

THE TYPE 5214 GALVANOMETER AMPLIFIER AND TYPE SR21 LIGHT SPOT GALVANOMETER

The amplifier operates on the differential photocell principle in conjunction with a liquid-filled primary galvanometer. The secondary galvanometer has a scale length of 120-0-120 mm and is stable and free from the effects of external vibration. Over-all sensitivity is approximately 350,000 mm/μa and 52,000 mm/μv. It is ideally suited for use with the type 9144 potentiometer.

Sensitive Research "COMMANDER" Instruments are manufactured by Guildline Instruments, Ltd. (formerly Tinsley Instruments (Canada) Ltd.)

SENSITIVE RESEARCH INSTRUMENT CORPORATION

NEW ROCHELLE, N. Y.

ELECTRICAL INSTRUMENTS OF PRECISION SINCE 1927

Symbol of Quality

NOW! A REMARKABLE, NEW 0-40 volt @ 500 ma DC POWER SUPPLY BY PERKIN

THE ONLY POWER SUPPLY AVAILABLE COMBINING THESE 20 FEATURES:



Model TVCR040-05 0-40 volts @ 0-500 ma

1. *Voltage Regulation:* ±.01% or ±2 mv
2. *Current Regulation:* ±.02% or ±50μ amp
3. *Remote Voltage Programming:* Full-range 0-40 v Factory calibrated @ 100 ohms/volt ±.25%
4. *Remote Current Programming:* Full range 15-500 ma Factory calibrated @ 1 mho/ampere ±1%
5. *Voltage Limiting:* Continuously adjustable 0-42 v
6. *Current Limiting:* Continuously adjustable 0-600 ma
7. *Remote Voltage Sensing* 8. *Parallel Operation* 9. *Series Operation*
10. *Vernier Voltage Adjust:* 5 mv resolution
11. *Vernier Current Adjust:* 50μ amp resolution
12. *Transient-Free* 13. *Short-Circuit Proof*
14. *Extremely Fast Response:* 25μ sec
15. *Low Ripple:* 500μ volts (voltage regulation mode) 50μ amps (current regulation mode)
16. *Convection Cooling* 17. *Portable* 18. *Regulation Mode Switch*
19. *Master-Slave Operation* 20. *Excellent Long-Term Stability*

Additional Specs ■ AC Input: 105-125 v, 1∅, 47-420 cps, 0.5 A ■ Max. Ambient Temp.: 45°C ■ Meters: Dual Scale 0-50 V.DC, 0-600 ma ■ Dimensions: 5¼" H, 8" W, 9" D—adapter to mount two in 19" rack ■ Weight: 15 lbs. (approx.) ■ Finish: Gray per MIL-E-15090B

AND ALL FOR JUST $198 f. o. b. El Segundo

PERKIN
ELECTRONICS CORPORATION
345 Kansas Street, El Segundo, California ☐ SPring 2-2171

Representatives in principal cities.

Meetings with Exhibits

● As a service both to Members and the industry, we will endeavor to record in this column each month those meetings of IRE, its sections and professional groups, which include exhibits.

Δ

November 13-16, 1961

Seventh Annual Conference on Magnetism & Magnetic Materials, Hotel Westward Ho, Phoenix, Ariz.

Exhibits: Mr. John L. Whitlock, 253 Waples Mill Road, Oakton, Va.

November 14-16, 1961

Northeast Research and Engineering Meeting (NEREM), Somerset Hotel & Commonwealth Armory, Boston, Mass.

Exhibits: Mr. Stewart K. Gibson, Instruments of New England, 108 Greenwood Lane, Waltham 54, Mass.

November 30-December 1, 1961

Professional Group on Vehicular Communications Conference, Hotel Radisson, Minneapolis, Minn.

Exhibits: Mr. Jean Poole, General Electric Co., 3280 Gorham Ave., Minneapolis, Minn.

December 12-14, 1961

Eastern Joint Computer Conference, Sheraton-Park Hotel, Washington, D.C.

Exhibits: Mr. Charles Phillips, 5603 Jordan Road, Washington 16, D.C.

February 7-9, 1962

3rd Winter Convention on Military Electronics, Ambassador Hotel, Los Angeles, Calif.

Exhibits: Mr. Walter E. Peterson, Automation Development Corp., 11824 Jefferson Blvd., Culver City, Calif.

March 1-3, 1962

Eighth Scintillation and Semiconductor Counter Symposium, Shoreham Hotel, Washington, D.C.

Exhibits: Dr. George A. Morton, RCA Labs., Princeton, N.J.

March 26-29, 1962

International Radio & Electronics Show and IRE International Convention, Waldorf-Astoria Hotel and New York Coliseum, New York, N.Y.

Exhibits: Mr. William C. Copp, IRE Advertising Dept., 72 West 45th St., New York 36, N.Y.

April 11-13, 1962

SWIRECO (South West IRE Conference & Electronics Show), Rice Hotel, Houston, Texas

Exhibits: Mr. R. J. Loofbourrow, Texaco Company, P.O. Box 425, Bellaire, Texas

(Continued on page 10A)

TOGGLE SWITCH MODEL 20

PRECISION HIGH FREQUENCY ATTENUATORS

DC TO 500 MEGACYCLES

- 50, 70, or 90 ohm impedance
- High-Frequency, Precision Teflon & Silver Switches
- 1% Carbon Film Resistors ■ Fully Shielded Units
- Up to 101 db ■ Fixed 0 or 10 db insertion loss
- **SWR:** 1.2 : 1 max up to 250 mc
  1.4 : 1 max 250 to 500 mc
- **Min. Insertion*:** 0.1 db at 250 mc; 0.2 db at 500 mc
- **Accuracy:** At Full Attenuation: 0.5 db at 250 mc, 1.2 db from 250 to 500 mc
- **Price:** (Model 20) $79.00 f.o.b. factory
  ($87.00 F.A.S. N. Y.)

*Zero insertion loss (Model 20-0) $75.00 f.o.b. factory

KAY ELECTRIC COMPANY
DEPT. I-11 • MAPLE AVENUE • PINE BROOK, N. J. • CAPITAL 6-4000

Write for Catalog Information

KAY
ELECTRONIC INSTRUMENTS

Sweeping Oscillators
Frequency Markers

Audio Spectrum Analyzers

Pulse — Pulsed RF Generators

Precision Attenuators

Random Noise Generators

Kilo-Sweeps®
Rada-Sweeps®
Ligna-Sweeps®
Sona-Sweeps®
Marka-Sweeps®
Vari-Sweeps®
Mega-Sweeps®

MINIATURE TRANSFORMERS

delivered in 24 hours

FROM STOCK

FRANCHISED STOCKING DISTRIBUTORS

CALIFORNIA, INGLEWOOD
Newark Electronics Co., Inc.
CALIFORNIA, LOS ANGELES
Graybar Electric Company
Universal Radio Supply Co.
CALIFORNIA, SAN DIEGO
Telrad Electronic Supply
CALIFORNIA, SAN JOSE
Weatherbie Industrial Electric
COLO., DENVER—Ward Terry
CONN., NEW HAVEN—Radio Shack
CONN., WATERBURY—Bond Radio
DIST. OF COL., WASHINGTON
Electronic Wholesalers, Inc.
FLORIDA, ORLANDO
East Coast Radio of Orlando Inc.
ILL., CHICAGO—Newark Elect.
INDIANA, SOUTH BEND—Radio Dist.
IOWA, CEDAR RAPIDS—Deeco, Inc.
KANSAS, WICHITA—Radio Supply
MARYLAND, BALTIMORE
Electronic Wholesalers, Inc.
D & H Dist. Co., Inc. Indus. Sales Div.
MASSACHUSETTS, BOSTON
Radio Shack Corp.
Sager Electrical Supply Co.
MINN., ST. PAUL—Gopher Electronics
MISSOURI, KANSAS CITY
Jones Electronic Sales
MISSOURI, ST. LOUIS
Interstate Supply Co.
NEW JERSEY—Federated Purchaser, Inc.
NEW YORK, LYNBROOK
Peerless Radio Distributors
NEW YORK, MINEOLA
Arrow Electronics, Inc.
NEW YORK, NEW YORK CITY
Harrison Radio
NEW YORK, BUFFALO
Summit Dist. Inc.
NEW YORK, SCHENECTADY
Schenectady Electronics
NEW YORK, UTICA
Valley Electronic Labs, Inc.
OHIO, CLEVELAND
Main Line Cleveland, Inc.
PENNSYLVANIA, ALLENTOWN & EASTON
Federated Purchaser, Inc.
PENNSYLVANIA, McKEESPORT
Barno Radio Co.
PENNSYLVANIA, NORRISTOWN & PHILA.
Philadelphia Electronics, Inc.
TEXAS, DALLAS—All-State Elect.
UTAH, SALT LAKE CITY—S. R. Ross
WASHINGTON, SEATTLE—F. B. Connelley
CANADA, MONTREAL
Atlas Wholesale Radio Inc.

TOROIDS

Custom-engineered to Exacting Specifications.

- **Frequency range: 20 cycles—100 kc**
- **Power level: Up to 150 watts**
- **Operating temp. range: –65 to 130°C**
- **Size range: Approximately ¾ to 4" O.D.**
- **DC current range: Depends on the size, frequency and power level**

MICROTRAN Quality and Reliability Guaranteed!

MICRO MINIATURE TRANSISTOR TRANSFORMER

Molded (-M) 7/8" x 25/32" x 17/32"
Hermetic (-H) 15/16" x 11/16", wt. ¾ oz.
Open Frame (-F) 7/16" x 19/32" x ¾", wt. .4 oz.

Part Number	Application	Primary Impedance	Secondary Impedance
MMT1*	Line to Base	600	600
MMT4*	P.P. Coll. to P.P. Base	50,000 C.T.	600 C.T.
MMT7*	Coll. to P.P. Base	25,000	1,200 C.T.
MMT8*	P.P Coll. to P.P. Base	50,000 C.T.	1,200 C.T.
MMT9*	Line to P.P. Base	600 C.T.	1,200 C.T.
MMT11*	P.P. Coll. to P.P. Base or Line	4,000 C.T.	600 C.T.
MMT17*	P.P. Coll. to P.P. Base	10,000 C.T.	200 C.T.
MMT18*	P.P. Coll. to P.P. Base	25,000 C.T.	1,200 C.T.
MMT19*	Coll. to P.P. Base	2,500	2,500 C.T.
MMT26*	Line to Base	600 C.T.	600 C.T.

*Add either -H, -M, or -FB to Part No. to designate construction. See catalog for detailed information.

ULTRA MINIATURE TRANSISTOR TRANSFORMER

Open-frame (-F)* Wt. .08 oz. size 3/8" x 3/8" x 11/32"
Molded (-M)* Wt. .14 oz. size ½" x ½" dia.
Nylon Bobbin, Nickel-Alloy Core. Levels to .5w.

Part Number	Application	Primary Impedance (D.C.)	Secondary Impedance
UM28-(*)	Choke	10 hy (0 dc)	
UM29-(*)	Interstage	600 C.T.	600 C.T.
UM30-(*)	Choke	1.5 hy (0 dc)	
UM31-(*)	Interstage	10,000 C.T.	1,200 C.T.
UM32-(*)	Output	1,500 C.T.	600
UM33-(*)	Output	1,000 C.T.	600
UM34-(*)	Driver	10,000 C.T.	600 C.T.

*Add either -F or -M to part number to designate construction. See catalog for detailed information.

TRANSISTOR TRANSFORMER SELECTOR KIT

Save valuable time in optimizing circuitry

Set of 9 transformers covers impedance range of 150 through 200,000 OHMS. Matches most new transistor impedance ratings.

FULL DESIGN DATA ENCLOSED

• Nomographs and circuitry for determining correct impedances • Power versus DBM chart • Guide to MIL-T-27A • Cross Reference index • Outline drawings.

VERI-MINIATURE TRANSISTOR TRANSFORMER

Open Frame (-FB)* Wt. .2 oz. [illegible] 7/16" x 11/32"
Molded (-M)* Wt. ¼ oz. [illegible] 1/2" high

Part Number	Application	Primary Impedance	Secondary Impedance
VM1*	Input	50	600 (1.5 ma.)
VM2*	Input or Interstage	100,000	600 (1.0 ma.)
VM3*	Interstage	25,000	600 (1 ma.)
VM4*	Input or Interstage	200,000	1,200 (.72 ma.)
VM5*	Interstage	50,000	600 (1.0 ma.)
VM6*	Interstage	100,000	1,200 C.T. (.72 ma.)
VM8*	Output	1,250 (2.0 ma.)	3.4
VM10*	Interstage	2,500 (1.5 ma.)	2,500 C.T.
VM11*	Choke	20 hy. (0 ma.)	12 hy. (.5 ma.)
VM13*	Interstage	20,000	1,000 C.T. (.75 ma.)

*Add either -M, or -FPB to part number to designate construction. See catalog. 4 color coded leads, resin impregnated.

MICROTRAN company, inc.
Write TODAY for catalog and price list of the complete MICROTRAN line.
145 E. MINEOLA AVE., VALLEY STREAM, N. Y.

Employment Opportunities East and West Coast Plants

Meetings with Exhibits

(Continued from page 8A)

May 1-3, 1962

Spring Joint Computer Conference, Fairmont Hotel, San Francisco, Calif.

Exhibits: Mr. John W. Ball, Pacific Telephone Co., 3240 Arden Way, Sacramento, Calif.

May 14-16, 1962

NAECON (National Aerospace Electronics Conference), Miami & Biltmore Hotels, Dayton, Ohio

Exhibits: IRE Dayton Office, 33 N. Torrence St., Dayton, Ohio

May 23-25, 1962

National Telemetering Conference, Sheraton Park Hotel, Washington, D.C.

Exhibits: Mr. H. W. Royce, Martin Company, Baltimore, Md.

June 12-14, 1962

Armed Forces Communications & Electronics Show, Sheraton Park and Shoreham Hotels, Washington, D.C.

Exhibits: Mr. William C. Copp, 72 W. 45th St., New York 36, N.Y.

August 21-24, 1962

Western Electronic Show and Convention (WESCON), Ambassador Hotel & Memorial Sports Arena, Los Angeles, Calif.

Exhibits: Mr. Don Larson, WESCON, 1435 La Cienega Blvd., Los Angeles, Calif.

August 29-September 1, 1962

Second International Conference on Information Processing, Munich, Germany

Exhibits: Dr. Heinz Billing, Max Planck Institute, Munich, Germany

October 1-3, 1962

Eighth National Communications Symposium, Hotel Utica & Utica Municipal Auditorium, Utica, N.Y.

Exhibits: Mr. R. E. Gaffney, General Electric Co., Light Military Electronics Dept., Utica, N.Y.

October 8-10, 1962

National Electronics Conference, Exposition Hall, Chicago, Ill.

Exhibits: Mr. Rudy Napolitan, National Electronics Conference, 228 N. LaSalle St., Chicago, Ill.

Δ

Note on Professional Group Meetings: Some of the Professional Groups conduct meetings at which there are exhibits. Working committeemen on these groups are asked to send advance data to this column for publicity information. You may address these notices to the Advertising Department and of course listings are free to IRE Professional Groups.

PANORAMIC PANADAPTORS give you continuous visual spectrum analysis of communications signals



Interference analysis with Model SA-8b Panadaptor. Sidebands from AM channel #3 is seen to spill into band occupied by intermittent CW channel #2.

- **Detecting and investigating interference caused by splatter, harmonics, r.f. parasitics and multipath transmissions.**
- **Tuning aid for telemetry and SSB signals.**
- **Rapidly locating and identifying intermittent and irregular transmissions.**
- **Spotting inadvertent off-frequency transmissions.**
- **Band occupancy studies.**

Operating in conjunction with a communications receiver, the Panadaptor automatically scans the band around the frequency to which the receiver is tuned. Scan is adjustable from full sweep width capacity for observing over-all band to reduced sweep widths for detailed narrow band signal analysis.

Panoramic Panadaptors are available in two models and 14 types, to operate with RF, VHF and UHF receivers having standard IFs. Also available are specially designed Panadaptors for use with receivers with non-standard IFs or other unusual properties.

PANORAMIC'S PANADAPTOR MODEL SA-8b is a professional-quality spectrum analyzer designed for convenience and exceptional versatility. Adjustable sweep width, sweep rate and IF bandwith controls provide for optimum frequency resolution. Log, linear and power amplitude scales are precisely calibrated on a long persistence 5" CRT.

PANORAMIC'S PANADAPTOR MODEL SA-3 is a rugged, compact, easy to operate unit with a 3" CRT. Only three controls are needed—sweep width, gain and center frequency. Cabinet or rack mounting optional.



	Model SA-8b				Model SA-3									
	Type T-100	Type T-200	Type T-1000	Type T-10,000	Type T-50	Type T-100	Type T-200	Type T-1000	Type T-1000	Type T-2000TD	Type T-2000NC	Type T-3000	Type T-3000C	Type T-6000
For receivers with IF	455kc or 500kc	455kc	5.25mc	30mc	455kc	455kc or 500kc	455kc	5.25mc	10.2mc or 10.7mc	30mc	30mc	30mc	21.4mc	30mc
Sweep Width	0-100kc	0-200kc	0-1mc	0-10mc	0-50kc	0-100kc	0-200kc	0-1mc	0-1mc	0-2mc	0-2mc	0-3mc	0-3mc	0-6mc
Direct Sensitivity*	1000μv	2000μv	2000μv	150μv	200μv	200μv	200μv	200μv	200μv	500μv	10μv	1mv	50μv	10mv
Sweep Rate	Sweep may be synch'd externally or to power line or free running.				30 sweeps per second, line synchronized. (25 sweeps/sec with 50-cps power line.)									
Amplitude Scales	Linear (calibrated from 0 to 1.0). Logarithmic (from 0 db to −40 db). Power.				Nominally linear									
Resolution Capabilities. Depends upon sweep rate and sweep width.	50cps to 4kc Variable	50cps to 4kc Variable	200cps to 10kc Variable	9kc to 80kc Variable	At maximum sweep width: 2.5kc	3.4kc	4.4kc	11kc	11kc	20kc	20kc	25kc	25kc	50kc
					Approximately 20% improvement at 20% of full sweep width.									

* Direct sensitivity (Model SA-8b) is the maximum voltage at the center frequency required for a full scale deflection on the linear amplitude scale. Direct sensitivity (Model SA-3) is the maximum voltage at the center frequency required for ¼ inch deflection.

Panadaptors are available for most receivers. For best over-all response, the receiver type should be mentioned when inquiring about Panadaptors.

Write today for detailed specifications bulletin. Also send for new Catalog Digest and ask to be put on the regular mailing list for The Panoramic Analyzer, featuring application data.

See us at N.E.R.E.M. Booth #809

WE CATALOG IN eem electronic engineers master Sec 2000

Panoramic electronics, inc.

the pioneer is the leader

Formerly Panoramic Radio Products, Inc.

dependable CERTIFIED SPECIFICATIONS for accurate data

PANORAMIC ELECTRONICS, INC.

522 South Fulton Avenue, Mount Vernon, N.Y. • Phone: OWens 9-4600 • Cables: Panoramic, Mount Vernon, N.Y. State

Painting in background: "The Piping Shepherd," by Sir Joshua Reynolds, P. R. A. (1723–1792)

New cost savings for users of dielectric materials

. . . a progress report on the MYCALEX METHOD
from Jerome Taishoff, President, Mycalex Corporation of America

"I don't have to tell you about the profit squeeze. It's a hard fact-of-life throughout our industry today. That's why we feel the *MYCALEX METHOD*—the unique molding and finishing technique we recently developed—offers so much promise.

Sample quotations point to cost savings up to 84%

"The many months spent in the developing of this new process enable us to turn out better-performing products for less: savings we, in line with our policy, will pass along directly to our customers. And those savings promise to be substantial! Note the typical parts shown in the photograph below, as well as the two mechanical diagrams. As you can see, this new production technique reveals cost reductions of 78% and 84%, respectively, when compared to previous cost quotations." Just as important, the savings are in *addition to* the high reliability SUPRAMICA® ceramoplastics and MYCALEX® glass-bonded micas are noted for.

Savings plus quality with the MYCALEX METHOD

Though these intricate parts now cost much less to make—they offer the temperature endurance, total dimensional stability, high dielectric strength and low loss that SUPRAMICA and MYCALEX formulations have been delivering for years.

Choose from any of these famous materials

SUPRAMICA 620 "BB", 560 and 555 ceramoplastics and MYCALEX 410 glass-bonded mica. *Maximum Temperature Endurance* (unstressed): 1200, 930, 650 and 650°F; *Loss Factor* (10^6 cycles/sec.): 0.020, 0.010, 0.013, 0.010; *Compressive Strength* (psi): 30,000, 25,000, 40,000 and 40,000, respectively.

So for electronic insulation materials with the high-performance properties you must have—at a profit-protecting price — look into the new *MYCALEX METHOD*. Send your blueprints and drawings for specific quotations and information.



78% LOWER IN PRICE



84% LOWER IN PRICE



SYNTHAMICA® SYNTHETIC MICA — SINCE 1919 MYCALEX® THE INSULATOR — SUPRAMICA® CERAMOPLASTIC

MYCALEX
CORPORATION OF AMERICA

General Offices and Plant: 126 Clifton Boulevard, Clifton, N. J.
Executive Offices: 30 Rockefeller Plaza, New York 20, N. Y.

World's largest manufacturer of ceramoplastics, glass-bonded mica and synthetic mica products

IRE News and Radio Notes

Current IRE Statistics

(As of September 30, 1961)

Membership—90,989
Sections*—110
Subsections*—31
Professional Groups*—28
Professional Group Chapters—283
Student Branches†—212

* See this issue for a list.
† See June, 1961, issue for a list.

Calendar of Coming Events and Author's Deadlines*

1961

Nov. 6–8: 6th Ann. Special Technical Conf. on Nonlinear Magnetics Statler-Hilton Hotel, Los Angeles, Calif.

Nov. 7–9: 7th Conf. on Radio Interference Reduction and Electronic Compatibility, Ill. Inst. Tech., Chicago, Ill.

Nov. 13 14: Conf. on Electrically-Exploded Wires, Kenmore Hotel, Boston, Mass.

Nov. 13–16: 7th Ann. Conf. on Magnetism and Magnetic Materials, Hotel Westward Ho, Phoenix, Ariz.

Nov. 14–16: NEREM, Somerset Hotel and Commonwealth Armory, Boston, Mass.

Nov. 14: Electronic Systems Reliability Symp., Linda Hall Library Auditorium, Kansas City, Mo.

Nov. 30–Dec. 1: PGVC Conf., Hotel Radisson, Minneapolis, Minn.

Dec. 12–14: Eastern Joint Computer Conf., Sheraton-Park Hotel, Washington, D. C.

1962

Jan. 9–11: 8th Nat'l. Symp. on Reliability and Quality Control, Statler Hilton Hotel, Washington, D. C.

Jan. 28–Feb. 2: AIEE 1962 Winter General Mtg., New York, N. Y.

Feb. 7–9: 3rd Winter Conv. on Military Electronics, Ambassador Hotel, Los Angeles, Calif. (DL*: Nov. 15, 1961, M. E. Brady, Space Tech. Labs., P.O. Box 95001, Los Angeles 45, Calif.)

Feb. 14–16: Internat'l. Solid State Circuits Conf., Philadelphia, Pa. (DL*: Nov. 1, 1961, R. B. Adler, Lincoln Lab., MIT, Lexington, Mass.)

Mar. 1–3: 8th Scintillation and Semiconductor Counter Symp., Shoreham Hotel, Washington, D. C.

Mar. 26–29: IRE Internat'l. Conv., Coliseum and Waldorf Astoria Hotel, New York, N. Y. (DL*: Oct. 20, 1961, D. B. Sinclair, IRE, 1 E. 79 St., New York, N. Y.)

*DL = Deadline for submitting abstracts.

(*Continued on page 15A*)

1961 NEREM
Program Expanded

Two special sessions have been added to the NEREM 61 program, bringing the total to twenty-three, involving eighteen subject areas.

One of the additional sessions, to be presented Tuesday evening, November 14, at the Somerset Hotel, will feature a discussion on Satellite Communications that will be moderated by General William M. Thames of the ADVENT Management Agency, Fort Monmouth, N. J.

The program will include three addresses:

"Economic Aspects of Communication Satellite Systems," *S. H. Reiger, The RAND Corp., Santa Monica, Calif.*

"The Design of Medium Height Random Orbit Satellite Systems," *J. L. Glaser, Bell Telephone Labs., Inc., Murray Hill, N. J.*

"NASA'S Relay," *R. M. Wilmotte, RCA, Princeton, N. J.*

The second additional session, on Automatic Controls, will be presented on Wednesday morning, November 15, at the Somerset Hotel and wi l be chaired by J. T. Thomas of the Boston Division, Minneapolis-Honeywell Regulator Company.

Six talks have been scheduled:

"The Foundation for Limit Cycling Adaptive Design," *A. Gelb, Dynamics Research Corp., Stoneham, Mass.*

"A Synthesis Technique for Quasi-Optimal Relay Control," *R. R. Saparacino, A. C. Spark Plug Boston Eng. Facility, Wakefield, Mass.*

"Obtaining the Roots of the Characteristic Equator by Analog Computer Techniques," *G. W. Ogar, Institute of Technology, Wright-Patterson Air Force Base, Ohio.*

"Considerations Relating to the Open-Loop Compensation of Dynamic Tracking Errors," *S. Adelman and S. M. Shinners, Sperry Gyroscope Corp., Great Neck, N. Y.*

"Recent Developments in State Vector Control," *Y. C. Ho and P. Brentani, Minneapolis-Honeywell, Boston, Mass.*

"Dynamic Analysis of Limit Cycling Control Systems," *A. Gelb, Dynamics Research Corp., Stoneham, Mass.*

One of the highlights of NEREM 61 will be a keynote address by John L. Burns, president of RCA who will discuss "New Directions in Electronics Research," and will evaluate major developments in the laboratory stage, their future market impact and significance in terms of tomorrow's corporate management.

During the three-day meeting, November 14–16, buses will run daily (every fifteen minutes) between the Commonwealth Armory and the Somerset Hotel, where exhibits and talks will be held.



Governor John A. Volpe issues a proclamation applauding NEREM 61 and declaring the week of November 12–19 as Electronics Week in Massachusetts. *Left to right:* Lewis Winner, Conference Consultant; Governor Volpe; S. K. Gibson, Exhibits Manager; and K. C. Black, General Chairman.

Call for Papers
Second IFAC Congress

The American Automatic Control Council invites authors to submit papers for the Second Congress of the International Federation of Automatic Control and requests that they signify their intention of doing so as soon as possible. The Second Congress of the IFAC will be held in Basel, Switzerland, in September, 1963, on the invitation of the Swiss Association of Automatic Control.

The total number of papers will be limited to one hundred and there will be no national quotas of papers as in the past. The final selection will be by the IFAC Committee and not the national committee submitting the paper. The majority of the papers on the program will be comprised of papers on theory and application of automatic controls. A few papers will be accepted on components, bibliography, terminology, and education.

Prospective authors should write directly to the Chairman of the appropriate committee. The Committee Chairman will provide the authors with details concerning deadlines, length of paper, etc. Each committee has a member from each of the five societies which provide the membership of AACC: IRE, AIEE, ASME, ISA, and AIChE. The IRE is represented on the AACC by the Professional Group on Automatic Control. The Committee Chairmen are as follows:

Dr. John Truxal, Chairman, AACC Theory Committee, Electrical Engineering Dept., Brooklyn Polytechnic Institute, 333 Jay St., Brooklyn 1, N. Y.

Prof. Irving Lefkowitz, Chairman, AACC Application Committee, Mechanical Engineering Dept., Case Institute of Technology, University Circle, Cleveland 6, Ohio.

Prof. J. L. Shearer, Chairman, AACC Component Committee, Dept. of Mechnical Engineering, Massachusetts Institute of Technology, Cambridge 39, Mass.

Prof. T. J. Higgins, Chairman, AACC Bibliography Committee, Engineering Dept., University of Wisconsin, Madison, Wis.

Dr. H. L. Mason, Chairman, AACC Terminology Committee, National Bureau of Standards, Washington 25, D. C.

Prof. J. H. Mulligan, Chairman, AACC Education Committee, Electrical Engineering Dept., College of Engineering, New York University, University Heights, New York 53, N. Y.

Air Force MARS
Announces Schedule

The Air Force MARS Eastern Technical Net broadcasting on 3295, 7540, and 15,715 kc announces the following schedule of broadcasts on Sundays, 2–4 P.M. EST:

Nov. 5—"Introduction to Sonar," T. G. Bell, Scientist, U. S. Navy Underwater Sound Laboratory.

Nov. 12—"Underwater Communications," H. J. Wilms, Jr., Engineer, U. S. Navy Underwater Sound Laboratory.

Nov. 19—"Modern Submarines," J. Bellah, U. S. Navy Submarine School.

Nov. 26—"Oceanography," G. Bond, Officer in Charge, Naval Medical Research Laboratory.

Obituaries

Hermann E. Kranz (M'23–SM'47), who was Regional Director of the East Central Region of the IRE from 1949 to 1950, died in Detroit on September 2, 1961.

He was born June 15, 1884 in Minonk, Ill. and received the B.A. degree from Lawrence College in 1909, the B.S. degree in electrical engineering in 1914 and the professional degree of electrical engineer in 1917, both from the University of Wisconsin.

He taught electrical engineering at the University of Wisconsin from 1914 to 1917. Later, he joined the Grigsby Grunow Company as Chief Engineer in 1926. In 1928 he was made plant Vice President in Charge of Engineering.

During World War II he was operations manager of the Radar Division of Research Enterprises Ltd. at Leaside, Ontario, Canada. After the war he was Director of the Industrial Technical Institute at Detroit, Mich., and in recent years he was with the Ordnance Corps of the U. S. Army at the Detroit Arsenal.

Mr. Kranz was one of the organizers of the Chicago Section of the IRE and served it as Secretary-Treasurer from 1926–1928 and as Chairman from 1929–1930. He was also Chairman of the Detroit Section.

He was a member of the AIEE, the American Society for Engineering Education, the Radio Engineers' Club of Chicago, the Engineering Society of Detroit and the Regional Committee for Technical Institutes of the Engineers' Council for Professional Development.

O. B. Hanson (A'18-M'27–F'41), who was a Life Member and former Director (1938–1943) of the IRE, died September 26, 1961 in Norwalk, Conn.

He was born February 11, 1894 in Huddersfield, England and was brought by his family to Connecticut when he was a year old. He entered the Marconi School in New York at the age of 20. He became a ship wireless operator and then obtained a position in the Engineering Department of the Marconi Wireless Telegraph Company of America; he rose to Chief Test Engineer in 1918. Later, in Newark, he joined radio station WAAM as Chief Engineer.

In 1923 he joined station WEAF (now WNBC), New York, as a staff engineer and later became plant manager of the station. He continued in that capacity when the National Broadcasting Company was formed in 1926, with WEAF as the key network station. He was advanced to Chief Engineer of NBC, and in 1937 was elected Vice President. In 1954 he was elected a Vice President of RCA and held that post until his retirement in 1959.

His activities included the design of studios for station WRCA-TV (now WNBC-TV), the first commercially licensed TV transmitter to go on the air, design of mobile TV units, and establishment of NBC facilities for the introduction of color television. In 1931 he wired the Metropolitan Opera House for sound broadcasts.

Mr. Hanson was a member of the Acoustical Society of America and the Society of Motion Picture Engineers.

Calendar of Coming Events and Author's Deadlines*

(*Continued from page 14A*)

Apr. 10–12: 2nd Symp. on the Plasma Sheath, New England Mutual Hall, Boston, Mass. (DL*: Oct. 15, 1961, A. Cahill, Air Force Cambridge Res. Labs., Hanscom Field, Bedford, Mass.)

Apr. 11–13: SWIRECO (S.W. IRE Conf. and Electronics Show), Rice Hotel, Houston, Tex. (DL*: Oct. 1, 1961, M. Graham, Rice Univ. Computer Project, Houston 1, Tex.)

May 1–3: Spring Joint Computer Conference, Fairmont Hotel, San Francisco, Calif. (DL*: Nov. 10, 1961, R. I. Tanaka, Lockheed Missiles and Space Co., Palo Alto, Calif.)

May 8–10: Electronic Components Conf. Marriott Twin Bridges Hotel, Washington, D. C. (DL*: Oct. 9, 1961, H. A. Stone, Bell Telephone Labs., Murray Hill, N. J.

May 14–16: NAECON, Dayton, Ohio.

May 22–24: Nat'l. Microwave Theory and Techniques Symp., Boulder, Colo. (DL*: Dec. 18, 1961, R. W. Beatty, Nat'l. Bur. Standards, Boulder, Colo.)

May 23–25: Nat'l. Telemetering Conf., Sheraton Park Hotel, Washington, D. C.

June 25–27: 6th Nat'l. Convention on Military Electronics, Shoreham Hotel, Washington, D. C.

June 25–30: Symp. on Electromagnetic Theory and Antennas, Tech. Univ. of Denmark, Copenhagen. (DL*: Dec. 1, 1961, H. L. Knudson, Øster Volgade 10 G, Copenhagen K, Denmark)

June 27–29: Joint Automatic Control Conf., New York Univ., New York, N. Y. (DL*: Oct. 15, 1961 (abstracts), Nov. 15, 1961 (papers), H. J. Hornfeck, Bailey Meter Co., 1050 Ivanhoe Rd., Cleveland 10, Ohio)

Aug. 14–16: Internat'l. Conf. on Precision Electromagnetic Measurements (former title: Conf. on Standards and Electronic Measurements), Nat'l. Bur. Standards, Boulder, Colo. (DL*: Mar. 15, 1962, Dr. G. Birnbaum, Hughes Res. Lab., Malibu, Calif.)

Aug. 21–24: WESCON (Western Electronics Show and Conf.), Los Angeles, Calif.

Aug. 27–Sept. 1: 2nd Internat'l. Federation of Information Processing Societies Congress, Munich, Germany.

Sept. 3–7: Internat'l. Symp. on Information Theory, Brussels, Belgium (DL*: Jan. 15, 1962, Dr. F. L. Stumpers, Philips Research Labs., Eindhoven, Netherlands)

Sept.: 10th Annual Engineering Management Conf., New Orleans, La.

Sept. 19–20: 11th Annual Industrial Electronics Symp., Chicago, Ill.

Oct. 1–3: 8th National Communications Symp., Utica, N. Y.

Oct. 8–10: National Electronics Conf., Exposition Hall, Chicago, Ill.

* DL = Deadline for submitting abstracts.

Seventh Conference on Magnetism and Magnetic Materials

HOTEL WESTWARD HO, PHOENIX, ARIZ., NOVEMBER 13–16, 1961

Speakers from France, England, and Japan have accepted invitations to present papers at the Seventh Annual International Conference on Magnetism and Magnetic Materials to be held November 13–16. Papers will be presented by Dr. E. F. Bertaut, Centre d'Etudes Nucleaires de Grenoble, Grenoble (Isere), France; E. M. Bradley, International Computers and Tabulators, Ltd., Stevenage, England; Professor M. Takahashi, The Research Institute for Iron, Steel and Other Metals, Tohoku University, Sendai, Japan; and Professor T. Nagamiya, Osaka University, Nakanoshima, Japan.

A variety of social events, tours, and fashion shows for wives of conference attendees were also announced by Mrs. Donald L. Fresh, Chairman of Women's Activities.

The conference is being sponsored jointly by the American Institute of Electrical Engineers and the American Institute of Physics in cooperation with the Office of Naval Research, the Institute of Radio Engineers, and the Metallurgical Society of the A.I.M.E. Dr. L. R. Bickford, Jr., of the IBM Research Labs. in Yorktown Heights, N. Y., is General Chairman of the Conference.

The technical program will be as follows:

Monday Morning, November 13
Session I—General Session

Chairman: *L. R. Bickford, Jr.*

"Modification of Screw Spin Structure Due to Anisotropy Energy and Applied Field,"* *T. Nagamiya, Dept. of Physics, Osaka University.*

"Magnetic Disorder as a First Order Phase Transition,"* *C. P. Bean and D. S. Rodbell, General Electric Res. Lab.*

"High Magnetic Field Research,"* *B. Lax, Lincoln Lab.*

"Superconducting Materials and High Magnetic Fields,"* *J. E. Kunzler, Bell Telephone Labs., Inc..*

"The State of The Art of Magnetic Memories," *Q. W. Simkins, International Business Machines, Inc.*

Monday Afternoon
Session IIA—Magnetic Devices

Chairman: *W. L. Shevel, Jr.*

"Properties of Magnetic Films for Memory Systems,"* *E. M. Bradley, International Computers and Tabulators (Engineering) Ltd., Stevenage, Herts., England.*

"Magneto-Optic Readout for Computer Memories," *R. L. Conger, U. S. Naval Ordnance Lab.*

"Magneto-Optically Measured High Speed Switching of Sandwich Film Elements," *J. C. Suits and E. W. Pugh, IBM Research Center.*

"Switching Properties of Multilayer Thin Film Structures," *A. Kolk, L. Douglas, and G. Schrader, The National Cash Register Co.*

"Magnetostatic Interactions Between Thin Magnetic Films," *H. W. Fuller and D. L. Sullivan, Computer Products Div., Lab. for Electronics, Inc.*

"Permalloy-Sheet Transfluxor-Array Memory," *G. R. Briggs and J. W. Tuska, RCA Labs.*

"Proposal for and Demonstration of Magnetic Domain-Wall Storage and Logic," *D. O. Smith and J. M. Ballantyne, Lincoln Lab.*

"Threshold Properties of Partially Switched Ferrite Cores," *V. T. Shahan and O. A. Gutwin, IBM Research Center.*

"Flux Reversal in Ferrite Cores under the Effect of a Transverse Field," *K. Li, RCA Labs.*

"Approximate Solution of the Equations of Magnetization Reversal by Coherent Rotation," *R. F. Elfant, IBM Research Center, and F. J. Friedlander, Purdue University.*

"All Magnetic Logic Elements Using Strained Permalloy Wire," *H. R. Irons, U. S. Naval Ordnance Lab.*

"A Permanent Magnet Twistor Memory Element of Improved Characteristics," *E. J. Alexander, J. C. McAlexander, R. J. Salhany, and L. H. Young, Bell Telephone Labs., Inc.*

Session IIB—Internal Fields

"Nuclear Resonance in Ferromagnetic Alloys,"* *T. Kushida and A. H. Silver, Scientific Lab., Ford Motor Co.; and Y. Koi and A. Tsujimura, Faculty of Engineering, Tokushima University.*

"Crystalline Electric Fields in Spinel-Type Crystals," *V. J. Folen, U. S. Naval Research Lab.*

"The Axial Crystal Field in Corundum and the Susceptibility of Ti_2O_3," *S. Geschwind, Bell Telephone Labs., Inc.*

"Hyperfine Fields in Transition Metal and Rare Earth Ions," *A. J. Freeman, Materials Research Lab., Ordnance Materials Research Office; and R. E. Watson, Avco R. A. D.*

"Hyperfine Magnetic Field and Electron Spin Relaxation in the Sm^{+3} Ion in Europium Iron Garnet," *M. E. Caspari, S. Frankel, and G. T. Wood, Dept. of Physics, University of Pennsylvania.*

"The de Haas van Alphen Effect in Zinc Manganese Alloys," *F. T. Hedgcock and W. B. Muir, The Franklin Institute Labs.*

"Anisotropy of the Hyperfine Interaction in Magnetite," *E. L. Boyd and J. C. Slonczewski, IBM Research Center.*

"The Atomic Moments and Hyperfine Fields in Fe_2Ti and Fe_2Zr," *C. W. Kocher and P. J. Brown, Brookhaven National Lab.*

"Internal Magnetic Fields in Nickel Rich Nickel-Cobalt Alloys," *L. H. Bennett and R. L. Streever, Jr., Natl. Bureau of Standards.*

Tuesday Morning, November 14
Session IIIA—Thin Films 1

Chairman: *C. I. Kriessman.*

"The Induced Anisotropy of Evaporated Films Formed in Magnetic Field,"* *M. Takahashi, The Research Institute for Iron, Steel and Other Metals, Tohoku University.*

"Labyrinth Domains in Permalloy Films," *K. J. Harte and D. O. Smith, Lincoln Lab.*

"Bitter Patterns of Epitaxially Grown Single Crystal Thin Films of Iron and Nickel," *H. Sato, R. S. Toth, and R. W. Astrue, Scientific Lab., Ford Motor Co.*

"Constriction of Hard Direction Hysteresis Loops in Thin Permalloy Films," *S. Middelhoek, Research Laboratory, International Business Machines Corp.*

"A Theoretical Model for Partial Rotation," *N. Thomas, Research Lab., International Business Machines Corp.*

"Support and Extension of the Rotational Model of Thin Film Magnetization," *J. E. Schwenker and T. R. Long, Bell Telephone Labs., Inc.*

"Inhomogeneous Coherent Magnetization Rotation in Thin Magnetic Films," *K. D. Leaver and M. Prutton, International Computers and Tabulators (Engrg.), Ltd.*

"Kerr Magneto-Optic Studies of the Angular Dispersion of the Easy Axis of Permalloy Films," *R. W. Olmen and S. M. Rubens, Remington Rand Univac.*

"Electron Microscope Study of the Roughness of Permalloy Films Using Surface Replication," *A. Baltz, The Franklin Institute Labs.*

"The Effect of Substrate Cleanness on Permalloy Thin Films," *J. S. Lemke, Remington Rand Univac.*

"Anisotrophy Sources for Electrodeposited Permalloy Films," *M. Lauriente and J. Bagrowski, Air Arm Div., Westinghouse Electric Corp.*

"Factors Influencing Coercive Field Values in Sputtered Permalloy Films," *A. J. Noreika and M. H. Francombe, Philco Research Div.*

Session IIIB—Spin Configurations and Anisotropy

Chairman: *I. S. Jacobs.*

Title to be announced, *G. T. Rado*

"The Lattice Theory of Spin Configurations,"* *E. F. Bertaut, Nuclear Center and Lab. d'Electrostatique et de Physique du Metal.*

"Magnetic Structure Work at the Nuclear Center of Grenoble," *E. F. Bertaut, A. Delapalme, F. Forrat, G. Roult, F. de Bergevin, and R. Pauthenet, Laboratoire d'Electrostatique et de Physique du Metal.*

"Weak Ferromagnetism of Some Orthoferrites," *D. Treves and S. Alexander, Bell Telephone Labs., Inc.*

"Appearance of Weak Ferromagnetism in Fine Particles of Antiferromagnetic Materials," *W. J. Schuele and V. D. Deets-*

* Invited paper.

Varian presents the
VA-834B amplifier klystron
—1 kW CW—rugged
—lightweight—for

tactical mobility

In Forward Scatter Transmitters



4.4 - 5.0 kMc
1 kW CW

Need a rugged power amplifier tube for transportable microwave field equipment? Varian's VA-834B klystron is air-cooled and permanent-magnet focused. Simplifies operation and minimizes prime power requirements. Quick and easy to install. Only adjustment necessary — just tune to desired frequency. Tunable 4.4 to 5.0 kMc with 1 kW CW output. Lightweight — only 60 lb. including magnet.

Specifically developed for tactical and transportable equipment. Suited to commercial forward-scatter communications and radar transmitters.

FEATURES ■ 1 kW CW ■ 4.4 to 5.0 kMc
■ Efficiency up to 40% ■ 45 db Gain ■ 7.5 Mc Bandwidth

Sound interesting? We'll be pleased to send you full technical data. Just write Tube Division.

VARIAN associates

PALO ALTO 2, CALIFORNIA

BOMAC LABORATORIES, INC.
VARIAN ASSOCIATES OF CANADA, LTD.
S-F-D LABORATORIES, INC.
SEMICON ASSOCIATES, INC.
SEMICON OF CALIFORNIA, INC.
VARIAN A. G. (SWITZERLAND)

creek, The Franklin Institute Labs.

"The Magnetic Structure of Manganese Chromite," *L. M. Corliss and J. M. Hastings, Brookhaven National Lab.*

"Magnetic Transitions in Cubic Spinels," *N. Menyuk, A. Wold, D. B. Rogers, and K. Dwight, Lincoln Lab.*

"Neutron Diffraction Studies on Europium Metals," *C. E. Olsen, N. G. Nereson, and G. P. Arnold, Los Alamos Scientific Lab.*

"Neutron Diffraction Study of Magnetic Ordering in Thulium," *W. C. Koehler, J. W. Cable, E. O. Wollan, and M. K. Wilkinson, Oak Ridge National Lab.*

"The Nature of One-Ion Models of the Ferrimagnetic Anisotropy," *P. J. Wojtowicz, RCA Labs.*

"The Temperature Dependence of the Magnetocrystalline Anisotropy of Face-Centered Cubic Cobalt," *D. S. Rodbell, General Electric Research Lab.*

Tuesday Afternoon
Session IVA—Thin Films 2

Chairman: *H. Rubinstein*

"Electrodeposition of Magnetic Materials,"* *I. W. Wolf, Electronics Lab., General Electric Co.*

"Rotatable Magnetic Anisotropy in Composite Films," *J. M. Lommel and C. D. Graham, Jr., General Electric Research Lab.*

"Unidirectional Hysteresis in Thin Permalloy Films," *W. D. Doyle, J. E. Rudisill, and S. Shtrikman, The Franklin Institute Labs.*

"Ferromagnetic Resonance in Single Crystal Nickel Films," *M. Pomerantz, J. F. Freedman, and J. C. Suits, IBM Research Center.*

"Stratification in Thin Permalloy Films," *R. J. Prosen, J. O. Holmen, B. E. Gran, and T. J. Cebulla, Minneapolis-Honeywell Research Center.*

"Ferromagnetic Resonances in Thin Films," *D. Chen and A. H. Morrish, University of Minnesota.*

"Isotropic Stress Measurements in Evaporated Permalloy Films," *G. P. Weiss and D. O. Smith, Lincoln Lab.*

"Hall Effect Determination of Planar Stress in Ferromagnetic Films," *R. L. Coren, Philco Research Div.*

"Stress Effects on the Magnetic Properties of Evaporated Single Crystal Nickel Films," *J. F. Freedman, IBM Research Center.*

"Magnetoelastic Behavior of Thin Ferromagnetic Films as a Function of Composition," *E. N. Mitchell and G. I. Lykken, University of North Dakota.*

Session IVB—Magnetization

Chairman: *S. Foner*

"Statistical Mechanics of Ferromagnetism,"* *H. Callen, Dept. of Physics, University of Pennsylvania.*

"Magnetization of Localized States in Metals,"* *P. A. Wolff, Bell Telephone Labs., Inc.*

"Magnetization of Nickel at Low Temperatures,"* *E. W. Pugh and B. E. Argyle, IBM Research Center.*

"Temperature Dependence of YIG Magnetization," *I. H. Solt, Jr., Research and Development Labs., Fairchild Semiconductor.*

"Nuclear Magnetic Resonance in the Insulating Ferromagnet $CrBr_3$," *A. C. Gossard, V. Jaccarino, and J. P. Remeika, Bell Telephone Labs., Inc.*

"Ferromagnetic Resonance in $CrBr_3$," *J. F. Dillon, Jr., Bell Telephone Labs., Inc.*

"Principles and Procedures for Precision Measurements of Magnetic Properties," *A. Arrott, C. H. Haakana, and J. E. Noakes, Scientific Lab., Ford Motor Co.*

Wednesday Morning, November 15
Session VA—Oxides 1

Chairman: *L. M. Corliss*

"Acoustic Losses in Ferromagnetic Insulators,"* *R. C. LeCraw, E. G. Spencer, and E. I. Gordon, Bell Telephone Labs., Inc.*

"Rare Earth Ruthenates," *R. Aleonard, E. F. Bertaut, M. C. Montmory, and R. Pauthenet, Laboratoire d'Electrostatique et de Physique du Metal.*

"Substitutions of Divalent Transition Metal Ions in Yttrium Iron Garnet," *S. Geller, H. J. Williams, R. C. Sherwood, and G. P. Espinosa, Bell Telephone Labs., Inc.*

"Low Temperature Anisotropy of Manganese-Iron Ferrites," *W. Palmer, IBM Research Center.*

"Preparation and Properties of Ferrospinels Containing Ni^{+3}," *M. W. Shafer, IBM Research Center.*

"Perminvar Characteristics of Nickel-Cadmium Ferrites with Small Additions of Molybdenum and Cobalt," *H. Lessoff and A. P. Greifer, Memory Products Operation, Radio Corp. of America.*

"Vanadium Iron Oxides," *A. Wold, D. Rogers, R. J. Arnott, and N. Menyuk, Lincoln Lab.*

"X-Ray and Magnetic Studies of CrO_2 Single Crystals," *W. H. Cloud, D. S. Schreiber, and K. R. Babcock, Central Research Dept., E. I. du Pont de Nemours and Co.*

"Cation--Cation Three-Electron Bonds," *J. B. Goodenough, Lincoln Lab.*

"Some Superparamagnetic Properties of Fine Particles δ FeOOH," *A. W. Simpson, Caswell Research Labs., The Plessey Co. Ltd.*

Title to be announced, *Malinofsky.*

Session VB—Soft Magnetic Materials

Chairman: *P. A. Albert*

"Recent Developments in Soft Magnetic Alloys," *E. Adams, U. S. Naval Ordnance Lab.*

"Magnetic Properties of Tape Wound Cores of High-Purity 3% Silicon Iron with the (110) [001] Texture," *J. L. Walter, General Electric Research Lab.*

"Magnetic Anisotrophy of the Demagnetized State," *J.-C. Barbier and B. Ferlin-Guion, Laboratoire d'Electrostatique et de Physique du Metal.*

"On the Two Effects of Changes in Tension," *O. Yamada, Laboratoire d'Electrostatique et de Physique du Metal.*

"Textured 6.5 Percent Silicon-Iron Alloy," *G. Facaros, Westinghouse Materials Manufacturing Dept. and R. G. Aspden, Westinghouse Research Labs.*

"Grain-Size Effects in Oriented 48 percent Nickel-Iron Cores at 400 Cycles," *M. F. Littmann, E. S. Harris, and C. E. Ward, Research Center, Armco Steel Corp.*

"Anisotropy in Rolled Permalloy Tape," *E. M. Gyorgy and D. Treves, Bell Telephone Labs., Inc.*

To be announced, *Burket, et al.*

"The Effects of Low Temperature Neutron Irradiation on the Magnetic Properties of Iron-Nickel Alloys," *A. I. Schindler, U. S. Naval Research Lab., and R. H. Kernohan, Solid State Div., Oak Ridge National Lab.*

"Cooling Rate Effect on Initial Permeability of 4-79 Moly-Permalloy," *A. A. Lykens, Research Lab., The Carpenter Steel Co.*

"Low Angle X-Ray Scattering from MnS in Silicon Steels," *B. R. Banerjee and R. E. Lenhart, Research Div., Crucible Steel Co. of America, and W. H. Robinson, Carnegie Inst. Tech.*

Wednesday Afternoon
Session VIA—Rare Earths

Chairman: *J. F. Dillon*

"Ferrimagnetic Resonance in Terbium Doped Yttrium Iron Garnet,"* *L. R. Walker, Bell Telephone Labs., Inc.*

"Far Infrared Spectra of Magnetic Materials,"* *M. Tinkham, Dept. of Physics, University of California.*

"Magnetocrystalline Anisotropy of Rare Earth Iron Garnets,"* *R. F. Pearson, Mullard Research Labs.*

"The Contributions of Rare Earth Ions to the Anisotropy of Iron Garnets," *B. A. Calhoun, M. J. Freiser, and R. F. Penoyer, IBM Research Center.*

"Spinwave Linewidths in Rare-Earth Substituted Yttrium Iron Garnet," *P. E. Seiden, IBM Research Center.*

"High Field Low Temperature Magnetization Studies of Praseodymium Substituted Yttrium Iron Garnet $5Fe_2O_3 \times Pr_2O_3(3\text{-}X)\ Y_2O_3$," *W. E. Henry, Lockheed Missiles and Space Co. and G. Villers and J. Loriers, Laboratoire de Bellevue, Centre National de la Recherche Scientifique.*

"Paramagnetic Resonance of Gd^{+++} in Yttrium Gallium Garnet," *L. Rimai and G. A. Demars, Research Div., Raytheon Co.*

"Neutron Magnetic Scattering from Rare Earth Ions," *R. E. Watson, AVCO R.A.D. and A. J. Freeman, Materials Research Lab., Ordnance Materials Research Office.*

"High Temperature Susceptibility of Garnets: Exchange Interactions in YIG and LuIG," *P. J. Wojtowicz, RCA Labs.*

Session VIB—Devices and Phenomena

Chairman: *C. L. Hogan*

"A Coaxial Ferrite Phase Shifter for High Power Applications," *A. S. Boxer and R. S. McCarter, Bell Telephone Labs., Inc.*

"Slow-Wave UHF Ferrite Phase Shifters," *N. G. Sakiotis and D. E. Allen, Solid State Electronics Dept., Motorola Inc.*

"Efficient Frequency Doubling from Ferrites at the 100-Watt Level," *A. S. Risley and I. Kaufman, Space Technology Labs. Inc.*

"A Magneto-Dynamic Mode Ferrite Amplifier," *R. W. Roberts and R. Schell, Melabs, and B. A. Auld, Stanford University.*

"A Miniaturized Ferrimagnetic High Power Coaxial Duplexer-Limiter," *J. Clark and J. Brown, Applied Physics Section, Sperry Microwave Electronics Co.*

"Design Considerations for Broadband Symmetrical "WYE" Tuneable Ferrite Circulators in TEM Mode Strip Transmission Line," *D. S. Elkort, NARDA Microwave Corp.*

"Nonlinear Effects in Ferrite Filled Reduced Size Waveguide," *F. S. Hickernell, B. H. Auten, and N. G. Sakiotis, Solid State Electronics Dept., Motorola Inc.*

Working from 18,000 to 90,000 mc?

Don't settle for less than narda precision Impedance Meters!



MILLIMETER IMPEDANCE METERS

Model:	Price:
K218	$ 500.
V217	600.
Q217	1100.
M217	995.
E217	1650.

Just because you're working in millimeter bands is no reason to "make do" with lesser specs than you get from L to KU Bands. It's true that it's more difficult to maintain top specs at 90,000 mc than at X Band, for example, but in most cases Narda does it! And especially, in our slotted lines!

Precision instruments in every way, Narda millimeter Impedance Meters give you these important benefits: Smooth, stable carriage travel, absolutely parallel to the transmission line axis, with complete freedom from backlash. Imperceptible slope (0.01 max.), thanks to precision milling of tellurium copper main transmission line, followed by a silver plate of molecular thickness and a rhodium flash.

Residual VSWR is under 1.01 for K and V Bands; 1.02 for Q, M and E. Position of the built-in probe is measured with a precision dial indicator having a least count of 0.001". And as an added advantage, the probe is usable with any waveguide detector.

All in all, an exceptionally fine instrument — and yet, typical of all Narda millimeter products. For complete information on the entire line, write for a free catalog. Address: Dept. PIRE-6.

Rely on narda *for these other precision millimeter products:*

Direct Reading VARIABLE ATTENUATORS
HARMONIC GENERATORS
High-Directivity DIRECTIONAL COUPLERS
FREQUENCY METERS
SLIDING TERMINATIONS
FIXED TERMINATIONS
TUNABLE SHORTS
CRYSTAL DETECTORS
STANDARD GAIN HORNS

the narda microwave corporation
PLAINVIEW, L. I., NEW YORK AREA CODE 516 GE 3-9000

"Millimeter Wave Parametric Amplification with Antiferromagnetic Materials," *R. A. Moore, Air Arm Div., Westinghouse Electric Corp.*

"A Microwave Magnetic Microscope," *R. F. Soohoo, Lincoln Lab.*

"Sampling Magnetometer Based on the Hall Effect," *H. H. Wieder, U. S. Naval Ordnance Lab.*

"New Type of Flux-Gate Magnetometer," *W. A. Geyger, U. S. Naval Ordnance Lab.*

"Waveform of the Time Rate of Change of Total Flux for Minimum Core Loss," *H. L. Schenk and F. J. Young, Westinghouse Research Labs.*

"Iron Losses in Elliptically Rotating Fields," *R. D. Strattan and F. J. Young, Carnegie Inst. Tech.*

"Low Frequency Losses and Domain Boundary Movements in Silicon Iron," *D. A. Wycklendt, Research Labs., Allis-Chalmers Manufacturing Co.*

"Properties of Reset Cores in Radar Pulse Transformers," *R. Lee, Westinghouse Electric Corp.*

Thursday Morning, November 16

Session VIIA—Antiferromagnetism and Resonance

Chairman: *M. T. Weiss*

To be announced, *Suhl.*

"Field Dependent Magnetic Susceptibility and Magnetostriction in Antiferromagnetic CoO, MnO and NiO Single Crystals," *T. R. McGuire and W. A. Crapo, IBM Research Center*

"Pulsed Critical Field Measurements in Magnetic Systems," *S. Foner and S.-L. Hou, Natl. Magnet Lab.*

"Antiferromagnetic Resonance in $MnTiO_3$," *J. J. Stickler and G. S. Heller, Lincoln Lab.*

"Antiferromagnetic and Paramagnetic Resonance in $CuF_2 \cdot 2H_2O$," *M. Peter and T. Moriya, Bell Telephone Labs., Inc.*

"Ferromagnetic Resonance Loss in Lithium Ferrite as a Function of Temperature," *R. T. Denton and E. G. Spencer, Bell Telephone Labs., Inc.*

"Impurity Ion Effects in the Ferrimagnetic Resonance of Ordered Lithium Ferrite," *A. D. Schnitzler, V. J. Folen, and G. T. Rado, U. S. Naval Research Lab.*

"Ferromagnetic Resonance Magnon Distribution in Yttrium Iron Garnet," *T. J. Matcovich, H. S. Belson, N. Goldberg, and C. W. Haas, Remington Rand Univac.*

"On the Possibility of Obtaining Large Amplitude Resonance in Very Thin Ferrimagnetic Disks," *F. R. Morgenthaler, Dept. Elec. Engrg., Mass. Inst. Tech.*

"Microwave Resonance Linewidth in Single Crystals of Cobalt Substituted Manganese Ferrite," *R. W. Teale, Mullard Research Labs.*

"DC Effects in Ferromagnetic Resonance in Thin Ferrite Films," *W. Heinz and L. Silber, Microwave Research Inst., Polytechnic Inst. Brooklyn.*

Session VIIB—Permanent Magnets and Micromagnetics

Chairman: *F. E. Luborsky*

"Exchange Anisotropy—A Review,"* *W. H. Meiklejohn, General Electric Research Lab.*

"Permanent Magnetic Properties of Iron-Cobalt Phosphides," *K. J. de Vos, W. A. J. J. Velge, and M. G. v. d. Steeg, N. V. Phillips' Gloeilampenfabrieken.*

"Studies of High Coercivity Cobalt-Phosphorous Electrodeposits," *J. S. Sallo and J. M. Carr, Minneapolis-Honeywell Research Center.*

"The Formation of Monocrystalline Alnico Magnets by Secondary Recrystallization Methods," *E. Steinort, Centro Magneti Permanenti, S. P. A., Milan, Italy, and E. R. Cronk, S. J. Garvin, and H. Tiderman, Thomas & Skinner, Inc.*

"Saturation Magnetization of Swaged Mn-Al," *M. A. Bohlmann, Indiana Steel Products Div., Indiana General Corp.*

"Study of Particle Arrangements and Magnetic Domains on the Surface of Permanent Magnets," *K. J. Kronenberg, Indiana Steel Products Div., Indiana General Corp.*

"On the Possibility of Domain Wall Nucleation by Thermal Agitation," *A. Aharoni, Dept. of Electronics, The Weizmann Inst. Science.*

"Failure of the Local-Field Concept for Hysteresis Calculations," *W. F. Brown, Jr., Dept. of Elec. Engrg., University of Minnesota*

"Single-Domain Magnetization Curves for the General Ellipsoid," *C. E. Johnson, Jr., Dept. Elec. Engrg., University of Minnesota.*

"The Dependence of Average Interaction Fields on Intensity of Magnetization in Assemblies of Ferromagnetic Particles," *G. Bate, International Business Machines Corp.*

"The Effect of Angular Variations in Field on Fine-Particle Remanence," *E. D. Daniel, Memorex Corp., and R. Noble, M.S.S. Recording Co.*

To be announced, *Flanders and Shtrikman.*

Thursday Afternoon

Session VIIIA—Alloys and Compounds

Chairman: *J. A. Osborn*

"Age-Hardened Gold Permalloy and Gold Perminvar," *E. A. Nesbitt and E. M. Gyorgy, Bell Telephone Labs., Inc.*

"Paramagnetic Behavior of Iron-Rich Iron-Vanadium Alloys," *S. Arajs, R. V. Colvin, H. Chessin, and J. M. Peck, Edgar C. Bain Lab. for Fundamental Research, U. S. Steel Corp.*

"Magnetic Characteristics of Hydrogenated Holmium," *Y. Kubota and W. E. Wallace, Dept. Chemistry, University of Pittsburgh.*

"New Modified Mn_2Sb Compositions Showing Exchange Inversion," *T. A. Bither, P. H. L. Walter, W. H. Cloud, T. J. Swoboda, and P. E. Bierstedt, Central Research Dept., E. I. du Pont de Nemours and Co.*

"Magnetic Structures of Mn_2As and $Mn_2Sb_{0.7}As_{0.3}$," *A. E. Austin and E. Adelson, Battelle Memorial Inst. and W. H. Cloud, Central Research Dept., E. I. du Pont de Nemours and Co.*

"Structural and Magnetic Properties of Copper-Substituted Manganese-Aluminum Alloys," *M. Sugihara and I. Tsuboya, Electrical Communication Lab., Nippon Telegraph and Telephone Public Corp.*

"Magnetic Susceptibility and Internal Friction of Tetragonal Manganese-Copper Alloys Containing 70 Per cent Manganese," *A. E. Schwaneke and J. W. Jensen, Rolla Metallurgy Research Center, Bureau of Mines.*

"Anomalous Magnetic Moments and Transformations in the Ordered Alloy FeRh," *J. S. Kouvel and C. C. Hartelius, General Electric Research Lab.*

"Alloys of the First Transition Series with Pd and Pt," *S. J. Pickart, U. S. Naval Ordnance Lab., and R. Nathans, Brookhaven National Lab.*

"Neutron Diffraction Investigations of Ferromagnetic Palladium and Iron Group Alloys," *J. W. Cable, E. O. Wollan, W. C. Koehler, and M. K. Wilkinson, Oak Ridge National Lab.*

"Magnetic Properties of Mixed Vanadium-Chromium Sulfides," *K. Dwight, R. W. Germann, A. Wold, and N. Menyuk, Lincoln Lab.*

"Magnetic Moment of Co-Cu Solid Solutions with 40 to 85 Percent Cu," *E. Kneller, IBM Research Center.*

"Magnetic Susceptibilities and Exchange Effects in Four Organic Free Radicals," *J. H. Burgess, R. S. Rhodes, M. Mandel, and A. S. Edelstein, Stanford University.*

Session VIIIB—Oxides 2 and Crystals

Chairman: *R. L. White*

"Temperature Stable Microwave Hybrid Garnets," *G. R. Harrison and L. R. Hodges, Jr., Applied Physics Section, Sperry Microwave Electronics Co.*

"Magnetic Properties of Yttrium-Gadolinium-Aluminum-Iron Garnets," *E. A. Maguire and J. J. Green, Research Div., Raytheon Co.*

"Nickel Aluminum Gallium Ferrites for Use at High Signal Levels," *J. W. Nielsen and J. Zneimer, Airtron Div. of Litton Industries.*

"Resonance Properties of Single Crystal Hexagonal Ferrites," *C. R. Buffler, Bomac Labs., Varian Associates.*

"Hexagonal Ferrites for Use at *X*- to *V*-Band Frequencies," *G. P. Rodrigue and J. E. Pippin, Sperry Microwave Electronics Co.*

"Spin Wave Excitation in Planar Ferrites," *I. Bady, U. S. Army Signal Corps Research and Development Lab. and E. Schlomann, Research Div., Raytheon Co.*

"Investigation of Spin-Wave Interactions by the Parallel Pumping Technique," *J. J. Green and E. Schlomann, Research Div., Raytheon Co.*

"Subsidiary Absorption Effects in Ferrimagnetics," *J. H. Saunders and J. J. Green, Research Div., Raytheon Co.*

"High-Power Characteristics of Single-Crystal Ferrites with Planar Anisotropy," *S. Dixon, Jr., U. S. Army Signal Research and Development Lab.*

"The Effect of Growth Conditions and Subsequent Thermal and Mechanical Treatment on the Ferrimagnetic Resonance Linewidth of Lithium Ferrite Single Crystals," *J. W. Nielsen, D. A. Lepore, J. Zneimer, and G. B. Townsend, Airtron Div. of Litton Industries.*

"The Growth of Yttrium-Iron Garnet on a Seed from a Molten Salt Solution," *R. A. Laudise, R. C. Linares, and E. F. Dearborn, Bell Telephone Labs., Inc.*

"Cobalt Ferrite Crystal Growth from the Ternary Flux System Na_2O-CoO-Fe_2O_3," *W. Kunnmann and A. Wold, Lincoln Lab., Mass. Inst. Tech., and E. Banks, Dept. of Chemistry, Polytechnic Inst. of Brooklyn.*

"Growth of Single-Crystal Hexagonal Ferrites Containing Zn," *A. Tauber, R. O. Savage, R. Gambino, and C. Whinfrey, U. S. Army Signal Research and Development Lab.*

LOW POWER SILICON DIGITAL MODULES

ENVIRONMENTALLY PROVED . . . AVAILABLE NOW!

Delco Radio's new silicon digital modules operate on less than 4 mw. of power per logic stage. They are rugged enough to withstand extreme environmental conditions and are small and lightweight. Encapsulated in light foamy epoxy, each module weighs less than 12 grams and occupies less than one-half cubic inch. The basic set of modules includes a bistable multivibrator, a diode NOR gate, a power driver, a monostable multivibrator and an astable multivibrator. From these basic units larger computer subassemblies can be assembled, such as shift registers, adders, binary counters, decimal counters and timing devices. A range of applications—from small scale switching circuits to large computers can be satisfied with these modules. Environmentally proved to:



Data sheets are available. Just write or call our Military Sales Department.

Physicists and electronics engineers: Join Delco Radio's search for new and better products through Solid State Physics.

PIONEERING ELECTRONIC PRODUCTS THROUGH SOLID STATE PHYSICS

DELCO RADIO

Division of General Motors • Kokomo, Indiana

Professional Groups*

Aerospace & Navigational Electronics (G-11)—G. M. Kirkpatrick, Electronics Equipment and Systems Lab., GE Co., Syracuse, N. Y.; H. R. Mimno, Cruft Lab., Harvard Univ., Cambridge 38, Mass.

Antennas & Propagation (G-3)—Dr. H. Fine, Applied Propagation Branch, Technical Research Div., FCC, Washington, D. C.; S. A. Bowhill, Pennsylvania State Univ., University Park, Pa.

Audio (G-1)—C. M. Harris, Electronics Res. Labs., Columbia Univ., New York 27, N. Y.; M. Camras, Armour Res. Foundation, Tech. Ctr., Chicago 16, Ill.

Automatic Control (G-23)—J. M. Salzer, Ramo-Wooldridge, 5500 E. Segunda, Hawthorne, Calif.; G. S. Axelby, Westinghouse Air Arm Div., Friendship Airport, Baltimore 3, Md.

Bio-Medical Electronics (G-18)—G. N. Webb, Dept. of Medicine, Biophysical Div., Johns Hopkins Hospital, Baltimore 5, Md.; L. B. Lusted, Dept. of Radiology, Univ. of Rochester, Rochester 20, N. Y.

Broadcast & Television Receivers (G-8)—R. R. Thalner, Sylvania Home Electronics, 700 Ellicott St., Batavia, N. Y.; C. W. Sall, RCA, Princeton, N. J.

Broadcasting (G-2)—R. F. Guy, 264 Franklin St., Haworth, N. J.; W. L. Hughes, School of Elec. Engrg., Oklahoma State University, Stillwater, Okla.

Circuit Theory (G-4)—Dr. J. H. Mulligan, Jr., College of Engrg., New York, Univ., University Heights, New York 53, N. Y.; M. E. Van Valkenburg, Dept. of E.E., Univ. of Illinois, Urbana, Ill.

Communications Systems (G-19)—R. L. Marks, Rome Air Dev. Ctr., Griffiss AFB, N. Y.; E. J. Baghdady, Elec. Engrg. Dept., M.I.T., Cambridge 39, Mass.

Component Parts (G-21)—F. E. Wenger, Headquarters ARDC, Andrews AFB, Washington 25, D. C.; G. Shapiro, Engineering Electronics Sec., Div. 1.6, NBS, Connecticut Ave. and Van Ness St., Washington 25, D. C.

Education (G-25)—G. E. Moore, Westinghouse Elec. Corp., East Pittsburgh, Pa.; W. R. LePage, Dept. of E.E., Syracuse Univ., Syracuse 10, N. Y.

Electron Devices (G-15)—W. A. Adcock, Texas Instruments, 6000 Lemmon Ave., Dallas 9, Tex.; G. Wade, Spencer Lab., Raytheon Co., Burlington, Mass.

Electronic Computers (G-16)—A. A. Cohen, Remington Rand Univac, St. Paul 16, Minn.; Prof. N. R. Scott, Dept. of Elec. Engrg., University of Michigan, Ann Arbor, Mich.

Engineering Management (G-14)—T. W. Jarmie, Engineered Electronics Co., 1441 E. Chestnut Ave., Santa Ana, Calif.; A. H. Rubenstein, Dept. of Indus. Engrg., Northwestern Univ., Evanston, Ill.

Engineering Writing and Speech (G-16)—J. M. Kimm, Jr., *IBM Journal*, 17th Floor, 545 Madison Ave., New York, N. Y.; H. B. Michaelson, IBM Res. Ctr., Box 218, Yorktown Heights, N. Y.

Human Factors in Electronics (G-28)—R. R. Riesz, Bell Telephone Labs., Murray Hill, N. J.; J. I. Elkind, Bolt Beranek and Newman, Inc., 50 Moulton St., Cambridge, Mass.

Industrial Electronics (G-13)—J. E. Eiselein, RCA Victor Div., Camden, N. J.; R. W. Bull, Coleman Instruments, Inc., 42 Madison St., Maywood, Ill.

Information Theory (G-2)—G. L. Turin, E.E. Dept., Univ. of California, Berkeley, Calif.; A. Kohlenberg, Melpar Inc., 11 Galen St., Watertown, Mass.

Instrumentation (G-9)—H. W. Lance, Nat'l. Bureau of Standards, Boulder, Colo.; G. B. Hoadley, Dept. of E.E., North Carolina State College, Raleigh, N. C.

Microwave Theory and Techniques (G-17)—T. N. Anderson, EMT Corp., Syosset Industrial Park, 210 Michael Dr., Syosset, L. I., N. Y.; D. D. King, Electronic Comm., Inc., 1830 York Rd., Timonium, Md.

Military Electronics (G-24)—W. L. Doxey, EC Dept., USASRDL, Fort Monmouth, N. J.; D. R. Rhodes, Radiation Inc., Box 37, Melbourne, Fla.

Nuclear Science (G-5)—L. Costrell, Nucleonic Inst. Sec., NBS, Washington 25, D. C.; R. F. Shea, Dig Power Plant Engrg., Knolls Atomic Power Lab., General Electric Company, Schenectady, N. Y.

Product Engineering and Production (G-22)—A. R. Gray, Astronics of Florida, Inc., 1110 S. Woods St., Box 5606, Orlando, Fla.; D. B. Ehrenpreis, 325 Spring St., New York, N. Y.

Radio Frequency Interference (G-27)—H. E. Dinger, Naval Research Lab., Washington 25, D. C.; O. P. Schreiber, Technical Wire Prods., Inc., 129 Dermody St., Cranford, N. J.

Reliability and Quality Control (G-7)—L. J. Paddison, Sandia Corp., Sandia Base, Albuquerque, N. Mex.; W. X. Lamb, Jr., 22124 Dumetz Rd., Woodland Hills, Calif.

Space Electronics and Telemetry (G-10)—K. M. Uglow, Jr., 2228 Oriole Dr., Saratoga Fla.; F. T. Sinnott, Mail Zone 549-30, Convair-Astronautics, San Diego 12, Calif.

Ultrasonics Engineering (G-20)—V. Salmon, Stanford Research Inst., Menlo Park, Calif.; O. E. Mattiat, Res. Div., Acoustica Associates Inc., 415 E. Montecito St., Santa Barbara, Calif.

Vehicular Communications (G-6)—R. P. Gifford, General Electric Co., Rm. 206, Mountain View Rd., Lynchburg, Va.; W. G. Chaney, AT&T Co., 195 Broadway, New York 7, N. Y.

* Names listed are Group Chairmen and TRANSACTIONS Editors.

124 completely hermetically sealed Microwave Mixer and Video Diodes

ALL ARE DIRECTLY SUBSTITUTABLE FOR CONVENTIONAL DIODES TO ASSURE UNPRECEDENTED SYSTEMS RELIABILITY.

Microwave Associates has answered your need for truly hermetically-sealed diodes. For the first time, both fixed-base and reversible polarity types have CERAMIC-TO-METAL SOLDER SEALS plus SOLDER END SEALS.

Whatever the requirement – from 1 Mc to 18 kMc, a new diode is available to replace the present diode — extra high burnout types for high signal level circuits and behind radar duplexers—new low-noise types for doppler receivers.

The MA-458F, for example, replacing the 1N23E, has a calculated overall noise figure of 7.0 db — the lowest noise figure available for high reliability applications.

These diodes (and coaxial case and subminiature glass packaged diodes) assure military and commercial applications the reliability essential to uninterrupted service for exceptional time spans. They perform to 150°C and meet the applicable environmental requirements of MIL-S-19500.

MICROWAVE ASSOCIATES, INC
SEMICONDUCTOR DIVISION
BURLINGTON, MASSACHUSETTS • WESTERN UNION FAX
TWX: BURLINGTON, MASS. 942 • BROWNING 2-3000
Export Sales: Microwave International Corp.
36 W. 44th St., N.Y.C., N.Y., U.S.A. Cable: Microken

SILICON MIXER DIODES

1 Mc — 4,000 Mc

CARTRIDGE CASE

Improved Types

For low noise superheterodyne mixer performance
Replace 1N21 series

Fixed Base Types		Matched Pair		Reversible Polarity Types	Calc. Overall Rec'r Noise Figure @ 1.5db (db)	Burnout Rating (ergs)
Forward Polarity	Reversed Polarity	Forward Pair	Forward & Reversed			
MA-449B	MA-449BR	MA-449BM	MA-449BMR	MA-459B	10.3	5.0
MA-449C	MA-449CR	MA-449CM	MA-449CMR	MA-459C	8.3	5.0
MA-449D	MA-449DR	MA-449DM	MA-449DMR	MA-459D	7.3	5.0
MA-449E	MA-449ER	MA-449EM	MA-449EMR	1N21WE	7.0	5.0
MA-449F	MA-449FR	MA-449FM	MA-449FMR	MA-459F	6.0	5.0

Higher Burnout Types

For use in pulse radars or other receivers exposed to high RF radiation fields.
Interchangeable with 1N21 series

MA-4127	MA-4127R	MA-4127M	MA-4127MR	MA-4132	8.3	10

Lower Noise Types

For best signal-to-noise performance in low frequency IF doppler systems.

MA-4126 MA-4126A	MA-4126R MA-4126AR	MA-4126M MA-4126AM	MA-4126MR MA-4126AMR	MA-4131 MA-4131A	— —	2.0 2.0

4,000 Mc — 10,000 Mc

Improved Types

For low noise superheterodyne mixer performance.
Replace 1N23 series

MA-451B	MA-451BR	MA-451BM	MA-451BMR	MA-458B	11.4	2.0
MA-451C	MA-451CR	MA-451CM	MA-451CMR	MA-458C	9.8	2.0
MA-451D	MA-451DR	MA-451DM	MA-451DMR	MA-458D	8.2	2.0
MA-451E	MA-451ER	MA-451EM	MA-451EMR	1N23WE	7.5	2.0
MA-451F	MA-451FR	MA-451FM	MA-451FMR	MA-458F	7.0	2.0

Higher Burnout Types

For use in pulse radars or other receivers exposed to high RF radiation fields.
Interchangeable with 1N23 series

MA-4133	MA-4133R	MA-4133M	MA-4133MR	MA-4134	9.8	5.0

Lower Noise Types

For best signal-to-noise performance in low frequency IF doppler systems.

MA-4125 MA-4125A	MA-4125R MA-4125AR	MA-4125M MA-4125AM	MA-4125MR MA-4125AMR	MA-4130 MA-4130A	— —	2.0 2.0

10,000 Mc — 18,000 Mc

COAXIAL CASE

Improved Types

For low noise superheterodyne mixer performance.
Replace 1N78 series

MA-443 MA-443A MA-443B MA-445 MA-445A MA-445B	MA-443R MA-443AR MA-443BR MA-445R MA-445AR MA-445BR	MA-443M MA-443AM MA-443BM MA-445M MA-445AM MA-445BM	MA-443MR MA-443AMR MA-443BMR MA-445MR MA-445AMR MA-445BMR	— — — — — —	— 9.8 8.8 — 9.8 8.8	0.6 0.6 0.6 1.0 1.0 1.0

Lower Noise Types

For best signal-to-noise performance in low frequency IF doppler systems.

MA-4124 MA-4124A	MA-4124R MA-4124AR	MA-4124M MA-4124AM	MA-4124MR MA-4124AMR	— —	— —	0.6 0.6

SILICON VIDEO DIODES

1 Mc — 10,000 Mc

Improved Types For high tangential signal-to-noise sensitivity in simplified beacon receivers, test equipment and other uses.
Replace MA-408 series CARTRIDGE CASE

Fixed Base Types		Reversible Polarity	Burnout (ergs)
Forward Polarity	Reversed Polarity		
MA-452 MA-452A MA-452B	MA-452R MA-452AR MA-452BR	MA-461 MA-461A MA-461B	1.0 1.0 1.0

Higher Burnout Wide Dynamic Range Types

For use in video receivers exposed to high RF radiation fields.
Interchangeable with MA-408 series

MA-4126	MA-4126R	MA-4129	5.0

Sections*

Akron (4)—C. M. Kelly, 2915 Silver Lake Circle, Cuyahoga Falls, Ohio; D. Grant, 1206 Thorndale Dr., Akron 20, Ohio.

Alamogordo-Hollman (7)—W. S. Stotts, 1507 Michigan Ave., Alamogordo, N. M.; H. T. Castillo, 2611 Pontiac Ave., Alamogordo, N. M.

Albuquerque-Los Alamos (7)—R. K. Moore, 608 Vassar Dr., N. E. Albuquerque, N. Mex.; F. H. Jean, 1017 Alcazar, N. E., Albuquerque, N. Mex.

Anchorage (7)—T. R. Young, 415 11th Ave., Anchorage, Alaska; C. A. Johnson, 1536 "I" St., Anchorage, Alaska.

Atlanta (3)—B. E. Montgomery, 6520 Bridgewood Valley, Atlanta 5, Ga.; R. S. Duggan, Jr., 1112 Mason Woods Dr., N. E., Atlanta 6, Ga.

Baltimore (3)—J. T. Wilner, 2610 N. Charles St., Station WBAL, Baltimore 18, Md.; E. B. Cole, Jr., 6016 Alta Ave., Baltimore 6, Md.

Bay of Quinte (8)—M. B. Broughton, Elec. Engrg. Dept., Royal Military College, Kingston, Ont., Canada; D. J. Cowan, 3 Smith Cresent, Belleville, Ont., Canada.

Beaumont-Port Arthur (6)—H. W. Bartlett, 3790 Ironton, Beaumont, Tex.; R. Cunningham, Rte. 1, Box 181, Kirbyville, Tex.

Benelux—Herre Rinia, Parklaan 24, Eindhoven, Netherlands; G. J. Siezen, 3 Konig Willem III Laan, Blaricum, Holland.

Binghamton (1)—F. W. Schaaf, R. D. 1, Apalachin, N. Y.; D. W. Deno, 3149 Briar Cliff Ave., R. D. 1, Vestal, N. Y.

Boston (1)—G. P. McCouch, Alcott Rd., Concord Mass.; R. E. Scott, 114-H Northeastern Univ., Boston 15, Mass.

Buenos Aires—J. M. Barcala, 71–385 La Plata, FCNGR, Republica, Argentina; E. J. Kirkscether, Arenales 3598-A, Buenos Aires, Argentina.

Buffalo-Niagara (1)—D. P. Sante, 4530 Greenbriar Rd., Williamsville 21, N. Y.; F. A. Timberlake, 169 Greenhaven Terrace, Tonawanda, N. Y.

Cedar Rapids (5)—P. G. Wulfsberg, 2348 Linden Dr., S.E., Cedar Rapids, Iowa; D. E. Newell, 200 Koser Ave., Iowa City, Iowa.

Central Florida (3)—C. E. Mattox, 209 Beverly Rd., Cocoa Fla.; W. J. Haberhern, Jr., 118 Atlantic Blvd., Eau Gallie, Fla.

Central Pennsylvania (4)—W. J. Ross, 105 Elec. Engrg. Dept., University Park, Pa.; J. L. Brown, Jr., Ordnance Research Lab., P.O. Box 30, State College, Pa.

Chicago (5)—W. B. McClelland, 1601 Cherry St., Park Ridge, Ill.; P. D. Huston, 233 S. Villa Ave., Elmhurst, Ill.

Chile—Chairman to be advised; J. de la Quintana, IBM World Trade Corp., Cassila 3630, Santiago, Chile.

China Lake (7)—L. D. Bryant, Box 333, Naval Ordnance Test Station, China Lake, Calif.; J. E. Colvard, Code 3045, USNOTS, China Lake, Calif.

Cincinnati (4)—J. R. Ebbeler, 7030 Ellen Ave., Cincinnati 39, Ohio; E. J. Emmerling, 5211 Ralph Ave., Cincinnati 38, Ohio.

Cleveland (4)—R. Kazarian, 2031 Lakeview Ave., Rocky River, Cleveland 16, Ohio; J. I. Sheetz, Ohio Bell Telephone Co., 700 Prospect Ave., Rm. 704, Cleveland 15, Ohio.

Colombia—A. Ospina (Acting Chairman), Comando Armado Nal., Bogotá, Colombia; A. S. Ochoa, Calle 90, #19–41, Bogotá 2, D.E., Colombia.

Columbus (4)—F. A. Wolf, 354 Chatham Rd., Columbus 14, Ohio; E. N. Wyler, 109 W. Stafford, Worthington, Ohio.

Connecticut (1)—S. C. Wadhams, 13 Derwen St., Glenbrook, Conn.; P. N. Johnstone, Twin Lakes Rd., North Branford, Conn.

Dallas (6)—T. Prickett, Jr., 805 Clearwater Dr., Richardson, Tex.; C. K. Hager, 2709 Greenbrook Dr., Garland, Tex.

Dayton (4)—R. J. Framme, 316 Claranna, Dayton 9, Ohio; S. Weissman, 805 Eppington Dr., N., Trotwood, Ohio.

Denver (6)—H. S. Johnson, 1241 Monaco Pkwy., Denver 20, Colo.; F. P. Venditti, Denver Res. Inst., Univ. of Denver, Denver 10, Colo.

Detroit (4)—D. V. Stocker, Dept. of Elec. Engrg., Wayne Univ., Detroit 2, Mich.; L. E. Barber, 402 N. Troy St., Royal Oak, Mich.

Egypt—H. M. Mahmoud, 24 Falaki St., Cairo, Egypt; El-Garhi I. El-Kashlan, 46 Suez-Kanal St., Engineering City, Imbaba, Cairo, Egypt.

Elmira-Corning (1)—T. G. Keeton, 611 McDowell Place, Elmira, N. Y.; R. K. Ainey, Westinghouse Elec. Corp., Box 284, Elmira, N. Y.

El Paso (6)—A. M. Rojas H., 2326 Copper St., El Paso, Tex.; C. W. Brown, 325 Encino Drive, El Paso, Tex.

Emporium (4)—J. L. McKain, Sylvan Heights, Emporium, Pa.; T. H. Carlstrom, Sylvania Electric Products, Inc., Emporium, Pa.

Erie (1)—R. S. Page, 1224 Idaho Ave., Erie, Pa.; K. L. Challstrom, Buffalo Rd., R.D. 1, Harborcreek, Pa.

Evansville-Owensboro (5)—K. G. Miles, 2105 East Gum St., Evansville 14, Ind.; F. R. Snyder, 2521 Iraquois Dr., Owensboro, Ky.

Florida West Coast (3)—R. E. Henning, Sperry Microwave Electronics Co., Box 1828, Clearwater, Fla.; C. W. Benfield, 605 First St., S.E., Largo, Fla.

Fort Huachuca (7)—J. W. Virden, 102 Crandel St., For Huachuca, Ariz.; L. J. Knight, 135 Jeffords St., Fort Huachuca, Ariz.

Fort Wayne (5)—C. F. Mason, 1519½ Crescent Ave., Fort Wayne, Inc.; D. W. Von Berg, 4015 Wedgewood Dr., Fort Wayne, Ind.

Fort Worth (6)—S. T. Lanham, Sr., 5017 Vicki, Fort Worth 17, Tex.; M. F. Shepherd, 2324 Clearview, Fort Worth, Tex.

Gainesville (3)—A. D. Sutherland, 1003 N.W. 11 Ave., Gainesville, Fla.; A. T. Raczynski, Sperry Elec. Tube Div., Gainesville, Fla.

Geneva—G. C. Gross, I.T.U., Palais Wilson, Geneva, Switzerland; J. H. Gayer, I.F.R.B., Palais Wilson, Geneva, Switzerland.

Hamilton (8)—F. H. Edwards, United-Carr Fastener Company of Canada, Ltd., 231 Gage Ave., N., Hamilton, Ont., Canada; C. C. Minchel, Canada Westinghouse Co., Elec. Tube Div., Plant 2, Hamilton, Ont., Canada.

Hawaii (7)—E. A. Piety, P.O. Box 2930, Honolulu 2, Hawaii; G. H. Stagner, 525 Lunalilo Home Rd., Honolulu 16, Hawaii.

Houston (6)—L. A. Mullan, Radio Station KTRH, Rice Hotel, Houston 2, Tex.; J. A. Beyer, 5221 Lincrest Lane, Houston 27, Tex.

Huntsville (3)—D. E. Rowe, 8602 Camille Dr., S.E., Huntsville, Ala.; J. A. Power, 4003 Marie St., Apt. 1, Huntsville, Ala.

India—Officers to be advised.

Indianapolis (5)—S. M. Stuhlbarg, 4904 Staughton Dr., Indianapolis, Ind.; R. C. Olsen, 4040 Adams Court, N., Indianapolis, Ind.

Israel—R. R. Gamzon, 11 Rehov Ezra, Rehovoth, Israel; H. Fischler, Weizmann Inst. of Science, Dept. of Electronics, Box 26, Rehovoth, Israel.

Italy—A. Marino, Via Guido d'Arezzo 14, Rome, Italy; G. P. Tarchini, Laboratorio Ricerche Elettr., Via de Parlamento N. 33, Borgolombardo, Milan, Italy.

Ithaca (1)—H. I. Heydt, GE Advanced Elec. Ctr., Tomkins County Airport, Ithaca, N. Y.; M. Hollar, 86 Besmer Rd., Ithaca, N. Y.

Kansas City (6)—F. A. Spies, Bendix Aviation Corp., Box 1159, Kansas City 41, Mo.; K. D. Benedict, 1032 East Alton, Independence, Mo.

Kitchener-Waterloo (8)—B. S. McConachie, Raytheon Canada, Ltd., 61 Laurel St., E., Waterloo, Ont., Canada; W. J. Grey, Raytheon Canada, Ltd., Box 8, 400 Phillip St., Waterloo, Ont., Canada.

Las Vegas (7)—J. H. Jurmain, Edgerton, Germeshausen, Grier, 300 Wall St., Box 1912, Las Vegas, Nev.; L. S. Kreyer, 617 Twin Lakes Dr., Las Vegas, Nev.

Little Rock (6)—R. V. Anders, 5801 Windamere Dr., Little Rock, Ark.; W. C. Allsopp, Jr., Ark. Industrial Electric Co., 5020 Club Rd., Little Rock, Ark.

London (8)—T. W. Stewart, 1 Susan Ave., London, Ont., Canada; R. W. Johnson, 9 Ingleside Place, London, Ont., Canada.

Long Island (2)—J. W. Kearney, Airborne Instruments Lab., Walt Whitman Rd., Melville, L. I., N. Y.; C. H. Doersam, Jr., Potter Instrument Co., Inc., Sunnyside Blvd., Plainview, L. I., N. Y.

Los Angeles (7)—J. J. Guarrera, 17160 Gresham St., Northridge, Calif.; E. E. Ingebretsen, 15435 Tupper St., Sepulveda, Calif.

Louisville (5)—H. T. Smith, Kentucky Rural Elec. Co-op Corp., 4515 Bishop

* Numerals in parentheses following sections designate region number. First name designates Chairman; second name Secretary.

K$_a$-BAND KLYSTRON OSCILLATOR, QKK 834, shown with 90° (above) or 180° (right below) positioning of tuner. **Above photo is actual size.**



New klystrons hold characteristics in grueling aerospace environments

K$_a$- and K-band tubes are tunable from 34.0—35.6 and 23.5—24.5 kMc

Now, Raytheon combines the advantages of small size, extreme ruggedness, thermal stability, and smooth wide-range tunability in a 20mW reflex klystron.

The new QKK 834 for K$_a$ band and QKK 923 for K band are all ceramic and metal tubes with typical electronic tuning range of 110 Mc. The tuner, utilizing a sapphire rod, can be specified for positioning anywhere on the circumference of the resonator at least 90 degrees from output flange (see illustrations above). Write today for detailed technical data or application service to Microwave & Power Tube Division, Raytheon Company, Waltham 54, Massachusetts. In Canada: Waterloo, Ontario.

QKK 834, QKK 923— GENERAL CHARACTERISTICS	
Power Output	20 mW (nominal)
Frequency	34-35.6*; 23.5-24.5† kMc
Resonator Voltage	400 V
Reflector Voltage Range	—65 to —175V
Temperature Coefficient	± 0.5 Mc/°C
Cooling	convection (no blower needed)
Overall Dimensions	1 5/8 x 1 1/16 x 2 in.*

*QKK 834 †QKK 923

RAYTHEON COMPANY

MICROWAVE AND POWER TUBE DIVISION

RAYTHEON

Lane, Louisville 18, Ky.; E. L. Marven, Sr., 811 Camden Ave., Louisville 15, Ky.

Lubbock (6)—J. P. Craig, Rte. 4, Box 210, Lubbock, Tex.; E. F. Kilcrease, 2114 38 St., Lubbock, Tex.

Miami (3)—F. R. Macklin, 325 Malaga Ave., Coral Gables, Fla.; G. A. Liedholz, 6060 S.W. 114 St., Miami 56, Fla.

Milwaukee (5)—T. H. Houle, 1000 S. 56 St., West Allis 14, Wis.; K. J. Schlager, 1519 N. 118 St., Wauwatosa 13, Wis.

Mobile (3)—T. F. Harbin, 4279 Taurus Dr., Mobile Ala.; E. G. Schone, Box 4102, Mobile, Ala.

Montreal (8)—H. H. Schwartz, 5212 King Edward Ave., Montreal 29, Que., Canada; A. Breton, Ecole Polytechnique, 2500 Ave. Guyard, Montreal 26, Que., Canada

Newfoundland (8)—M. D. MacGray, Canadian Marconi Co., 3 Prescott St., St. John's, Newf., Canada; F. A. Mulloy, 55 Calver Ave., St. John's, Newf., Canada.

New Orleans (6)—G. Allen, 4239 St. Charles Ave., Apt. C, New Orleans 15, La.; N. R. Landry, 6079 Louisville St., New Orleans 24, La.

New York (2)—H. W. Pollack, 300 Lennox Road, Brooklyn, N. Y.; E. Schutzman, College of Engrg., New York University University Heights, New York 53, N. Y.

North Carolina (3)—A. B. MacIntyre, Stagecoach Rd., Chapel Hill, N. C.; H. A. Voorhees, 1015 Wendover Circle, Winston-Salem, N. C.

Northern Alberta (9)—L. N. Donovan, 24 Birch Dr., Box 136, St. Alberta, Alta., Canada; W. E. Cunningham, 10265 Princess Elizabeth Ave., Edmonton, Alta., Canada.

Northern New Jersey (2)—H. S. Wertz, 111 Parsonage Rd., Short Hills, N. J.; M. E. Levine, Tung-Sol. Electric, Inc., 545 N. Arlington Ave., East Orange, N. J.

Northwest Florida (3)—F. J. Sites, 29-B Boatner Dr., Eglin Village, Eglin AFB, Fla.; H. G. Wise, Box 878, Fort Walton Beach, Fla.

Oklahoma City (6)—E. Black, 1701 N. W. 35 St., Oklahoma City 18, Okla.; J. M. Ashworth, 3934 N. W. 34 St., Oklahoma City 12, Okla.

Omaha-Lincoln (5)—J. A. Rogers, 3815 Marcy St., Omaha 5, Neb.; C. Hyde, 312 Ferguson Hall, Univ. of Neb., Lincoln 8, Neb.

Orlando (3)—J. R. Matzinger, 1825 Whitehall Dr., Winter Park, Fla.; C. E. McGinnis, 1720 Shawnee Trail, Maitland, Fla.

Ottawa (8)—W. R. Conway, 2075 Woodcrest Rd., Ottawa 1, Ont., Canada; S. G. Jones, 1910 Haig Dr., Ottawa 1, Ont., Canada.

Philadelphia (3)—R. M. Showers, Moore School of Elec. Engrg., 200 S. 33 St., Philadelphia 4, Pa.; P. A. Lathrop, 19 Sweetgum Rd., Levittown, Pa.

Phoenix (7)—H. R. Hyder, III, 2523 N. 57 St., Phoenix, Ariz.; R. K. Peterson, 2034 W. Rancho Dr., Phoenix 15, Ariz.

Pittsburgh (4)—R. I. Van Nice, 112 Delaware Court, Glenshaw, Pa.; R. P. O'Shea, Rear 125 Woodvale Ave., Johnstown, Pa.

Portland (7)—M. L. Morgan, 12907 S.W. 62 Ave., Portland 19, Ore.; C. H. Moulton, 1625 S.W. 87 Ave., Portland 1, Ore.

Princeton (2)—R. D. Lohman, RCA, Somerville, N. J.; O. E. Dow, RCA Labs., Princeton, N. J.

Quebec (8)—R. M. Vaillancourt, 638 Ave. Mon Repos, Ste. Foy, Quebec 10, Canada; K. A. Laurie, 775 Calixa LaVallee, Apt. 15, Quebec 6, Que., Canada.

Regina (8)—S. K. Smith, c/o Saskatchewan Gov't. Tel., 2350 Albert, Regina, Sask., Canada.; G. H. Beuker, 2808 Borden St., Regina, Sask., Canada.

Rio de Janeiro—J. A. Wiltgen, Caixa Postal 450, Rio de Janeiro, D. F., Brazil; C. J. Chapin, c/o Riggs National Bank, DuPont Circle Branch, 1913 Massachusetts Ave., N. W., Washington 6, D. C.

Rochester (1)—J. L. Wheeler, 535 Rondo Lane, Webster, N. Y.; D. W. Healy, Jr., Univ. of Rochester, River Campus Station, Rochester 20, N. Y.

Rome-Utica (1)—R. A. Zachary, Jr., 11 Arbor Dr., New Hartford, N. Y.; W. P. Bethke, 1806 N. James St., Rome, N. Y.

Sacramento (7)—A. O. Rohde, 3160 Adams Rd., Sacramento 25, Calif.; J. C. Bissett, 8717 Jonnie Way, Fair Oaks, Calif.

St. Louis (6)—G. E. Barnard, 639 N. 69 St., East St. Louis, Ill.; E. A. Kuhlman, 9020 Cardinal Ter., Brentwood 17, Mo.

Salt Lake City (7)—C. L. Alley, Elec. Engrg. Dept., Univ. of Utah, Salt Lake City, Utah; J. E. Dalley, 3920 S. 1380 E., Salt Lake City 17, Utah.

San Antonio-Austin (6)—W. L. Donaldson, 129 El Cerrito Circle, San Antonio 12, Tex.; C. R. Graf, 207 Addax Dr., San Antonio 1, Tex.

San Diego (7)—D. G. De Haas, 1923 Cable St., San Diego 7, Calif.; D. Proctor, 2120 Rexford Dr., San Diego 5, Calif.

San Francisco (7)—S. F. Kaisel, Microwave Electronics Corp., 4061 Transport St., Palo Alto, Calif.; Acting Secretary: A. T. Waterman, Jr., Electronics Research Lab., Stanford University, Stanford, Calif.

Schenectady (1)—T. G. Mihran, G. E. Research Lab., Box 1088, Schenectady, N. Y.; F. L. Ellert, G. E. Co., Bldg. 37, Rm. 578, 1 River Rd., Schenectady, N. Y.

Seattle (7)—W. J. Siddons, 6539 39 St., N.E., Seattle 15, Wash.; M. R. Paisley, 17805 Fourth Ave., S.W., Seattle 66, Wash.

Shreveport (6)—E. J. Culling, 3252 Sarah St., Bossier City, La.; E. C. Strickland, 2914 Bolch St., Shreveport, La,

South Bend-Mishawaka (5)—H. W. Vogtmann, Bendix Mishawaka Div., 400 S. Beiger St., Mishawaka, Ind.; N. O. Kindt, 50635 Dresden Dr., South Bend 17, Ind.

South Carolina (3)—P. A. McMasters, 5809 Moore St., North Charleston, S. C.; H. L. Hunter, 49 Fort Dr., Rt. 6, Box 423, North Charleston, S. C.

Southern Alberta (8)—R. E. Smith, 1507–20 A St., N.W., Calgary, Alta., Canada; E. T. Ball, 37 Connaught Dr., Calgary, Alta., Canada.

Syracuse (1)—G. F. Platts, 101 Iroquois Lane, Liverpool, N. Y.; G. M. Kirkpatrick, 202 David Dr., N. Syracuse 12, N. Y.

Tokyo—Isaac Koga, 254 8-Chome, Kami-Meguro, Tokyo, Japan; Fumio Minozuma, 16 Ohara-Machi, Meguro-Ku, Tokyo, Japan.

Toledo (4)—R. N. Hanna, 1924 Glencairn Ave., Toledo 14, Ohio; H. K. Seike, 2920 Kendale Dr., Toledo 6, Ohio.

Toronto (8)—G. T. Quigley, Philips Industries, Ltd., Vanderhoof Ave., Leaside, Toronto 17, Ont., Canada; F. A. Ford, Canadian GE Co., Ltd., 830 Lansdowne Ave., Toronto 4, Ont., Canada.

Tucson (7)—R. L. Patterson, 5418 E. Second St., Tucson, Ariz.; J. L. Dunn, 725 W. Comobabi Dr., Rt. 6, Box 319C, Tucson, Ariz.

Tulsa (6)—P. M. Ferguson, 1133 N. Lewis, Tulsa 10, Okla.; D. P. Hearn, 748 S. 87th E. Ave., Tulsa 12, Okla.

Twin Cities (5)—H. D. Shekels, 1942 Beechwood, St. Paul 16, Minn.; A. L. Martin, Jr., 8714 Second Ave., S., Bloomington 20, Minn.

Vancouver (8)—H. A. Hoyles, 1846 Beaulynn Pl., Westlynn Park, North Vancouver, B. C., Canada; T. D. Cushing, Lenkurt Elec. Co. of Canada, N. Barnaby P.O., Vancouver, B. C., Canada.

Virginia (3)—G. L. Harvey, Sperry Piedmont Co., Rte. 29, Charlottesville, Va.; E. J. Brauner, 1412 Brookville La., Lynchburg, Va.

Washington (3)—B. S. Melton, 3921 Mayfair Lane, Alexandria, Va.; C. L. Engleman, Engleman and Co., Inc., 2480 16 St., N.W., Washington 9, D. C.

Western Massachusetts (1)—R. H. Shupe, 52 Elaine Dr., Pittsfield, Mass.; W. B. Conover, General Electric Co., 100 Plastics Ave., Pittsfield, Mass.

Western Michigan (4)—R. V. Hammer, 1961 Leahy St., Muskegon, Mich.; J. F. Giardina, 1528 Ball, N.E., R. 4, Grand Rapids 5, Mich.

Wichita (6)—R. L. Schrag, Elec. Engrg. Dept., Univ. of Wichita, Wichita 8, Kan.; W. G. Louie, 758 Mansfield Drive, Wichita 7, Kan.

Williamsport (5)—J. J. De Gan, 117 Eldred St., Williamsport, Pa.; T. P. Warne, 324 Tinsman Ave., Williamsport, Pa.

Winnipeg (8)—P. F. Windrick, 669 Oxford St., Winnipeg 9, Man., Canada; R. I. Punshon, Canadian Broadcasting Corp., 540 Portage Ave., Winnipeg, Man., Canada.

IN ELECTRICAL CONNECTORS, TOO

Craftsmanship produces enduring quality

For over three centuries, the Stradivarius has provided unmatched violin quality, reflecting the integrity of its maker. Similarly, companies today achieve their goals—or fall short—through varying degrees of quality and integrity.

Bendix® Electrical Connectors, made by the Scintilla Division, are recognized by their users as products of the highest quality—with no premium in cost. If connector quality interests you, write us at Sidney, N. Y.

Scintilla Division

THE Bendix CORPORATION

Canadian Affiliate: Aviation Electric, Ltd., 200 Laurentien Blvd., Montreal 9, Quebec. Export Sales & Service: Bendix International, 205 E. 42nd St., New York 17, N. Y.

Subsections

Buenaventura (7)—L. E. Wood, 630 W. Highland Dr., Camarillo, Calif.; J. A. Frederick, 455 Corsicana Dr., Oxnard, Calif.

Burlington (5)—H. L. Clark, 2549 Surrey Rd., Burlington, Iowa; E. A. Kruse, 314 Cottage Grove, West Burlington, Iowa.

Catskill (2)—C. R. Eickhorn, Jr., 29 Ratterman Rd., Woodstock, N. Y.; R. A. Heassler, R.D. 5, Box 52, Kingston, N. Y.

Crescent Bay (7)—H. Iams, 1325 Goucher St., Pacific Palisades, Calif.; H. H. Wilson, 16623 Gilmore St., Van Nuys, Calif.

East Bay (7)—A. J. Stripeika, 2759 Miranda Ave., Alamo, Calif.; J. T. Lavrischeff, 7029 Cutting Blvd., El Cerrito, Calif.

Eastern North Carolina (3)—W. J. Speed, 3028 E. Rothgeb Dr., Raleigh, N. C.; W. H. Horne III, Rt. 1, Raleigh, N. C.

Fairfield County (1)—T. J. Calvert, 11 Bedford Ave., Norwalk, Conn.; H. F. Wischnia, 50 De Leo Dr., Stamford, Conn.

Lancaster (3)—Y. Uyeda, 1924 Pine Dr., Lancaster, Pa.; R. M. Matheson, 2728 Brookfield Rd., Lancaster, Pa.

Las Cruces-White Sands Proving Ground (6)—H. Coleman, Rte. 1, Box 4B, Las Cruces, N. M.; Secretary to be advised.

Lehigh Valley (3)—J. H. Volk, 411 Grant St., Easton, Pa.; A. I. Larky, Lehigh Univ., Dept. of Elec. Engrg., Bethlehem, Pa.

Memphis (3)—C. Ray, Dept. of Neurosurgery, Baptist Memorial Hospital, Memphis 3, Tenn.; Brother I. J. Haas, Christian Brothers College, Memphis 4, Tenn.

Merrimac Valley (1)—D. D. Sagaser, Bell Telephone Labs., 1600 Osgood St., North Andover, Mass.; W. Banton, 21 Walnut St., North Andover, Mass.

Mid-Hudson (2)—R. J. Domenico, IBM Research Lab., Poughkeepsie, N. Y.; W. Cadden, 67 Round Hill Rd., Poughkeepsie, N. Y.

Monmouth (2)—P. E. Griffith, 557 Cedar Ave., W. Long Branch, N. J.; V. E. Reilly, 25 Lenox Rd., Eatontown, N. J.

Nashville (3)—G. P. McAllister, 2923 Twin Lawn Dr., Nashville 14, Tenn.; W. B. Kincaid, Jr., 210 Graeme Dr., Nashville 14, Tenn.

New Hamsphire (1)—R. O. Goodwin, 130 Colgate Rd., Nashua, N. H.; J. Butler, Groton Rd., R.F.D. 2, Nashua, N. H.

Northern Vermont (1)—F. J. M. Sichel, 35 Henderson Terrace, Burlington, Vt.; W. C. Chase, WDEV, 9 Stowe St., Waterbury, Vt.

Orange Belt (7)—J. F. McElwee, 455 N. Live Oak Ave., Glendora, Calif.; A. G. Holtum, Jr., 941 E. Marylind, Claremont, Calif.

Palm Beach (3)—C. E. Cronin, 544 Ebb Tide Dr., North Palm Beach Fla.; A. S. Baran, 301 Bayside Rd., Lake Worth, Fla.

Panama City (3)—J. F. Ault, 1305 Cornell Dr., Panama City, Fla.; R. C. Lowry, 2342 Pretty Bayou Dr., Panama City, Fla.

Pasadena (7)—F. L. Mosely, 535 S. Wilson Ave., Pasadena 5, Calif.; J. C. Crosby, 9018 Youngdale, San Gabriel, Calif.

Pikes Peak (6)—A. O. Behnke, 204 Westcott Ave., Colorado Springs, Colo.; Secretary to be advised.

Reading (3)—H. S. Hauck, 216 Jameson Pl., Reading, Pa.; R. M. LeLacheur, 1637 Dauphin Ave., Wyomissing, Pa.

Richland (7)—R. A. Harvey, 657 Cottonwood Dr., Richland, Wash.; D. D. Bisby, 703 Catskill, Richland, Wash.

San Fernando Valley (7)—R. L. Halpern, 3315 Longridge Ave., Sherman Oaks, Calif.; J. L. Brown, 17408 Mayflower Dr., Granada Hills, Calif.

Santa Ana (7)—J. E. Elms, 4615 Fairfield Dr., Corona del Mar, Calif.; K. Goodman, 2567 Columbia Dr., Costa Mesa, Calif.

Santa Barbara (7)—J. E. Hacke, Box 535, Santa Barbara, Calif.; S. R. Boyle, Defense Electronics Div., General Electric Co., 735 State St., Santa Barbara, Calif.

Southwestern Ontario (8)—W. A. Ruse, Bell Telephone Co., 1149 Goyeau St., Windsor, Ont., Canada; G. L. Virtue, 619 Lounsborough Rd., Sandwich-South, Windsor, Ont., Canada.

Victoria (8)—C. L. Madill, 2786 Murray Dr., Victoria, B. C., Canada; A. M. Baxter, 620 Rockland Place, Victoria, B. C., Canada.

Westchester County (2)—M. Ziserman, 26 Edgewood Rd., Hartsdale, N. Y.; M. L. Brailey, 12 Dupont Ave., White Plains, N. Y.

Western North Carolina (3)—J. I. Barron, Southern Bell T&T Co., Box 240, Charlotte, N. C.; T. C. Livingston, 926 N. Sharon Amity Rd., Charlotte, N. C.

1-6 Commutator assembly—analog input

7 Digital input processor

8 Housing

9 Programmer

10 Low-level amplifier and super multiplexers

11-13 Analog to digital converter

14 Automatic, drift and gain compensation networks

15 Output filter

16 Power converter



NOW PCM TELEMETRY SYSTEMS . . . for millivolt data inputs!

Now on short delivery schedules . . . Texas Instruments offers high accuracy pulse code modulation telemetry systems for millivolt, high level or combination inputs.

The complete PCM system shown is a lightweight, 0.9 cubic foot package that multiplexes and encodes 196 analog channels to eight-bit accuracy and processes six digital data inputs. Output information rate is 173,000 bits per second. The system's unique zero and full scale digital servo loop corrects system drift and gain change to assure overall system accuracy of ±0.4% in missile environments. Precision low-level electronic commutation is accomplished with less than ±20 microvolt offset error over a 0 to 70°C temperature range.

PCM encoding and decoding is only one of several advanced data link projects at TI. Others include millivolt oscillators, signal conditioners, solid-state transmitters, FM/FM systems, advanced microwave components, programmers, command and control systems, and space electronics. For detailed information on TI's capability to meet your particular requirements, contact MARKETING DEPARTMENT.

APPARATUS DIVISION
PLANTS IN DALLAS
AND HOUSTON, TEXAS

TEXAS INSTRUMENTS
INCORPORATED
6000 LEMMON AVENUE
P. O. BOX 6015 DALLAS 22, TEXAS

NOW . . . IN ONE INSTRUMENT

ANALOG DISPLAYS PLUS DIGITAL READOUT

DIGITAL READOUT
of time differences to 50 picoseconds.

DIGITAL READOUT
of pulse risetimes to one-half nanosecond.

DIGITAL READOUT
of pulse amplitudes to 2 millivolts peak-to-peak.

TEKTRONIX DIGITAL READOUT OSCILLOSCOPE TYPE 567

The Tektronix Type 567 Oscilloscope adds digital readout convenience to your dual-trace applications. It presents simultaneously an analog display on the 5-inch crt with a digital presentation on the automatic computing programmer. It enables you to select and intensify the actual points—for the automatic normalization—on the crt waveforms which you wish to measure. Then you merely read directly the corresponding up-to-4-digit decimal units of actual measurement. Indicators light to designate the readout status—whether *in* the preset-limit range, *below* it, or *above* it. You set the program *once* for all successive similar measurements.

To achieve this faster and simpler approach to precision measurement, the Type 567 incorporates many features *new* to an oscilloscope. In the automatic computing programmer, for example, some of these new features include: positionable measurement-reference zones, automatic normalization, zone-intensity markers, automatic and manual start-timing and stop-timing systems, preset-limit selector and indicators, and provision for external programming. These features—and others in the two sampling plug-in units and the oscilloscope itself—enable the new Type 567 to greatly increase your measurement proficiency.

You can measure pulse amplitudes and time increments between percentages of selected amplitude levels *on an absolute or relative basis* faster and with more accuracy—especially in sustained testing programs. In addition, you can also measure pulse amplitudes and time increments on differential signals between A and B inputs.

In a typical application such as transistor-switching-time measurements, you can read directly such characteristics as the delay, rise, storage, and fall times; the total turn-on and turn-off times; the width of pulse A and pulse B; and time and amplitude between two selected points on either or both waveforms. You know immediately by the digital presentation and indicator lights whether or not the item tested has met specifications.

Type 567 Readout Oscilloscope (without plug-ins).....$700
5-inch rectangular crt. 3.3-kv accelerating potential. 8-cm by 10-cm display area. Amplitude Calibrator. Edge-lighted graticule. Separate regulated heater supply. Electronically-regulated dc-supply—powers plug-in units, operates between 105-125 volts or 210-250 volts, 50 to 60 cycles.

Type 3S76 Sampling Dual-Trace Unit.....$1100
Identical Channels with Independent Controls—for positioning, dc-offsetting, attenuating, inverting input signals as desired. **Risetime**—less than one-half nanosecond. **Calibrated Sensitivity**—from 2 mv/div to 200 mv/div in 7 steps, also continuously variable between steps uncalibrated. **Noise**—less than 2 mv peak-to-peak (referred to input). **Operating Modes**—either channel separately, dual-trace, algebraic additions, differential output (with common mode rejection ratio approximately 50:1), lissajous (A vertical, B horizontal). **DC-Offset Voltage**—for measuring millivolt signals in the presence of a substantial dc component (offset voltage monitorable at front panel). **Internal Triggering**—built-in trigger takeoffs and delay lines internally connected to Sampling Sweep Unit. Sweep Unit receives a nominal one-fifth amplitude signal from trigger takeoff.

Type 3T77 Sampling Sweep Unit $650
Calibrated Sweep Range—for equivalent sweep times from 0.2 nsec/div to 10 μsec/div in 15 steps, also continuously variable between steps uncalibrated, and to approximately .007 nsec/div. **10X Horizontal Magnifier. Single-Sweep Provision. 10 or 100 Samples-Per-Division. Sweep Delay Through 100 Nanoseconds. Manual Control of Scanning Function**—for XY or YT Recorders. **Internal or External Triggering**—either positive or negative, 5 mv sensitivity. (Internal 25 mv signal in *Type 3S76* results in 5 mv at *3T77*.)

Type 3D1 Digital Plug-In Unit $2500
Internal Input—from horizontal and vertical plug-in units. **In-Line Nixie*Readouts**—with up-to-4-digit decimal units of actual measurement. **Measurement-Reference Zone**—from fixed zero to 100% zone positionable over the sweep range . . . for each trace. **Automatic Normalization**—for establishing pulse amplitude or time measurements independent of dc position or pulse amplitude. **Zone-Intensity Markers**—for indicating the position of the reference zone in relation to the waveform and also the actual start-to-stop interval . . . for each trace. **Automatic Start-Timing and Stop-Timing Systems**—for controlling start and stop . . . on any of 7 calibrated % steps on either trace . . . or any combination of percentage, amplitude, polarity, first or second pulse slope or input channels A or B. **Manual Timing**—for setting the start-timing and stop-timing at selected points on the displayed waveforms. **Display-Time Control**—for varying amount of display time needed to take readings or operate associated equipment. **Preset-Limit Selector**—for setting the upper and lower limits of the readout digits. **Limit-Selector Indicators**—for designating measurements occurring *below*, *in*, or *above* the preset-limit range. **Provision for External Programming**—for sequencing automatically between various measurement programs, or for other applications.

* Registered by Burroughs

U.S. Sales Prices f.o.b. Beaverton, Oregon

To arrange a demonstration of this compact and complete Digital Readout Oscilloscope, please call your Tektronix Field Engineer.

Tektronix, Inc. *P. O. BOX 500 · BEAVERTON, OREGON* *Mitchell 4-0161 · TWX—BEAV 311 · Cable: TEKTRONIX*

TEKTRONIX FIELD OFFICES: Albuquerque, N. Mex. • Atlanta, Ga. • Baltimore (Towson) Md. • Boston (Lexington) Mass. • Buffalo, N.Y. • Chicago (Park Ridge) Ill. • Cleveland, Ohio • Dallas, Texas • Dayton, Ohio • Denver, Colo. • Detroit (Lathrup Village) Mich. • Endicott (Endwell) N.Y. • Greensboro, N.C. • Houston, Texas • Indianapolis, Ind. • Kansas City (Mission) Kan. • Los Angeles (Culver City) Area • Los Angeles (Glendale) Area • Los Angeles (San Fernando) Area • Los Angeles (Santa Monica) Area • Los Angeles (Whittier) Area • Orlando, Fla. • Philadelphia, Pa. • Phoenix (Scottsdale) Area • Portland, Oreg. • Poughkeepsie, N.Y. • San Diego, Calif. • San Francisco, Calif. Area (Lafayette, Palo Alto) • Seattle, Wash. • Syracuse, N.Y. • Toronto (Willowdale) Ont., Canada • Washington, D.C. (Annandale, Va.).

ENGINEERING REPRESENTATIVES: Kentron Hawaii Ltd., Honolulu, Hawaii. Tektronix is represented in twenty-five overseas countries by qualified engineering organizations.

European and African countries, the countries of Lebanon and Turkey, please contact TEKTRONIX INTERNATIONAL A.G., Terrassenweg 1A, Zug, Switzerland, for the name of your local engineering representative. Other Overseas areas, please write or cable directly to Tektronix, Inc., International Marketing Department, P. O. Box 500, Beaverton, Oregon, U.S.A. Cable: TEKTRONIX.

SEE THE TYPE 567 AND OTHER NEW TEKTRONIX INSTRUMENTS AT NEREM, BOOTHS 7 & 8

IS *YOUR* COMPANY ON THE *OFFENSE* FOR *DEFENSE?*

***SIGNAL** is your introduction to the men who control the growing $4 billion dollar government radio-electronics spending*

Never before have our armed forces so badly needed the thinking and products of the electronics industry. Advertising in SIGNAL, the official journal of the *Armed Forces Communications and Electronics Association*, puts you in touch with almost 10,000 of the most successful men in the field—every one a prospect for your defense products!

Share in the defense and the profits! Company membership in the AFCEA, with SIGNAL as your spokesman, puts you in touch with government decision-makers!

SIGNAL serves liaison duty between the armed forces and industry. It informs manufacturers about the latest government projects and military needs, while it lets armed forces buyers know what *you* have to offer to contribute to our armed might. SIGNAL coordinates needs with available products and makes developments possible.

But SIGNAL is more than just a magazine. It's *part of an over-all plan!*

A concerted *offensive* to let the government, which has great faith in industry and the private individual producer, know exactly what's available to launch its far-sighted plans. Part of this offensive is the giant AFCEA National Convention and Exhibit (to be held next year in Washington, D.C., June 12-14). Here, you can *show* what you have to contribute directly to the important buyers. Your sales team meets fellow manufacturers and military purchasers and keeps "on top" of current government needs and market news.

Besides *advertising* in SIGNAL which affords year-round exposure by focusing your firm and products directly on the proper market . . . besides *participation* in the huge AFCEA National Convention and Exhibit . . the over-all plan of company membership in the AFCEA *gives your firm a highly influential organization's experience and prestige to draw upon.*

As a member, you join some 175 group members who feel the chances of winning million dollar contracts are worth the relatively low investment of time and money. On a local basis, you organize your team (9 of your top men with you as manager and team captain), attend monthly chapter meetings and dinners, meet defense buyers, procurement agents and sub-contractors. Like the other 59 local chapters of the AFCEA, your team gets to know the "right" people.

In effect, company membership in the AFCEA is a "three-barrelled" offensive aimed at putting your company in the "elite" group of government contractors —the group that, for example in 1957, for less than $8,000 (for the full AFCEA plan) made an amazing total of *459.7 million dollars!*

This "three-barrelled" offensive consists of

(1) Concentrated advertising coverage in SIGNAL, the official publication of the AFCEA;

(2) Group membership in the AFCEA, a select organization specializing in all aspects of production and sales in our growing communications and electronics industry; and

(3) Attending AFCEA chapter meetings, dinners and a big annual exposition for publicizing your firm and displaying your products.

If *you're* in the field of communications and electronics . . . and want prestige, contacts and exposure . . . let SIGNAL put your company on the *offense* for *defense!* Call or write for more details—now!

SIGNAL

Wm. C. Copp & Associates
72 West 45th Street,
New York 36, New York
MUrray Hill 2-6606
Boston · Chicago · Minneapolis · Los Angeles · San Francisco

BPA

Professional Group Meetings

Antennas and Propagation Microwave Theory and Techniques

Orange Belt Subsection—May 25

"Recent Advances in Electromagnetic Theory," L. J. Chu, MIT, Boston, Mass.

Bio-Medical Electronics

Metropolitan New York—May 18

"Problems and Potentials of Ultrasonics in Dentistry," L. Zach, DDS, and Dr. L. Balamuth, NYU College of Dentistry.

"Microscopic and Submicroscopic Pressure-Indicating Devices," H. Zinsser, M.D., Columbia University College of Physicians and Surgeons.

Electron Devices

Metropolitan New York—May 4

"Optical Masers," Dr. A. Schawlow, Bell Telephone Labs.

Information Theory

Washington, D. C.—May 31

"Statistical Communication Theory Involving Sequential Detection Theory and Applications," Dr. H. Blasbalg, IBM Communication Systems Center, Rockville, Md.

Instrumentation

Los Angeles—April 12

"Instrumentation and Data-Reduction System Compatibility," W. F. Kamsler, Epsco West, Anaheim, Calif.

Vehicular Communications

Los Angeles—June 15

"The Use of Level Controlling Devices in the Radio Telephone Service," L. E. Getgen, Lenkurt Electric Co., San Carlos, Calif.

Los Angeles—May 18

"The Mobile Radio System and Communication Operation of the Iron Ore Company of Canada," K. Haase, IT&T, San Fernando, Calif.

Metropolitán New York—May 16

"New Concept in Electronic Aids to Motor Vehicles," F. C. Becker, General Motors Res. Lab., Warren, Mich.

Use Low Cost Allen-Bradley Type J Pots for Constant Impedance Attenuators



Allen-Bradley dual and triple Type J variable resistors are widely used in attenuators in electronic circuitry because they provide dependably smooth and uniform attenuation plus constant characteristic impedance.

Stability, high wattage, long life, ideal uniformity, plus remarkable compact structure are combined in the Type J to assure top performance. The solid resistance element—made by A-B's exclusive hot molding process—provides smooth control at all times.

With this precise control over the resistance-rotation characteristics during production, A-B attenuators have a consistently uniform attenuation that approaches calibration accuracy . . . and the characteristic impedance can be held to ±10% over *entire* rotation—*end* to *end*. The virtually infinite resolution eliminates the definite incremental steps of wire-wound units, while freedom from inductance insures excellent high frequency response. For full details on Type J variable resistors, send for Publication 6024.

Allen-Bradley Co., 222 W. Greenfield Ave., Milwaukee 4, Wis. • In Canada: Allen-Bradley Canada Ltd., Galt, Ont.

8-61-R

ALLEN-BRADLEY

QUALITY ELECTRONIC COMPONENTS

Non-Linear Systems, Inc. designs first digital voltmeter to satisfy critical standards for missile work

Digital voltmeters — originated by NLS — permit rapid and accurate voltage measurements. New Series 20 unit — with one plug-in decade board removed — shows the use of Allen-Bradley fixed resistors.

Resistor Failures UNHEARD OF

...naturally, NLS uses ALLEN-BRADLEY hot molded resistors

To satisfy the high standards of consistent accuracy and reliability demanded for missile and weapons checkout, Non-Linear Systems, Inc., developed this digital voltmeter. It uses scores of Allen-Bradley fixed resistors. (For example, the latest Series 20 unit, shown above, contains about 1,000 in each instrument.) "In the selection of A-B resistors," says NLS, "quality and availability have never been a problem."

A-B resistors have such consistently uniform electrical characteristics that their performance can be accurately predicted over long periods of time under various operating conditions . . . with *complete freedom* from catastrophic failure while in service! The hot molding process used exclusively by A-B is the reason for this uniformity and reliability.

To obtain this same measure of superior performance for your equipment, always insist on Allen-Bradley quality fixed resistors available in various types. For full details, send today for your copy of Technical Bulletin 5000 or Publication 6024. Write to: Allen-Bradley Co., 222 W. Greenfield Ave., Milwaukee 4, Wis. In Canada: Allen-Bradley Canada Ltd., Galt, Ontario.

ALLEN-BRADLEY
Hot Molded Resistors
ACTUAL SIZE

Hot molded composition resistors are available in all standard EIA and MIL-R-11 resistance values and tolerances.

**Pending MIL Spec Assignment*

ALLEN-BRADLEY

QUALITY ELECTRONIC COMPONENTS

8-61-E

Industrial Engineering Notes*

Military and Space

The Pentagon has consolidated the advisory services carried out by the Advisory Group on Electron Tubes and the Advisory Group on Electronic Parts into a single organization called the Advisory Group on Electron Devices.

The group, comprising scientists and engineers specializing in electron devices, will advise the Director of Defense Research and Engineering on "all phases of research and development devices (active and passive microwave devices, high and lower power non-microwave devices, special electron devices, and conventional passive devices) whether undertaken separately, as part of equipment and systems contracts, or as part of production engineering measures or manufacturing methods contracts."

The advisory group's specific functions, as spelled out in DOD Instruction 5129.39, are to:

1. Survey and evaluate electron device research and development programs, both within and outside the Department of Defense.

2. Review and evaluate projects and programs in its field of interest, including those pertaining to the Mutual Weapons Development Program.

3. Provide technical advice on a continuing basis regarding long-range supporting research and development programs for the Department of Defense, with particular attention to programs which will reduce the lead time required for the development of devices to meet future equipment and systems needs.

4. Provide advice on insuring that the present and planned electron device development programs of the Military Departments reflect equipment and systems requirements and that there is a proper balance between these development programs and the long-range supporting research program.

5. Provide advice on insuring that the long-range program is designed to make available the technology which will be needed to meet planned equipment and systems requirements.

6. Advise of significant advances or discoveries in new areas, or unanticipated difficulties encountered, in the electron device field which may affect to an appreciable degree the availability dates of major equipment and weapons systems under development or being planned.

7. Provide a medium for the interchange of technical research and development information within the Department of Defense, interested Government agencies and contractors.

The group will also conduct a continuing long-range supporting research program for electron devices. A report to the R&E Director on its activities will be required at least once a year.

Industry Marketing Data

The Business and Defense Services Administration, U. S. Department of Commerce, announced last week that the country-by-country telecommunications survey of Latin America initiated earlier this year to determine actual and potential markets for U. S. telecommunications producers has been partially completed. The survey covered Trinidad, Mexico, Jamaica, Surinam, Uruguay, Paraguay, Venezuela, Argentina, and Bolivia. BDSA is not issuing a formal publication, but is prepared to make the available information on these countries accessible to American producing companies interested in or engaged in exports of communications equipment, the agency said.

Electronics Exports

E. MacDonald Nyhen, Acting Director, of the Electronics Division of the Business and Defense Services Administration, predicted that electronics industry exports would total about $600 million this year in comparison with about $483 million for 1960. He said last year's foreign business and overseas sales expected for 1961 could be rated as "good accomplishment" by the industry, but that the industry's foreign sales record "should be much better."

Definition of Electronics Industries

For the purpose of defining the scope of the Electronic Industries Association and its several divisions, the EIA Board of Directors on September 14, 1961, adopted the following definitions:

Electronics is that branch of science and technology which deals with the study, application, and control of the phenomena of conduction of electricity in a vacuum, in gases, in liquids, in semiconductors and in conducting and super-conducting materials.

Electronic products consist of materials, parts, components, sub-assemblies and equipment which employ the principles of electronics in performing their major functions. These products may be used as instruments and controls in communication, detection, amplification, computation, inspection, testing, measurement, operation, recording, analysis, and other functions employing electronic principles.

Electronic industries comprise industrial organizations engaged in the manufacture, design and development, and/or substantial assembly of electronic equipment, systems, assemblies, or the components thereof.

* The data on which these Notes are based were selected by permission from *Weekly Report*, issues of August 28 and September 19, 1961, published by the Electronic Industries Association, whole helpfulness is gratefully acknowledged.

when

you want to amplify microvolt-level data signals with 0.1% accuracy... and 2μv stability... from DC to 40 KC...

Choose a KIN TEL Wideband DC Amplifier

The KIN TEL 112A simplifies the design of data measurement systems, offers more bandwidth and accuracy, reduced maintenance, and none of the capacitive balance problems inherent in AC carrier equipment. Drift <2 μv for hundreds of hours. Gain is 20 to 2000. Gain accuracy is 0.5%, can be set to 0.01% on individual gain steps. Output is ±45 volts and up to 40 ma, bandwidth 40 kc, input impedance 100,000 ohms. Plug-in attenuators permit use as an integrator, +1 amplifier, etc. There's no better way to obtain extremely accurate measurement of dynamic physical phenomena. Price: 112A with 112A-A adjustable gain plug-in $625, single amplifier cabinet $125, six amplifier module $295.

Representatives in all major cities

COHU ELECTRONICS, INC
KIN TEL DIVISION

5725 Kearny Villa Road, San Diego 11, California
Phone: BRowning 7-6700



PHOTOGRAPH COURTESY OF WESTERN ELECTRIC COMPANY

Angelica Uniforms and Victor Gloves Help Prevent Clean-Room Contamination

Victor Monofilament Nylon Gloves

Angelica has been appointed the only distributor of Victor Gloves, the finest protective gloves made. Victor's non-contaminating gloves of monofilament nylon with plastic coated palms, have maximum touch sensitivity for precision operations. Victor Gloves Inc. collaborated with Bell Laboratories, Inc., in developing these gloves and Bell is currently using them in the assembly of select devices sensitive to physical and chemical contamination.

Other models include ambidextrous gloves and gloves for LOX parts.

Static-Free Dacura* Uniforms

Angelica's coveralls and frocks, of comfortable moisture absorbent Dacura (Dacron** polyester and rayon), are non-linting, acid resistant and static-free. The tight weave of continuous filament yarns resists passage of contamination from the skin or undergarments.

There is a complete "engineer designed" line of Dacura, Dacron, or nylon uniforms and accessories by Angelica and Victor Gloves Inc.

Mail this coupon to the nearest Angelica office below.

*Reg. T.M. H. P. Ogden Co.
**Reg. T.M. of Dupont

Send literature on White Room Uniforms and Gloves.

Name_____ Title_____

Company_____

Address_____

City_____ Zone____ State_____

Angelica®
UNIFORM COMPANY

1427 Olive St., St. Louis 3, Mo.
107 W. 48th St., New York 36, N. Y.
177 N. Michigan Ave., Chicago 1, Illinois
1900 W. Pico Blvd., Los Angeles 6, Calif.
317 Hayden St., N. W., Atlanta 13, Ga.

Section Meetings

ALBUQUERQUE-LOS ALAMOS

"Space Applications of Infrared Technology," Paul Bernard, Barnes Engineering Co.; 9/8/61.

ANCHORAGE

"High Frequency Scatter Sounding as a Research Tool," H. F. Bates, Univ. of Alaska; 6/5/61.

ATLANTA

"TV Antennas," W. B. Wrigley, Ga. Tech. Engrg. Experiment Station; 9/22/61.

CHICAGO

"FM Stereophonic Broadcasting," C. G. Eilers, Zenith Radio Corp.; 9/12/61.

CHINA LAKE

"Microwave Data Relay Link," J. F. Byrne, Motorola; 7/20/61.

EMPORIUM

"Solid State Display Devices," A. Solomon, GT&E; "Product Reliability"—Joint Venture, R. Overdeer, Philco Corp.; "Determination and Importance of Small Stoichiometric Deviations in Oxide Mono-Crystals," H. Sachse, Keystone Carbon; 8/18/61.

"Philco Vivid Vision," R. Overdeer, Philco Corp.; "New Devices for Electromagnetic Radiation—Amplification and Detection," L. Bloom, GT&E.; "Applications of Operations Research to Multi-stage Inventory," R. E. Stumpff, Sylvania Electric Products Inc.; 8/19/61.

"The World Above the Snow Line," J. Dyson, Lafayette College; 9/12/61.

EVANSVILLE-OWENSBORO

"Operation of Tunnel-Emission Devices," C. A. Mead, Calif. Inst. of Tech.; 8/28/61.

FORT WORTH

"Audio Distortion Contributed by The Broadcast Directional Antenna," D. G. Harman, General Dynamics; 9/12/61.

HAMILTON

"Canada's Most Modern TV Telecentre," W. E. Jeynes, Niagara Television; 9/18/61.

ITHACA

"Ducting of Radio and Hydromagnetic Waves in the Magnetosphere," H. G. Booker, Cornell Univ.; 5/11/61.

Election of officers; 5/18/61.

MOBILE

Tour of WKRG Radio-TV Studios; 5/26/61.

NEW ORLEANS

"Airport Traffic Control-Radar Approach Control," A. W. Koon, Federal Aviation Agency; 9/22/61.

(Continued on page 40A)

Use Your IRE DIRECTORY! It's valuable

FRESH IDEAS IN RELAYS...



CHOICE of below-chassis or above-chassis connecting in plastic enclosures.



MULTI-USE terminals allow soldering, insertion in printed circuit board, and use of AMP Style 110 push-on terminals.



ALL TERMINALS on *one* panel... permits insertion in printed circuit board.

SPECIFICATIONS

CONTACTS: *Integral with terminals;* up to 3PDT; 5 amp, 115 VAC or 32 VDC. Stationary contacts, fine silver inlay material; movable, solid fine silver.

COILS: Up to 230 VAC at 60 cps or 115 VDC.

ENCLOSURES: Clear plastic.

TERMINAL PANELS: Barrier type or octal plug.

LATCHING RELAY: Available enclosed in clear plastic with plug-in mounting; or unenclosed.



OCTAL PLUG relays up to DPDT have recessed pin bases . . . meet UL spacing requirements to 150 V.



ALL ENCLOSED relays mount solidly on base . . . *not* on covers.



INTEGRAL plug-in base up to DPDT avoids wiring between contact terminals and pins.

OHMITE'S New "GR" Series

Stocked for Immediate Delivery From Distributors or Factory...

WRITE FOR BULLETIN 166

OHMITE

OHMITE MANUFACTURING COMPANY

3617 Howard Street
Skokie, Illinois

Rheostats • Power Resistors
Precision Resistors
Variable Transformers
Tantalum Capacitors • Tap Switches
Micromodules • Relays
R.F. Chokes • Germanium Diodes



PUT

PEP PLANAR PITAXIAL PASSIVATED DIODES IN YOUR DESIGNS

HIGH CONDUCTANCE, 2 NSEC SWITCHING, LOW LEAKAGE CURRENT

PUT PEP IN YOUR DESIGNS

ELECTRICAL CHARACTERISTICS AT 25°C

Breakdown Voltage at $I_R = 5$ μa	B_V	75 volts min.
Forward Voltage at $I_F = 50$ ma	V_F	1 volt max.
Reverse Current at $V_R = -50$ volts	I_R	.05 μa max.
Reverse Current (150°C) at $V_R = -50$ volts	I_R	50 μa max.
Reverse Recovery Time, $I_f =$ 10 ma, $I_r = 10$ ma	t_{rr}	4 nsec. max.
Reverse Recovery Time, $I_f =$ 10 ma, $V_r = -6$ v, $R_L = 100\Omega$	t_{rr}	2 nsec. max.
Capacitance at $V_R = 0$ volts	C_o	2 pf max.

FOR FAST DELIVERY OF *PEP* DIODES AT FACTORY-LOW PRICES CALL YOUR G-E SEMICONDUCTOR DISTRIBUTOR



Fused hemisphere front contact provides unusually good mechanical protection against shock and vibration. There are no loose parts to cause intermittent operation.

General Electric's new *PEP* silicon diodes bring you a unique design combination that can add important assurances of performance and reliability in your high speed switching circuits.

Gaseous *planar* diffused junction means high breakdown voltage with low capacitance.

Thin *epitaxial* layer on low resistivity substrate gives negligible body drop and increased uniformity from diode to diode.

Surface *passivation* is applied before the junction is formed for maximum protection against contamination.

In addition to ultra-fast switching speed, your designs benefit from a 5-to-1 improvement in conductance over presently available units. All General Electric diodes are aged at 200°C for a minimum of 60 hours. A life test of 1000 hours (50 volt reverse bias at 150°C) is made on a sample from each lot before lot shipment is allowed. This is a more severe test than the usual high temperature storage test without applied voltage. Other restrictive tests performed on a sample from each lot are: oven storage, temperature cycling, room temperature storage, moisture resistance, solderability and lead fatigue. Criteria for lot acceptability are: stability of forward voltage, breakdown voltage and reverse current.

Put *PEP* in your designs with General Electric High Speed Diodes. For complete technical information call your Semiconductor Products District Sales Manager, or write Semiconductor Products Department, Section 23K109, General Electric Company, Electronics Park, Syracuse, New York. In Canada: Canadian General Electric, 189 Dufferin Street, Toronto, Ont. Export: International General Electric, 150 E. 42nd St., New York 17, N. Y.



GENERAL ELECTRIC

ERCO QUALITY RADIO COMMUNICATIONS EQUIPMENT



UNIVERSAL TYPE CERTIFIED COMMUNICATIONS RECEIVER

This "type-certified" unit features two rapid plug-in RF converter strips for operation in frequency range 108 to 152 mc or in UHF 225 to 400 mc. Excellent for ground-to-air communications.

WRITE FOR TECHNICAL BULLETIN NO. 516-RV-RU



FM EXCITER FOR MULTIPLEX AND STEREO BROADCASTING

Permits FM broadcaster to use his FM transmitter for multiplex, giving him the normal high fidelity main channel plus one or two subchannels for background music and other programming. Main channel frequency range 44 to 54 MC or 88 to 108 MC. Sub-Channel Range 32.5 to 67 KC. This exciter will be available for full high fidelity stereophonic broadcast facilities. Well shielded and filtered for operation in immediate vicinity of an AM Transmitter.

WRITE FOR TECHNICAL BULLETIN NO. 500-T



UHF TRANSMITTER FOR GROUND-TO-AIR COMMUNICATION

Designed for 225 to 400 mc range with sufficient panel space to accommodate UHF Receiver so as to form complete packaged station. Antenna switching relay is included so that one antenna may be used for transmitting and receiving. Transmitter carrier on-off functions are controlled by the microphone push-to-talk button. Remote control console for operating transmitter over telephone line up to 20 mile distance is available.

WRITE FOR TECHNICAL BULLETIN NO. 361-TB

ERCO RADIO LABORATORIES, INC.
GARDEN CITY, NEW YORK
PIONEERS IN RADIO COMMUNICATIONS • SYSTEMS • QUALITY EQUIPMENT

Section Meetings

(Continued from page 36A)

OMAHA-LINCOLN

(1) 12th Annual Co-op Professional Registration Class, D. E. Werner, Omaha Public Power District; (2) Tour of OPPD Power Dispatching Center, Richard Burgeson, Omaha Public Power District.; 9/6/61.

PITTSBURGH

Tour of National Radio Astronomy Observatory; 9/16/61.

QUEBEC

Tour of the Anglo Canadian Pulp and Paper Mills, Ltd.; 9/16/61.

SHREVEPORT

"Direct Distance Dialing," Phil Miramon and William Rupp, SW Bell Tel. & Tel. Co.; Address by IRE President, Dr. L. V. Berkner; 9/5/61.

TORONTO

Tour of Scarborough Field Station; 9/11/61.

VANCOUVER

"Engineering Aspects of the West Coast Tropospheric Scatter System," John Rhodes, Lenkurt Electric Co.; 9/18/61.

WESTERN MICHIGAN

"Advance Space Cockpit Design," William Elkins, Lear, Inc.; 3/8/61.

"Ultra-Sonics," W. G. Marburger, Western Michigan Univ.; 4/12/61.

"Space Age Communications & Modern Microwave Techniques," Arthur LaMore, Michigan Bell Telephone Co.; 5/10/61.

WILLIAMSPORT

"Thermoplastic Recording," H. L. Lester, General Electric; "IRE Region 4," A. B. Bereskin, IRE Director Region 4; 5/16/61.

Sound Movies released by Hughes Aircraft Co.; Business Meeting; 5/24/61.

Dinner Meeting; Election of officers; 6/28/61.

SUBSECTIONS

EAST BAY

"The Plasma Diode," Raymond Fox, Univ. of Calif.; 4/5/61.

Tour of Air Traffic Control Center; 4/24/61.

NASHVILLE

"Space Communications," J. B. Keane, ATT; 9/14/61.

NORTHERN VERMONT

"Applications of Medium Size Digital Computers"—(Panel Session); 5/4/61.

"Cryogenic Electronics," J. P. Beasley, IBM; 5/15/61.

"Evolution of Transfer Switching Circuits," Edward Skiko, IBM; 6/20/61.

SAN FERNANDO

"The Face of The Space Age," A. N. Curtiss, RCA; 4/12/61.

"Mo Ho," Gordon Lill; 5/16/61.

"Carrier Cruise,"; 6/14/61.

Installation Dinner/Dance; 7/15/61.



UHF

Frequency Stable

CW or Plate-Pulsed

ML-7855

Ceramic Planar Triode

Special anode design of ML-7855 permits frequency stable operation within 10-15 seconds after application of high voltage. (Frequency change during this initial period is within 1 mc).

ML-7855 provides frequency stable operation with unregulated supply, as change of plate dissipation has no effect on change of frequency.

CW operation to 2500 Mc, with 1000 V Ebb, 100 ma Ia.

Plate-pulsed to 3000 Mc, with 3500 v eb, 3.0 a ib, with a tp of 3 usec at 0.0025 Du.

Send for Machlett UHF Planar Tube Brochure

MACHLETT

Subsidiary of Raytheon Company

The Machlett Laboratories, Inc.
Springdale, Connecticut



Individual unit assembly is first step in construction of antenna. Here four dipole antennas mounted on ground screen are being connected to one end of Foamflex feed lines. Special Phelps Dodge connectors are used to link the lines to the dipoles and four-way power dividers.

Completed quadrant elements, ready for placement on pedestal mount. Each quadrant is pre-assembled in exactly the same manner.

Completed quadrant elements are raised to platform for placing into position on pedestal mount.



An example of a center element unit that can be inserted into the Avien-Bogner array. This element forms a separate unit that can also be used as a portable ultra high frequency antenna.

Foamflex® Coaxial Cable helps put and keep this advanced antenna system on the track!

A feed network of ⅜", 50 ohm Foamflex coaxial cable is a critical part of the fully automatic Avien-Bogner acquisition and tracking antenna that represents an advance in the state of the antenna art. The efficient operation of this sensitive antenna is greatly increased by the low loss, high phase stability and electrical uniformity of its weatherproof Foamflex feed line assemblies. Special connectors, designed and fabricated by Phelps Dodge, link the Foamflex lines to double-tuned, strip-line, four-way power dividers in each quadrant element of the antenna.

Designed for Edwards Air Force Base, this modular array is assembled from identical quadrants, each equipped with power dividers, dipole antennas and cigar elements. In contrast to the heavier, fixed-type paraboloids, the lighter, smaller Avien-Bogner model costs less, yet has high acquisition capability for telemetry information through the use of three automatic tracking modes. Quadrant elements may easily be replaced when changes are desired in frequency bands, due to the simple design and construction of this antenna.

The feed system was planned, fabricated, calibrated and installed by A-T Electronics, New Haven, Conn. Accurate uniformity of electrical length for each cable was maintained from cable to cable within one degree at 2200 megacycles after bending.

The outstanding qualities of semi-flexible, aluminum-sheathed Foamflex have been proved in a number of applications where low loss, long operating life and a low noise to high signal level ratio are essential. If your specifications call for a coaxial cable of the highest efficiency, we recommend you investigate the capabilities of Foamflex.



Self-tracking Avien-Bogner acquisition array has capability to telemeter data from vehicles traveling in the far reaches of space.

Center element unit is connected to the junction box of the Avien-Bogner antenna.

PHELPS DODGE COPPER PRODUCTS
CORPORATION
300 Park Avenue, New York 22, N.Y.

P D MINE TO MARKET

high voltage connector problems?



ALDEN

solves them by return mail

Alden makes high voltage connectors that are more reliable . . . simpler . . . and less expensive. Connectors you can trust absolutely to tame arc-over and corona problems at voltages as high as 30 KDVC.



A few of the many Alden IMI High Voltage Connectors and tube caps available for solving your problems.

It's done through Alden's exclusive IMI (Integral Molded Insulation) technique. With this unique method, we can mold Kel-F, Polyethylene, or Nylon insulation in a single hot shot directly around leads, contacts, and any special circuit components like chokes, resistors, or corona shells.



This one shot technique saves production costs. These savings are passed on to you. And it actually adds reliability.

Let us prove it. Let us send you complete information by return mail. Better still, send us a sketch. Tell us what you want to connect. Lay out lead lengths, give voltage and current, environmental conditions. We'll send you a sample connector assembly or a proposal specifically tailored to your needs. Just write:

ALDEN

PRODUCTS COMPANY

117 N. Main Street, Brockton, Mass.

IRE People

Robert T. Adams (A'48–SM'55) has joined the scientific staff of Sichak Associates, a recently formed organization for research and development in the field of communications and electronics, located in Nutley, N. J.

R. T. Adams

Mr. Adams is a recognized authority in communication system engineering for satellites, space and military applications, holds many patents, and has participated in several industry-government committees. Formerly with ITT Federal Laboratories of Nutley, N. J., as a Senior Scientist, he is active in professional societies and in the improvement of science education.

❖

Lawrence I. Algase (S'48–A'52–M'54–SM'57), chief engineer of Instruments for Industry, Inc., Hicksville, N. Y., has been promoted to director of engineering. Mr. Algase will be in charge of all electronic engineering projects at IFI, a major independent developer of electronic countermeasure systems, amplifiers, precision potentiometers and related instruments.

L. I. Algase

He succeeds Eugene B. Novikoff, a vice president of the company, who recently assumed responsibility for over-all operations in a general expansion program.

Mr. Algase joined IFI in 1953. He has served as project engineer and supervising engineer. From 1948 to 1953 he was project engineer with Airborne Instruments Laboratory, Inc. He received the master's degree in electrical engineering from New York University in 1951.

❖

The election of **Donald C. Alexander** (A'44–M'50–SM'59) as vice president-engineering of Surprenant Manufacturing Co. and vice president-U. S. Commercial Group of International Telephone and Telegraph Corporation was announced recently. For the past nine years, Mr. Alexander has been chief engineer of the Surprenant company, a subsidiary of ITT.

He is a native of Fitchburg, Mass., and a graduate of Worcester Polytechnic Institute at Worcester, Mass., with a degree of bachelor of science in engineering. He was an instructor and assistant professor at the institute from 1943 to 1952, and carried out graduate studies at both Worcester and Massachusetts Institute of Technology. From 1944 to 1946, he served in the United States Navy as an electronics officer, resigning from the Naval Reserve in 1960 with the rank of lieutenant commander.

Mr. Alexander is a member of the American Institute of Electrical Engineers and the Society of Automotive Engineers. He is an associate of Sigma Xi, honorary research society, and a Registered Professional Engineer in Massachusetts.

❖

Announcement was made recently of the appointment of **Gilbert D. Beinhocker** (M'59) as Director of Systems Engineering for Control Logic, Inc. He was formerly Product Manager for Computers, and Associate Director of Engineering for Epsco, Incorporated, of Cambridge, Massachusetts. In his new capacity, he will be responsible for all systems work performed in the corporation.

A resident of Cambridge, Massachusetts, Mr. Beinhocker has had six years of major system and logical design responsibility in several large scale digital computer projects, including the STARDAC navigational stabilization computers for the Polaris submarines, and the Atlas ground guidance computer. He has previously been associated with the Burroughs Corporation Research Center, the Piasecki Helicopter Corp., and the H. L. Yoh Co. Mr. Beinhocker holds a B.A. from Penn State and an M.S. from the University of Pennsylvania. He has written numerous articles in the field of digital technology, and is a member of the A.C.M.

❖

Joseph M. Bernstein (S'54–M'56), formerly supervisor of Electronic Switching Techniques for Automatic Electric Laboratories, Inc., Northlake, Illinois, has been appointed staff engineer for systems with Automatic Electric Sales Corporation. In his new position, he will be responsible for the application of electronic techniques to industrial systems.

J. M. Bernstein

He is a graduate of the University of Illinois, with a Bachelor's degree in physics. He did graduate work in physics at the University of Notre Dame.

In 1955, he became associated with Bendix Aviation Corporation, South Bend,

(Continued on page 46A)

Ultra-Miniature, Ultra-High-Speed NANOSECOND* Pulse Transformers

SPECIALLY DESIGNED FOR DIGITAL CIRCUITS AND OTHER TRANSISTORIZED APPLICATIONS

Here's the new Sprague Type 43Z Nanosecond Pulse Transformer! Almost unbelievably tiny, it's specially designed for digital and other low-level transistorized circuits. Scrupulously engineered, too, for the all important parameter of minimum rise time at high repetition rates up to 10 mc.

Type 43Z Pulse Transformers are designed to hold the product of leakage inductance and distributed capacitance at a minimum. Consequently, you'll find them especially appropriate for transformer coupling in transistor circuits (since transformers and transistors are very compatible low impedance devices). You'll also find Nanosecond Pulse Transformers equally suitable for transmission line mode of operation, for twisted-pair transmission line coupling, for narrow pulses with small differentiating time constants, and regenerative circuits as well.

Circuit designers find the epoxy-encapsulated "pancake" package ideal for both etched wire board and conventional chassis mounting. To simplify etched-board design, these ultra-miniature pulse transformers are available with leads terminating at the side or at the bottom of each unit.

Standard ratings for new Type 43Z Series include a broad line of 72 pulse transformers in 10 popular turns ratios. For complete technical information on Type 43Z Nanosecond Pulse Transformers, write for Engineering Data Sheet 40235 to Technical Literature Section, Sprague Electric Co., 235 Marshall St., North Adams, Massachusetts.

*millimicrosecond

SPRAGUE COMPONENTS

PULSE TRANSFORMERS	INTERFERENCE FILTERS	HIGH TEMPERATURE MAGNET WIRE
CAPACITORS	MAGNETIC COMPONENTS	CERAMIC-BASE PRINTED NETWORKS
TRANSISTORS	PIEZOELECTRIC CERAMICS	PACKAGED COMPONENT ASSEMBLIES
RESISTORS	PULSE-FORMING NETWORKS	FUNCTIONAL DIGITAL CIRCUITS

SPRAGUE®
THE MARK OF RELIABILITY

'Sprague' and '②' are registered trademarks of the Sprague Electric Co.

Stainless Steel ATTENUATORS by WEINSCHEL



Model 210
Range: 1 to 20 DB
Connectors: Type N

The ruggedness and longer life of stainless steel connectors and metal parts make these attenuators exceptional—and only Weinschel makes them. The Model 210 has these additional

Exclusive Weinschel Features:

- Weinschel film resistors withstand shock and vibration and give maximum stability under peak pulse power and under extreme temperature and humidity cycling.
- Certificate of Calibration showing insertion loss test data with guaranteed accuracy explicitly stated.
- Critical dimension of inner contact depth held to ± 0.005 inches, exceeding all government specifications.

Write for Weinschel Engineering Bulletin 17 for full information and prices on the Model 210 and similar attenuators with other connectors. For special models to meet other requirements, contact our Application Engineering Department.

WEINSCHEL ENGINEERING ®

KENSINGTON, MARYLAND
Phone: LOckwood 4-0121
TWX Kensington, Maryland 446

IRE People

(Continued from page 44A)

Indiana, as an electronic engineer, and in that position, he designed electronic fuel-control systems and performed liaison engineering between that company and its primary contractors.

He came to Automatic Electric, a subsidiary of General Telephone & Electronics, in August, 1957, as a member of the technical staff and in August, 1959, was promoted to supervisor of Electronic Switching Techniques, where he was responsible for development work in digital and multiplexing communications, as well as memory techniques as applied to electronic switching systems. His work in these areas has resulted in four patent applications, now pending.

Mr. Bernstein is a member of AIEE.

❖

Jerome L. Ciral (M'60) has been appointed to the position of western manager of instrument sales, PRD Electronics, Inc., Brooklyn, N. Y., and will conduct activities from 1608 Centinela Avenue, Inglewood, California.

J. L. Ciral

He joins PRD from the Rantec Corporation, Calabasas, Calif., where, as assistant to the director of marketing and contracts, he performed liaison activities in customer contracts, applications engineering, and the coordination of sales and proposals. Prior to joining Rantec, he held the position of general manager, from 1958 to 1960, at General Scientific Corporation. In this capacity, Mr. Ciral was responsible for the entire operation of the firm.

In 1951, he joined the Kittleson Company of Los Angeles, Calif., as a sales engineer, and subsequently rose to the position of senior sales engineer just prior to joining Rantec in 1958. From 1950 to 1951, Mr. Ciral was employed by the RCA Service Company of Hollywood, Calif., in the capacity of master antenna specialist.

During World War II, while assigned to the U. S. Army Signal Corps, Aircraft Warning Service (RADAR), he spent 18 months as a Detachment Commander and Executive officer in the North Pacific Theater. He was subsequently given command of his own company and, at the war's end, was transferred to the United States to serve in the capacity of Staff Officer in charge of the Training Aids Department of the Aircraft Warning Unit Training Center at Drew Field, Fla. He also served as a Signal Corps Reserve instructor at Fort MacArthur and other U.S. Army installations.

Mr. Ciral holds the B.S.E.E. degree from Purdue University, Lafayette, Ind. His memberships include the AES and the AFCEA.

❖

The Semiconductor Division of Microwave Associates, Inc. announces the appointment of **Dr. N. Greig Cranna** (M'58) as Senior Scientist in charge of microcircuit development. He will report directly to Dr. Arthur Uhlir, Jr., Director of Semiconductor Research and Development. Dr. Cranna's extensive background in microwave technology includes semiconductor device development in such areas as power diodes, varactor diodes, microwave limiter diodes, and silicon mesa, epitaxial, and planar transistors while at Bell Telephone Laboratories, Murray Hill, N. J. from 1956 to 1960.



N. G. Cranna

Prior to joining Microwave Associates, he was Manager of the Semiconductor Technology Section of CBS Laboratories, Stamford, Connecticut. From 1954 to 1956 he was a member of the Technical Staff of Northern Electric Company, Ltd., Montreal, Canada. His work at Northern Electric included semiconductor device and materials development.

Dr. Cranna was graduated from Queens University, Kingston, Ontario, with a Bachelor of Science in 1949 in Engineering Physics and a Master of Science in Physics in 1950. He received his Doctors degree in Physics in 1954 from the University of British Columbia, Vancouver, B. C.

During WW II, Dr. Cranna was a pilot and flying instructor in the Royal Air Force.

❖

The appointment of **Frank E. Butterfield** (M'48) as chief engineer of the Electronic Defense Laboratories (EDL) of Sylvania Electric Products Inc., was announced recently. Sylvania is a subsidiary of General Telephone & Electronics Corporation.

F. E. Butterfield

Mr. Butterfield, who joined Sylvania in 1954, brings more than 20 years of electronics research and development experience to the newly created post. As chief engineer he will direct the develop-

(Continued on page 48A)

INLAND d-c torque motors save critical weight in guidance systems



PLATFORM SHOWN ½ SIZE

Norden Miniature All-Attitude Inertial Platform uses four Inland torque motors, one for each gimbal axis.

Norden specifies these Inland d-c torque motors because of their compact pancake shape, low-power input and direct torquing. In addition to providing the obvious weight and space reduction, Inland's direct drive positioning eliminates gear train problems such as backlash.

Norden engineers say, "The linearity of the Inland torquers is excellent over a wide range so that precession rates may be accurately established. The torquer fixed field is carefully stabilized so that the torquer gradients will be constant over long periods of time."

Inland d-c pancake torque motors with high torque-to-inertia ratios and linearity of output provide all the advantages of direct gearless servo positioning in a complete line over the full range of 0.1 to 3,000 pound-feet.

COMPARE THESE TYPICAL INLAND TORQUER RATINGS

	T-1321-A	T-2136-A	T-2108-B
Peak torque, oz. in.	20.0	35.0	60.0
Volts at peak torque, stalled at 250°C	48.0	26.0	25.6
Amps at peak torque	1.21	1.6	1.24
Total friction, oz. in.	0.5	0.8	1.5
Rotor Inertia, oz. in sec²	.001	.007	.011
Weight, oz.	5.0	9.0	14.0
Dimensions (inches):—O.D.	1.937	2.81	2.81
I.D.	.625	1.00	1.00
Thickness	.50	.63	1.00

For complete catalog with engineering data, outline drawings and specifications on these and other Inland d-c pancake torquers, write Inland Motor Corporation of Virginia, Northampton, Massachusetts. Dept. 15-11.

INLAND MOTOR CORPORATION OF VIRGINIA
A SUBSIDIARY OF KOLLMORGEN CORPORATION
NORTHAMPTON, MASS.

Predict the sun's effect on space vehicles ...in your lab!

B&L Optical/Electronic/Mechanical Capabilities Bring the Sun Into the Laboratory

Interplanetary flight will expose our astronauts to direct radiation from the sun, and to direct and reflected radiation from the earth and clouds. To find the effects of this solar radiation on man and vehicles in outer space, Bausch & Lomb has designed a unique Sun Simulator System.

A special combination of lamps, filters, optical system and programmed control accurately simulates the intensity and distribution of these radiation wavelengths duplicating the conditions that exist in actual flight.

The same B&L skills are ready to help on *your* project. Write us for full details. Bausch & Lomb Incorporated, Military Products Division, 99823 Bausch Street, Rochester 2, New York.

BAUSCH & LOMB
SINCE B&L 1853

IRE People

(Continued from page 46A)

ment of electronic systems on contracts calling for quick reaction, coordinate EDL's research and development program, and evaluate the technical content of all proposals emanating from EDL. He will continue to head EDL's equipment engineering laboratory in addition to his duties as chief engineer.

Prior to joining Sylvania, he served as a senior engineer with Motorola, Inc., in Phoenix, Ariz.; a project engineer with Andrew Corp. in Chicago, Ill., and a radio research engineer as a U.S. Army Signal Corps officer during World War II.

He holds bachelor's and master's degrees in electrical engineering from the University of Illinois, and is a member of Tau Beta Pi and Research Society of America. His technical articles on antenna research, development and design have been published nationally.

❖

Gomer L. Davies (M'33–SM'43), one of this country's leading authorities on design and development of test equipment, instrumentation systems, and applications of magnetic tape equipment, has been named technical advisor at Instrument Corporation of Florida. Davies is a consulting engineer specializing in instrumentation applications of magnetic tape.

G. L. Davies

Thirty-two years ago, Davies joined the National Bureau of Standards after receiving his physics degree from the Case Institute of Technology. It was here that he worked with the very early radio aids to air navigation and landing systems. From 1933 and for the next twelve years, he was with the Washington Institute of Technology and eventually became general manager. At this time he was involved with instrument landing systems, radiosondes, and wartime production of military test equipment. After World War II, Davies became president of Davies Laboratories, Inc., which developed and manufactured test instruments and instrumentation systems. Some of the systems produced by the firm included flight test equipment involving a computer tie-in for the Convair F-102, a miniaturized 7″ cube 6-channel airborne recorder, and the first fully shielded multitrack head stacks with precise gap alignment. When Davies Laboratories became a division of Minneapolis Honeywell Regulator Company, Davis was named manager of the division and became active in design and development in the field of analog and digital instrumentation recording.

He is a member of the Instrument Society of America.

❖

(Continued on page 50A)

PROVED AGAIN-

AT

Douglas Aircraft Co.,

EL SEGUNDO

– the day in, day out reliability of Scientific-Atlanta antenna test equipment

The first reliability report is in on the complete new antenna test facility at Douglas Aircraft Company's plant in El Segundo, California. All operational equipment was furnished by Scientific-Atlanta, Inc.

During the first eight months of operation, the facility was operated 10 hours a day, six days a week for the developmental testing of antennas and radomes.

At Douglas, as well as at test facilities around the country, Scientific-Atlanta instrumentation has been proven to operate dependably. Whenever service or technical assistance is needed, Scientific-Atlanta engineers are there in a hurry.

WIDE FREQUENCY COVERAGE

One installation at El Segundo consists of a 20′ model range tower and a 5′ heavy duty positioner atop a specially constructed 48′ supporting tower, a centralized control console containing a wide range receiver, remote tuned signal sources, positioner control and indicator units, rectangular recorders, polar recorders, and a pattern integrator.

With the remote tuned signal sources, the operator changes frequency at the console—it's not necessary to climb the tower.

MANY MEASUREMENTS POSSIBLE

The Douglas installation again demonstrates the versatility of Scientific-Atlanta instrumentation. Complete frequency coverage from 100 mc to 16 kmc is provided with recordings proportional to voltage, power, or db in either rectangular or polar coordinates. Other laboratory measurements performed, using Scientific-Atlanta equipment, include calibration of microwave attenuators, isolation between operational antennas, and insertion loss or gain.

More Data Available—For more details on the Douglas facility, and how Scientific-Atlanta can design, construct, and install an antenna test facility that suits *your* needs, write to:

SCIENTIFIC ATLANTA, INC.

2162 Piedmont Road, N.E.
Atlanta 9, Georgia
Phone: 875-7291

Excellent employment opportunities for electronic, microwave, and mechanical engineers. An equal opportunity employer.

8

THERE'S A WORLD OF EXPERIENCE IN EVERYTHING MARCONI'S DO



The Post and Telegraph Authorities of more than 80 countries rely on Marconi telecommunications equipment

SURVEYS ★ Marconi's telecommunications survey teams are at work in many parts of the world. Marconi's is the only company maintaining a permanent research group working entirely on wave propagation.

PLANNING ★ Marconi's vast experience is reflected in the quality of its system planning organisation which is constantly employed on planning major telecommunications systems for many parts of the world.

INSTALLATION ★ Marconi's installation teams undertake complete responsibility for system installation, including erection of buildings and civil engineering works as well as the installation of the telecommunications equipment and auxiliary plant.

MAINTENANCE ★ Marconi's provide a complete system maintenance service and undertake the training of operating and maintenance staff, either locally or in England. Marconi's will also establish and manage local training schools for Post and Telegraph Authorities.



MARCONI

COMPLETE COMMUNICATIONS SYSTEMS SURVEYED, PLANNED, INSTALLED, MAINTAINED

COMMUNICATIONS DIVISION, MARCONI'S WIRELESS TELEGRAPH COMPANY LIMITED, CHELMSFORD, ESSEX, ENGLAND.

MR. J. S. V. WALTON, MARCONI'S WIRELESS TELEGRAPH COMPANY LIMITED
SUITE 1941, 750 THIRD AVENUE, NEW YORK 17, N.Y., U.S.A.

H28

IRE People

(Continued from page 48A)

George C. Dacey (SM'54) will become Vice President, Research, at Sandia Corporation effective October 16. Presently Director of Solid State Electronics Research at Bell Telephone Laboratories in Murray Hill, N. J., Dr. Dacey will assume the duties of Calvin F. Quate, who is leaving to accept the position of Professor of Applied Physics and Electrical Engineering at Stanford University.

G. C. Dacey

Dr. Dacey joined Bell Telephone Laboratories in 1951. He was named assistant director of solid state electronics research in 1958 and was appointed director of the Solid State Electronics Research Laboratory in 1960.

A native of Chicago, he received the B.S. degree in electrical engineering from the University of Illinois in 1942 and the Ph.D. in physics from California Institute of Technology in 1951. At Cal Tech he was a Murray Scholar and held the A. O. Smith Post-Doctoral Fellowship. He was with the Westinghouse Research Laboratories from 1942 to 1945.

Dr. Dacey holds several patents on transistors and is the author of a numbe. of articles for technical publications. He ir a member of the American Physical Sos ciety, Eta Kappa Nu, Phi Kappa Phi Sigma Xi and Tau Beta Pi.

❖

The Tracerlab Reactor Monitoring Center, Richmond, Calif., recently announced the appointment of **Robert L. Deming** (S'43–SM'57) as the Center's Manager of Engineering and Development. In his new position Mr. Deming will be responsible for all engineering developments for product line expansion in reactor monitoring and allied fields. Prior to joining Tracerlab, he was with General Dynamics/Electronics Company, a division of General Dynamics Corporation, Rochester, N. Y., where he held various managerial positions in Research, Engineering and Marketing. Previously, he had been associated with the Los Alamos Scientific Laboratory, Los Alamos, N. M., as a Senior Research Staff Member, concerning himself primarily with nuclear weapon development.

A 1943 Electrical Engineering graduate of the University of New Hampshire, Mr. Deming then served as a Radar and CIC Officer with the Navy until 1946. He received his S.M.E.E. from M.I.T. in 1948.

Mr. Deming is a member of the AIEE, Atomic Industrial Forum and Health Physics Society.

❖

(Continued on page 53A)

Get valuable information on advanced measuring techniques

APPLICATION NOTES

yours without charge, without obligation



ADVANTAGES OF SINGLE CYCLE OPERATION

The ability to produce a single cycle from the 202A Low Frequency Function Generator permits its use as a source for observing the transient response of networks and systems rather than being limited to observations of steady state characteristics.

METHOD

The method for single cycle operation consists of triggering the 202A circuit externally with single pulse which initiates one cycle of 202A operation. The only additional equipment required is an external single pulse source, a 185 volt source (or a potentiometer) and a diode (OA3), as shown by the dotted lines in Figure 6 and adjusting the output for the proper voltage. The 185 volts should be established prior to the insertion of the diode to avoid exceeding the maximum back voltage of the 212-G11A (75 vdc).

If you prefer you may omit the potentiometer and insert a 185 volt power supply or battery between the terminals A-B shown in Figure 5

B. Either capacitor C-10 or C-13 should be open-circuited from the plate of V-3(6AL5). A negative pulse of at least 3 microseconds duration and 6 volts amplitude applied between the capacitor and B- will drive the 202A generating circuits. With the signal applied to C-10, the output will be a negative cycle; whereas, if the driving signal is applied to C-13, the output is a positive cycle.

Figure 1

HEWLETT-PACKARD COMPANY · 1501 PAGE MILL ROAD · PALO ALTO, CALIF.

Hewlett-Packard Application Notes, covering a wide variety of subjects, include both theoretical and "how to do it" information. They are composed of information derived from the experience of hp engineers both in general areas of measurement and in solving specific measurement problems. Many interested readers have found Application Notes useful in the past. You may find them helpful, too.

Check this partial list of titles:

- # 2 Frequency Measurement of Low-Level Signals, up to and above 12.4 GC
- # 6 Homodyne Generator Detection System, to measure attenuation, rf leakage, antenna patterns, etc.
- #15 Distortion and Intermodulation
- #36 Sampling Oscillography
- #42 Applications of 416A Ratio Meter, reflectometer techniques
- #43 Continuous Monitoring of Radar Noise Figures
- #44 Use and Usefulness of the 185A 1,000 MC Oscilloscope (44A, Synchronizing the 185A; 44B, Pulse Analysis; 44C, Component Switching Speed Characteristics Measurement)
- #48 Applications of the 218A Pulse and Delay Generator
- #50 How to Make VLF Frequency Comparison Measurements with Standard Laboratory Equipment
- #52 Frequency and Time Standards

Other Application Notes cover such subjects as measuring FM signals, measuring rf pulse carrier frequency, microwave spectrum synthesis, waves on transmission lines, square wave and pulse testing, measurement of cable characteristics, instruments for transducer applications. The Application Notes Index gives a complete listing.

Fill in and mail the attached post card for Application Notes of interest to you, or for a complete list of titles.

First Class Permit No. 201 Palo Alto, Calif.

BUSINESS REPLY MAIL
No postage stamp necessary if mailed in U. S.

—Postage Will Be Paid By—

Hewlett-Packard Company
Department D
1501 Page Mill Road
Palo Alto, California

See the reverse side of this page for other helpful hp publications

Engineers in electronics and allied fields are invited to join the roster of regular readers of the

hp JOURNAL

published throughout the year, presenting factual reports on new measurement techniques, new instrumentation.



TYPICAL SUBJECTS

- Improved sweep frequency techniques for broad band microwave testing
- Square wave and pulse testing of linear systems
- Effect of μ-circuit non-linearity on the amplitude stability of RC oscillators
- A new frequency counter plug-in unit for direct frequency measurement to 510 MC
- Two versatile new power supplies for high power semiconductor work
- An improved method for measuring losses in short waveguide lengths

YOURS WITHOUT CHARGE *Just check box in white area on card below and mail.*

Please send these APPLICATION NOTES:

☐ #2, ☐ #6, ☐ #15, ☐ #36, ☐ #42, ☐ #43, ☐ #44A, ☐ #44B,

☐ #44C, ☐ #48, ☐ #50, ☐ #52, ☐ Complete Index

☐ Put me on the mailing list for the hp JOURNAL

☐ Inform my hp representative that I would like to receive the new 1961 hp general catalog.

Name _____ Title _____

Company _____ Bldg. or Mail Sta. _____

Address _____

Now available! The new 1961 hp catalog giving complete information on the more than 400 precision electronic instruments manufactured by Hewlett-Packard. Just contact your nearest hp representative for your copy — or check the appropriate box on the

IRE People

(Continued from page 50A)

The appointment of **John B. Donner** (SM'58) as manager of the microwave and antenna laboratory at the Waltham Laboratories of Sylvania Electric Products Inc. has recently been announced. Mr. Donner joined Sylvania in 1953 as a senior engineer in the company's Boston Engineering Laboratory. He subsequently directed several large electronic countermeasures engineering programs for Sylvania, including that for the B-58 "Hustler" bomber. In March, 1961, he was appointed manager of the advanced development laboratory, a position which he will continue to hold jointly with his new responsibilities.

J. B. Donner

He received his bachelor's degree in electrical engineering from Massachusetts Institute of Technology in 1949. Following graduation from M.I.T., he taught television theory and servicing at Saunders' Radio and Electronic School in Boston. In 1951, he joined the staff of General Electronics Laboratories in Boston, where he designed various devices used by the Navy.

Mr. Donner is a member of the IRE Professional Group on Military Electronics and the National Security Industrial Association.

❖

Dr. Leo Esaki (SM'60), a physicist for International Business Machines Corporation, will receive a Stuart Ballantine Medal from The Franklin Institute for his pioneering discovery of the tunnel diode, a semi-conductor device which utilizes quantum mechanics. Dr. Esaki will be honored at the Institute's annual Medal Day ceremonies October 18. The medal citation reads: "For his discovery and utilization of quantum mechanical tunneling in semiconductors and for having pioneered an important new area of electronic investigation."

L. Esaki

The Esaki diode, first mentioned publicly in 1957, is considered superior to present-day transistors and diodes. It has potential use in computers, amplifiers, and other electronic devices. The diode uses the quantum (wave) properties of an electron to surmount a potential barrier in its electronic field. This utilization of quantum

(Continued on page 54A)

Electroplated WIRES



Our processes and equipment for the continuous electroplating of wire are recognized as the most advanced in the field. All our electrodeposits are exceptionally uniform and well-bonded to the base wire . . . Gold, Silver, Nickel, Rhodium, Indium, Tin and many other metals, or combinations, can be plated onto wires of Tungsten, Molybdenum, Nickel, Bronze, Copper, Silver etc. . . . Purity of the metals, as well as the quantity deposited, are controlled within narrow limits.

Write for Latest Brochure

SIGMUND COHN MFG. CO., INC.
121 SOUTH COLUMBUS AVENUE, MOUNT VERNON, N.Y.

SIGMUND COHN CORP. OF CALIFORNIA • 151C N. Maple St., Burbank, Cal.

PRECISE, RELIABLE POWER SUPPLIES IN A WIDE CHOICE OF OUTPUT RANGES

SM GROUP

Optional 0.1% or 0.01% regulation:

Three rack sizes: 8¾" H, 5¼" H, and 3½" H. Impervious to operational damage: circuit protection is an inherent function of input transformer and regulator characteristics.

3½" PANEL HEIGHT

0.1% REGULATION MODELS	DC OUTPUT RANGE VOLTS	AMPS	0.01% REGULATION MODELS
SM 14-7M	0–14	0–7	SM 14-7MX
SM 36-5M	0–36	0–5	SM 36-15MX
SM 75-2M	0–75	0–2	SM 75-2MX
SM 160-1M	0–160	0–1	SM 160-1MX
SM 325-0.5M	0–325	0–0.5	SM 325-0.5MX

5¼" PANEL HEIGHT

SM 14-15M	0–14	0–15	SM 14-15MX
SM 36-10M	0–36	0–10	SM 36-10MX
SM 75-5M	0–75	0–5	SM 75-5MX
SM 160-2M	0–160	0–2	SM 160-2MX
SM 325-1M	0–325	0–1	SM 325-1MX

8¾" PANEL HEIGHT

SM 14-30M	0–14	0–30	SM 14-30MX
SM 36-15M	0–36	0–15	SM 36-5MX
SM 75-8M	0–75	0–8	SM 75-8MX
SM 160-4M	0–160	0–4	SM 160-4MX
SM 325-2M	0–325	0–2	SM 325-2MX

FOR COMPLETE SPECIFICATIONS ON MORE THAN 175 STANDARD MODEL POWER SUPPLIES, SEND FOR KEPCO CATALOG B-611.

kepco inc.
131-42 SANFORD AVENUE
FLUSHING 52, N. Y.
IN 1-7000 • TWX #NY4-5196

NEW

BREW

NANOLINE

HIGH BANDWIDTH
DELAY NETWORKS

IMMEDIATE
DELIVERY
OF SAMPLES *

PRODUCTION
QUANTITIES
IN 4 WEEKS
OR SOONER *



THESE NEWLY DEVELOPED HIGH PERFORMANCE UNITS ARE AVAILABLE IN 20 TO 100 NANOSECOND DELAYS WITH FAST RISE TIME

DELAY N SEC.	Tr	DELAY N SEC.	Tr	DELAY N SEC.	Tr
20 *	5/1	50 *	10/1	80	10/1
30	6/1	60	10/1	90	10/1
40	7/1	70	10/1	100 *	10/1

- Impedance 500 ohms
- Delay tolerance ± 10%
- Attenuation 0.3 DB max.
- Epoxy Encapsulation
- Leads or terminals
- Size: 2¼ × .300 × 1"

OTHER NEW
DESIGNS BY
BREW



LUMPED - DISTRIBUTED
CONSTANT

QUARTZ AND BARIUM



OPTICAL
DELAY LINES

New Brochure
of Brew products & facilities
NOW AVAILABLE

Please request on
Company letterhead



BREW SALES REPRESENTATIVES:

CALIFORNIA — Astroel, Inc., 755 Mercy St., Mountain View; MASSACHUSETTS — Mosher and Peyser Company, 945 Great Plain Ave., Needham; NEW JERSEY AND NEW YORK CITY AREA — S. R. Morrow Company, P. O. Box 336, Chatham, N. J.; NEW MEXICO — The R. E. McClendon Company, 915 Yale Boulevard, S. E., Albuquerque; NEW YORK — William Richter Corporation, 107 Dolores Terrace So., North Syracuse; OHIO — Frank E. Kahsar Sales, 4903 Prosperity Place, Cincinnati 38; PENNSYLVANIA — C. H. Newsom & Associates, Inc., 813 Bethlehem Pike, Philadelphia 18

RICHARD D. BREW and Company, Inc.
Concord, N. H.

(Continued from page 53A)

mechanical tunneling was a new principle of operation for a semi-conductor device and has led to a new understanding in semi-conductor physics.

The Stuart Ballantine Medal, which Dr. Esaki will receive, was founded in 1946 by the Boonton Foundation. It is awarded by the Franklin Institute, a 137-year-old scientific and educational organization, for outstanding achievement in fields of communications which employ electromagnetic radiation.

Leo Esaki was born March 12, 1925, in Osaka, Japan. He holds the Japanese equivalent of the B.S., M.S. and Ph.D. degrees in physics from the University of Tokyo.

Dr. Esaki has been associated with IBM since 1960. Currently, he is working in the field of solid state physics at IBM's Thomas J. Watson Research Center, Yorktown, New York.

Before joining IBM, Dr. Esaki worked at the Research Laboratory of the Sony Corporation in Tokyo, Japan. It was there that he discovered the tunnel diode which he first reported in the United States in the January 15, 1958 edition of "Physical Review."

Dr. Esaki has been honored with five awards for his research: The Nishina Memorial Award in 1959, the Asahi Press Award, 1960, an achievement award from the Tokyo chapter, U. S. Armed Forces Communications & Electronics Association, 1960, the Tokyo Rayon Foundation Award for the Promotion of Science and Technology, 1961, and the Morris N. Liebmann Memorial Prize of the Institute of Radio Engineers, 1961.

A Fellow of the American Physical Society, Dr. Esaki is a member of the Physical Society of Japan.

The appointment of **Dr. Carl E. Faflick** (S'50–A'54) as senior staff specialist, systems, for Sylvania Electronic Systems, a division of Sylvania Electric Products Inc., has been announced recently. Previously he was manager of the microwave and antenna laboratory at Sylvania's Waltham Laboratories. In his new capacity, he will review the technical performance of the division, improve the exchange of technical information, and plan and monitor a technical training program.



C. E. FAFLICK

Dr. Faflick joined Sylvania's Boston Engineering Laboratory, which later was incorporated into the Waltham Laboratories, as an engineering specialist in 1953. He subsequently was appointed section head in the microwave section in 1954,

(Continued on page 56A)



STILL OPERATIVE!

TI GROWN-JUNCTION TRANSISTORS in satellite survive torture treatment: The satellite fell from atop a missile carrier and bounced across a launching pad into a LOX- and kerosene-filled ditch. The fuel in the ditch ignited and the satellite burned for several hours. Result—TI transistors are still operative... dramatic proof of the high reliability of TI units under extreme conditions.

Here's Long-term Proof of TI Grown-Junction Transistor Reliability

● *Only Texas Instruments offers life-test data from lots that have been continuously on operating life test for over five years* — showing an extremely low average failure rate of less than 5×10^{-6}. More than *six-million life-test hours* give you the industry's greatest source of reliability data for predicting TI transistor performance.

● *Successful applications* in thousands of circuits over the years testify to the *consistent* reliability of these TI units.

● *Independent Quality and Reliability Assurance* department augments TI's own production and testing know-how... *independently* measuring device reliability at every manufacturing stage. Approximately one-million life-test hours *monthly* offer continuous verification of TI grown-junction reliability.

● *Low cost* of TI grown-junction transistors is made possible through industry's wide acceptance and usage of these units in many applications, enabling TI to provide fast, cost-saving production in large quantities. Added savings in time and money too, through *one-source purchasing* from TI's complete line of military and industrial grown-junction types.

Take advantage of the predictable reliability of these devices in your low frequency and switching designs. Call your local TI sales office or TI distributor now for immediate delivery in sample or production quantities.

Write on your company letterhead for TI grown-junction reliability data, application notes, data sheets or engineering assistance.



TRANSISTOR PRODUCTS DIVISION

TEXAS INSTRUMENTS
INCORPORATED
13500 N. CENTRAL EXPRESSWAY
P. O. BOX 5012 • DALLAS 22, TEXAS

18594

LEADING BRITISH ENGINEERING GROUP SEEKS U. S. LICENSEE FOR ELECTRONIC REMOTE SUPERVISORY CONTROL SYSTEMS

The systems available are applicable to oil and gas gathering and pipeline installations, to electricity distribution and to water supply systems.

The systems are digital, using exclusively solid state components and make efficient use of communication bandwidth whether it be on wire, radio or microwave.

The systems are designed to handle controls, monitoring data and numerical information.

A cross-license for an electronic or mechanical engineering product would be considered.

Interested firms are invited to apply for Preliminary Evaluation Report, enclosing copies of their own technical literature.

Replies should be addressed to:—

International Department A
The McCarty Company
116 New Montgomery Street
San Francisco 5, California

BOOKS OF SPECIAL INTEREST . . .

PHYSICS and TECHNIQUES OF ELECTRON TUBES (Vol. 1, Principles of Vacuum Techniques) R. Champeix, *Laboratories d'Electronique et de Physique Appliquée, Paris*

This authoritative work unites the best qualities which characterize French technical education —logic, perspicuity and simplicity. **Vol. I, approx. 160 pp. (1961) approx. $10.00**

THEORY of the TRANSMISSION and PROCESSING of INFORMATION
A. G. Vitushkin, Translation Editor, A. D. Booth, *Birbeck College*

A monograph dealing with the theory of the transmission and processing of information. Attempts to define mathematically the concept of the complexity of a tabulation problem by using concrete problems as examples. The formal definition of a concept of this kind, apart from its purely theoretical interest, is required in machine mathematics and, in the first instance, in the automation of programming. **224 pp. $15.00**

All books available for 14 days' free examination.

PERGAMON PRESS, INC. Dept. IR3 122 E. 55th St., New York 22, N. Y.

IRE People

(Continued from page 54A)

manager of the antenna and microwave department in 1955, and manager, antenna and microwave laboratory in 1960. Prior to joining Sylvania, Dr. Faflick was a research fellow at Harvard University for four years. He also served as an instructor at New Mexico State College for one year.

Dr. Faflick received a bachelor's degree from Oberlin College, Ohio, in 1943. Following graduation, he served with the U. S. Army Signal Corps for three years, during which time he attended the radar officers training course conducted jointly by Harvard University and the Massachusetts Institute of Technology. He received a doctor's degree in applied science from Harvard in 1953. While there, he was the recipient of the Sheldon traveling fellowship, which provided additional study at the Swiss Federal Technical Institute at Zurich, Switzerland.

Dr. Faflick is a member of Sigma Xi, honorary scientific fraternity, and a former chairman of the Boston chapter of the Institute of Radio Engineers' Professional Group on Microwave Theory. He is currently vice chairman of the Boston Section of IRE.

❖

John E. Fulenwider (M'57) has recently been appointed supervisor of Electronic Switching Techniques with the Research Department of Automatic Electric Laboratories, Inc., Northlake, Ill., a subsidiary of General Telephone and Electronics. In his new position, he will be responsible for the development of techniques for use in electronic telephone exchange switching equipment.

J. E. FULENWIDER

He formerly did engineering consulting work for Booz, Allen Applied Research, Glenview, Ill., an affiliate of Booz, Allen and Hamilton, management consultants. While with Booz, Allen, one of Fulenwider's assignments was with the Air Force Office of Intelligence, Dayton, Ohio, working on critical electronic projects.

He developed an interest in medical electronics while serving with the Army Medical Corps, and in July, he presented a paper before the Fourth International Conference on Medical Electronics, entitled "Model Study of the Cat Retinal Ganglion Cell System."

He holds the B.S. and M.S. degrees in electrical engineering from Northwestern University, Evanston, Ill., where he expects to receive his doctorate in January, 1962. He is a member of Eta Kappa Nu, honorary electrical engineering fraternity,

(Continued on page 60A)

ON THE SHELF—
ARNOLD CORES
IN WAREHOUSE STOCK
FOR IMMEDIATE DELIVERY

Let us handle your inventory problems and save you time and money on your magnetic core requirements.

Extensive stocks of four types of Arnold cores in the most popular sizes have been set up in our Marengo, Illinois and Fullerton, Calif. plants. Subject of course to temporary exhaustion of stock by prior sales, these cores will be shipped *the same day* on orders received at the warehouse by 12:00 noon. When cores are out of stock at the nearest plant, we may be able to ship within 24 hours from the other.

Arnold core products covered by this warehouse stock program include: 1) Silectron C, E and O cores in 2, 4 and 12-mil tape. 2) Type 6T aluminum-cased cores of Deltamax, Square Permalloy and Supermalloy, in 1, 2 and 4-mil tape. 3) Mo-Permalloy powder cores, both temperature-stabilized and unstabilized types, ranging down to "cheerio" sizes. 4) Iron powder toroids, threaded cores and insert cores.

All four products are available in a wide range of selection, for your convenience and economy in ordering either prototype design lots or regular production quantities. • Stock lists, bulletins, etc. are available—write for information. *The Arnold Engineering Company, Marengo, Ill.*

2998

ADDRESS DEPT. P-11

ARNOLD

SPECIALISTS in MAGNETIC MATERIALS

BRANCH OFFICES and REPRESENTATIVES in PRINCIPAL CITIES • *Find them FAST in the YELLOW PAGES*



28 Fields of Special Interest-

The 28 Professional Groups are listed below, together with a brief definition of each, the name of

Aerospace and Navigational Electronics

Annual fee: $3.

The application of electronics to operation and traffic control of aircraft and to navigation of all craft.

Mr. George M. Kirkpatrick, Chairman, General Electric Co., Syracuse, N.Y.

40 Transactions, *6, & *9, Vol 1, No. 3; Vol. 2, No. 1-3; Vol 4, No. 1, 2, 3; Vol, 5, No. 2, 3, 4; Vol. 6, No. 1, 2, 4: Vol. 7, No. 1, 2, 3, 4; Vol. 8, No. 1, 2.

Antennas and Propagation

Annual fee: $6.

Technical advances in antennas and wave propagation theory and the utilization of techniques or products of this field.

Dr. Harry Fine, Chairman, Applied Propagation Branch FCC, Washington, D.C.

38 Transactions, *Vol. AP-2, No. 2; AP-4, No. 4; AP-5, No. 1-4; AP-6, No. 1, 2, 3, 4; AP-7, No. 1, 2, 3, 4; AP-8, No. 1, 2, 3, 4, 5, 6; AP-9, No. 1, 2, 3, 4, 5.

Audio

Annual fee: $2.

Technology of communication at audio frequencies and of the audio portion of radio frequency systems, including acoustic terminations, recording and reproduction.

Prof. Cyril M. Harris, Chairman, Columbia University, 632 W. 125 St., New York 27, N.Y.

60 Transactions, *Vol. AU-1, No. 6; *Vol. AU-2, No. 4; Vol. AU-3, No. 1, 3, 5; Vol. AU-4, No. 1, 5-6; Vol. AU-5, No. 1, 2, 3, 4, 5, 6; AU-6, No. 1, 2, 3, 4, 5, 6; AU-7, No. 1, 2, 3, 4, 5, 6; AU-8, No. 1, 2, 3, 4, 5, 6; AU-9, No. 1, 2, 3, 4.

Automatic Control

Annual fee: $3.

The theory and application of automatic control techniques including feedback control systems.

Mr. John M. Salzer, Chairman, 909 Berkeley St., Santa Monica, Calif.

14 Transactions, PGAC-3-4-5-6, AC-4, No. 1, 2, 3; AC-5, No. 1, 2, 4; AC-6, No. 1, 2, 3.

Bio-Medical Electronics

Annual fee: $3.

The use of electronic theory and techniques in problems of medicine and biology.

Mr. George N. Webb, Chairman, Dept. of Med. Biophysical Div., Johns Hopkins Hospital, Baltimore 5, Md.

21 Transactions, 8, 9, 11, 12; ME-6, No. 1, 2, 3, 4; ME-7, No. 2, 3, 4; BME-8, No. 1, 2, 3.

Broadcast & Television Receivers

Annual fee: $4.

The design and manufacture of broadcast and television receivers and components and activities related thereto.

Mr. Robert R. Thalner, Chairman, Sylvania Home Electronics, Batavia, N.Y.

29 Transactions, *7, 8; BTR-1, No. 1-3, BTR-2, No. 1-2-3; BTR-3, No. 1-2; BTR-4, No. 2, 3-4; BTR-5, No. 1, 2; BTR-6, No. 1, 2, 3; BTR-7, No. 1, 2.

Broadcasting

Annual fee: $2.

Broadcast transmission systems engineering, including the design and utilization of broadcast equipment.

Mr. Raymond F. Guy, Chairman, 264 Franklin St., Haworth, N.J.

20 Transactions, No. 10, 11, 12, 13, 14; BC-6, No. 1, 2, 3,; BC-7, No. 1, 2, 3

Circuit Theory

Annual fee: $4.

Design and theory of operation of circuits for use in radio and electronic equipment.

Dr. James H. Mulligan, Jr., Chairman, College of Eng., New York University, New York 53, N.Y.

31 Transactions, CT-4, No. 3-4; CT-5, No. 1, 2, 3, 4; CT-6, No. 1, 2, 3, 4; CT-7, No. 2, 3, 4; CT-8, No. 1, 2.

Communications Systems

Annual fee: $2.

Radio and wire telephone, telegraph and facsimile in marine, aeronautical, radio-relay, coaxial cable and fixed station services.

Mr. Ralph L. Marks, Chairman, Rome Air Dev. Center, Griffiss AFB, N.Y.

22 Transactions, CS-5, No. 2, 3; CS-6, No. 1, 2; CS-7, No. 1, 3, 4; CS-8, No. 1, 2, 3, 4; CS-9, No. 1, 2.

Component Parts

Annual fee: $3.

The characteristics, limitation, applications, development, performance and reliability of component parts.

Mr. Floyd E. Wenger, Chairman, Headquarters ARDC, Andrews AFB, Washington 25, D.C.

24 Transactions, CP-4, No. 1, 2, 3, 4; CP-5, No. 1, 2, 3, 4; CP-6, No. 1, 2, 3, 4; CP-7, No. 1, 2, 3, 4; CP-8, No. 1, 2.

Education

Annual fee: $3.

To foster improved relations between the electronic and affiliated industries and schools, colleges, and universities.

Mr. George E. Moore, Chairman, Westinghouse Electric Corp., East Pittsburgh, Pa.

14 Transactions, Vol. E-1, No. 3, 4; E-2, No. 1, 2, 3, 4; E-3, No. 1, 2, 3, 4; E-4, No. 1, 2.

Electron Devices

Annual fee: $3.

Electron devices, including particularly electron tubes and solid state devices.

Mr. Willis A. Adcock, Chairman, Texas Instruments Co., Dallas 9, Tex.

34 Transactions, *Vol. ED-1, No. 3, 4; ED-3, No. 2, 4; ED-4, No. 2, 3, 4; ED-5, No. 2, 3, 4; ED-6, No. 1, 3; ED-7, No. 2, 3, 4; ED-8, No. 1, 2, 3, 4.

Electronic Computers

Annual fee: $4.

Design and operation of electronic computers.

Dr. A. A. Cohen, Chairman, Remington-Rand Univac, St. Paul 16, Minn.

39 Transactions, EC-6, No. 2, 3; EC-7, No. 1, 2, 3, 4; EC-8, No. 1, 2, 3, 4; EC-9, No. 1, 2, 3, 4; EC-10, No. 1, 2, 3.

Engineering Management

Annual fee: $3.

Engineering management and administration as applied to technical, industrial and educational activities in the field of electronics.

Mr. T. W. Jarmie, Chairman, Engineered Electronics, 1441 East Chestnut Ave., Santa Ana, Calif.

22 Transactions, EM-3, No. 2; EM-4, No. 1, 3, 4; EM-5, No. 1-4; EM-6, No. 1, 2, 3; EM-7, No. 1, 2, 3, 4; EM-8, No. 1, 2.

Engineering Writing and Speech

Annual fee: $3.

The promotion, study, development, and improvement of the techniques of preparation, organization, processing, editing, and delivery of any form of information in the electronic-engineering and related fields by and to individuals and groups by means of direct or derived methods of communication.

John M. Kinn, Jr., Chairman, IBM Journal, 545 Madison Ave., New York, N.Y.

9 Transactions, Vol. EWS-1, No. 2; EWS-2, No. 1, 2, 3; EWS-3, No. 1; EWS-4, No. 1, 2.

THE INSTITUTE OF RADIO

-IRE's 28 Professional Groups

the group chairman, and publications to date.

*** Indicates publications still available**

Human Factors in Electronics
Annual fee: $2.

Development and application of human factors and knowledge germane to the design of electronic equipment.

Mr. Robert R. Riesz, Chairman, Bell Tel. Labs, Murray Hill, N.J.

4 Transactions, HFE-1, No. 1, 2; HFE-2, No. 1, 2.

Industrial Electronics
Annual fee: $3.

Electronics pertaining to control, treatment and measurement, specifically, in industrial processes.

Mr. J. E. Eiselein, Chairman, RCA Victor Div., Camden, N. J.

16 Transactions, *PGIE 1, 3, 5, 6, 7, 8, 9, 10, 11; IE-7, No. 1, 2, 3; IE-8, No. 1, 2.

Information Theory
Annual fee: $4.

The theoretical and experimental aspects of information transmission, processing and utilization.

Dr. George L. Turin, Chairman, Dept. of E.E., Univ. of California, Berkeley 4, Calif.

27 Transactions, PGIT-4, IT-1, No. 3! IT-2, No. 3; IT-3, No. 1, 2, 3, 4; IT-4, No. 1, 2, 3, 4; IT-5, No. 1, 2, 3, 4; IT-6, No. 1, 3, 4, 5; IT-7, No. 1, 2. 3.

Instrumentation
Annual fee: $3.

Measurements and instrumentation utilizing electronic techniques.

Mr. Harvey W. Lance, Chairman, Natl. Bureau of Standards, Boulder, Colo.

20 Transactions, PGI-4, Vol. 1-6, No. 2, 3, 4; Vol. 1-7, No. 1, 2; Vol. 1-8, No. 1, 2; Vol. 1-9, No. 1, 2, 3; Vol. 1-10, No. 1.

Microwave Theory and Techniques
Annual fee: $3.

Microwave theory, microwave circuitry and techniques, microwave measurements and the generation and amplification of microwaves.

Mr. Tore N. Anderson, Chairman, EMT Corp., Syosett, Long Island, N.Y.

37 Transactions, MTT-4, No. 3; MTT-5, No. 3, 4; MTT-6, No. 1, 2, 3, 4; MTT-7, No. 2, 3, 4; MTT-8, No. 1, 2, 3, 4, 5, 6; MTT 9, No. 1, 2, 3, 4.

Military Electronics
Annual fee: $2.

The electronics sciences, systems, activities and services germane to the requirements of the military. Aids other Professional Groups in liaison with the military.

Mr. Willie L. Doxey, Chairman, EC Dept., USASRDL, Fort Monmouth, N.J.

13 Transactions, MIL-1, No. 1; MIL-2, No. 1; MIL-3, No. 2, 3, 4; MIL-4, No. 2-3, 4; MIL-5, No. 1, 2, 3.

Nuclear Science
Annual fee: $3.

Application of electronic techniques and devices to the nuclear field.

Mr. Louis Costrell, Chairman, N.B.S., Washington 25, D.C.

21 Transactions, NS-1, No. 1; NS-4, No. 2; NS-5, No. 1, 2, 3; NS-6, No. 1, 2, 3, 4; NS-7, No. 1, 2-3, 4; NS-8, No. 1, 2, 3.

Product Engineering & Production
Annual fee: $2.

New advances and materials applications for the improvement of production techniques, including automation techniques.

Mr. Alfred R. Gray, Chairman, Astronics of Florida, Inc., Orlando, Fla.

8 Transactions, No. 2-3, 4, 5, 6, PEP-5, No. 1, 2.

Radio Frequency Interference
Annual fee: $2.

Origin, effect, control and measurement of radio frequency interference.

Mr. Harold E. Dinger, Chairman, Naval Research Lab., Washington 25, D.C.

3 Transactions, RFI-1, No. 1, RFI-2, No. 1, RFI-3 No. 1.

Reliability and Quality Control
Annual fee: $3.

Techniques of determining and controlling the quality of electronic parts and equipment during their manufacture.

Mr. L. J. Paddison, Chairman, Sandia Corp., Sandia Base, Albuquerque, N.M.

21 Transactions, *3, 5, 10, 11, 12, 13, 14, 15, RQC-9, No. 1, 2, 3; RQC-10, No. 1, 2.

Space Electronics and Telemetry
Annual fee: $3.

The control of devices and the measurement and recording of data from a remote point by radio.

Mr. Kenneth V. Uglow, Chairman, Electro-Mechanical Research Inc., Sarasota, Fla.

19 Transactions, TRC-1, No. 2-3; TRC-2, No. 1; TRC-3, No. 2, 3; TRC-4, No. 1; SET-5, No. 1, 2, 3, 4; SET-6, No. 1, 2, 3-4; SET-7, No. 1, 2, 3.

Ultrasonics Engineering
Annual fee: $2.

Ultrasonic measurements and communications, including underwater sound, ultrasonic delay lines, and various chemical and industrial ultrasonic devices.

Dr. Vincent Salmon, Chairman, Stanford Research Inst., Menlo Park, Calif.

10 Transactions, PGUE, 5, 6, 7; UE-7, No. 1, 2; UE-8, No. 1.

Vehicular Communications
Annual fee: $3.

Communications problems in the field of land and mobile radio services, such as public safety, public utilities, railroads, commercial and transportation, etc.

Mr. Richard P. Gifford, Chairman, General Electric Co., Lynchburg, Va.

18 Transactions, 5, 8, 9, 10, 11, 12, 13; Vol. VC-9, No. 1, 2, 3; Vol.-10, No. 1, 2

USE THIS COUPON

Miss Emily Sirjane PG-11-61
IRE—1 East 79th St., New York 21, N.Y.
Please enroll me for these IRE Professional Groups
..... $ .....
..... $ .....
Name .....
Address .....
Place .....
Please enclose remittance with this order.
Professional group membership is limited to active IRE members.

ENGINEERS R⊙E® **1 East 79th Street, New York 21, N.Y.**

ISOLATORS

IN STOCK

from
2.6GC
to 40GC
...broadest
line of
waveguide
test
equipment isolators

■ All of your ferrite test equipment isolator needs are available *in stock* — competitively priced — from Ferrotec. In 8 waveguide sizes from 2.6GC to 40GC. Unique design provides rugged mechanical construction and a high degree of magnetic stability. New developments include coaxial test equipment isolators with octave bandwidth coverage in 3 units, from 1GC to 8GC.

Shown: x-band isolator *Write for Data Sheet*

Frequency Range MC	Waveguide Size	Isolation Min. db	Insertion Loss Max. db	VSWR Max.	Model No.	Price
2600- 3950	RG-48/U	20	1.0	1.20	I-151L	$340
3950- 5850	RG-49/U	25	1.0	1.15	I-152L	$240
5850- 8200	RG-50/U	30	1.0	1.15	I-153L	$220
7050-10000	RG-51/U	30	1.0	1.15	I-154L	$195
8200-12400	RG-52/U	30	1.0	1.15	I-155L	$190
12400-18000	RG-91/U	30	1.2	1.15	I-156L	$260
18000-26500	RG-53/U	25	1.5	1.15	I-157L	$280
26500-40000	RG-96/U	20	2.0	1.15	I-158L	$320

FERROTEC INC.

217 CALIFORNIA STREET • NEWTON 58, MASS.

Design • Development • Production
of microwave ferrite components

IRE People

(Continued from page 56A)

and of Sigma Xi, honorary graduate scientific fraternity. He is also a Registered Professional Engineer in Illinois and Ohio, and a member of AIEE.

❖

Paul Gottfried (SM'58) has joined Booz, Allen Applied Research, Inc., national scientific and technical consultants, as a reliability scientist in the company's Washington, D.C. offices. He will participate in projects the firm currently is conducting under contracts with the National Science and Space Administration, Department of Defense and industrial firms.

Prior to joining Booz, Allen Applied Research, Inc., he was a partner in Reliability Engineering Associates of Chicago. His earlier experience includes positions as a project director for the Inland Testing Laboratories, division of Cook Electric Company, and engineering positions in development and design for Chicago Aerial Industries, the Chambers Corporation and Charles N. Debes & Associates. He holds three industrial patents, has written a number of papers in the reliability and testing fields, and is a Registered Professional Engineer in Illinois. His professional memberships include Institute of Environmental Sciences, the IRE PGRQC Speaker's Who's Who List, American Institute of Electrical Engineers, National Society of Professional Engineers, and Tau Beta Pi.

Mr. Gottfried, born in Vienna, Austria, is now an American citizen. He was graduated from Rose Polytechnic Institute and pursued his advanced graduate studies at Illinois Institute of Technology and Northwestern University.

❖

Lieut. Commander Winford T. Higgins U. S. Navy, Ret., (M'60) has been appointed Assistant to the Marketing Vice-President at Intercontinental Electronics Corp., it was recently announced. He will assist in administrative operations and long range planning for the Marketing Division.

He is a recognized authority on air traffic control and was head of the Air Traffic Control and Air Navigation Aid Facilities Section in the Office of Chief of Naval Operations, Washington, D.C., prior to his recent retirement. He has completed 22 years of naval service which included executive assignments in anti-submarine warfare patrol and supervision of numerous ground controlled approach facilities.

❖

Appointment of **Robert J. Horak** (M'58) as marketing manager for transducer products, Consolidated Electrodynamics Corp., was announced recently. Horak joined the data processing marketing group of CEC, subsidiary of Bell & Howell Co., in 1959 as manager of strain-gage applications. Previously, he was an

(Continued on page 62A)

RMC "HEAVY DUTY"

BY-PASS DISCAPS®



SPECIFICATIONS

POWER FACTOR: 1.5% Max. @ 1 KC (initial)

POWER FACTOR: 2.5% Max. @ 1 KC (after humidity)

WORKING VOLTAGE: 1000 V.D.C.

TEST VOLTAGE (FLASH): 2000 V.D.C.

LEADS: No. 22 tinned copper (.026 dia.)

INSULATION: Durez phenolic—vacuum waxed

INITIAL LEAKAGE RESISTANCE: Guaranteed higher than 7500 megohms

AFTER HUMIDITY LEAKAGE RESISTANCE: Guaranteed higher than 1000 megohms

Type B DISCAPS meet or exceed all EIA RS-198 specifications for Z5U ceramic capacitors. Designed for by-passing, coupling, or filtering applications, Type B DISCAPS are manufactured in capacities between .00015 and .04 MFD.

A heavy ceramic dielectric element provides a safety factor where steady or intermittent high voltages occur. Type B DISCAPS show a minimum capacity charge between +10°C and +85°C (see curve).



DISCAP CERAMIC CAPACITORS

RMC

RADIO MATERIALS COMPANY
A DIVISION OF P. R. MALLORY & CO., INC.
GENERAL OFFICE: 4242 W. Bryn Mawr Ave., Chicago 46, Ill.
Two RMC Plants Devoted Exclusively to Ceramic Capacitors
FACTORIES AT CHICAGO, ILL. AND ATTICA, IND.

WOLLENSAK...

the shortest path

from glass to finished project.

We specialize in the design, development and manufacture of custom optical-mechanical devices. Our skills in the field of optics have solved complex optical-electro-mechanical problems for many of America's leading corporations. We are eager —and qualified—to work with you on your next project.

WRITE or call:

OPTO-MECHANICAL

WOLLENSAK

OPTICAL COMPANY • ROCHESTER 21, N. Y.

broaden the scope of your technical knowledge through Convenient, Accredited CREI Extension Programs

Prepare for new responsibilities by supplementing or up-dating your education with CREI advanced, specialized courses. Flexible Home Study Programs will fit your busy schedule.

ELECTRONIC ENGINEERING TECHNOLOGY including:

- COMMUNICATIONS ■ TELEVISION
- AERONAUTICAL AND NAVIGATIONAL
- SERVOMECHANISMS AND COMPUTER
- ENGINEERING MATHEMATICS
- AUTOMATION AND INDUSTRIAL ELECTRONICS
- NUCLEAR ENGINEERING TECHNOLOGY

HOME STUDY PROGRAMS • RESIDENCE SCHOOL

For full particulars write to:

THE CAPITOL RADIO ENGINEERING INSTITUTE

ECPD Accredited Technical Institute Curricula • Founded 1927

3224 Sixteenth St., N.W., Dept. 2611H

Washington 10, D.C.

IRE People

(Continued from page 60A)

engineer with the Marquardt Corp. and E. I. du Pont de Nemours & Co.

He has a B.S. degree in electrical engineering from the University of Kansas.

❖

Gerald W. Karlsruher (M'56) has joined S-F-D Laboratories as a senior mechanical engineer. He will be engaged primarily in product refinement and development of high power microwave tubes. He was formerly associated with the General Telephone and Electronics Laboratories, Bayside, N. Y., as head of the engineering services section. He is the author of several papers on electron tube fabrication techniques and holds patents in this area.



G. W. KARLSRUHER

He received his degree in Mechanical Engineering from the Polytechnic Institute of Brooklyn in 1951 and an M.S. in Mechanical Engineering from Columbia University in 1957. He presently serves on the national administrative committee of the IRE Professional Group on Product Engineering and Production. He is also a member of the Research Society of America, New York Society of Professional Engineers, the American Society of Mechanical Engineers, and Pi Tau Sigma.

❖

Harold W. Kaye (A'47–M'48) has been named to the new position of Technical Assistant to the Vice President and General Manager of Adler Electronics, Inc. Formerly Manager of Customer Liaison in the Military Products Division, he also has served as engineering project manager during his ten years with Adler.



H. W. KAYE

Mr. Kaye is a member of the Armed Forces Communications and Electronics Association, and the American Radio Relay League. A pioneer radio amateur, he has operated ham station W2KKE for over 30 years, and is a member of the Quarter Century Wireless Association.

❖

Frederick B. Llewellyn (A'23–F'28) will retire as assistant to the president of Bell Telephone Laboratories on September 1, 1961.

Dr. Llewellyn, who has had a 38-year career in the Bell System, has accepted an

(Continued on page 64A)

Microwave Sweep Oscillators

with

FLAT OUTPUT

Alfred Model 623BK Microwave Oscillator, featuring built-in leveler, drift less than ±.02% per hour, adjustable frequency markers and Quick Look Readout.

NEW in Alfred Series 620 Oscillators:

• BUILT-IN FEEDBACK LEVELER

Holds power output constant to ±¾ db over these ranges... 1 to 2, 1.4 to 2.5, 2 to 4, 4 to 8, 7 to 11 Gc. Feedback Leveler unique in holding output variation to approximately ±0.1 db over any 100 Mc interval. Feedback method makes RF flatness independent of RF level or microwave tube aging. Components being developed for leveling above 11 Gc.

• SYMMETRICAL NARROW BAND SWEEP

Up to ±5% of band width; about any center frequency. A significant time saver for component testing.

PLUS ALL THESE FEATURES, STILL EXCLUSIVE WITH ALFRED

- **Drift** — less than ±0.02% per hour.
- **Residual FM** — less than 0.0025% peak.
- **Adjustable Frequency Markers** — time-saving indicators of band limits or intermediate frequency values.
- **Quick Look Readout** — shows frequency range, markers and sweep time at a glance.
- **Ten Frequency Ranges, 1 to 26 Gc** — covering 1—2; 1.4—2.5; 2—4; 4—8; 6.5—11.5; 8—12.4; 8.2—12.4; 10—15.5; 12.4—18; 15—22; 18—26.5 Gc. (Internal leveling 1 to 11 Gc only.)
- **0.5 microsecond rise and fall response to AM** — equivalent to a 2 megacycle band pass.
- **Frequency accuracy** ±1% unswept or swept.
- **Direct coupled external sweep connection** — response dc to 10 kc. Ideal for external frequency programming.

GET **COMPLETE** DETAILS — Alfred's policy is to publish specifications — not to withhold them. All specifications are guaranteed as stated. For detailed information on Series 620 oscillators, contact your Alfred engineering representative or write to:

ALFRED ELECTRONICS

3176 Porter Drive, Palo Alto, California · Phone: DAvenport 6-6496

PUBLI-SERVICE PARIS

IN PARIS PORTE DE VERSAILLES
FROM 16TH TO 20TH FEBRUARY 1962

5th INTERNATIONAL EXHIBITION OF ELECTRONIC COMPONENTS

THE GREATEST WORLD MEETING IN THE FIELD OF ELECTRONICS

SALON INTERNATIONAL DES COMPOSANTS ÉLECTRONIQUES

FÉDÉRATION NATIONALE DES INDUSTRIES ÉLECTRONIQUES • 23, RUE DE LÜBECK PARIS-16e - PASSY 10-16

IRE People

(Continued from page 62A)

appointment as research physicist at the Institute of Science and Technology of the University of Michigan. He will assume responsibilities in connection with the planning and administration of the research program beginning in the fall 1961 term.

In 1923, he joined the Western Electric Company's Engineering Department, which was incorporated as Bell Laboratories in 1925. His early work was in radio research and later in studies of broadband amplification, signal-to-noise relations and high-frequency tube circuits. In 1935, he was awarded the Morris Leibmann Memorial Prize of the Institute of Radio Engineers for his work in high-frequency electronics and on constant frequency oscillators.

After World War II, he was engaged in consulting on systems engineering and was especially concerned with transoceanic and land repeater transmission systems. He was appointed assistant to the president of the company in 1956.

Dr. Llewellyn has served the government in several consulting capacities. He was a consultant to the Secretary of War in 1944 and 1945 and later served on the Weapons Systems Evaluation Group of the Joint Chiefs of Staff. He was Executive Secretary of the President's Science Advisory Committee of the Office of Defense Mobilization in 1951–1952.

He is a graduate of Stevens Institute of Technology and received the Ph.D. degree from Columbia University in 1928. He received the Stevens Honor Award from his alma mater in 1948 and has served as President of the Stevens Alumni Association and on the Institute's Board of Trustees.

He is active in professional affairs and is a Fellow and past president of the Institute of Radio Engineers. He is also a Fellow of the American Physical Society and the AAAS and a member of the Operations Research Society of America, Tau Beta Pi and Sigma Xi. In addition Dr. Llewellyn has served as a member of the Engineering Division of the National Research Council, the Electrical Standards Committee of the American Standards Association and the U. S. National Committee of the International Electrical Committee. He has also been a delegate to several international conferences on radio and telecommunications.

He has been granted 39 U. S. patents and is the author of numerous articles.

✣

Dr. D. E. Newell (S'52–A'53–M'58), who has been associate professor of electrical engineering at the State University of Iowa, has joined the staff of the Pioneer-Central division of The Bendix Corporation. He will assist in the expansion of the division's capabilities in the field of electronics and also will assume responsibilities for student research programs with local colleges and universities.

Dr. Newell is secretary of the Cedar Rapids Section of the IRE and a member

(Continued on page 68A)

To Contractors and Subcontractors on U. S. Government Projects

THE 1N3471 "PINHEAD"

Western Electric offers this new Microminiature Switching Diode from Laureldale

The 1N3471 is a diffused silicon microminiature switching diode designed for high-speed operation. The size and construction of this pinhead diode suit it for high-density packaging. Controlled manufacturing conditions assure the circuit designer of uniform lot-to-lot diode characteristics with exceptional performance and reliability. (A leaded version of the 1N3471 diode is also available.)





STRESS-TIME RELIABILITY

High-temperature life tests are conducted for 1000 hours to assure (with 90% confidence) a failure rate at 250°C of less than 5% per 1000 hours.

MAXIMUM RATINGS
(Mounting Surface Temp. 100°C)

BV	40 Min.
Power dissipation	0.5 Watt
Tstg	−65°C to +250°C
I_F	120 mAdc

SPECIFIED LIMITS FOR ELECTRICAL CHARACTERIZATION

trr ($I_F = I_R = 10$ mAdc)	2 nsec max.
V_f ($I_F = 10$ mAdc)	1 Volt dc
Is ($V_R = 20$ Vdc)	20 nAdc
C ($V_R = 0$; $f_o = 100$ kc)	3 pf
BV ($I_R = 5$ μAdc)	40 Vdc

The 1N3471 microminiature switching diode can be purchased in quantity from Western Electric's Laureldale Plant. For technical information, price, and delivery, please address your request to: Sales Department, Room 106, Western Electric Company, Incorporated, Laureldale Plant, Laureldale, Pa. Telephone—Area Code 215—WAlker 9-9411.

LAURELDALE PLANT
MAKER OF ELECTRON PRODUCTS
FOR U. S. MILITARY AND SPACE APPLICATIONS

Western Electric
MANUFACTURING AND SUPPLY UNIT OF THE BELL SYSTEM



3-channel, high isolation, low insertion loss multiplexer

Telemetry Antenna Multiplexer

Rantec multiplexers are used on a large number of missile and space programs, includi Mercury, Titan, Polaris, Discoverer, Midas, Nike Zeus, Nike Hercul Subroc, Samos, X-17, Centaur, etc.

Airborne antennas
ommunication, beacons
nd radar augmentation



Helix array for telemetry tracking systems

Antennas

Rantec tracking antennas are currently in operation at missile ranges throughout the free world. In addition, Rantec's airborne antennas are in quantity production for major missile and airframe programs.



5-channel, high isolation, low insertion loss multiplexer – 225-260 Mc



Dipole array for telemetry tracking systems



Two-dimensional "flat plate" slot array for missile tracking and guidance – monopulse or electronically conical scan applications

rantechnology

Over the years, a company normally becomes "pegged" into one or two specific categories of interest. Rantec has variously been described as "those people who make antennas" or "they're in ferrites." We would like to take this opportunity of outlining Rantec's broad level of design, development and production capability.



S-Band monopulse tracking feed, integral L-band monitoring dipole

X-band single sideband modulator



X-band high speed switch



Antenna Feed Systems

Rantec feed assemblies are used on parabolic tracking and acquisition antennas ranging in size from 10 to 85 feet.





400 Mc remotely controlled rotatable linearly polarized tracking feed – hybrid assembly – drive





Airborne
4-channel multiplexer

Coax, diplexing filter,
2300 Mc and 2900 Mc



X-band
multiplexing filter



Strip line diplexing filter,
L-band and S-band





Airborne
3-channel multiplexer

Filters

In addition to the units shown, Rantec has developed many other filters for special applications. An impressive staff of engineers is available to handle complicated "state-of-the-art" problems.

890 Mc-960 Mc high power,
diplexing filter



Precision microwave phase
measurement system with
automatic frequency swept display



ınd monopulse
simulator





Band pass filter, 15 watt
CW unpressurized, 2200-2300 Mc

Special Test Equipment and R-F Sub-Systems

From the number of essential microwave components available in Rantec's standard line, considerable flexibility exists for designing special test equipment, simulators and radar sub-systems.



C-band doppler simulator,
using ferrite single sideband modulator

Radar
sub-system, X-band



power, broadband,
d ısolator



20% bandwidth S-band
Y-junction circulator



Dual channel C-Band
parametric amplifier system

Stabilized parametric
amplifier power supply



Parametric Amplifiers

Rantec's line of broadband, low insertion loss, ferrite devices and filters assure optimum performance of complete parametric amplifier systems. A variety of stable, low noise parametric amplifiers is available.

Ferrite Devices

ide variety of advanced ferrite devices is available in frequency ranges from below L-band through K-band.



C-band high power,
low VSWR circulator,

These products are "typical" of Rantec's know-how, but represent only a part of the total picture. Write or call Rantec for complete product information in any of the above categories.

rantec

RANTEC CORPORATION
CALABASAS, CALIFORN



LOW NOISE CHOPPER "TECHNIQUE REPORT" offered on request

IN DC INSTRUMENTATION

THE LOWEST NOISE AND DRIFT CHOPPERS ARE JAMES

The measure of how low or stable a level of DC signal can be modulated by a chopper is a complexed analysis of circuit and component. JAMES has prepared a complete technical review of measurement techniques and correct use of mechanical choppers.

On all criteria . . . magnetic, electrostatic, triboelectric, electrochemical noise and thermal drift JAMES has the superior components. The correct chopper for commercial, industrial and military.

Write for your free copy of "Chopper Noise Sources and Measurement Techniques." We solicit your chopper engineering application inquiries.

PERFORMANCE • RELIABILITY • SERVICE

JAMES®
ELECTRONICS INC.
4050 North Rockwell • Chicago 18, Illinois • CO 7-6333

IRE People

(Continued from page 64A)

of Sigma Xi, Eta Kappa Nu, and the Iowa Academy of Science. He received his Ph.D. degree in 1958 from the State University of Iowa.

❖

Edward H. Lillibridge (A'54–M'60) formerly assistant program manager for Litton Systems, has joined MS&A, computer consultants in Hawthorne, Calif.



E. H. LILLIBRIDGE

At Litton, he participated in the development of computers for aircraft navigation and fire control. His previous experience also includes work on the Atlas ICBM Guidance and Control System. In his position as a senior consultant with MS&A, he will assist clients in the application of advanced computer technology in various military systems.

❖

Wayne R. Lundberg (M'58) has joined S-F-D laboratories as a senior mechanical engineer. He will be engaged primarily in the development of high power magnetron tubes, particularly those for high resolution detection radars.



W. R. LUNDBERG

Mr. Lundberg was formerly associated with the Western Electric Company, Laureldale, Pa. as department chief of the product engineering department. His work there included the development of advanced techniques related to the production refinement of advanced magnetrons.

He received his degree in Electrical Engineering from Iowa State University in 1956.

❖

Walter A. Mainberger (S'43–A'45–M'51–SM'58) former manager of the electronic systems department of National Co., Inc., has been appointed technical assistant to the vice president for technical operations of Dunn Engineering Corp., Cambridge, Mass.

W. A. MAINBERGER

Mr. Mainberger was with National from 1955 until he resigned to join Dunn. Previously he had served as

(Continued on page 70A)

DC to 5000 cycles over an amplitude of 4" peak to peak

NEW SANBORN "650" SYSTEM OFFERS DIRECT READOUT, 8 TO 24 CHANNELS, ALL SOLID STATE CIRCUITS, FOR RACK MOUNTING OR INDIVIDUAL CASES.

Here's the *one* system that lets you record inputs from DC to 5 KC within 3 db at 4" peak-to-peak amplitudes, without changing galvanometers. The "650" system consists of an 8-channel medium gain, general purpose amplifier unit driving a high speed, high resolution optical oscillographic recorder. It can be easily built into your system, packaged in a mobile cabinet or housed in individual cases. The single-chassis, 7" high amplifier module has 8 separate channels, *complete from floating and guarded inputs to galvanometer outputs;* each channel comprises a front end modulator and input transformer, carrier amplifier, demodulator, filter and driver amplifier. Power Supply and Master Oscillator Power Amplifier are built-in. All amplifier elements are plug-in transistorized units for easy servicing.

Immediately readable recordings are made on 8" wide daylight-loading ultra-violet-sensitive charts which require no chemical development. Features of the 12¼" high recorder unit include 9 electrically controlled chart speeds from ¼" to 100"/sec; calibrated monitoring screen; automatic trace identification and timing lines at 0.01 or 0.1 sec. intervals; amplitude lines spaced 0.1" apart which can be blanked from ¼, ½, ¾ or all of chart. Recorder is available with an 8-, 16- or 24-channel galvanometer block which is then equipped with the number of galvanometer elements desired by the customer. Either the Recorder or Amplifier are also available as individual units for use with other equipment.

SENSITIVITY 20 mv input gives 8" deflection; 12 attenuator steps to X5000, smooth gain control.

INPUT RESISTANCE 100,000 ohms all ranges, floating and guarded; DC source resistance must be kept below 1000 ohms on mv ranges only.

COMMON MODE PERFORMANCE Rejection at least 140 db at DC, tolerance to ±500 volts, max.

GAIN STABILITY Better than 1% to 50° C. and for line voltage variation from 103 to 127 volts.

LINEARITY 1½% of full scale (8 in.)

NOISE 0.02" peak-to-peak, max.

MONITOR OUTPUT On front panel; provides ±1v full scale across 100,000 ohm load

POWER REQUIREMENTS 103-127 volts, 60 cycle AC, 625 watts

Contact your Sanborn Sales-Engineering Representative for complete specifications and applications engineering assistance. Offices throughout the U. S., Canada and foreign countries.

SANBORN COMPANY
INDUSTRIAL DIVISION
175 Wyman St., Waltham 54, Massachusetts

IRE People

(Continued from page 68A)

project manager with W. L. Maxson Corp., and senior engineer with Federal Telecommunications Laboratories Division of International Telephone and Telegraph Co.

He holds an engineering degree from New York's City College (1943) and a master's in electrical engineering from New York University (1951). He is a Registered Professional Engineer in Massachusetts.

❖

Alvin R. Margolin (S'46–A'49–M'55–SM'58) has recently established an office as private consultant at 16218 Ventura Blvd., Encino, Calif.

A. R. MARGOLIN

He was formerly with the Microwave Tube Division of Hughes Aircraft Co. as Project Engineer. He has had fourteen years experience in the design, development, testing and production of microwave systems, subsystems, components, and tubes. His services will be available to anyone with problems related to his fields of specialization, or to other areas relating to microwaves.

He received the B.S. degree from Iowa State University, Iowa City, in 1944, the M.S. degree in 1947 and the Engineering degree in 1949, the two latter degrees from Stanford University, Stanford, Calif.

Mr. Margolin is a member of the Los Angeles Chapter of the IRE and of the Professional Groups Coordinating Committee.

❖

The Hazeltine Corporation of Little Neck, N. Y. has announced the appointment of **G. B. McClellan** (SM'46) as Head of the company's Test Engineering Department.

G. B. MCCLELLAN

Mr. McClellan joined Hazeltine in 1945. As Chief Test Engineer, he has administrative cognizance of both the Test Engineering Division and the Publications Division. He attended Lawrence College in Appleton, Wis.

❖

Edward F. Moore (A'53–M'58) a member of technical staff at Bell Telephone Laboratories in Murray Hill, N. J., will serve as a faculty member at Harvard and Massachusetts Institute of Technology during the academic year 1961–62. He will be a Visiting Professor of Electrical Engineering at M.I.T., and a Gordon McKay

(Continued on page 72A)

BUCKBEE MEARS IS VERSATILE!

MASKS, GRIDS, SIEVES . . .
Components etched and electroformed

MATERIALS

Glass, Metal

SIZE

From Transistor Evaporation Masks
to 20 Ft. Radar Screens

ACCURACY

± .000039 Inches.

PRODUCTION KNOW HOW

When volume warrants we design and build automatic equipment. One such machine emulsifies cold rolled steel strip, prints, washes and etches 441,222 perfect holes in 21 inch color TV masks at the rate of 120 per hour—automatically.



Photo-mechanical etchings on glass have been mass produced at BMC to an accuracy that was unbelievable just a few years ago. Configurations, scales and calibrations are etched to specified depths and widths to tolerances of .0001.

Evaporation masks in micro miniature sizes, micro mesh sieves and screens are standard production at BMC.

Anything that can be drawn can be reproduced. Because the master is made photo-mechanically small runs are made at moderate cost.

To test the accuracy of our production and the flexibility of our thinking, just send us one of your problems.

buckbee mears

247 E. 6th STREET • ST. PAUL 1, MINNESOTA

NOW... SSB STABILITY

AND... Continuously Variable



DIGITALLY TUNED EXCITER

Unequalled stability, accuracy, legibility and operational versatility are provided by this new self-contained continuously variable Frequency Synthesizer Type DTO-23. It provides stability of 1 part in 10^6 and continuous frequency coverage with ample power output from 2 to 32 Mc/s* in 4 automatically tuned bands. Outstanding readout legibility results from the employment of four decades of direct reading neon indicators plus one continuously variable dial calibrated from 000 to 999 cycles per second. Digital Tuning and complete absence of charts, graphs and verniers ensures exceptional operational simplicity. Frequency adjustments are accomplished by means of 3 decade switches and one continuously variable dial. Foolproof internal calibration is arranged to provide ten single check frequencies for the cycles dial without possibility of error.

* *Actual upper frequency limit 31.999999 Mc/s.*

FEATURES

- 1 Part in 10^6 Stability
- Readout Legibility
- Digital Tuning
- Self-Contained
- Autotracking Multipliers
- Self-Checking
- Modular Construction
- Error Proof Calibration
- Functional Simplicity

SALIENT SPECIFICATIONS

FREQUENCY:	2 to 32 Mc
STABILITY:	1 part in 10^6*
POWER OUTPUT:	2 watt, 2-8 Mc .5 watt, 8-32 Mc
OUT IMPEDANCE:	75 ohms
OUTPUT SOURCE:	Digitally Tuned Oscillator OR one of four CR27 crystals
ALL SPURIOUS:	40 db or better

* Digitally Tuned Oscillator only.

Another new development from

FV TOPPING ELECTRONICS LIMITED

94 Laird Drive, Toronto 17, Ontario.

IRE People

(Continued from page 70A)

Visiting Lecturer on Applied Mathematics at Harvard.

Dr. Moore, who joined the Laboratories in 1951, received a B.S. degree in chemistry from Virginia Polytechnic Institute in 1947, and the M.S. and Ph.D. degrees in mathematics from Brown University in 1949 and 1950, respectively.

Since joining the Laboratories, Dr. Moore has worked in the switching research and mathematical research departments, with emphasis on switching circuit theory and automata theory, including the theory of self-reproducing machines. He holds 4 patents on switching circuits, and is the author of numerous technical articles.

Dr. Moore is a member of the American Mathematical Society, the Society for Industrial and Applied Mathematics, the Association for Symbolic Logic, and the Association for Computing Machinery. He is also a member of Phi Lambda Upsilon, Phi Kappa Phi, and Sigma Xi, honorary professional fraternities.

Dr. Moore will return to Bell Laboratories at the end of June, 1962.

❖

C. Ray Porter (A'60) has been named manager of Aerospace Corporation's New England office at Lexington, Mass. He will serve as liaison representative in administration and personnel matters for the company.

C. R. Porter

Prior to joining Aerospace Corporation, Porter headed his own management firm, and served in various managerial positions with the Philco Corporation, Arma Corporation and Goodyear Aircraft Corporation. A Navy veteran of World War II and Korean War, he was born in New York City, earned his B.A. degree from Lafayette College and received post-graduate training at the University of Pennsylvania.

❖

Delmer Ports (A'38–SM'45), Vice president of Jansky and Bailey, Division of Atlantic Research Corporation, and **Edward Mischler** (SM'56), Vice President of National Engineering Service, have been elected Directors of White Electromagnetics, Inc., it was announced recently.

The firm recently changed its name from Don White Associates to White Electromagnetics, Inc. The firm deals principally in RFI prediction and control, space communications systems and design, weapons system evaluation, system evaluation by computer simulation, and other phases of systems analysis.

❖

(Continued on page 74A)



NORAD ON THE ALERT

Inputs from BMEWS Provide Instantaneous Missile Data Direct to NORAD Headquarters

From our vast outer defense perimeter, over thousands of miles, to the nerve center of the North American Air Defense Command at Colorado Springs, the most advanced concept of data handling and checkout is being utilized in the BMEWS system. The stakes are high, for the purpose is defense of the North American Continent.

At BMEWS installations operated by USAF Air Defense Command, computers read out missile tracking data from giant radars. This information is simultaneously relayed to NORAD's Combat Operations Center.

The Radio Corporation of America is prime systems contractor for BMEWS. At the COC, RCA's Display Information Processor computing equipment automatically evaluates missile sightings, launch sites and target areas. By means of data processing and projection equipment installed by RCA and a team of other electronics manufacturers, the findings are displayed on huge, two-story high map-screens in coded color symbols, providing the NORAD battle staff with an electronic panorama of the North American and Eurasian land masses.

The handling of BMEWS inputs at NORAD is an example of how RCA data processing capabilities are assuring the high degree of reliability so vital to continental defense.

Out of the defense needs of today a new generation of RCA electronic data processing equipments has been born. For tomorrow's needs RCA offers one of the nation's foremost capabilities in research, design, development and production of data processing equipment for space and missile projects. For information on these and other new RCA scientific developments, write Dept. 434, Defense Electronic Products, Radio Corporation of America, Camden, N. J.

RCA®

The Most Trusted Name in Electronics

RADIO CORPORATION OF AMERICA

Mr. RAFRIN*
got your goat?

He'll take other things, too, including accurate telemetering signals, clear radar displays, correct computer answers — almost anything in the electronics communication field can fall victim to this menace. May we recommend our protection? Electro ● International has satisfied Military requirements governing RFI Control for over a decade — all over the world. Write for our RFI Control Capabilities Brochure.

*RAdio FRequency INterference TM

ELECTRO INTERNATIONAL INC
Box 391, Annapolis, Md., CO.3-2661
Subsidiary of Electro Instruments, San Diego, Cal.

IRE People

(Continued from page 72A)

Alfred J. Poté (A'41–SM'48–F'59), prominent communications-electronics engineer and former Vice President, Itek Corporation, has recently been elected Senior Vice President and Assistant to the President of Page Communications Engineers, Inc.

A. J. Poté

Mr. Poté, who has over thirty years experience in communications and electronics engineering which includes basic research as well as practical application of advanced communications developments, assumes a newly created position where he will be chiefly responsible for the company's growth and diversification planning.

Before assuming the Vice Presidency of Itek Corporation, he was President of Itek's Hermes Electronics Division. Earlier he served at the Lincoln Laboratory of the Massachusetts Institute of Technology as Head of the Communications Systems Design Group, where he was responsible for development of components, transmitters, receivers and other equipments for voice, telegraph, teleprinter, and data transmission systems. He conducted basic research on VHF and UHF scatter propagation systems in which radio signals are reflected from the ionosphere or troposphere for long distance transmission.

He was a Consultant on radio communications to the Department of Defense and to the various departments of the Lincoln Laboratory in connection with defense projects. He also directed experimental programs for the Voice of America. During World War II, he led the LORAN (ship-to-shore communications) equipment development group at the Radiation Laboratory, M.I.T., where he was engaged in the research and development of LORAN transmitters, modulators, and antennas. He was LORAN consultant to the U. S. Navy Bureau of Ships, AAF, DuMont, GE, Sperry, RCA, and Bendix.

Mr. Poté is the inventor of the saturable core voltage regulator as well as other inventions in the communications-electronics field. He has produced equipment designs for high power radio-frequency installations such as frequency-modulated cyclotrons, large broadcasting stations, and industrial heat-treatment apparatus.

He received his B.S.E.E. degree from M.I.T. in 1926. He is a Fellow in the American Association for the Advancement of Science.

❖

The appointment of **Dr. Jan A. Rajchman** (SM'46–F'53), nationally-known pioneer in computer research, as Director of

(Continued on page 76A)

new —

A COMPLETE RANGE OF
"HI-POT" TESTERS
AND
POWER SUPPLIES



Model No. 30 HPT-3-1

DEL "HI-POT" TESTER MODELS

Model No.	Voltage Range Full Load	Current Range MA	Regulation % / MA	Ripple % RMS/MA	Size	Polarity
2.5 HPT-2-1	0-2,500	2	13	0.30	9½" x 11" x 12"	Reversible
5 HPT-2-1	0-5,000	2	9	0.20	9½" x 11" x 12"	Reversible
10 HPT-1-1	0-10,000	1.25	15	0.45	9½" x 11" x 12"	Reversible
15 HPT 1-1	0-15,000	1.25	11	0.30	9½" x 11" x 12"	Reversible
20 HPT-1-1	0-20,000	1.25	10	0.30	9½" x 11" x 12"	Reversible
20 HPT-5-1	0-20,000	5	4	0.50	9½" x 11" x 12"	Reversible
30 HPT-3-1	0-30,000	3	4	0.50	9½" x 11" x 12"	Reversible
40 HPT-2-1	0-40,000	2	7	0.30	20" x 12" x 14"	*Positive
50 HPT-1-1	0-50,000	1	10	0.50	20" x 12" x 14"	*Positive
60 HPT-1-1	0-60,000	1	10	0.50	20" x 12" x 14"	*Positive

* Negative Polarity available on special order

Compact-Portable
●
Zero Start Interlock
●
Over-Voltage Protection
●
Surge Limiting Protection
●
Input: 115 V, 60 cycles

WRITE FOR DATA

DEL ELECTRONICS CORPORATION
521 HOMESTEAD AVENUE • MOUNT VERNON, N. Y. • OWENS 9-2000

A TRIO OF TUNABLE FERRITE POT CORES FOR TRANSFORMER & INDUCTOR APPLICATIONS

This Trio was carefully designed to fulfill several levels of required accuracy of performance and adjustment. Decide on the precision required for your particular application and select the assembly for the job. Many features are common to all three tunable ferrite cores, such as (1) close permeability tolerances;* (2) very high "Q" for applications up to 3 Mc; (3) excellent linear temperature stability; (4) ease of assembly; (5) ease of "vernier" adjustment. Interested? Write us today for the full story.

1.

FERROXKOR®

The unexcelled optimum in a precision assembly. All factors fully controlled to obtain precision adjustability and stability. Minimum tuning range of 14%. Final adjustment accuracy of 0.02%. Unique, labor-saving, ruggedly constructed hardware allows accurate and repeatable re-alignment of pot core halves. Easy disassembly. Effective electrostatic shielding. Full selection of stock assemblies available. Complete with individual design data.



2.

FERROXKOR® STAGE IV

Precision made, optimized ferrite pot cores and tuning assembly. Minimum tuning range of 14%. Assembled with simple, clamp-type hardware. For applications where size is of prime importance, or where slightly less precision can be tolerated.



3.

INTERNATIONAL SERIES

Utilizes new optimized pot core design in industry-wide standard sizes. Versatile line in a variety of ferrite materials. Ideally suited where less precision than that afforded by FERROXKOR is required. Newly engineered metal-plastic tuning assembly offers 10% tuning range with 0.1% accuracy.

(Also available with interchangeable, all-polystyrene tuning mechanism providing an accuracy of 0.5%).



*All assemblies use precision ferrite pot core sets which are electrically pre-adjusted to allow ±3% inductance pre-calculation of the assembled inductor.

FERROXCUBE CORPORATION OF AMERICA
SAUGERTIES, NEW YORK • FOREMOST IN THE FIELD OF FERRITE

WRAP-AROUND MAGNETIC SHIELDS

...APPLIED IN SECONDS

Economical CO-NETIC & NETIC Magnetic Shielding Foils

For Any Size or Shape Components

Netic and Co-Netic foils are universally used as an evaluation tool; ultimately, as a production solution. Available in continuous lengths on rolls up to 15″ wide . . . for human production line or to fit automated existing reels of your tape serving machinery. Furnished in final annealed state ready for your operation.

HOW YOU SAVE SPACE, WEIGHT, TIME, MONEY

Minimum weight and displacement shielding designs are possible due to the magnetic shielding effectiveness of Co-Netic and Netic foils . . . foils can be supplied FROM .002″, even thinner if you desire. Ordinary scissors cut foil easily to exact contour and size required. Foil can be wrapped quickly around hard-to-get-at components, saving valuable time, minimizing tooling costs.

HOW TO INCREASE RELIABILITY

Guard against performance degradation from unpredictable magnetic field conditions to which your equipment may be exposed. Eliminate such failure or erratic performance possibilities with dependable Co-Netic and Netic protection . . . assuring *performance repeatability* for your device over a *wider range* of magnetic field conditions.

Co-Netic and Netic alloys are not affected significantly by dropping, vibration or shock. They are characterized by low magnetic retention and do not require periodic annealing. When grounded, they effectively shield electrostatic as well as magnetic fields over a wide range of intensities.

Every satellite and virtually all guidance devices increase reliability with Netic and Co-Netic magnetic shielding alloys. Use these highly adaptable foils for saving valuable space, weight, time and money . . . in solving your magnetic shielding problems for military, commercial and laboratory applications.

PHONE YOUR NEAREST SALES OFFICE TODAY:

MERIDEN, CONNECTICUT, BEverly 7-9232
UNION CITY, NEW JERSEY, UNion 4-9577
BALTIMORE, MARYLAND, HOpkins 7-3766
DECATUR, GEORGIA, 378-7516
CORAL GABLES, FLORIDA, HIghlands 3-7439
MAITLAND, FLORIDA, MIdway 7-7830
ST. PETERSBURG, FLORIDA, WAverly 1-9735
DALLAS, TEXAS, FLeetwood 1-1615
HOUSTON, TEXAS, HOmestead 5-7780
ALBUQUERQUE, NEW MEXICO, AMherst 8-6797
PHOENIX, ARIZONA, AMhurst 4-4934
SAN DIEGO, CALIFORNIA, BRowning 8-6230
LOS ANGELES, CALIFORNIA, WEbster 1-1041
PALO ALTO, CALIFORNIA, DAvenport 1-5064
SEATTLE, WASHINGTON, EA 3-8545
MONTREAL, QUEBEC, WEllington 7-1167

MAGNETIC SHIELD DIVISION

Perfection Mica Company

1322 N. ELSTON AVENUE, CHICAGO 22, ILLINOIS

ORIGINATORS OF PERMANENTLY EFFECTIVE NETIC CO-NETIC MAGNETIC SHIELDING

IRE People

(Continued from page 74A)

the Computer Research Laboratory at RCA's David Sarnoff Research Center, was announced recently.

Dr. Rajchman, whose contributions include the magnetic core memory system used for information storage in virtually all modern computers, has for the past few years headed an RCA Laboratories group in the development of high-speed techniques for computers up to 1,000 times faster in operation than those in use today.

Dr. Rajchman, who has been with RCA since 1935, was born in 1911 in London, England. He attended the College de Geneve in Geneva, Switzerland, and the Swiss Federal Institute of Technology, where he received the degree of Doctor of Science. As a research engineer with the RCA Manufacturing Company from 1936 to 1942, he made pioneering contributions to the development of the electron multiplier tube. During World War II, he was among the first to apply electronic techniques to computers, in response to the urgent military need for improved fire-control methods.

In 1942, Dr. Rajchman was transferred to the newly-established RCA Laboratories at Princeton as a member of the technical staff. Resuming work on computers after the war, he developed a succession of new information storage techniques and devices, beginning with the "Selectron" electrostatic storage tube and continuing through the magnetic core memory, magnetic switching circuits, the transfluxor, and the magnetic plate memory. He was named an Associate Laboratory Director, RCA Laboratories, in 1959.

In 1960, Dr. Rajchman received the Morris Liebmann Memorial Prize of the Institute of Radio Engineers for his work on magnetic devices for information processing. In addition, he has won a number of RCA Achievement Awards for his contributions in this and other fields.

Dr. Rajchman is a member of the American Physical Society and a member of the Association of Computing Machinery and Sigma Xi.

❖

A ceremony honoring the 35th anniversary of radio station WWRL on Friday, August 25th, was held at City Hall where Mayor Robert F. Wagner presented a certificate of merit to **William H. Reuman** (A'25), owner and founder of the station.

In a broadcast direct from City Hall, Mayor Wagner congratulated WWRL for its long service to the community and, "by concentrating a major portion of its broadcast week for the benefit of various communities, WWRL makes an invaluable contribution to our cultural advancement and social welfare."

WWRL, New York, started in August, 1926, in the living room studio of the owner-founder's home. Today, WWRL operates on 5,000 watts and still airs its programs on the original site from which

(Continued on page 78)



SAME-DAY SHIPMENT of standard panel meters. DISTRIBUTORS, 26 in key cities throughout the country, insure you same-day shipment on all standard Honeywell Meters and prompt handling of all orders for our top-quality instruments. Just get in touch with our stocking distributor nearest you, (You'll find him listed above), our Sales Representatives, or contact us directly: PRECISION METER DIVISION, Minneapolis-Honeywell Regulator Company, Manchester, N. H., U. S. A. In Canada, Honeywell Controls Limited Toronto 17, Ontario, Honeywell International Sales and Service Offices in all principal cities of the world."

Honeywell

H Precision Meters

Another New High Order of Reliability!

El-Menco *MYLAR-PAPER DIPPED CAPACITORS TYPE MPD

ASSURE A LOW FAILURE RATE OF

Only 1 Failure in ~~7,000,000~~ Unit-Hours for 0.1 MFD Capacitors★

14,336,000

Setting A New High Standard Of Performance!

★ Life tests have proved that El-Menco Mylar-Paper Dipped Capacitors — tested at 105°C with rated voltage applied — have yielded a failure rate of only 1 per 1,433,600 unit-hours for 1.0-MFD. Since the number of unit-hours of these capacitors is inversely proportional to the capacitance, 0.1 MFD El-Menco Mylar-Paper Dipped Capacitors will yield ONLY 1 FAILURE IN 14,336,000 UNIT-HOURS.

CAPACITANCE AND VOLTAGE CHART

- *Five case sizes in working voltages and ranges:*

200 WVDC —	.018 to .5 MFD
400 WVDC —	.0082 to .33 MFD
600 WVDC —	.0018 to .25 MFD
1000 WVDC —	.001 to .1 MFD
1600 WVDC —	.001 to .05 MFD



Write for Technical Brochure

*Registered Trade Mark of DuPont Co.

THE ELECTRO MOTIVE MFG. CO., INC.

Manufacturers of El-Menco Capacitors

WILLIMANTIC CONNECTICUT

• molded mica • mica trimmer • dipped mica • silvered mica films
• tubular paper • mylar-paper dipped • ceramic feed-thrus • ceramic discs

Arco Electronics, Inc., Community Drive, Great Neck, L.I., New York
Exclusive Supplier To Jobbers and Distributors in the U.S. and Canada
WEST COAST MANUFACTURERS CONTACT:
COLLINS ELECTRONIC SALES, INC., 535 MIDDLEFIELD ROAD, PALO ALTO, CALIFORNIA

electronics center of the east



$100 MILLION IN ELECTRONICS SALES

Fort Monmouth's Research & Development Laboratory, the U. S. Army Signal Equipment Support Agency, & Signal School form a mecca for many Electronic leaders of the nation. Here are Bell Laboratories, Bendix, Electronic Associates, Frequency Standards and many others. Superb living conditions afford easy recruiting of professional Engineers, Scientists, Technicians, skilled, trained personnel. You are invited to join this BLUE CHIP LIST.

Monmouth County NEW JERSEY

Write: REID N. DICKERSON, Industrial Representative
Monmouth County Planning Board
18 Court Street, Freehold, N. J., HOpkins 2-1940

(Continued from page 76A)

the station's first broadcast was launched. However, the living room studio has been replaced by a modern two-story brick building housing streamlined air-conditioned studios and executive offices. Mr. Reuman's longevity of ownership of WWRL for 35 years is unparalleled in the history of radio in New York.

❖

Francis L. Ross (M'59) has been named sales manager of Micromodular Components Division of Ling-Temco-Vought, Inc. His extensive experience in engineering and sales includes work as sales engineer for Sylvania Electric Products Inc., and the Semiconductor Division of Hughes Aircraft Company. He also completed Pacific Telephone and Telegraph Company's engineer executive training program.



F. L. Ross

Ross holds a B.S. degree in engineering from the University of California at Los Angeles, where he also did graduate work. He served as an officer in the Marine Air Corps.

❖

The appointment of **Laurue D. Rexroat** (M'53) as manager of Government Relations, Western Region, for Sylvania Electronic Systems, a division of Sylvania Electric Products Inc., has been announced recently. In his new capacity, he is responsible for marketing and customer relations in the western region of the country, including Alaska and Hawaii, and will make his headquarters at Santa Monica, Calif.

Prior to joining Sylvania, he was President and a member of the Board of Directors of the U. S. Science Corporation, Los Angeles, Calif. He served with the U. S. Air Force from 1941–1945 and from 1946–1952 as a communications officer. He retired in 1952 with the rank of lieutenant colonel. Following military service, he was a consultant and special representative with Philco Corp. He subsequently joined Haller-Raymond-Brown, Inc., as sales and marketing manager.

Mr. Rexroat attended Kansas State University and Pennsylvania State University management school. He is a member of the Professional Group on Engineering Management of the IRE, Armed Forces Communications and Electronics Association, Air Force Association and the Air Force Aid Society.

❖

Appointment of **Dr. Lindon E. Saline** (S'48–SM'59) as manager of the Specialty Devices Operation of the General Electric

(Continued on page 80A)

ONE INTEGRATED SOURCE for Ceramic-to-Metal Seals



In all phases of planning for high-alumina ceramic-to-metal seals you can rely on Alite for the "know-how" and "do-how" required to produce highest quality for critical applications.

From design to finished part, every manufacturing step — including formulating, firing, metalizing and testing — is handled within our own plant and carefully supervised to assure strict adherence to specifications, utmost uniformity and reliability.

To simplify design problems and speed delivery, Alite terminals, feed-throughs and cable end seals are available in over 100 standard sizes.

INSIDE LOOK AT ALITE—



Write today for Bulletin A-40R—Full technical data on standard and special Alite ceramic-to-metal seals.

ALITE DIVISION

U. S. STONEWARE

Box 119 • Orrville, Ohio

88-H



SAFETY OF LIFE IN THE AIR

SELENIA AIR TRAFFIC CONTROL RADAR OFFERS:

SOLID, LONG RANGE, HIGH ALTITUDE DETECTION OF EVEN THE SMALLEST TYPES OF AIRCRAFT THROUGH THE USE OF HIGH AVERAGE POWER AND A PARAMETRIC AMPLIFIER RECEIVER.

THE MOST ADVANCED TRUE MTI SYSTEM IN THE WORLD WITH THREE PULSE CANCELLATION FOR CLUTTER-FREE PRESENTATION AND STAGGERED REPETITION RATE FOR BLIND SPEEDS ELIMINATION.

THE USE OF L-BAND ASSURES SHARP AZIMUTH DISCRIMINATION AND LOW PRECIPITATION ATTENUATION WITH REASONABLY SIZED ANTENNA STRUCTURES

SPECIAL HIGH-LOBE ANTENNA FOR GREATLY IMPROVED SUBCLUTTER VISIBILITY FOR CLOSE-IN TARGETS AND CIRCULAR POLARIZATION FOR NEARLY COMPLETE CANCELLATION OF RETURNS FROM PRECIPITATION.

A RADAR COMPLETELY COMPATIBLE WITH JET AGE REQUIREMENTS.

A DIRECT SUCCESSOR OF THE PROVEN RAYTHEON AIRPORT AND AIRWAYS RADARS CHOSEN BY THE AIR TRAFFIC CONTROL AUTHORITIES IN CANADA, THE UNITED STATES AND SWITZERLAND.

Your inquiry is invited for more specific information
ROME ITALY
P.O. BOX 7083

MANAGED BY RAYTHEON

SELENIA

Excellence in Electronics in Europe

IRE People

(Continued from page 78A)



L. A. SALINE

Company's Defense Systems Department was recently announced. He was formerly manager of the Defense Systems Department's Information Systems Section, Bethesda, Md.

Dr. Saline's operation has responsibility for the development, manufacture, and marketing of electronic components which incorporate new and sophisticated fabricating techniques. Most of the current activity includes manufacture of modular component assemblies and basic electronic devices such as digital computer transistor logic modules, magnetic shift register and magnetic logic elements, ancillary circuit modules for data and signal processing equipment, and ferrite core memory planes.

During his 13 years with General Electric, Dr. Saline has accumulated broad experience in the engineering field. For six years, he was active in analytical engineering; performing power system analysis, analog and digital computer applications, operations research and synthesis, and administration and customer consultation. He was an analyst for one year at the General Electric Research Laboratory, Schenectady, N. Y., and was Manager of Engineering Recruiting Service, headquarters region, for three years.

In 1958, Dr. Saline was named Manager of the Operations Analysis Subsection of the Computer Department, Phoenix, Ariz. Under his direction, original concepts and techniques were developed to fulfill requirements and meet objectives for an intelligence data processing system. He was named Manager of the Information Systems Section of the Defense Systems Department in 1959. Information Systems is responsible for conceiving, designing, implementing and operating complex man-machine information systems.

Dr. Saline is a graduate of Marquette University where he received his B.S.E.E. degree in 1945. He was awarded his Ph.D. in electrical engineering from the University of Wisconsin in 1950.

He is a member of Tau Beta Pi, Eta Kappa Nu, Pi Mu Epsilon, and Sigma Xi, the American Institute of Electrical Engineers, and the American Society of Mechanical Engineers. He also belongs to the Operations Research Society of America.

Dr. Saline has been active in the Institute of Management Science, American Society for Engineering Education, International Conference on Large Electric High-Tension Systems, and the Syracuse General Electric Engineers Association.

❖

(Continued on page 82A)

An Analogy to Ideation

The seed will achieve its fullest potential when nurtured in the most receptive environment.

So, too, ideas.

If your ideas need a place in the sun, we would like very much to hear from you.

FAIRCHILD

SEMICONDUCTOR

545 WHISMAN ROAD, MOUNTAIN VIEW, CALIF. • YORKSHIRE 8-8161 • TWX: MN VW CAL 853

A DIVISION OF FAIRCHILD CAMERA AND INSTRUMENT CORPORATION

BALLANTINE Wide Band, Sensitive VTVM

model
317

Price: $495
with probe

Measures
300 μV to 300 V
at Frequencies **10 cps to 11 Mc**

A stable, multi-loop feedback amplifier with as much as 50 db feedback, and 10,000 hour frame grid instrument tubes operated conservatively, aid in keeping the Model 317 within the specified accuracy limits over a long life. A million to one in voltage range and over a million to one in frequency coverage makes it attractive as a general purpose instrument for measurement of af or rf as well as the complete band. **All readings have the same high accuracy over the entire five inch voltage scales.** This is typical of all Ballantine voltmeters due to the use of individually calibrated logarithmic scales.

The 317 may be used as a null detector from 5 cps to 30 Mc having a sensitivity of approximately 100 μV from 10 cps to 20 Mc.

SPECIFICATIONS

VOLTAGE: 300 μV to 300 V.
FREQUENCY: 10 cps to 11 Mc (As a null detector, 5 cps to 30 Mc).

ACCURACY: % of reading anywhere on scale at any voltage. 20 cps to 2 Mc — 2%; 10 cps to 6 Mc — 4%; 10 cps to 11 Mc — 6%.

SCALES: Voltage, 1 to 3 and 3 to 10, each with 10% overlap. 0 to 10 db scale.

INPUT IMPEDANCE: With probe, 10 megohms shunted by 7 pF. Less probe, 2 megohms shunted by 11 pF to 24 pF.

AMPLIFIER: Gain of 60 db ± 1 db from 6 cps to 11 Mc; output 2.5 volts.

POWER SUPPLY: 115/230 V, 50 — 400 cps, 70 watts.

Write for brochure giving many more details

— Since 1932 —

BALLANTINE LABORATORIES INC.

Boonton, New Jersey

CHECK WITH BALLANTINE FIRST FOR LABORATORY AC VACUUM TUBE VOLTMETERS, REGARDLESS OF YOUR REQUIREMENTS FOR AMPLITUDE, FREQUENCY, OR WAVEFORM. WE HAVE A LARGE LINE, WITH ADDITIONS EACH YEAR. ALSO AC/DC AND DC/AC INVERTERS, CALIBRATORS, CALIBRATED WIDE BAND AF AMPLIFIER, DIRECT-READING CAPACITANCE METER, OTHER ACCESSORIES. ASK ABOUT OUR LABORATORY VOLTAGE STANDARDS TO 1,000 MC.

IRE People

(Continued from page 80A)

The appointment of **Walter W. Smock** (M'56) as product manager of militarized computers for the Data Systems Operations of Sylvania Electric Products Inc. has been recently announced. The Data Systems Operations are engaged in design, development and production of both general and special-purpose digital electronic data processing systems for the military and other agencies of the federal government.



W. W. Smock

Prior to joining Sylvania, Mr. Smock was director of marketing for Wolf Research and Development Corp. in Boston, Mass. Previously, he was manager of digital communications marketing for Radio Corporation of America in Camden, N. J.

Mr. Smock graduated from the University of Scranton in 1948 with a bachelor's degree in electrical engineering. He has also done graduate work in mathematics at the University of Villanova. He is a member of the Association for Computing Machinery.

❖

The Semiconductor Division of Microwave Associates, Inc. announces the appointment of **Simon Stopek** (M'59) as a Senior Engineer in in the Semiconductor Division. He will be engaged in semiconductor research and development, including novel types of microwave oscillators and harmonic generators.

S. Stopek

Prior to his appointment at Microwave Associates, he was a member of the technical staff of Hughes Semiconductors at Newport Beach, California, where he was engaged in research and development of intermetallic compound devices and other semiconductor devices. From 1953 to 1956 he was associated with the Advanced Development Group at RCA Semiconductors, then in Harrison, N. J., where he was active in research and development of transistors and in surface studies.

Mr. Stopek received his Bachelor's degree in 1949 in Chemistry from Harvard University, and his Master's degree in 1950 from Columbia University. He continued his studies at Columbia where he completed two years toward his doctorate.

He is a member of the American Physical Society and Sigma Xi.

❖

(Continued on page 87A)

New

CORNING CYFM CAPACITOR has reliability you can see

You get total protection against environment for less money than ever before

The new Corning CYFM capacitor gives you reliability at a markedly lower cost than that of any like capacitor.

The CYFM goes far beyond MIL-C-11272B specs. It has proved its performance through more than 3,000,000 hours of testing. It took a 50-day MIL moisture test and a 96-hour salt spray test with no measurable effects. We stopped testing only when it became evident that no more significant data could be developed. The CYFM went through other tests, with solvents, fluxes, boiling salt, and steam, to make sure it is the most completely sealed capacitor you can buy.

You'll see why the CYFM can take such torture when you check its design. We stack alternate layers of stable ribbon glass and aluminum foil. Then we weld the foils to the bead-terminal assembly, which has a glass bead sealed to the Dumet wire lead. With heat and pressure, the entire capacitive element is frozen in glass for complete protection against environment and for structured protection against physical shock.

True glass-to-metal seals at the weld area and along the leads bar moisture. The seal of the leads to the glass shifts stresses from the leads to the entire monolithic unit, guarding the capacitance area. Of course, you get electrical performance to match this environmental stability, since the CYFM has our glass-foil capacitor construction.

The CYFM is machine made . . . each capacitor is the same as every other, to give you uniformity which hand production cannot match.

You can get immediate delivery on the CYFM in four types. The CYFM-10 gives capacitance values from 0.5 to 300 *pf*; the CYFM-15, from 220 to 1200 *pf*; the CYFM-20, from 560 to 5100 *pf*, and the CYFM-30, from 3600 to 10000 *pf*.

For the rest of the story on this capacitor, send for our data sheet. Write to Corning Glass Works, 542 High St., Bradford, Pa.



This is the CYFM capacitor. 6 times actual size. The dark areas between the ends of the glass and the capacitance element are your visual proof of the complete glass-to-metal seal.

CORNING ELECTRONIC COMPONENTS

CORNING GLASS WORKS, BRADFORD, PA.

REALIZE NEW INDUSTRIAL CIRCUIT ECONOMIES WITH THESE 9 RCA LOW-PRICE GENERAL-PURPOSE DEVICES



RCA's new Recommended Economy/Performance List of 9 volume-produced transistors and rectifiers can bring you brand-new answers to industrial reliability and performance at low prices

Here's why RCA's new recommended economy/performance list of 9 general-purpose semiconductor devices can open the way to new circuit economies, new equipment reliability:

- **Low Price**—due to advanced mass-production techniques used at RCA's Findlay, Ohio plant devoted exclusively to general-purpose types.
- **Excellent Uniformity**—due to many years of experience and continuing refinements in manufacturing general-purpose types.
- **Exceptional Reliability**—because of rigid quality control and proved by extensive studies of customers' actual experience with these transistor types from incoming inspection to actual field use by the end user. Field failure returns of these units in battery-portable radios since January, 1958 have been less than 0.008% per 1,000 hours of operation. A rigorous quality-control program makes product improvement a continuing positive process at RCA.
- **Time-Proved Constructions**—Alloy-Junction Construction, Graded Base Drift-Field Construction, Silicon Diffused-Junction Construction...techniques developed and improved by RCA's long experience in the field of solid-state devices and proved through widespread product application.

For complete information and data on these nine general-purpose types, write for your free copy of RCA's new booklet "RCA's Recommended Economy/Performance List" to RCA Semiconductor and Materials Division, Commercial Engineering, Section X-35-NN, Somerville, N. J. For further sales information, contact your RCA Field Representative today.



RCA FIELD OFFICES...EAST: Newark, N. J., 744 Broad St., HUmboldt 5-3900 • (Camden, N. J. area) Erlton, N. J., 605 Marlton Pike, HAzel 8-4802 • Syracuse, N. Y., 731 James St., Room 402, GRanite 4-5591 • Baltimore, Md., ENterprise 9-1850 • **NORTHEAST:** Needham Heights 94, Mass., 64 "A" St., HIllcrest 4-7200 • **SOUTHEAST:** Orlando, Fla., 1520 Edgewater Drive, Suite #1, GArden 4-4768 • **EAST CENTRAL:** Detroit 2, Mich., 714 New Center Bldg., TRinity 5-5600 • **CENTRAL:** Chicago, Ill., Suite 1154, Merchandise Mart Plaza, WHitehall 4-2900 • Minneapolis, Minn., 5805 Excelsior Blvd., WEst 9-0676 • **WEST:** Los Angeles 54, Calif., Box 54074, RAymond 3-8361 • (San Francisco area) Burlingame, Calif., 1838 El Camino Real, OXford 7-1620 • **SOUTHWEST:** Dallas 7, Texas, 7905 Carpenter Freeway, FLeetwood 7-8167 • **GOV'T:** Dayton, Ohio, 224 N. Wilkinson St., BAldwin 6-2366 • Washington, D.C., 1725 "K" St., N.W., FEderal 7-8500.

AVAILABLE THROUGH YOUR RCA DISTRIBUTOR

The Most Trusted Name in Electronics
RADIO CORPORATION OF AMERICA

November, 1961
Vol. 49 No. 11

Proceedings of the IRE

Poles and Zeros



Ex-Editor Month. IRE celebrates its fiftieth anniversary in 1962. During its half century of existence it has had remarkably few Editors, six by actual count. This amazing record is entirely due to the energy, wisdom, and stamina of Alfred N. Goldsmith, Editor Emeritus, IRE Founder, and Charter Member. Dr. Goldsmith served IRE as Editor continuously from 1912 through 1953, with the single exception of the year 1929. The 1929 Editor was W. G. Cady.

Since the year 1953, IRE has been served by a less hardy group. For two-year periods the Editors have been J. R. Pierce, D. G. Fink, J. D. Ryder, and the incumbent. Just to prove that old Editors never stop writing, this month's Poles and Zeros' page comprises items directly attributable to past Editors. The first item to follow was prepared in its entirety by J. D. Ryder, the second results from a communication from J. R. Pierce, and the third from the activity of the Editor Emeritus.

Travel Still Broadens. Under a similar heading we reported in 1958 on a visit to the electronic industry of Japan, and to other oriental points. We return to report once more on travel —this time primarily to India to visit educational institutions.

Our first impression was of people, people everywhere—hands that must be kept busy, and mouths which must be fed. In talking with Indian engineers, and long-time British and American residents, we were told that India is indeed making progress on its population and economic problems. Our second impression was of the excellence of people in government and in the colleges—sure of their direction and that of India. In engineering education there was realization of the need for change, but some doubt as to the methods to be employed in bringing it about.

This doubt was not so apparent at a bright spot in the educational field—the Indian Institute of Science at Bangalore. We were taken in hand by Dr. S. V. C. Aiya, head of Electronics and Communications, and also immediate past president of the Institute of Telecommunications Engineers of India. A fast tour revealed excellent research facilities and plans for more. Areas of activity included atmospheric noise, artificial dielectrics, surface-wave transmission, information content of languages (for which India provides ample material), and some very pure acoustic-research on the Indian drum. We say pure, since the results are not likely to be applied to drum design, especially when the research shows the design produced by 2000 years of empirical effort to be correct!

Being a professor—part time—we willingly accepted Dr. Aiya's invitation to address a meeting of students, faculty, and Bangalore communications engineers, and we can at least report that the event was enjoyed by the speaker.

Bombay, Madras, Calcutta, Delhi all were points of educational interest and the Taj Mahal surpassed all words or pictures. We returned ready to go again.—J.D.R.

Editorial Faux Pas. Ex-Editor J. R. Pierce wrote, in a letter to President Berkner: "People who write papers want to see them in print as soon as possible. People who read papers find them most valuable when they are freshest. Editors, editorial staff, and reviewers of the IRE know this, and they mean to act promptly and sensibly. Usually they succeed. But, the price of promptness is eternal vigilance. I think it is salutary to consider what can (and did) happen to one good paper."

The letter then contains ten indictments of the editorial procedure and the crucial statement: "In short, it took 21 months for a good paper to get from submission to acceptance for publication." The Editor, the Managing Editor, and the IRE publication staff express sincere regret to the rightfully offended author. Ex-Editor Pierce concluded his letter: "Please, reviewers, editors, and staff, this shouldn't happen to even a dog of a paper." Speaking for the editors and the staff—we heartily agree. Speaking to the reviewers—we urge careful consideration and promptness in handling papers submitted for review.

There is no point in reiterating the details of the indictments. Those aspects that can be corrected in the editorial department routine have been corrected; at least we sincerely hope they have. The point that must be emphasized, however, is that all those who handle manuscripts for review should give them priority in handling—treat them as if they represented your own submission!

Anniversary Issue. Editor Emeritus Goldsmith, having accepted the appointment as Editor of the Anniversary Issue, has attacked the task with his usual vim and vigor. This issue, to appear in May, 1962, will be truly an outstanding one. It will comprise, exclusively, invited papers prepared by the most distinguished members of IRE. The issue will present papers giving the evolution, present status, and future trends as well as certain original contributions in the fields of each of the twenty-eight Professional Groups. There will also be a brief presentation of IRE, its past, present, and future together with a symposium of predictions "Communications and Electronics—2012 A.D." This one thousand page volume will be a fitting climax to IRE's first half century.—F. H., Jr.

M. W. Bullock

Director, 1961–1962

Mark W. Bullock (S'33–A'37–M'45–SM'54) was born in West Winfield, N. Y. on August 20, 1911. He received the B.A. degree in 1933 and the B.S.E.E. degree in 1934, both from the University of Nebraska in Lincoln.

From 1934 to 1937, he was Transmitter Supervisor for KOIL, Omaha, Nebr.; from 1938 to 1944, he was Technical Director of KFAB, Omaha, and KFOR, Lincoln. He was Chief Engineer of KFNF, Shenandoah, Iowa, from 1948 to 1951. During World War II, he designed shortwave transmission facilities for the Bureau of Communications Facilities, Office of War Information, Washington, D.C.

He joined Continental Electronics Manufacturing Company, Dallas, Tex., in 1951 and was in charge of the design of broadcast transmitters. He became Engineering Manager in 1953. The manufacture of BMEWS radar transmitters required the establishment of a separate Production Division, and he was Manager of this operation from 1958 to 1960. He is now Vice President for Engineering, and in this position he is Engineering Manager, directing the design and development of super-power radio and radar transmitting equipment. This includes the BMEWS surveillance and tracker radars and the Nike Zeus acquisition radar.

His IRE activities include having been the first Chairman of the Omaha-Lincoln Section, 1948–1959. In the Dallas-Fort Worth Section he has served as Secretary-Treasurer, 1953–1954; Vice Chairman, 1954–1955, and Chairman, 1955–1956. The Southwest IRE Conference elected him Chairman of the Board of Advisors for 1956–1957. In the Dallas Section, he has served as Professional Group Advisor, 1956–1957; Nominating Committee, 1957–1958 and 1958–1959; SWIRECO Section Co-ordinator, 1959; SWIRECO Board of Advisors, 1959–1961.

He holds patents covering a cabinet design for transmitting equipment and the screen modulation-regulation circuit used n Continental Electronics transmitters.

Mr. Bullock is a member of AIEE, Texas Society for Professional Engineers, National Society of Professional Engineers, and he is a Registered Professional Engineer in the States of Nebraska and Texas.

Scanning the Issue

The Cryosistor: A Field-Effect Controlled Impact Ionization Switch (Melngailis and Milnes, p. 1616)—When a semiconductor is subjected to very low temperatures (about 4° K), a small applied voltage will cause a rapid ionization of impurities, resulting in an avalanche breakdown. This phenomenon, known as impact ionization, has been employed lately in the development of several novel cryogenic devices. Notable among these is the cryosar, a two-terminal computer switch and memory element described here two years ago. Since then it has been found that the breakdown in compensated germanium is filamentary in nature, that is, before breakdown the current is distributed throughout the bulk of the material but after breakdown it is confined to an ionized filament of very small cross section. This discovery has now led to the development of a new three-element switch, called the cryosistor, in which the ionization process, because it is restricted to a small region, can be field-effect controlled by the third element. The many interesting properties of the new device suggest a variety of applications, including memory, logic and counter elements for computers as well as pulse amplifiers and thyratron-type trigger circuits.

A New Semiconductor Tetrode—The Surface-Potential Controlled Transistor (Sah, p. 1623)—In the preceding paper a field-effect electrode was added to a device to control internal phenomena; in this paper a field-effect electrode has been added to control surface phenomena. The device in question is a common planar transistor to which a fourth electrode has been affixed to the oxide which covers the surface of the emitter-base junction. The result is a tetrode device in which the additional terminal serves as a grid to control the surface potential, surface recombination rate and the size of the surface channel, and thereby the current gain of the transistor. Thus, we have a new family of semiconductor devices which, thanks to the additional control element, can provide heretofore unobtainable electrical performance.

The Pulsed Ruby Maser as a Light Amplifier (Kisliuk and Boyle, p. 1635)—The successful operation of optical maser oscillators has left no doubt that the gain of a maser is sufficient to make up for losses at the end mirrors. However, past experiments have given no independent measurement of the gain or loss separately. The difficulty in observing amplification directly is that of distinguishing coherent maser light from the natural fluorescent light of the maser. The authors have solved this difficulty by generating a coherent light which was so bright that the amount of fluorescence was small by comparison. They accomplished this by setting up two ruby masers in tandem. The output of one maser, operating as an oscillator, was beamed into the other, operating as an amplifier. Amplification of light by a factor of two was observed. This is the first published description of an optical maser experiment designed to observe and measure such large amplification directly.

Inductance in Thin-Film Superconducting Structures (Meyers, p. 1640)—There is widespread interest today in thin-film superconducting components and circuits for digital computers. Much of the attention to date has been focused on new devices or circuit arrangements and on fabrication techniques. This paper deals with another important aspect of the subject, namely, methods of evaluating the electrical characteristics and behavior of such components and circuits. Most components and their associated interconnections take the form of coupled strip-transmission lines, with resistance, inductance and capacitance all entering into the behavior of such structures. The author's chief interest here is the inductance because it is the most difficult parameter to calculate and plays a dominant role in determining the gain and bandwidth of the circuitry. Among other things he points out the considerations that are necessary and sufficient for calculating inductances up to about 1 kMc and the pitfalls of using the familiar flux-per-unit-current definition of inductance. Device designers will be particularly interested in the relatively simple formula which the author develops for calculating the inductance of a strip line.

Reduction of the Frequency-Temperature Shift of Piezoelectric Resonators by Mechanical Stress (Gerber and Miles, p. 1650)—It has been known for several years that the frequency of a quartz resonator can be changed by applying external pressure to the crystal. The authors have succeeded in utilizing this effect to counteract, and thus drastically reduce, frequency shifts which result from changes in temperature. The applied pressure must, of course, be made a function of temperature. This is accomplished by attaching bimetallic strips at selected spots on the circumference of the crystal disk. This technique represents an outstanding advance in practical frequency control methods. It will make it possible to achieve a high degree of frequency stability without using crystal ovens, an advantage of considerable practical importance in military and satellite applications where space and power are at a premium.

Fundamental Limitations to Optical Doppler Measurements for Space Navigation (Norton and Wildey, p. 1655)—Last year in the Space Electronics Issue of the PROCEEDINGS it was suggested that a spacecraft might obtain midcourse navigational guidance by performing optical Doppler measurements of astronomical objects to determine the spacecraft's velocity. This paper examines the accuracy with which such measurements might be made. The author first considers the maximum Doppler variations that might be caused by various physical mechanisms at work in the stellar atmosphere and then examines the accuracy of present-day measuring equipment. His results shed considerable light on the principal causes of inaccuracy, revealing that the stellar variations rather than the measuring instruments pose the major problem, and, indirectly, underscoring the importance of developing integration techniques to modify the effects of such variations.

Timing Potentials of Loran-C (Doherty, *et al*, p. 1659)—This paper describes a highly accurate pulse navigation system operating on a basic frequency of 100 kc. The system consists of a master station and two or more slave stations, with the slave station clocks synchronized to the master station clock. An outstanding feature of the system is the accuracy with which the several clocks in the system are synchronized with one another—an accuracy of better than one microsecond. This makes it possible for the system to provide both position and time with great precision over wide areas. Loran-C will find many important applications in the future. Among the many possibilities are providing precise time for large areas of the world, determining the position of aircraft, missiles, satellites, thunderstorms and nuclear detonations, surveying remote areas, and measurement of various radio propagation phenomena.

A Provisional Ground Conductivity Map for Canada (Ireland, p. 1674)—On January 1 of this year the Department of Transport in Ottawa issued a new ground conductivity map for Canada. The map, together with a discussion of how it was derived, is presented in this paper. The word "provisional" in the title indicates that this map, when used in conjunction with the U. S. ground conductivity map (published in the September, 1954 PROCEEDINGS), produces a few anomalies along the U. S.-Canadian boundary which will be mutually resolved at a later date. The numerical data provided by the map will be of value to those concerned with the propagation of radio waves in Canada.

The Cryosistor—A Field-Effect Controlled Impact Ionization Switch*

I. MELNGAILIS†, MEMBER, IRE, AND A. G. MILNES‡

Summary—**The cryosistor is a new three-terminal device in which the low-temperature (4.2°K) impact ionization of impurities in germanium is controlled by means of the depletion field effect of a reverse-biased *p-n* junction. Compensated germanium has an inherent bistable voltage-current characteristic at liquid helium temperature. With such a material, bistable switching by means of pulses applied to the gate-junction located between two ohmic contacts is shown to be possible. The critical gate voltages may be calculated from elementary consideration and a wide range of values of the switching voltages, as well as power dissipation, is shown to be possible with suitable choice of material and physical dimensions. The switching speed is basically limited by the ionization and recombination times of the bulk material and may be as fast as a few nsec, depending upon the amplitude of the switching pulse.**

Possible applications of the device at 4.2°K include computer components such as binary counters, logic functions, and memory arrays, in addition to pulse amplifiers and trigger circuits of the thyratron type. The localized nature of the ionization should permit the construction of a large number of independent cryosistors on a single germanium wafer.

Introduction

THE cryosar, a previously described two-terminal computer switch or memory element,[1] depends for its action on the bulk voltage-current characteristics resulting from impact ionization in germanium at 4.2°K. In this device partially compensated germanium provides the possibility of bistable operation, since the ionization breakdown is followed by a drop of voltage with increasing current (negative resistance). Recent experiments have indicated the filamentary nature of the breakdown in compensated germanium.[2] The current before breakdown is distributed throughout the bulk, but after breakdown, conduction occurs in an ionized filament of a very small cross section. The size of the ionized region has been studied in cylindrical field-effect structures in which the diameter of the conduction channel can be reduced by reverse biasing a ring-shaped *p-n* junction alloyed around a small cylindrical bar.[3]

An interesting consequence of this filament study has been the discovery that cylindrical or planar field-effect devices made of compensated germanium offer new and worthwhile three-terminal properties at 4.2°K. The name "cryosistor" has been given to this class of device structure.

Static Characteristics

In unipolar (field effect) transistors,[4,5] a reverse bias applied to a junction depletes carriers from a region under the junction forming a space-charge layer. The depletion region is found to be very nearly the same at liquid helium temperature as at room temperature since fields near the junction are sufficiently large to deplete bound carriers from the impurity level at low temperatures. Thus, in a unipolar transistor configuration, the biased junction provides an insulating layer which can prevent the formation of an ionized filament between the "drain" and "source" ohmic contacts.

For ease of fabrication, most of the structures investigated here are in the form of rectangular wafers of *n*-type compensated germanium ($\rho = 6.5$ ohm-cm, $N_D = 2.25 \times 10^{15}$ cm^{-3}, and $n_A = 2.0 \times 10^{15}$ cm^{-3}), with two ohmic contacts and a long indium-alloyed junction on one face [Fig. 1(a)]. The wafer under the junction is etched thin electrolytically, so that this region can be depleted of carriers at a desired reverse bias of the junction.

Fig. 1(b) shows the dc circuit of a cryosistor with the gate voltage V_g and current I_g, the drain voltage V_d and current I_d and the source current I_s. The operation of a cryosistor can be understood in terms of the schematic representation of its characteristics in Fig. 1(c) which shows the variation of drain current I_d with drain voltage V_d at different values of gate bias V_g. With $V_g = 0$, the drain has the bistable characteristic of the bulk material with a breakdown voltage V_B, breakdown current I_B, sustaining voltage V_H, and sustaining current I_H. For $V_g > 0$, the drain current saturates as the channel is pinched off, before or after ionization in the channel, depending on the value of V_g. The total reverse bias of the junction near the drain is the sum of the externally applied voltage V_g and the voltage drop across parts d_j and d_s. The length d_s is chosen so that this voltage drop is an

* Received by the IRE, July 7, 1961; revised manuscript received, September 1, 1961. This work represents partial fulfillment by Melngailis of requirements for the Ph.D. degree at Carnegie Institute of Technology, Pittsburgh, Pa. Financial support was received in part from the Office of Naval Research, Contract Nonr 760(09).

† Now at Lincoln Laboratory, Lexington, Mass.

‡ Carnegie Institute of Technology, Pittsburgh, Pa.

[1] A. L. McWhorter and R. H. Rediker, "The Cryosar—A new low-temperature computer component," PROC. IRE, vol. 47, pp. 1207–1213; July, 1959.

[2] A. L. McWhorter, "Impact Ionization of Impurities in Compensated Germanium," M.I.T. Lincoln Lab., Cambridge, Mass., Rept. 85 C-006; August, 1960.

[3] "Filamentary Impact Ionization in Compensated Germanium at 4.2°K" (paper in preparation).

[4] W. Shockley, "A unipolar 'field-effect' transistor," PROC. IRE, vol. 40, pp. 1365–1376; November, 1952.

[5] G. C. Dacey and I. M. Ross, "Unipolar 'field-effect' transistor," PROC. IRE, vol. 48, p. 970–979; August, 1953.

appreciable fraction of the junction voltage at which the channel is pinched off. Because of the bistable voltage-current characteristic of the channel material, the voltage across d_s is greater just before breakdown than after breakdown. This implies that within a certain range of values of the applied voltage V_g, the drain circuit may have a different characteristic curve for the same V_g, depending on the order in which V_g and V are applied.

For example, if V_g is set at V_{g0} and V is then increased to $V_0 > V_B$ (where V_B is the breakdown voltage of the undepleted channel), no breakdown occurs since the drain current saturates at a value which is less than the current necessary for ionization [Fig. 1(c), point 1]. If V_g is now reduced to $V_{g2} < V_{g0}$, thereby increasing the saturation current to I_B, the channel ionizes and the drain current shifts along the load line to point 3. The total junction voltage now is reduced because the voltage across d_s has dropped. In order to cause the channel to de-ionize and return to the high-impedance region, V_g has to be increased to a value $V_{g1} > V_{g0}$ (point 4), to reduce the saturation current below the value necessary to sustain an ionized filament. The de-ionization is accompanied by an increase in the total junction voltage, and the drain current decreases to the value at point 5.



Fig. 1—(a) Top and side views of an experimental cryosistor showing the gate-junction and the drain and source ohmic contacts. (b) The dc circuit used with a cryosistor indicating the proper polarities of applied voltages. (c) Schematic representation of the drain characteristics before and after breakdown. A typical loadline with reference to the circuit of (b) is shown.

This indicates the possibility of bistable switching by means of pulses applied to the gate. With $V_g = V_{g0}$, a positive voltage pulse will cause ionization and a jump from point 1 to 6. To return the drain current to 1, a negative pulse is required.

The critical values of the gate voltage V_{g1} and V_{g2}, which determine bistable operation can be calculated with an accuracy somewhat better than 10% by simply considering the voltages which make up the total junction voltage at points 2 and 4. If at 2 the junction voltage near the edge of the junction close to the drain is W_2 (the value which causes the drain current to saturate just at the breakdown current I_B), then W_2 is the sum of V_{g2} and the appropriate fraction of the drain voltage, determined by the location of the gate along the bar:

$$W_2 = V_{g2} + \frac{d_s + d_j}{d_t} V_B. \tag{1}$$

Similarly, at point 4 there is a value W_1 with a saturation current just equal to the minimum required to sustain ionization:

$$W_1 = V_{g1} + \frac{d_s + d_j}{d_t} V_H. \tag{2}$$

Experiments with a number of cryosistors have shown W_1 and W_2 to be nearly equal, when estimated from (1) and (2), as shown in Table I. This may be expected, considering that a certain minimum cross section (10^{-6} cm^2) of undepleted material is necessary for an ionized filament to form and to be sustained. Consistent with this consideration, the values of W_1 and W_2 in most cases are somewhat lower than the pinchoff voltages W_0 measured in liquid nitrogen.

Setting $W_1 = W_2 = W_k$, the two critical values of V_g are

$$V_{g1} = W_k - (d_s + d_j)E_H$$
$$V_{g2} = W_k - (d_s + d_j)E_B \tag{3}$$

and

$$V_{g1} - V_{g2} = \Delta V_g = (d_s + d_j)(E_B - E_H),$$

where E_B and E_H are the breakdown and sustaining fields, respectively, and are characteristic of the channel material.

For most purposes it is sufficient to assume $W_k = W_0$ and to evaluate the latter at room temperature using results derived previously for an abrupt depletion layer:[4]

$$W_0 = \frac{1}{2} \frac{a^2}{\rho\mu\epsilon}, \tag{4}$$

where a is the thickness of the wafer under the junction in cm [Fig. 1(a)], ρ is the room temperature resistivity in ohm-cm, μ is the majority carrier mobility in cm^2 volts^{-1} sec^{-1} and ϵ is the dielectric constant in farads cm^{-1}.

TABLE I

PROPERTIES OF CRYOSISTORS*

No.	Dimensions [Fig. 1(a)]				Breakdown Voltage V_B	Sustaining Voltage V_H	Critical Gate Voltages		Junction Voltages calculated from V_{g1} and V_{g2}		Pinchoff Voltage at 77°K W_0
	a(cm)	d_d(cm)	d_j(cm)	d_s(cm)			V_{g1}	V_{g2}	W_1	W_2	
C1	1.6×10^{-3}	9.1×10^{-2}	4.1×10^{-2}	20.6×10^{-2}	34	19	21	12	36	37	37.4
C2	1.5×10^{-3}	8.2×10^{-2}	4.6×10^{-2}	21×10^{-2}	32	17	17	7.8	30	31	33.3
C3	1.8×10^{-3}	8.2×10^{-2}	4.6×10^{-2}	21×10^{-2}	33	17	38	29	52	54	55
C4	8.0×10^{-2}	8.0×10^{-2}	6.0×10^{-2}	21.8×10^{-2}	32	18	0.7	−10	15	15.5	17.2
T2		4.3×10^{-2}	1.8×10^{-2}	5.8×10^{-2}	15	9	1.4	− 1.8	7.3	8.1	8.13

* C1 to C4 are planar structures with $\rho(300°)=6.5$ ohm-cm, $N_D=2.25\times10^{15}$ cm^{-3}, $N_A=2\times10^{15}$ cm^{-3}. T2 is cylindrical in shape with a channel diameter of 3.3×10^{-3} cm, $\rho(300°)=15$ ohm-cm, $N_D=1.0\times10^{15}$ cm^{-3}, and $N_A=0.9\times10^{15}$ cm^{-3}.

Fig. 2 shows a plot of drain voltage before and after breakdown in the channel as a function of drain current for cryosistor C1 with the gate voltage as a parameter. The resistance of the channel before breakdown is seen to be quite nonlinear. At currents near breakdown the nonlinearity is a bulk effect resulting from partial ionization, since it has been observed in wafers as well as bars.[1] For lower currents surface leakage may be an important factor because the surface to volume ratio is large.



Fig. 2—Drain voltage as a function of drain current in cryosistor C1 with the gate voltage as a parameter before and after ionization in the channel.

The characteristics after breakdown have a slope of zero for values of gate bias not too close to the pinch-off voltage since the drain voltage begins to increase only when the ionized filament has spread over the available channel. Accurate calculation of the characteristics is difficult to make in planar structures, because the ionized filament is restricted by the depletion layer only in one dimension, permitting a further spreading parallel to the gate junction. The gate characteristics indicate a very low reverse leakage current ($<10^{-10}$ amp) for the junction at low voltages (<30 volts).

Design Considerations

From (3) and (4) the critical voltages V_{g1} and V_{g2} are determined by device dimensions and the breakdown and sustaining fields of the material. This allows for considerable flexibility in design, particularly because the breakdown fields are found to vary between 10 and 200 volts/cm.

In an example of a low-power design consider a compensated material with $E_B=140$ v/cm and $E_H=35$ v/cm. Then (3) and (4) give $V_{g1}=0.54$ volt and $V_{g2}=-0.54$ volt for the dimensions $a=3\times10^{-4}$ cm, $d_t=1.5\times10^{-2}$ cm, $d_j=0.4\times10^{-2}$ cm and $d_s=0.6\times10^{-2}$ cm. The estimated minimum power consumption in the "on" state is about 1.6 microwatts, which could be tolerated in large arrays. The 3-micron active layer could be vapor-grown on a thicker wafer of germanium with a higher breakdown field to act as an effective insulator. [Such an arrangement is suggested in Fig. 10(a) in connection with a proposed memory array.] The voltages V_{g1} and V_{g2} can be chosen equal and of opposite sign to avoid the necessity of an external gate bias for bistable operation.

Dynamic Characteristics

Measuring System

The response speed of bistably operated cryosistors was studied in the circuit of Fig. 3. Coaxial 50-ohm cables, terminated with 50-ohm resistors in all pulsed parts of the circuit, were used as transmission lines to the device in the helium Dewar flask. The drain and the gate were biased with $V_d>V_B$ and V_{g0} such that $V_{g2}<V_{g0}<V_{g1}$. The 0.1-μf capacitors serve to isolate the dc bias. Resistors R_1 and R_2 (10 to 100 KΩ) were used to establish the drain loadline and to isolate the drain from the biasing cable and the voltage probe. A single pulse from a mercury relay pulse generator (rise time <0.5 nsec) was reflected from a shorted cable (C) to provide a turn-on pulse followed by a turn-off pulse after a time equal to twice the transit time of the cable length (about 100 nsec for the traces of Fig. 4, for example). For an off-on switching sequence the polarity of the input pulse was simply reversed. The resulting current pulse i_s was observed by means of a type-555 Tektronix dual-beam oscilloscope. The entire pulse was displayed by one of the beams using a type-L high-sensitivity preamplifier, and the rise and fall times were measured by means of a type-N sampling unit used with the other beam.



Fig. 3—Circuit for measuring cryosistor switching speed.



Fig. 4—Switching response of cryosistor C1. (a) 10-nsec switching pulses applied to gate (time increases to left). Vertical scale, 0.5 volt per large division. Horizontal scale, 100 nsec per division. (b) Positive switching pulse displayed by sampling unit indicates rise-time limitation of preamplifier to be about 10 nsec. Vertical scale, 2 v per division. Horizontal scale, 5 nsec per division. (c) Lower trace is the resulting pulse of cryosistor source current. Vertical scale, 0.4 ma per division. Horizontal scale, 100 nsec per division. Upper trace shows detail of current rise. Vertical scale, 0.2 ma per division. Horizontal scale, 10 nsec per division. (d) Detail of current fall. Vertical scale, 0.2 ma per division. Horizontal scale, 1 nsec per division.

Rise Time

The voltage pulses applied to the gate and the resulting source current as functions of time in sample C1 with biasing values $V_{g0}=17$ volts and $V=45$ volts are shown in the oscilloscope traces of Fig. 4. The captions under each photograph explain the parameters for each trace.

The switching operation can be understood in terms of the equivalent circuit of Fig. 5. The depletion capacitance of the junction C_j is of the order of 10 $\mu\mu$f from room temperature measurements. This should be the same in liquid helium, since the depletion layer is unchanged, judging from the similarity of helium and room temperature pinch-off voltages. R_d and R_s represent portions of the channel on the drain and source side of the junction respectively. L_d, L_g and L_s are small lead inductances. Because of the large value of the resistance R_s before breakdown (5×10^9 ohms) the incoming switching pulse bypasses the junction impedance and appears across R_s for a time sufficient to trigger the breakdown of R_s. Thus the switching speed is limited by the impact ionization process rather than by circuit parameters.



Fig. 5—Equivalent circuit of the cryosistor, showing capacitance of junction C (typically about 10 $\mu\mu$f), bulk resistances R_d and R_s on the drain and source side of the junction, respectively; stray lead inductances L_g, L_d, and L_s contact and lead capacitance C_1, and external resistance R_1 (10 to 100 K ohms).

A small induced pulse marks the beginning of the switching pulse in Fig. 4(c) [upper trace]. This is followed by an apparent delay of about 15 nsec, after which the current rises with an overshoot above the steady-state value. As in other impact ionization devices,[1] the current rise time is inversely related to the amplitude of the switching pulse. However, if pulses which are too large (>10 volts) are supplied to the gate, spurious switching results from oscillations associated with the small lead inductances and device capacitances. Some improvement can be expected if the lead length (about 2.5 cm in the present case) is reduced or eliminated by a different method of mounting, such as incorporating the device in a stripline. Decreased junction area, and hence lower junction capacitance, should also help to prevent oscillations. To assist in estimating ultimate limitations to cryosistor switching speed, current rise times were measured in a small two-terminal bar (length 0.56 mm, square cross-sectional area 1.3×10^{-3} mm^2) and in cryosistor C1 with the gate contact disconnected and the

voltage pulse applied between the drain and source contacts. The rise time (up to 90 per cent of the final value) is plotted in Fig. 6 as a function of the overdrive ratio $(V-V_B)/V_B$. Curves 1 and 2 are for cryosistor C_1 and the bar, respectively, and the slopes are -0.96 and -0.84, *i.e.*, sufficiently close to -1 to suggest inverse proportionality between rise time and overdrive:

$$\frac{1}{\tau} \sim \frac{V - V_B}{V_B}.$$



Fig. 6—Total current rise time (measured to 90 per cent of the final value) as a function of the pulse voltage in excess of the breakdown voltage. Curves 1 and 2 are for the channel of cryosistor C1 and for a two-terminal bar respectively.

Such a relation has been found previously in two terminal wafers.[6] The difference in magnitudes of curves 1 and 2 may be a result of differences in material. Fig. 6 indicates that, with high overdrive rise times as short as a few nsec are possible. To predict the approximate rise time in the three-terminal circuit from this graph, the voltage appearing across R_s (Fig. 5) for the duration of the gate pulse must be considered. Since the dc voltage in R_s before switching is nearly equal to the breakdown voltage, the overdrive voltage is just the switching pulse amplitude. On this basis, a rise time of 24 nsec may be predicted from Fig. 6 for test conditions that actually result [Fig. 4(c)] in a rise time of about 20 nsec. A faster rise could be expected in the three-terminal operation because, here, the ionization is aided by the large value of drain bias, once the gate pulse initiates an avalanche.

[6] R. C. Johnston, "Considerations in the Design of a Random-Access Cryosar Memory," MIT Lincoln Lab., Cambridge, Mass., Rept. 536-0039; July, 1960.

Fall Time

In the turn-off operation a negative gate pulse reduces the current in R_s below the sustaining current and R_s switches to the high impedance state. This results in an increasing of junction bias sufficient to pinch off the channel. The fall time of the current, observed in Fig. 4, is not more than 1 nsec long. As this is comparable with the response time of the external circuit and the sampling system without the specimen present, it appears that the cryosistor recovery time is faster than can be observed with these measuring techniques.

Measurements of recombination transients in two-terminal bars of the same material showed maximum time constants of about 5 nsec as compared to 80 nsec published for uncompensated germanium.[7] It is to be expected that recombination should be faster in compensated crystals because of a larger density of recombination centers resulting from compensation.

The fact that the recovery time in the cryosistors made from this material appears to be even faster than 5 nsec is attributed to the lower current level and the large amplitude switching pulse in this device.

Applications

The bistable operation of the cryosistor suggests its use as a fast three-terminal memory element. In addition, the combination of gating control and the naturally bistable drain characteristic allows a variety of other circuit functions. In addition to bistable switching, monostable operation is also possible with a sufficiently large gate bias. This implies the possibility of simple pulse amplification where this is required at cryogenic temperatures.

Some proposals for circuit applications are presented in the remainder of the paper.

"Thyratron" Operation

If the load line of the drain circuit intersects the negative resistance region of the voltage-current characteristic [line 1 in Fig. 7(a)], the channel will not stay ionized in the steady state, but relaxation oscillations associated with stray capacitance (C_d) will normally result. Attempts to stabilize the circuit have failed. If, however, the gate is biased between the two critical values V_{g1} and V_{g2} [see (3)], and a small positive pulse is applied to the gate to cause breakdown, then the ionization will be sustained only during one discharge of the drain capacitance. As soon as the drain current falls below the sustaining value I_H the channel switches back to its high impedance state and stays there because the increased junction voltage pinches off the channel. The path of this cycle is indicated in Fig. 7(a). The length of the discharge can be increased by adding an external capacitance, for example in Fig. 7(b), in the form of a transmission line.

[7] S. H. Koenig, "Recombination of thermal electrons in *n*-type germanium below 10°K," *Phys. Rev.*, vol. 110, pp. 988–990; May 15, 1958.



Fig. 7—"Thyratron" switching of a cryosistor. (a) Drain characteristics with steady-state loadline: 1) for "thyratron" operation, and 2) for pulse amplification. (b) "Thyratron" circuit with discharge line A.

Tests with this circuit have borne out the predicted operation. While the rise time of the output pulse is limited by impact ionization, the fall time is determined by the RC time constant of the drain circuit (including line A), since the device resistance R_d+R_s is larger than the characteristic impedance of the discharge line.

Pulse Amplification

To amplify pulse voltages, the gate is biased for monostable ($V_g > V_{g1}$) switching with the loadline of the drain intersecting the drain characteristic at a stable point [line 2 in Fig. 7(a)]. Then a positive ionizing pulse at the gate causes a drop in the drain voltage of magnitude $V_0 - V_H$ for the duration of the pulse and so results in a large negative output pulse. Since V_H is a constant parameter of the device, the amplitude of the output depends on V_0, which is limited only by the reverse breakdown of the gate junction (typically larger than 100 volts for good junctions). The minimum required amplitude for the switching pulses depends largely on the breakdown field of the material and on the device dimensions. This could be reduced to a fraction of one volt with suitable design.

Logic Functions

In monostable operation the cryosistor can also perform the function of a simple gate, whereby strongly localized conduction after ionization provides the possibility of fabricating arrays of cryosistors on the same wafer without harmful interactions. Fig. 8(a) shows a proposed OR gate where the junction strips are made long compared to the channel length to prevent undesired breakdown. A positive pulse to any of the four gate junctions causes an output signal to appear. A possible configuration for an AND gate is indicated in Fig. 8(b). The number of inputs here may be limited by the voltage drop in the channel.



Fig. 8—Examples of cryosistor logic structures. (a) OR gate. (b) AND gate.

Counter Circuits

Two bistable cryosistors can be combined in the circuit of Fig. 9(a) to produce a flip-flop for a conventional binary counter. A positive pulse at the gate of each cryosistor can cause breakdown in the channel and a downward shift along the loadline from V_0 to V_H in Fig. 9(b), whereas a negative pulse is followed by an upward shift.

To understand the flip-flop operation, assume that unit A is in the ON state while B is on the OFF state. Then the voltages at points 1 and 2 are V_H and V_0 respectively. If a negative pulse is now applied to the input I, the pulse will appear at point 2 (since B presents a high impedance) and cause de-ionization in A. This, in turn, results in an increase of the voltage at 1 from V_H to V_0 and a positive ionizing pulse appears at the gate of B. By contrast, a positive pulse of the same magnitude in the input does not cause switching because only a fraction of it appears at the gate of the deionized unit since the pulse is attenuated by the other unit, which is ionized.

Connecting a number of such flip-flops in series results in a binary counter. The wave shapes of Fig. 9(c) result because each stage is switched only by the negative output pulses of the preceding one. The resistors R_g may be needed to provide a discharge path for the coupling capacitors.



Fig. 9—Circuit and waveshapes of a binary counter resulting from a series connection of cryosistor flip-flops.



Fig. 10—(a) Proposed cryosistor memory array with a thin active layer on the surface of an insulating germanium wafer. (b) and (c) Operation of a voltage-coincident random-access memory with a nondestructive readout.

If the two gates A and B are biased sufficiently to prevent ionization in the steady state, the basic circuit should operate as a free running multivibrator with a square-wave output and a period determined by the R_gC time constant.

Cryosistor Memory

The bistable characteristic of compensated germanium has already been used in designing the two-terminal random-access cryosar memory.[1,6] A three-terminal cryosistor memory may have some advantage in improved stability at the expense of a somewhat more complex array such as in Fig. 10(a). Coincident switching can be achieved by a positive pulse to all the gates of a column (word line) and a negative pulse to the common source of a row (digit line) in Fig. 10(b). The total gate voltage at the coincident element is the sum of the two pulses and switching occurs along the solid loadline of Fig. 10(c). A nondestructive readout is obtained by a positive pulse to the drain contacts of a column. The READ signal shifts the loadline of each drain circuit upward, as shown in Fig. 10(b). A current pulse is detected on the digit line if the element is in the ON state. To clear all elements in a column the word line is pulsed with a sufficiently large negative pulse.

The READ operation requires a resistor for each drain, which could be made in the form of another germanium wafer alloyed to the contact. To avoid the necessity for a resistor the elements could be switched to point P and READ by means of a negative pulse which would decrease the source current but would not be sufficient to cause deionization.

Acknowledgment

The authors wish to thank Dr. J. B. Woodford for advice during the early stages of this work and Dr. R. H. Rediker and Dr. A. L. McWhorter for helpful discussions. The compensated crystals used here were supplied by the Massachusetts Institute of Technology Lincoln Laboratory.

A New Semiconductor Tetrode — The Surface-Potential Controlled Transistor*

C. T. SAH†, MEMBER, IRE

Summary—**The theory and operating characteristics of a new semiconductor tetrode is discussed in this paper. This semiconductor junction device has the usual geometry of the planar transistor, but with an additional metal electrode placed on the oxide which covers the surface of the emitter-base junction. This electrode serves as a grid. The grid-base voltage controls the surface potential, surface recombination rate and the size of the surface channel, and thereby the current gain of the transistor. In the common emitter connection the grid serves as a second input in addition to the base input. Input impedance of the grid is typically in the range of 1 to 100 pf and 10^{15} ohms. Transconductances dI_C/dV_{GE} of several thousand micromhos have been achieved in the common emitter connection. The cutoff frequency of the transconductance is approximately the same as that of the h_{fe}.**

I. Introduction

IT is well known that surface plays a very important part in controlling the electrical characteristics of transistors and diodes. It has been demonstrated recently that surface protection by thermal oxidation of silicon transistor (the planar transistor) greatly improves the low-current characteristics such as the leakage current and the current-gain factor h_{FE}.[1] In addition oxide surface protection has provided orders of magnitude improvement in the stability and reliability in the over-all performance of transistors and diodes.

The development of the silicon-oxide surface-protection techniques has facilitated the study of surface effects on the electrical characteristics of p-n junctions through controlled and designed experiments.[2] In addition it has considerably simplified the fabrication problems of silicon semiconductor components which have rather complicated geometries, such as the various microcircuit elements (*i.e.*, flip-flops, gates, half-shift registers, etc.), which consist of transistors, diodes, resistors and capacitors all built on the same block of silicon by solid-state diffusion techniques. In this paper one of a new family of semiconductor devices will be described which may be considered as an integrated circuit consisting of a surface-potential controlled junction and a transistor triode.

This family of semiconductor junction devices consists of modified versions of the usual diodes, triodes and p-n-p-n or multijunction switches. In addition to the usual electrodes, these devices have one or more metal electrodes placed on top of the oxides which cover the surface of the junction transition regions. A cross-sectional view of the tetrode is shown in Fig. 1.



Fig. 1—A cross-sectional view of the surface-potential controlled tetrode.

Both the emitter-base and the collector-base junctions are oxide protected. A grid electrode is placed on the oxide of the emitter-base junction surface. The voltage applied to the metal electrode, or the grid, controls the surface potential, the recombination rate, and the size of the surface channel. The modulation of the reverse current-voltage characteristics of the junction by the grid voltage is somewhat similar to the effect of the gate voltage on the source to drain current-voltage characteristics of the field-effect transistor.[3] However, there is a major difference: in the surface-potential controlled devices, minority carrier recombination and generation in the channel provides a considerable amount of junction current, while in the field effect transistors the modulation of the source to drain characteristics by the gate voltage is obtained through the control of the channel conductance of the majority carriers. In this paper the electrical performance and the physical theory of the tetrode will be discussed.

II. Electrical Characteristics

Experimental measurements on a number of n-p-n- and p-n-p-type surface-potential controlled tetrodes are made. Families of electrical characteristics will be presented.

* Received by the IRE, July 5, 1961; revised manuscript received, September 1, 1961. This paper was presented at the WESCON Convention, San Francisco, Calif.; August 25, 1961.

† Fairchild Semiconductor, Div. of Fairchild Camera and Instrument Corp., Palo Alto, Calif.

[1] J. A. Hoerni, "Planar Transistors," presented at the IRE Annual Electron Devices Conf., Washington, D. C.; October 27–29, 1960. Published as Fairchild Tech. Paper TP-14.

[2] C. T. Sah, "Effect of Surface Recumbination and Channel on Diode and Transistor Characteristics," presented at the AIEE-IRE Solid State Device Res. Conf., Stanford University, Calif.; June 26–28, 1961.

[3] W. Shockley, "A unipolar field effect transistor," PROC. IRE, vol. 40, pp. 1365–1376; November, 1952.



Fig. 2—The dc current gain h_{FE} for an *n-p-n* tetrode plotted as a function of collector current for several grid voltages.



Fig. 3—The dc current gain h_{FE} for a *p-n-p* tetrode plotted as a function of collector current for several grid voltages.

A. $h_{FE}-I_C$

The dc beta or h_{FE} is measured as a function of collector current in the common-emitter configuration with the grid voltage as a parameter.[4] The experimental data are plotted for the high-voltage version of the *n-p-n* and *p-n-p* units in Figs. 2 and 3. The leakage current I_{CEO} is less than 0.5 mμa for both units. The characteristics are very similar and show considerable reduction of current gain at low current and large grid voltage. The slope of the curves asymptotically approaches 0.5 at large grid voltage and low currents; *i.e.*, $h_{FE}=(I_C-I_{CEO})/I_B \sim \sqrt{I_C}$, indicating that the base current varies approximately as $\sqrt{I_C}$. It has been observed[2] that the collector current varies as exp (qV_{EB}/kT) over almost ten decades of collector current; thus the base current varies as exp $(qV_{EB}/2kT)$.

[4] The definition of h_{FE} in this paper is slightly different from that of the IRE Standard, as pointed out by R. L. Pritchard to us during the WESCON. The defining equation for h_{FE} used in this paper is $h_{FE}=(I_C-I_{CEO})/I_B$, which is more useful than the standard definition $h_{FE}=I_C/I_B$, since the latter one goes to infinite at zero base current while the former one approaches h_{fe} at low base current and is still a meaningful quantity in equivalent circuits.



Fig. 4—The high-current transfer characteristics of an *n-p-n* tetrode with thin oxide on the emitter-base junction in the common-emitter connection.



Fig. 5—The medium-current transfer characteristics of an *n-p-n* tetrode with thick oxide on the emitter-base junction in the common-emitter connection.

B. I_C-V_{GE} (*Transconductance*)

The transfer characteristics are also obtained in the grounded emitter configuration and are shown in Figs. 4–6. The tetrode 1NP2 of Fig. 4 is a low grid-voltage *n-p-n* device which has thinner oxide and lower surface concentration in the base region than the *n-p-n* tetrode 1W1-3, shown in Fig. 5.

For the low-voltage tetrode 1NP2 shown in Fig. 4, the maximum h_{FE} for a given base current is obtained at a negative grid voltage of approximately −8 volts at low current and the optimum grid voltage decreases to −12 volts at high current. The grid voltage at maximum h_{FE} varies in a similar way for the high grid-voltage device 1W1-3, shown in Fig. 5.

Maximum transconductance $g_m=dI_C/dV_{GE}$ at a given base current is reached at a positive grid voltage as indicated in Figs. 4 and 5. The transconductance also increases with base or collector current, and is nearly proportional to the base current or the square root of



Fig. 6—The medium-current transfer characteristics of a *p-n-p* tetrode with thick oxide on the emitter-base junction in the common-emitter connection.



Fig. 7—The frequency dependence of the transconductance and current gain of a thick oxide *n-p-n* tetrode.



Fig. 8—The frequency dependence of base input-noise voltage for several grid voltages.

the collector current at low currents. At large base current unit 1NP2 in Fig. 4 shows a g_m of 7000 μmhos at $I_C = 50$ ma and a grid voltage of 5 volts. The sign of the transconductance is negative in the positive grid-voltage region. However, at large negative grid voltage, a positive transconductance is obtained. The magnitude of the negative grid voltage for large positive g_m approaches the destructive dielectric breakdown condition in the oxide.

An entirely similar behavior with the *same* sign for the grid voltage is observed for the transfer characteristics or *p-n-p* tetrodes, shown in Fig. 6. Thus, a positive g_m is obtained for the *p-n-p* devices with a positive grid voltage which is safely below the dielectric breakdown limit. It is believed that surface channel formation may account for the observed behavior of both the *n-p-n* and the *p-n-p* devices. In the *n-p-n* tetrode the maximum g_m region of positive grid voltage corresponds to an increase in size of the channel formed on the surface of the *p*-type base under the grid-metal electrode, while for the *p-n-p* tetrode the channel is also formed in the *p*-type region but in the emitter. A more detailed discussion of the physical theory will be given in a subsequent section.

C. g_m Frequency

The frequency response of the transconductance appears to be limited by the usual minority-carrier diffusion time in the base. A preliminary measurement for an *n-p-n* tetrode is shown in Fig. 7. The 3-db point for g_m is about 600 kc, which is nearly equal to the h_{fe} cutoff frequency of this device.

D. Grid Input Impedance

The input capacitance of the grid to the combined emitter and base leads is about 4.5 pf for the high grid-voltage devices 1W1-1, 1W1-3, 47-SCT1-1 and 47-2C1-5; and about 22.5 pf for the low grid-voltage unit 1NP2. The capacitance is independent of the grid voltage over the entire range up to the dielectric breakdown voltage corresponding to about 2 to 5×10^6 volts/cm.

The leakage or the input resistance has not been measured successfully with commercial electrometers indicating a value greater than 10^{14} ohms. An alternative approach is made by measuring the RC discharge time of the input capacitance, using the collector current as an indicator of the grid voltage, and using a constant-base current drive in the common-emitter connection. The decay time constant thus measured is from one to three hours giving a leakage resistance of greater than 10^{15} ohms for the 1W1-3 unit. The variation of the experimental results of the decay time constant appear to be associated with the humidity of the room ambient and the leakage in the lead through the glass of the transistor package.

E. Base Input Noise

The input-noise voltage referred to the base input terminal is measured as a function of frequency with the grid voltage as a parameter. In Fig. 8 the narrow-band noise voltage referred to the input is plotted as a function of frequency for a bandwidth of 6 cps and a source resistance of 500 ohms. At large positive grid voltage, the h_{fe} of the tetrode is decreased but is sufficient so that the noise from the amplifier is still unimportant. The data in Fig. 8 show that the 1/f noise is increased as much as 20 db at low frequencies by the grid voltage, and the crossover frequency to shot noise f_{co} is increased from 700 cps to 30 kc when the grid voltage is increased

from 0 to 10 volts. The tetrode unit shown in Fig. 8 is similar to the unit 1NP2 shown in Fig. 4. The result of the base input noise is not surprising since it is well known that in semiconductor devices the 1/f noise is closely associated with the formation of surface channels.[5] The input noise referred to the grid lead at present has not been measured.

III. Physical Theory

The design theory and the basic mechanisms which control the electrical characteristics of the surface-potential controlled transistors and diodes may be best analyzed using the physical circuit of the device shown in Fig. 9(a). An enlarged view of the region where the emitter-base junction intercepts the surface is shown and the junction transition regions are shaded in Fig. 9(a). These transition regions are defined in the sense that negligible voltage drop occurs outside these regions, *i.e.*, about kT/q or less.[6,7] The shape of the shaded transition region near the surface corresponds to a positive voltage applied to the grid electrode relative to the base electrode, and an *n*-type surface channel on the base side is formed. This situation corresponds closely to that in the *n-p-n* tetrodes shown in Figs. 2, 4 and 5 at fairly large positive grid voltage. The potential energy diagram showing an equipotential surface for electrons is given in Fig. 10.

The equivalent circuit of the tetrode may be derived from Fig. 9(a) and is given in Fig. 9(b). The effect of the grid induced emitter-base surface channel may be conveniently included as a surface diode *SD* connected to the *external* base and emitter leads of a real silicon transistor which has no surface leakage in the emitter-base junction. Thus, the characteristics for a typical tetrode may be discussed in two parts with little interaction between the two, except through the two external lead connections.

A. The Transistor Characteristics

In addition to the usual diffusion currents, the ideal transistor shown in Fig. 9(b) includes also the recombination and generation currents in the transition regions of the junctions.[8] Thus, the usual transistor equations in the grounded base connection are (*p-n-p*)

$$J_E = j_{ET} 2 \sinh \theta_E/2 + j_D[(e^{\theta_E} - 1)/\gamma_N - (e^{\theta_C} - 1)\alpha_T] \quad (1)$$

$$J_C = j_{CT} 2 \sinh \theta_C/2 + j_D[(e^{\theta_C} - 1)/\gamma_I - (e^{\theta_E} - 1)\alpha_T] \quad (2)$$



Fig. 9—(a) The physical circuit, and (b) the equivalent circuit, of the surface-potential controlled transistor tetrode.



Fig. 10—The equipotential surface (top figure) and the cross-sectional view of an asymmetrical emitter-base surface diode in which the *n*-type emitter is more heavily doped than the *p*-type base.

where

$$\theta_E = qV_{EB}/kT$$
$$\theta_C = qV_{CB}/kT$$
$$\alpha_T = \text{sech } (W_B/L_B)$$
$$\gamma_N = j_D/(j_E + j_D)$$
$$\gamma_I = j_D/(j_C + j_D)$$
$$j_D = (qn_B L_B/\tau_B) \text{ ctnh } (W_B/L_B)$$
$$j_C = (qn_C L_C/\tau_C) \text{ ctnh } (W_C/L_C)$$
$$j_E = (qn_E L_E/\tau_E) \text{ ctnh } (W_E/L_E)$$
$$j_{ET} = qn_i W_{ET} f(b_E)/\sqrt{\tau_{po}\tau_{no}}\alpha_E$$
$$j_{CT} = qn_i W_{CT} f(b_C)/\sqrt{\tau_{po}\tau_{no}}\alpha_C$$

for unit emitter and collector area.

The widths W_B, W_C, and W_E are the widths of the base, collector and emitter layers, respectively, while W_{CT} and W_{ET} are the widths of the collector and emitter transition regions. The n's are the minority-carrier concentrations, n_i is the intrinsic carrier concentration, and

[5] A. L. McWhorter, "1/f noise and germanium surface properties," in "Semiconductor Physics," R. H. Kingston, Ed., University of Pennsylvania Press, Philadelphia, pp. 207–228, 1957; "1/f Noise and Related Surface Effects in Germanium," Res. Lab. of Electronics, Mass. Inst. Tech., Cambridge, Tech. Rept. 295, May 20, 1955.

[6] C. T. Sah, "Effect of electrons and holes on the transition layer characteristics of linearly graded *p-n* junctions," Proc. IRE, vol. 49, pp. 603–618; March, 1961.

[7] W. Shockley, "The theory of *p-n* junctions in semiconductors and *p-n* junction transistors," *Bell Sys. Tech. J.*, vol. 28, pp. 435–489; July, 1949.

[8] C. T. Sah, R. N. Noyce and W. Shockley, "Carrier generation and recombination in *p-n* junctions and *p-n* junction characteristics," Proc. IRE, vol. 45, pp. 1228–1243; September, 1957.



Fig. 11—The forward characteristics of an emitter-base surface diode with the grid voltage as a parameter. The quantity m is given by (3).



Fig. 12—The transfer characteristics of thin oxide emitter-base surface diodes with emitter-base voltage as a parameter.

the τ's are the minority-carrier lifetime in the emitter, collector and base layers. The L's are the minority-carrier diffusion lengths given by $L=\sqrt{D\tau}$, and τ_{po} and τ_{no} are the minority-carrier lifetimes in heavily doped n- and p-type specimens, respectively. The quantity $f(b)/\alpha$ may be approximated by $2/(\sqrt{\tau_{po}/\tau_{no}}+\sqrt{\tau_{no}/\tau_{po}})$ for $V_{EB}>4kT/q$ if the energy level of the recombination center is located nearly at the intrinsic Fermi level and if $\tau_{po}=\tau_{no}$.[6] For the reverse-biased collector junction, the leakage current $J_{CBO}\doteq j_{CT}2\sinh\theta_C/2$ is proportional to W_{CT}.[8]

The ac equations may be obtained from (1) and (2) in the usual way by expanding the currents and voltages in the form of $A=A_0+A_1\exp(j\omega t)$ and assuming $A_0\gg A_1$.

B. The Emitter-Base Surface-Diode Characteristics

The theoretical analysis of the surface diode characteristics is extremely complicated since it involves the solution of three nonlinear simultaneous partial-differential equations[7] in a two-dimensional geometry. The problem is further complicated by the discontinuity of the crystal lattice at the Si-SiO_2 interface which may result in high concentration of surface states that are continuously distributed in the energy gap. Preferential precipation of impurities such as gold or other metals at the interface might occur due to the high electric field near the surface. These impurities may provide additional recombination sites at the interface which have surface recombination properties different from those in the bulk. The derivation of the surface-diode current-voltage relation is possible only by using rather simplified assumptions based on plausible physical considerations and experimental observations.

The observed current-voltage relation of the emitter-



Fig. 13—The transfer characteristics of a thick oxide emitter-base surface diode with emitter-base voltage as a parameter.

base surface diode SD shown in Fig. 9(b) may be approximated by

$$J_{SD}=j_{SD}2\sinh(qV_{EB}/mkT), \tag{3}$$

where both j_{SD} and m are functions of the grid-base or grid-emitter voltage. The factor m may vary from 1 to as high as 10 or more, depending on the width and doping of the surface channel, and it also varies with the emitter-base voltage. The usually observed values of m for the emitter-base surface diode of the tetrodes such as that in Fig. 11 are in the range of 1.5 to 4, and the coefficient j_{SD} has a thermal activation energy of from half of the energy gap to one-fourth the energy gap in silicon.

The experimental data given in Figs. 12 and 13, where I_B is plotted against V_{GE} for two oxide thicknesses, indi-

cate that the current flowing in the surface diodes may result from two distinct mechanisms. Fig. 12 shows that 1NP2 has only one type of behavior, which is characterized by the appearance of a maximum in the diode-current vs the grid-voltage characteristics. The data of the high grid-voltage tetrode 1W1-3 shown in Fig. 13 appear to have also only one type of behavior which is characterized by a monotonically increasing current with increasing or decreasing grid voltage from the minimum current point. The data for 2L2-4 given in Fig. 12 clearly show both types of behavior, indicating that both components of the surface current are present and are superimposed on each other. The fine structures near $V_{GE}=80$ v in the characteristics of 1W1-3 in Fig. 13 suggest that a second component of surface current is probably present in this unit.

For mathematical simplicity, ease of discussion, and physical understanding, it is convenient to break up the surface into two regions: 1) the region corresponding to the projection of the emitter-base transition region onto the surface; and 2) the channel region outside of the emitter-base transition region. Both of these regions are labeled and shown in Fig. 10. In the following discussion it will be shown that the surface-current component which has a maximum vs the grid voltage may be accounted for by the recombination current in the transition region on the surface, while the surface-current component which is monotonically increasing from a minimum value with increasing or decreasing grid voltage corresponds to the recombination current flowing in the surface channels.

1) Surface-Recombination Current in the Transition Region: The diode current due to surface recombination in the transition region would be expected to go through a maximum when the surface potential (or the intrinsic Fermi level at the surface) is moved by the grid voltage to within $(\frac{1}{2})\log_e(S_{po}/S_{no})$ from the average value of the quasi-Fermi levels for electrons and holes, where S_{po} and S_{no} are the surface-recombination velocities for holes and electrons on degenerate n- or p-type surfaces. The diode current from this region would decrease asymptotically to constant values when the grid voltage is either decreased or increased from the value of the maximum surface recombination. The shapes of the diode current vs grid voltage or surface-potential characteristics are very similar to those of the surface-recombination velocity observed on uniform surfaces which have no junctions. Several maxima may be expected if there are several independent surface-recombination centers.[2]

The derivation of this result may be developed using a simple example: the ideal symmetrical junction with linear potential variation in the junction. In Fig. 14 the energy-band diagram at the surface for a symmetrical emitter-base surface diode is shown. The surface energy-band diagram in Fig. 14(b) corresponds to the condition of zero grid voltage and forward bias of the junction. The diagram in Fig. 14(c) includes only the surface



Fig. 14—(a) The cross-sectional view, (b) the energy band diagram at $V_G=0$, and (c) The surface-potential variation along the surface of a hypothetical symmetrical emitter-base surface diode.

potential curves, u_S (dashed) and the quasi-Fermi levels for electrons and holes on the surface. However, Fig. 14(c) shows the relative position of the surface potential u_S, under various grid voltages.

The steady-state recombination rate per unit surface area may be obtained from the Hall-Shockley-Read statistics.[9] It is given by

$$U_S = n_i\sqrt{S_{po}S_{no}}\sinh(qV_{BE}/2kT) \times \{\cosh[u_S-(u_p+u_n)/2+(1/2)\log_e S_{no}/S_{po}] + \exp(-qV_{BE}/2kT)\cosh[u_s-u_t + (1/2)\log_e S_{no}/S_{po}]\}^{-1}, \quad (4)$$

where S_{po} and S_{no} are the surface-recombination velocities on degenerate n- and p-type surfaces, respectively, u_p and u_n are the hole and electron quasi-Fermi levels, and u_S-u_t is the energy level of recombination centers measured from the intrinsic Fermi level. These energy levels are normalized to the thermal voltage $-kT/q$. In Fig. 14 and (4) it is assumed that the change of quasi-Fermi levels across the transition region is negligible but may be appreciable in the channel due to channel resistance. The maximum surface recombination occurs when the surface potential in (4) is

$$u_S=(u_p+u_n-\log_e S_{no}/S_{po})/2. \quad (5)$$

[9] R. N. Hall, "Germanium rectifier characteristics," *Phys. Rev.*, vol. 83, p. 228, 1951; "Electron-hole recombination in germanium," *Phys. Rev.*, vol. 87, p. 387; July, 1952. W. Shockley and W. T. Read, Jr., "Statistics of recombinations of holes and electrons," *Phys. Rev.*, vol. 87, pp. 835–842; September, 1952. D. T. Stevenson and R. J. Keyes, "Measurements of the recombination velocity at germanium surfaces," *Physica*, vol. 20, pp. 1041–1046; November, 1954.

The position of the maximum surface-recombination rate is shown in Fig. 14(c) as heavy dots. For this example, it is assumed that at zero junction and grid voltage an accumulation layer is formed on the p-type surface under the grid, and an exhaustion layer is formed on the n-type surface under the grid. The formation of accumulation and exhaustion layers might arise due to the work function differences between the silicon, oxide and metal of the grid electrode. Thus, the position of the maximum recombination rate $U_S(\max)$ coincides with the center of the junction when the grid voltage is a positive value labeled $V_G=1$ in Fig. 14(c). At zero grid voltage, the point of maximum surface recombination is slightly to the right of the center of the junction or closer to the n region. As the grid voltage is increased from large negative values, the maximum surface recombination point moves from the n region into the junction-transition region and then out of the transition region into the p region.

The surface potential u_S may be related to the grid voltage by an analytical procedure similar to that used for the metal-oxide-silicon capacitors.[10] However, the situation is somewhat different in the present case since there is a large minority-carrier concentration near the surface which is injected by the forward-biased junction. The results of the metal-oxide-semiconductor capacitor may be used as a zeroth approximation, using the carrier concentration in the transition region instead of that in the bulk to obtain the surface potential from the grid voltage.

The surface current may be approximated by assuming a constant recombination rate on the surface of the transition layer. The result is

$$I_{SD} = qW_{ET}U_SL_S, \tag{6}$$

where L_S is the circumference, W_{ET} is the emitter-base transition-layer width in the bulk, and U_S is given by (4) evaluated at the center of the junction-transition layer. Thus, using (4) and (5), (6) has the form given by (3) in which j_{SD} is a function of the grid-base voltage. Furthermore, (6) predicts the observed shape of the junction-current vs grid-voltage characteristics of device 1NP2 shown in Fig. 12. The maximum occurs at a grid voltage corresponding to the surface potential condition given by (5).

In the ideal symmetrical junction considered here the shape of the I_{SD} vs V_G plot is symmetrical with respect to the grid voltage corresponding to point of maximum surface recombination or maximum current. In the real emitter-base surface diodes of the n-p-n surface-potential controlled transistors, the surface of the n-emitter is more heavily doped than the surface of the p base. Thus, an asymmetrical junction is usually obtained, and the recombination rate would be asymmetrical with respect to the grid voltage, where the surface-recombination current is a maximum.

The diffusion current along the surface outside the transition region is similar to that in the bulk and is usually small compared with the recombination current in the transition region on the surface if a surface channel or an inversion layer is not formed.[8] The situation is more complicated if the width of the grid is comparable to the diffusion length.

In the case where the surface diffusion length is very long compared with the width of the grid electrode, the electron Fermi level u_n shown in Fig. 14(c) would be quite horizontal in the p region under the grid, and the entire surface area under the grid electrode in the p region would be important for carrier recombination, for positive grid voltage. An approximate result may be obtained by assuming no voltage drop along the surface under the grid electrode in the p region. The expression for current is in the same form as that given by (6) if W_{ET}, the width of the emitter-base transition layer, is replaced by the half width of the grid electrode $W_G/2$ and the recombination rate U_S is evaluated at the center of the region under the grid electrode on the p side. A similar consideration applies to the n region when the grid voltage is negative.

2) Channel Current: As the grid voltage is increased to certain value, such as that corresponding to $v_G=3$, shown in Fig. 14(c), the surface potential is pulled down and coincides with the Fermi level of holes on the surface of the p region outside the junction-transition region under the metal-grid electrode. The surface under the grid in the p region now becomes intrinsic. Further increase of the grid voltage results in the formation of an inversion layer although *not* a channel on the p surface, since the energy band is also lower in the n region. (A surface channel is defined as a region near a p-n junction into which either electrons or holes from the other side of the junction can flow without having to climb a potential barrier. For example, the channel shown in Fig. 10 under the grid in the p region is an electron channel, while the exhaustion surface layer in the p region not under the grid electrode is not an electron channel since the electrons must climb a barrier when they flow from the channel into the exhaustion layer.)

The appearance of a channel on one side of the junction under the grid where the band is flat or lower with respect to the other side of the junction near the surface, such as that shown in Fig. 10, may occur in asymmetrical junctions. The requirement for channel formation is that the grid voltage can change the surface potential or

[10] The problem of the potential variation in a metal-oxide-semiconductor sandwich was analyzed by its inventor, J. L. Moll, in "Variable capacitance with large capacity change," 1959 IRE WESCON Convention Record, pt. 3, pp. 32–36, and has since been analyzed by a large number of authors recently. Our notations follow closely that of R. H. Kingston and S. F. Neustadter, "Calculations of the space charge, electric field and free carrier concentration at the surface of a semiconductor," *J. Appl. Phys.*, vol. 26, pp. 718–720; June, 1955. More recent papers on the analysis of the oxide capacitor are: R. Linder, "Semiconductor surface varactor," 2nd Interim Rept. on Microwave Solid State Devices, Bell Telephone Labs. (Contract DA 36-039-sc-85325), pp. 13–40, November 30, 1960; and D. R. Frankl, "Some effects of material parameters on the design of surface space-charge varactors, "*Solid State Electronics*, vol. 2, pp. 71–76; January, 1961.

bend the energy band perpendicular to the surface effectively only on one side of the junction and not on the other side. A channel will be formed on the side where the surface potential can be changed more readily by the grid voltage. The readiness of bending the band may be controlled by the thickness of the oxide, the impurity concentration at the surface and the surface-state densities. In the case where a channel can be formed, it can occur at a grid voltage either before, at the same time, or after the onset of surface inversion. For example, let us consider the case shown in Fig. 15 in which the surface potential on the n side is locked in position and cannot be bent by the grid voltage appreciably. Then, as the grid voltage is increased, the surface potential or the energy band on the p side will be pulled down and become flat with respect to the n side ($V_G=3$) before the surface potential u_S coincides with the Fermi level for holes u_p ($V_G=4$). Thus, a channel for electrons is formed on the p surface before the onset of surface inversion $u_S=u_p$.



Fig. 15—(a) The cross-sectional view, (b) the energy band diagram at $V_G=0$, and (c) the surface-potential variation along the surface of a hypothetical asymmetrical emitter-base surface diode.

In the practical silicon tetrodes fabricated surface inversion and channel formation appear to be more readily achieved on the p-type than on the n-type surface under the oxide. This is evidenced by the experimental observations that the emitter-base surface-diode current, or the collector current of the tetrode, when plotted as a function of grid voltage, has almost the identical behavior for the n-p-n and the p-n-p tetrodes. Some typical data were shown in Figs. 5 and 6. Since the oxide thickness is fairly uniform and probably slightly thicker on the base side than on the emitter side due to the diffusion sequence, the nonuniformity of the oxide would probably not account for the same behavior of n-p-n and p-n-p tetrodes. The oxides on the emitter-base junction for the n-p-n and the p-n-p tetrodes are grown in the same way so that it is unlikely that there is high concentration of surface states preferentially located in the n region at the silicon-silicon-oxide interface. The surface-state density required to interpret the similarity of the transfer characteristics of n-p-n and p-n-p tetrodes would be extremely high in order that channel or surface inversion can barely be obtained in the n-type base surface of the p-n-p unit. However, it would still not explain why a channel is easily formed on the emitter surface of the p-n-p unit which is presumably doped to 10^{20} to 10^{21} surface concentration. Thus, it must be concluded that impurity segregation is important so that the n-type impurity is rejected by the oxide during thermal oxidation and forms a degenerate layer near the surface, while the p-type impurity, in this case boron, prefers the silicon oxide under the thermal oxidation condition and thus is depleted at the silicon-silicon-oxide interface. This conclusion seems to be in agreement with the thermodynamic calculation of Thurmond,[11] although his estimate of the segregation coefficient of boron between silicon and silicon oxide is not sufficiently accurate (*i.e.*, from 10^{-3} to 10^{3}) to substantiate the quantitative results obtained for the p-n-p tetrodes.

The formation of the channel or surface inversion layer in the base region or the emitter region may be calculated in a zeroth approximation by neglecting the electrons injected into the channel by the forward-biased emitter-base junction. This assumption is a somewhat better approximation here than when it was applied previously to the surface within the transition region in calculating the surface-recombination current. The results of the metal-oxide-semiconductor capacitor analysis can again be applied.[10]

The condition for the onset of surface inversion, *i.e.*, u_S coincides the Fermi level for the majority carriers, is plotted in Fig. 16. Let us consider a numerical example using unit 1W1-3 shown in Fig. 13. The oxide thickness is approximately $L_e=0.6$ micron, and the surface concentrations of the impurity in the base and the emitter regions are approximately 10^{18}/cc and 10^{20}/cc. From Fig. 16 one may obtain an approximate effective width of the surface space-charge layer width using the surface concentration instead of the true profile of the diffused emitter or base layers. In the base region Fig. 16 gives $x_e=0.02$ micron indicating that the surface-inversion layer is very thin and concentrated near the surface so that the use of the surface concentration instead of the

[11] C. D. Thurmond, "Distribution coefficients of impurities distributed between Ge or Si crystals and ternary alloys or surface oxides," *Proc. Metallurgical Soc. Conf.*, vol. 5, "Properties of Elemental and Compound Semiconductors," H. C. Gatos, Ed., Interscience Publishers, pp. 121–140; 1960. M. M. Atalla and E. Tannenbaum, "Impurity redistribution and junction formation in silicon by thermal oxidation," *Bell. Sys. Tech. J.*, vol. 39, pp. 933–946; July, 1960.

true impurity concentration profile is a good approximation. From Fig. 16 the electric field in the oxide at the onset of surface inversion may also be obtained. In the base region $E_o = 10^6$ v/cm and the voltage drop in the oxide is $V_o = L_o E_o = 60$ volts. The voltage drop in the space-charge region of the semiconductor is approximately 0.4 volt, given by $u_S - u_{SO}$ in Fig. 16. Thus, the total grid voltage required for surface inversion in the p base is about 60 volts, which corresponds well with the observed voltage where there is a rapid rise of I_B shown in Fig. 13.



Fig. 16—A chart of the electrical field in the oxide E_o; the total charge per unit area, Q_s; the equivalent thickness of the space-charge layer in the silicon; and the voltage drop in the silicon plotted as a function of the carrier concentration in the bulk for both n- and p-type silicon under the condition of surface inversion.

A similar calculation can be made to obtain the required grid voltage for surface inversion in the n emitter. Fig. 16 does not cover the degenerate range; however, a linear extrapolation on the log-log plot may be used for a rough estimate which yields $E_o = 5 \times 10^7$ v/cm or $V_o = 3000$ volts, a value considerably greater than the dielectric breakdown of the oxide.

In order to make a better approximation, it is necessary to include the injected carrier by the forward-biased junction. In the first-order approximation one may replace the carrier concentration in the bulk p_o (or n_o) by $n_i \exp(u_p - u_B) - n_i \exp(u_B - u_n)$, where u_p and u_n are the quasi-Fermi potential for holes and electrons and u_B is the intrinsic Fermi potential in the bulk.

An exact analysis of the recombination current in the channel or the surface-inversion layer is quite complicated since the channel or the inversion layer is quite thin and highly resistive. Consequently, there is a considerable amount of voltage drop along the length of the channel. For example, let us consider the case of an inversion layer and a channel formed at the same time in the p region such as that shown in Fig. 10. As the surface-inversion layer and channel are formed by increasing the grid voltage, a region of high recombination rate given by the condition similar to (5) if u_s is replaced by u appears at the silicon-silicon-oxide interface under the grid. As the grid voltage is further increased, the layer of high recombination rate moves away from the interface into the interior of the channel. The recombination rate decreases along the channel in the y direction in Fig. 10 due to the voltage drop in the channel. Thus, in calculating the total current flowing into the channel due to carrier recombination in the channel it is necessary to take into account the voltage drop along the channel.

The mathematical analysis of the channel current can be worked out with a procedure very similar to that used by McWhorter and Kingston[12] which was subsequently extended by Culter and Bath[13] to include the forward-bias region of silicon-alloyed diodes. These authors take into account the voltage drop in the channel. However, they neglected to use the appropriate recombination rate in the channel, which provides the most important voltage dependence of the channel current. For example, Culter and Bath took the diffusion current outside the channel to calculate the total current in the channel for silicon diodes. This approximation is valid only for channels in germanium diodes, since it is well known that the most important current in silicon junctions below or near room temperature comes from minority-carrier recombination in the transition region of the junction.[8] Consequently, the results of Culter and Bath, when correlated with experimental data in silicon,[13] require a channel length which is considerably greater than the maximum physical dimension of the silicon wafer of the diode. Furthermore, their theoretical results cannot account for a voltage dependence of $j_{SD} \exp(qV/mkT)$ of the channel current in which m is greater than 2 and j_{SD} has a thermal activation energy less than half of the energy gap. The extension of these analyses to the case appropriate to silicon junctions is fairly obvious if carrier recombination in the transition region in the channel is taken into consideration. The results can then account for a value of m as high as 4 and an activation energy of j_{SD} as low as $\frac{1}{4}$ of the thermal energy gap of silicon.

The calculation of the channel current may be formulated with reference to Figs. 10 and 17. It is assumed that the surface potential is changed by the grid voltage only in the p region and not in the n region, so that a channel will definitely be formed with positive grid voltage, and an equipotential surface similar to that given by Fig. 10 is obtained.

It is also assumed that the quasi-Fermi level for holes u_p is flat and that there is negligible recombination near the surface of the channel so that the total current flow there is entirely carried by electron flowing into the channel from heavily doped n-type emitter. Thus, the hole and the electron currents in the channel are[6,7]

$$I_p(y) = -qD_p p(du_p/dy)W_I L_S = 0 \qquad (7)$$

[12] A. L. McWhorter and R. H. Kingston, "Channels and excess reverse current in grown germanium p-n junction diodes," Proc. IRE, vol. 42, pp. 1376–1380; September, 1960.

[13] M. Culter and H. M. Bath, "Surface leakage current in silicon fused junction diodes," Proc. IRE, vol. 45, pp. 39–43; January, 1957.



Fig. 17—(a) The cross-sectional view, (b) the energy-band diagram at $V_G=0$, and (c) the surface-potential variation along the surface of a typical asymmetrical emitter-base surface diode.

and

$$I_n(y) = -qD_n n(du_n/dy)W_I L_S, \tag{8}$$

where D_n is the diffusion constant of electrons in the channel, n is the electron concentration in the channel, W_I is the inversion or channel width in the x direction and may be a function of y, and L_S is the circumference. The total current in the channel at a distance y from the emitter-base junction may be obtained (using the continuity relation) and is given by

$$I = I_n(y). \tag{9}$$

It is further assumed that the electron concentration is a constant along the surface of the channel. Thus, the change of the electron quasi-Fermi level u_n is entirely due to the voltage drop in the channel; *i.e.*,

$$n_S = n_i \exp(u_S - u_n) = \text{constant} \tag{10a}$$

or

$$du_S = du_n, \tag{10b}$$

where u_S is the surface potential normalized to the thermal voltage kT/q. The results given by (10a) and (10b), based on the assumption of constant electron concentration on the surface, is consistent with the relation

$$u_p - u_n = v, \tag{11}$$

where v is the normalized voltage drop along the channel. Thus, using (7), (8), (10b) and (11), and replacing n by n_S in (8), the total current flowing in the channel given by (9) may be written as

$$I(y) = qD_n n_S W_I L_S(dv/dy). \tag{12}$$

Another relationship between current and voltage along the channel may be derived by calculating the current flowing out of the channel in the x direction across the surface-potential barrier (see Fig. 10). This current $J_x(v)$ is provided by the electron and hole recombination in the region near the surface where the condition of maximum recombination rate given by

$$u = (u_p + u_n - \log_e S_{no}/S_{po})/2 \tag{13}$$

holds. This condition is similar to that given by (5) for recombination in the transition region on the surface. The recombination current $J_x(v)$ has the form given in Sah, Noyce and Shockley.[8] With the help of the continuity relation $\operatorname{div} \bar{I} = 0$, the change of the current flow along the channel in the y direction may be set equal to the current flowing out of the channel in the x direction due to electron-hole recombination. Thus,

$$dI(y)/dy = L_S J_x(v), \tag{14}$$

where

$$J_x(v) = qW_I U_I \tag{15}$$

is the recombination current per unit area in the transition region of the surface barrier in the channel. The major variation of $J_x(v)$ with voltage v for positive voltage or forward-bias comes from the term $\sinh(v/2)$ in the recombination-rate expression for U_I which is similar in form to (4).[6,8] Thus, (15) may be written as

$$J_x(v) = j_{SI} 2 \sinh v/2, \tag{16}$$

where

$$\begin{aligned} j_{SI} &= qn_i W_I f(b)/2\alpha\sqrt{\tau_{po}\tau_{no}} \\ &\doteq qn_i W_I/(\tau_{po} + \tau_{no}). \end{aligned} \tag{17}$$

Using (16) and (17), (14) may be written as

$$dI(y)/dy = [2qn_i W_I L_S/(\tau_{po} + \tau_{no})] \sinh v/2. \tag{18}$$

The two equations (12) and (18) may be combined to yield

$$\frac{d^2v}{dy^2} = \frac{2n_i}{n_s D_n(\tau_{po} + \tau_{no})} \sinh \frac{v}{2} \tag{19}$$

if it is assumed that W_I is not a function of y. This assumption is valid inside the channel not too close to the edge of the emitter-base transition region. The solution of (19) may readily be obtained if the channel or the inversion layer is short compared with the width of the grid electrode. Under this condition, it may be assumed that at $y = \infty$, $v(y) = 0$, $I(y) = 0$ and the solution for the current flowing into the surface-inversion layer or channel is

$$I_{SI} = I(0) = 4qW_I L_S \sqrt{\frac{D_n n_i n_s}{\tau_{po} + \tau_{no}}} \sinh \frac{qV_{EB}}{4kT}. \tag{20}$$

Thus, the above result has again the desired form required by the empirical formula given by (3). In particular, (20) shows that m may be as high as 4 if surface-channel or surface-inversion layer current dominates. It also shows that the thermal activation energy of j_{SD} in (3) is that of $\sqrt{n_i}$ in (20) or one fourth the energy gap of silicon. It further shows that the dependence of the channel current on the grid voltage comes from j_{SD} or W_I and n_s. A more accurate solution of (12) may be obtained from (19) if finite boundary conditions are used and the more accurate expression for $J_x(v)$ is used.

IV. Small-Signal Equivalent Circuit

The equivalent circuit of the tetrode was obtained in Fig. 9(b) from the physical circuit in Fig. 9(a). The most useful small-signal equivalent-circuit parameters are the hybrid parameters in the grounded emitter connection given by the following equations:

$$V_1 = h_{11}I_1 + h_{12}V_2 + h_{13}V_3 \tag{21}$$

$$I_2 = h_{21}I_1 + h_{22}V_2 + h_{23}V_3 \tag{22}$$

$$I_3 = h_{31}I_1 + h_{32}V_2 + h_{33}V_3. \tag{23}$$

The numerals refer to the electrodes shown in Fig. 9(b): 1 = base, 2 = collector, 3 = grid. Thus, $h_{21} = h_{fe}$, $h_{22} = h_{oe}$, $h_{23} = g_m$, $h_{12} = \mu_{12}$, etc. The hybrid-circuit representation is preferred since it reduces to the usual transistor representation if the base lead is used as input and grid is either dc biased or modulated. If the base lead is ac open circuited and the grid is the input, then the hybrid equations reduce to those similar to the vacuum-tube pentode, thus facilitating the comparison with vacuum pentodes.

The derivation of these h parameters from the equivalent circuit shown in Fig. 9(b) is straight forward with the help of (1) and (2) for the ideal transistor and (3) for the surface diode. The algebra involved is tedious, and only two important parameters will be discussed in the open-base-operation. These are the transconductance $h_{23} = g_m$ and the output admittance $h_{22} = h_{oe}$. The complete expression, neglecting the base resistance $r_{b'}$ and assuming open base, *i.e.*, I_1 (Base) = 0, are

$$g_m = h_{23} = h_{11}\left[j\omega C_{ge} + g_{SD}\sqrt{\frac{|I_c - I_{co}|}{j_D\alpha_T}}\right] \times \left[|I_c - I_{co}|\frac{q}{kT} - j\omega C_c\right] \tag{24}$$

$$Y_c = h_{22} = j\omega C_c + h_{11}(j\omega C_c + g_c) \times \left[|I_c - I_{co}|\frac{q}{kT} - j\omega C_c\right], \tag{25}$$

where

$$h_{11}^{-1} = \left[g_c + \sqrt{\frac{|I_c - I_{co}|}{j_D\alpha_T}}\, g_{SD} + h_{fe}^{-1}|I_c - I_{co}| \times \frac{q}{kT} + j\omega(C_c + C_e + C_{gb})\right] \tag{26}$$

$$h_{fe}^{-1} = \frac{1 - \alpha_T\gamma_N}{\alpha_T\gamma_N} + \frac{(j_{ET} + j_{SD})}{2\sqrt{j_D\alpha_T|I_c - I_{co}|}} \tag{27}$$

and

$$g_{SD} = \frac{\partial j_{SD}}{\partial V_{GB}},$$

which is the transconductance of the surface diode. In this derivation it is assumed that $m = 2$ in the surface-diode characteristics.

These relations may be simplified for low and intermediate frequencies. For practical tetrodes, most of the terms in h_{11}^{-1} given by (26) may be neglected, except $h_{fe}^{-1}|I_c - I_{c0}|q/kT$. Thus,

$$h_{11}^{-1} \doteq h_{fe}^{-1}|I_{co} - I_c|\frac{q}{kT}. \tag{28}$$

The output admittance becomes

$$Y_c = h_{22} \doteq (1 + h_{fe})j\omega C_c + h_{fe}g_c, \tag{29}$$

and the transconductance is

$$g_m = h_{23} \doteq \left[j\omega C_{ge} + g_{SD}\sqrt{\frac{|I_c - I_{co}|}{j_D\alpha_T}}\right] \times h_{fe}\left[1 - j\omega C_c\cdot\frac{kT}{q}|I_c - I_{co}|\right]. \tag{30}$$

Usually $j_D\alpha_T = 10^{-13}$ amp, $j_{SE} = 10^{-14}$ amp, $C_c = 10$ pf, $C_{ge} \sim 10$ pf and

$$g_{SD}\left[\frac{\alpha_T\gamma_N}{1 - \alpha_T\gamma_N}\right] \sim 10^{-10} \text{ mhos}.$$

Thus, the 3-db frequency of g_m given in (30) is essentially that of h_{fe}, in agreement with that observed in Fig. 7.

The low-frequency transconductance in the intermediate collector-current range may be approximated by

$$g_m = g_{SD}\sqrt{\frac{|I_c - I_{co}|}{j_D\alpha_T}}\,\frac{\alpha_T\gamma_N}{1 - \alpha_T\gamma_N}. \tag{31}$$

Only the first term in h_{fe}^{-1} given by (27) is retained to obtain (31). The square-root dependence of the transconductance on the collector current is observed in tetrodes in the intermediate collector-current range, and a sample of the experimental data is shown in Fig. 18.



Fig. 18—The low-frequency transconductance plotted as a function of collector current for a *p-n-p* tetrode.

V. Concluding Remarks

A new semiconductor tetrode, the surface-potential controlled transistor, has been described. This tetrode employs a field-effect electrode as the grid to modulate the emitter-base surface-diode characteristics of the transistor and thereby the h_{fe} characteristics. The grid features an extremely high input impedance of greater than 10^{15} ohms, and a small capacitance of a few picofarads. Transconductance of 7000 μmhos has been achieved which is frequency limited by the h_{fe} cutoff.

The elementary theory of the tetrode transistor is worked out, and the theory of the current-voltage characteristics of the emitter-base surface diode is developed in detail.

The development of the surface-potential controlled transistor adds to the transistors and diodes a new family of semiconductor devices which has additional control terminals and which provides additional flexibility and heretofore unobtainable electrical performance.

VI. Acknowledgment

The author is deeply grateful to a number of his colleagues who made the surface-potential controlled transistors a reality. In particular, he is indebted to G. E. Moore and V. H. Grinich for numerous suggestions. He wishes to thank D. A. Tremere and P. S. Flint for fabricating the devices, and H. Bogert for providing the high-frequency data shown in Fig. 7.

Correction

C. V. Freiman, author of "Statistical Analysis of Certain Binary Division Algorithms," which appeared on pp. 91–103 of the January, 1961, issue of Proceedings, has called the following to the attention of the *Editor:*

1) On p. 94, line 11 of the first paragraph, $\bar{s}_j$ replaces s_j.
2) On p. 95, (4), $\beta \rightarrow (\alpha\epsilon)$ replaces $\beta \rightarrow (\alpha)$.
3) On p. 101, (18), first row of matrix,
   6 6 12 42 6 · · · replaces
   6 6 12 42 66 · · · .
4) On p. 102, fifth line from bottom, drop $\hat{s}$.
5) On p. 103, Table IV, each entry of 3−2D should be replaced by 2−2D.

Corrections 4) and 5) were called to the author's attention by Dr. Algirdas Avizienis of the Jet Propulsion Laboratory of the California Institute of Technology.

The Pulsed Ruby Maser as a Light Amplifier*

P. P. KISLIUK† AND W. S. BOYLE†

Summary—**A pulsed ruby maser has been operated as a light amplifier using a ruby maser oscillator as a source. A net gain of a factor of two was observed. The dependence of the gain on temperature and pumping power agrees with theory within experimental limits.**

Introduction

USING two pulsed ruby masers, one for the signal source, the other as a light amplifier, we have observed power amplification of a factor of two for visible light. Early observations of line narrowing and the change in the relative intensity of the two R lines in ruby [1], showed that an appreciable part of the fluorescent light at achieved levels of excitation was in fact due to induced emission. The successful operation of maser oscillators [2], [6] leaves no doubt that sufficient gain is attained to overcome the losses [7], but gives no independant measurement of the gain or loss separately. While direct observation of amplification has been obtained in the helium-neon gas device [5], [8] the gain is considerably less than that to be reported herein, and the technique of measurement is different.

The difficulty in observing gain directly is that of distinguishing the signal from the natural fluorescence of the amplifier, *i.e.*, the high noise temperature [7]. By our use of a ruby maser oscillator as a source in these experiments, the signal was made so large that the signal-to-noise ratio was favorable.

Preliminary Remarks

The intensity I of an electromagnetic wave after traversing a distance x through a medium of absorption coefficient α is

$$I = I_0 e^{-\alpha x}, \tag{1}$$

where I_0 is the incident intensity at $x=0$. At the center frequency of an absorption line [7], [9],

$$\alpha = \frac{2}{\Delta\nu}\sqrt{\frac{\ln 2}{\pi}}\,\frac{\lambda_0^2}{8\pi\mu^2}\,\frac{N_1\left(\frac{g_2}{g_1}\right) - N_2}{\tau}, \tag{2}$$

where $\Delta\nu$ is the width of the absorption line at half maximum (a Gaussian shape is assumed) in cycles per second, λ_0 is the wavelength in cm, g_1 and g_2 are the statistical weights of the lower and upper states respectively, μ is the refractive index, N_1 and N_2 are the number of atoms per cm³ of the active species in the lower and upper states, respectively, and τ is the lifetime for spontaneous emission of the upper state in seconds. When $(g_2/g_1)\ N_1 - N_2$ is negative, one obtains amplification at wavelengths near λ_0. In solids $\Delta\nu$, λ_0, μ, and τ may be temperature dependent. For the transition in ruby of interest in this paper, μ and τ are relatively constant, while $\Delta\bar{\lambda}_0$ and the change in $\bar{\lambda}_0$ are given as functions of temperature in Fig. 1. (These symbols represent the line width and the line position expressed in cm^{-1}.) The maser oscillator yields light in a very narrow range at a wavelength close to that of the center of the natural line at the temperature of the ruby [10]. Therefore, to achieve maximum amplification, the temperature of the amplifier ruby must be close to that of the source ruby. Nevertheless, the optimum condition for a given temperature of the source is reached not when the amplifier is at exactly that temperature, but rather when it is somewhat colder because the narrowing of the line with decreasing temperature causes the gain (or absorption) to be an asymmetric function of the temperature difference between the amplifier ruby and the source ruby. The expected difference is of the order of a few degrees near room temperature for the parameters



Fig. 1—*Upper Curve*—Departure of center of R_1 line toward lower wave numbers from an arbitrary zero near 14,418 cm^{-1} as a function of absolute temperature. At low temperatures where the two components due to the ground state splitting of 0.38 cm^{-1} are resolved, the mean position is plotted. (Data from A. L. Schawlow and G. E. Devlin.)

Lower Curve—Line width at half maximum as a function of absolute temperature [13].

* Received by the IRE, July 19, 1961; revised manuscript received, August 30, 1961. This paper was presented at the WESCON Convention, San Francisco, Calif.; August 25, 1961.

† Bell Telephone Labs., Inc., Murray Hill, N. J.

plotted in Fig. 1. As the temperature is lowered, its control becomes more critical because of the narrowing of the line. The exponential dependence of the gain on the departure in frequency from the line center makes the gain appear to be a sharper function of frequency when it is large, which further exaggerates the importance of thermal control at low temperatures.

Consider a three-level maser system with $g_1 = g_2$ in which the time spent in the highest (pumping) state is negligible compared with the normal lifetime in the upper state of the maser transition, τ_u, or with the lifetime—in the presence of the pumping light—of the ground state, τ_g. So long as the average lifetime in the upper maser state is not appreciably shortened by stimulated emission, we have

$$N_2/N_1 = \tau_u/\tau_g. \tag{3}$$

Now τ_g is inversely proportional to the pumping power P.

$$\tau_g = C'/P, \tag{4}$$

whence

$$N_2 - N_1 \equiv -\Delta N = \left(\frac{\tau_u P}{C'} - 1\right) N_1. \tag{5}$$

Furthermore we have

$$N_1 + N_2 = N, \tag{6}$$

the total density of the active species. Therefore,

$$-\Delta N = \left(\frac{CP - 1}{CP + 1}\right) N. \tag{7}$$

Substituting into (1) and (2) and taking the logarithm of both sides,

$$\ln G = \frac{CP - 1}{CP + 1} + K, \tag{8}$$

where G is the gain and K is another constant. For small P, where $CP \ll 1$, the RHS of (8) becomes $\approx (2CP - 1) + K$, and $\ln G$ is a linear function of pumping power, while for $CP \gg 1$ $\ln G$ approaches $1 + K$ asymptotically. One would expect τ_u to be shortened by stimulated emission when $\ln G$ becomes greater than zero, and the asymptote, therefore, to be approached more gradually than indicated by (8). Note that (2) predicts the maximum possible gain at a given temperature to be the inverse of the attenuation at that temperature (for no pumping power) and that if we define the attenuation factor to be A, and $f \equiv \Delta N/N$,

$$\ln G/\ln A = f. \tag{9}$$

For ruby the situation described in this simple treatment is complicated by the fact that the lower state consists, in fact, of two closely spaced levels. At the temperatures of these experiments this can be taken into account by letting the statistical weight of the ground state be twice that of the upper level, *i.e.*, $g_1 = 2g_2$. Furthermore there are two metastable R levels which are populated by the pumping light with appreciable quantum efficiency. When there is maser action evacuating the lower of these levels, the tendency to re-establish a Boltzmann distribution between them occurs so rapidly that a large part of the excitation of the upper state is actually available for induced emission in the maser [11], but the derivation of (3)–(9) requires modification to take the appreciable population of the higher R level into account. Nevertheless, the form of (8) is unchanged and (9) is valid.

Apparatus

The essential parts of the apparatus are shown in the simplified diagram of Fig. 2. The signal source is a pulsed ruby maser of the conventional type, using a ruby rod 0.2 inch in diameter and 2 inches long, of about 0.05 per cent chromium by weight. The ends are



Fig. 2—Simplified diagram of the experimental arrangement.

polished flat and parallel. One end is silvered opaquely; the other silvered to allow a transmission of roughly 5 per cent. The maser light passes first through a filter which cuts down stray light from the oscillator flashtube, then through a collimator, following which a small portion of the beam is reflected out by a microscope cover glass to a phototube which monitors the input signal. A filter in front of this phototube cuts down the stray pumping light from the amplifier flashtube. The main portion of the signal beam then passes through the amplifying ruby which is similar to the source ruby ex-

cept that it is not silvered. The beam from the collimator is small enough in cross section so that no part of it strikes the side of the amplifying ruby or is masked by the amplifier housing. The beam then passes through another filter, and an attenuator, into a photomultiplier tube, which measures the output signal. Both the input monitor and the output signal are displayed on a dual beam oscilloscope. While the GE FT 524 flashtubes which supply pumping power to the two rubies are energized by separate power supplies and capacitors, they are fired simultaneously by a single switch. The housings of the rubies are designed to permit cooling by the flow of cold nitrogen, the temperature of which is measured in both inflow and outflow by means of thermocouples. The housings are lined with magnesium oxide powder in double-walled glass envelopes, providing white surfaces for efficient use of the pumping light. Even with this housing and the filters, a small amount of light from the amplifier flashtube reached the detectors, as well as some of the fluorescent light from the amplifier ruby (the noise referred to above). This is further minimized by masking the entrance to the photomultiplier tube so that it accepts only the solid angle containing the signal beam, but the undesired response is nevertheless easily detected. It is separated from the desired signal by means of its different time dependence.

Gain is measured by comparing the output to input ratio with the amplifier in place, $R_g = I_g/I_m$, to that received when the amplifier is completely removed from the beam, $R_0 = I_0/I_m'$. It is necessary to remove the ruby because the lower state in the transition giving rise to maser action is the ground state. Therefore, if the ruby is in place but not illuminated by the pumping light, it absorbs the signal light. While gain measured in this way, $G = R_g/R_0$, is the net external gain, the true amplification is greater than this because there are losses. The greatest of these losses is a reflection of about 8 per cent as the beam passes through each air-ruby interface.[1]

Results

Oscilloscope traces showing gain are exhibited in Fig. 3. The gain and attenuation (both corrected for reflection losses) observed at various temperatures for a constant input energy to the flashtubes are given in Fig. 4 together with theoretical plots of gain or attenuation computed using the parameters plotted in Fig. 1. The theoretical attenuation factor or gain is plotted for various constant values of $-\Delta N$ or ΔN, respectively. Because of inadequate temperature control for the more critical conditions encountered at lower temperature, and because of the difficulty in this region due to frost on the ruby surfaces, gains were not plotted at lower temperatures. However, it was observed at about -100°C that the amplifier broke into oscillation, and that, therefore, the gain must have been at least a factor of 12.5 to make up for the 92 per cent loss at each end (*i.e.*, only 8 per cent reflected). The gain obtained in this way is also indicated on Fig. 4 to show that it is consistent with the extrapolation from the directly measured gain.

The gain at a fixed temperature is given on a semilog plot as a function of the input energy to the flashtube in Fig. 5.

In both cases the behavior of the measured gain is consistent with the theory outlined earlier. Experimental errors giving rise to the scatter of the experimental points may be due to the crudity of the temperature measurement and control, and possibly also to the unavoidable thermal gradients introduced during the flash. Indeed, the true gains may be somewhat larger than those reported, since all errors outside our control were in the direction of reducing the measured gain, *e.g.*, scattering due to inclusions in the ruby, possible spreading of a small portion of the beam outside of the mask on the detector due to optical inhomogeneity in the ruby, etc. The errors due to these effects are certainly no larger than a few per cent, and are less than the scatter in the experimental points.

The oscilloscope traces of Fig. 3 have been smoothed by the use of long time constants in the detector circuits. If this is not done, the traces are quite ragged because of "spikes" [6], [12] in the output of the maser oscillator.

Because no new spikes appeared in our amplified signal when the long time constant was removed, we conclude that the amplification showed no sudden discontinuities in time, and that the origin of the spikes in maser oscillators lies in the interaction of the amplification and feedback and not in the amplification alone.

The gain of a factor of two at -40°C in the 5 cm long ruby corresponds to an α of -0.14 cm^{-1} for the state of inversion achieved. From (9) we compute f for this condition of pumping to be about 0.18 ± 0.05 consistently for all of the data of Fig. 4. This corresponds to a 26:30.5:43.5 division between the R_2, R_1, and ground state levels when the quantum statistical weights are taken into consideration, and the R_1 and R_2 states are assumed to be in thermal equilibrium.

At the highest outputs of the oscillator maser it was possible to saturate the gain so that reduced gain was observed ($\sim$1.3 where $\sim$2.0 was obtained at lower levels). While we observed no saturation of absorption at these levels, it is possible to construct considerably brighter oscillator masers than the one used in this experiment. All the data reported above was taken with such attenuation present that the intensity was at least a factor of four below that where saturation was ob-

[1] This could be minimized by means of antireflection coatings on the ruby faces, but this was not done in the present experiments.



Fig. 3—Oscillograms showing observation of gain. Upper trace in each of the three pairs is response of the input monitor phototube, while lower is signal received at final photomultiplier. Top pair: amplifier ruby removed from beam; middle pair: amplifier ruby present and pumped to exhibit amplified signal; bottom pair: amplifier ruby pumped with no input signal present, showing normal fluorescence and some unavoidable pumping light. Time scale—200 μsec/div.

The procedure is to subtract the curve of the bottom traces from the corresponding curves of the middle traces, then to compare the ratio of the amplified signal to its monitor with the ratio of the no ruby signal to its monitor.



Fig. 4—Solid curves are theoretical values of $e^{\alpha D}$ (*i.e.*, optical density) from (2) for the ruby length $D=5$ cm, and various indicated constant values of (N_1-N_2) for attenuation, or (N_2-N_1) for gain. For the attenuation factor at room temperature $N_1-N_2=N$, the number of chromium ions per cm^3, and the experimental points (+) are for Ruby #1 (nominally 0.05 weight per cent Cr_2O_3) and the points (□) for Ruby #2 (nominally 0.04 per cent Cr_2O_3). The measured values satisfy (2) for a concentration about 60 per cent of nominal, which is in satisfactory agreement with the true to nominal concentration ratio measured for such rubies [14]. The points (×) and (○) are the measured gains for Ruby #1 and Ruby #2, respectively, at a constant pumping condition, corrected for reflection at the ruby faces. The point (△) is the gain obtained from the fact that the amplifier broke into oscillation at that temperature, taking the reflection to be 8 per cent as obtained from the refractive index. The pumping condition is the same as that in the other gain measurements.



Fig. 5—Gain as a function of input energy to the flashtube at constant temperature.

served, in a region where gain was independent of signal strength within experimental error.

Although the feedback under the conditions of the direct gain measurements was small enough to be ignored, a new problem arises in an amplifier when the feedback is sufficient to nearly cancel the loss. In an oscillator the frequency is automatically that for which the feedback is positive. Since the phase of the feedback is reversed by a change in length of the ruby of only $\lambda_0/4\mu$, where μ is the refractive index, the phase of the feedback in an amplifier for an arbitrary frequency is difficult to control experimentally. The behavior of the amplifier under these conditions would be an interesting experiment in which one might expect large gain for a number of closely spaced extremely narrow frequency bands.

Acknowledgment

Helpful suggestions by D. A. Kleinman and C. G. B. Garrett are gratefully acknowledged. Without the equipment borrowed from a large number of our colleagues this experiment would not have been feasible.

Bibliography

[1] T. H. Maiman, "Optical and microwave-optical experiments in ruby," *Phys. Rev. Letts.*, vol. 4, pp. 564–566; June, 1960.
[2] ——, "Stimulated optical emission in ruby," *Nature*, vol. 187, pp. 493–494; August, 1960.
[3] P. P. Sorokin and M. J. Stevenson, *Phys. Rev. Letts.*, vol. 5, p. 557; 1960.
[4] ——, "Solid state optical maser using divalent samarium in calcium fluoride," *IBM J. Res. & Dev.*, vol. 5, pp. 56–58; January, 1961.
[5] A. Javan, W. R. Bennett, Jr., and D. R. Herriott, "Population inversion and continuous optical maser oscillation in a gas discharge containing a He-Ne mixture," *Phys. Rev. Letts.*, vol. 6, pp. 106–110; February, 1961.
[6] R. J. Collins, *et al.*, "Coherence, narrowing, directionality, and relaxation oscillations in the light emission from ruby," *Phys. Rev. Letts.*, vol. 5, pp. 303–305; October, 1960.
[7] A. L. Schawlow and C. H. Townes, "Infra-red and optical masers," *Phys. Rev.*, vol. 112, pp. 1940–1949; December, 1958.
[8] A. Javan, W. R. Bennett, Jr., and E. A. Ballik, private communication.
[9] A. L. Schawlow, "Infra-red and optical masers," *Solid State J.*, vol. 2, pp. 21–27; June, 1961.
[10] I. D. Abella and H. Z. Cummins, "Thermal tuning of ruby optical maser," *J. Appl. Phys.*, vol. 32, pp. 1177–1178; June, 1961.
[11] I. Wieder, private communication.
[12] R. J. Collins, private communication.
[13] A. L. Schawlow, "Fine structure and properties of chromium fluorescence in aluminum and magnesium oxide," *Advances in Quantum Electronics*, to be published.
[14] S. V. Grum-Grzhimailo and E. I. Utkina, *Trudy Inst. Krist. Akad. Nauk, U.S.S.R.*, vol. 8, p. 991, 1953; and D. M. Dodd, private communication.

Correction

I. Gerst, co-author of "The Elimination of Intersymbol Interference by Input Signal Shaping," which appeared on pp. 1195–1203 of the July, 1961, issue of Proceedings, has called the following to the attention of the *Editor*.

On p. 1196, condition c of Theorem 1 should read:

c) $|G(x+iy)| \leq Ce^{-ax}$, for $x<0$.

Inductance in Thin-Film Superconducting Structures*

NORMAN H. MEYERS†, SENIOR MEMBER, IRE

Summary—**Thin-film superconducting components and circuits assume the form of coupled strip-transmission lines. The self and mutual inductances of these lines are important to the gain and bandwidth of the circuits. The inductances are influenced strongly by penetration of magnetic fields into the conductors.**

This paper gives a field solution which shows that the lowest-order mode on a thin-film superconducting strip line is a TM or E wave because of penetration effects. This mode has a non-negligible axial electric field which makes it incorrect to calculate inductance on a flux-linkage-per-unit-current basis even at low frequencies. However, the low-frequency inductance can be correctly calculated on an energy basis if the kinetic energy of the superelectrons is included in the free energy. This latter method is applied to a structure of current practical interest, that of an arbitrary number of infinitely long, very wide, thin, parallel, superimposed, closely spaced conductors above a common ground plane. All distributed self and mutual inductances with any conductor or combination of conductors in either the super or normal state are evaluated.

Introduction

CONSIDERABLE work is being done to develop evaporated thin-film superconducting components and circuits for computer applications. This type of circuitry offers the potential advantages of high speed, small size, low-power dissipation, low cost, and logical simplicity. In addition, thin-film superconducting circuitry lends itself readily to batch fabrication by evaporation through masks. Many components and their associated interconnections can be evaporated simultaneously through the same set of masks. The structures thus fabricated assume the form of coupled transmission lines. The components, the thin-film cryotrons, are, in a sense, controlled transmission-line terminations.

Fig. 1 illustrates what is meant here. A control transmission line made of a hard superconductor such as lead passes over a gate transmission line which contains a series section of some softer superconductor such as tin. Suppose that the gate line carriers a dc current too small to cause the tin to self-switch into the resistive state. It is possible then, by passing a sufficiently large current pulse along the control line, to cause the associated magnetic field to switch the tin resistive without disturbing the lead. The sudden appearance of a resistive section in the gate line will cause a pair of wavefronts to propagate outward from the tin along the gate line. Eventually, these wavefronts can cause complete transfer of the initial dc gate current into an alternate superconducting path.

Each transmission line of Fig. 1 has a series self-inductance and shunt capacitance per unit length associated with it. In addition, the two lines are inductively and capacitively coupled together. Furthermore, the gate line may contain a series resistance. The resistance, inductance, and capacitance all enter into the dynamic behavior of such structures. The inductance, however, is the most interesting and difficult parameter to calculate since it is influence by the penetration of magnetic fields into both superconducting and normal conductors. The shunt capacitance and series resistance may be calculated by inspection over a wide range of frequencies, as will be shown.



Fig. 1—A thin-film cryotron in the form of coupled strip-transmission lines.

Usually the cryotron gate resistance is small compared with the characteristic impedance of the transmission line in which it is inserted. Under this condition, the transient behavior of the circuit may be adequately characterized in terms of lumped inductance and resistance alone. The shunt capacitance may be neglected in such a case.

There is another reason for emphasizing the role of inductance in the behavior of thin-film superconducting components and circuits. The switching of a superconducting film into the normal state under the influence of an applied magnetic field is governed by magnetic free-energy considerations.[1] The magnetic free energy of a given structure is conveniently expressed in terms of self and mutual inductances. Consequently, the current-gain characteristics of various thin-film cryotrons are related to their inductance parameters. Thus, both the gain and bandwidth of this type of circuitry are dependent on the inductance parameters.

The specific objectives of this paper are as follows.

1) To demonstrate that the lowest-order mode on a superconducting strip line is a TM or E wave because of penetration effects.

* Received by the IRE, April 21, 1961; revised manuscript received, August 28, 1961. The work described in this paper was supported by the Bureau of Ships, U. S. Navy.

† Harvard Business School, Boston 63, Mass. Formerly with Research Center, IBM Corp., Yorktown, N. Y.

[1] F. London, "Superfluids," John Wiley and Sons, Inc., New York, N. Y., vol. 1, p. 130; 1950.

2) To show that the low-frequency field solution has a transmission-line equivalent in terms of a distributed series inductance and resistance and a distributed shunt capacitance. It is further intended to set upper frequency limits on the validity of the equivalent transmission line.

3) To point out that the transmission-line inductance may be correctly calculated by consideration of the static magnetic-field energy only if the kinetic energy of the superelectrons is included as part of the free energy of the structure. It is also intended to show that the familiar *flux-per-unit-current* definition of inductance may not be applied unless the non-negligible axial electric field of the TM mode is taken into account.

4) To demonstrate the important role of the kinetic energy of superelectrons on the inductances of thin-film superconducting structures and to show that this energy leads to an interesting type of lossless slow wave in superconducting strip lines.

5) To apply the method developed for evaluating inductance to the case of an arbitrary number of wide, parallel, superimposed, closely spaced, infinitely long, thin-film conductors above a common ground plane and to calculate all the self and mutual inductances involved with any conductor or combination of conductors, either super or normal.

As early as 1947, Pippard[2] pointed out that a wave in a superconducting transmission line would be slowed because of penetration of the magnetic field into the conductors. More recently, Young[3] suggested that this phenomenon could be exploited in thin-film strip lines to measure penetration depth. Early experiments by Tansal[3] agree with predictions. Swihart[4] has done an exhaustive and excellent analysis of a strip line in which one superconductor is infinitely thick and the other is a thin film. The conductors in Swihart's work are characterized by the two-fluid model, and the dielectric regions inside and outside of the line are treated as lossy. He shows that the velocity is essentially dispersionless at low frequencies and low temperatures where the losses are low. He derives expressions which show the effects on velocity and attenuation as the frequency is raised or the temperature brought close to the critical value.

The field solution given in the Appendix may be regarded as a vast simplification of Swihart's analysis. It is included, however, since it is essential to an understanding of the present paper. The portions of this paper which may be regarded as new contributions are contained primarily in objectives 3) and 5) above. Item 5) is of particular practical significance and is treated at length.

[2] A. B. Pippard, *Proc. Roy. Soc.* (*London*), vol. A191, p. 399; 1947.
[3] D. R. Young, J. C. Swihart, S. Tansal, and N. H. Meyers, "Use of a superconducting transmission line for measuring penetration depths," *Bull. Am. Phys. Soc.*, ser. 2, vol. 5, p. 163; 1960.
[4] J. C. Swihart, "Field solution for a thin-film superconducting strip transmission line," *J. Appl. Phys.*, vol. 32; March, 1961.

Symbols

A complete list of the symbols used in this paper follows. The list is intended to assist the reader in interpreting the equations since, in this particular work, the equations express the salient ideas more clearly than is possible in the text.

Rationalized MKS units are used exclusively throughout this paper.

E = electric-field intensity
H = magnetic-field intensity
x, y, z, t = Cartesian space coordinates and time
I = amplitude of transmission-line current
V = amplitude of transmission-line voltage
a = transmission line, longitudinal propagation constant
j = square root of minus one
ω = radian or angular frequency
μ_0 = permeability of free space $= 4\pi \times 10^{-7}$ hy/m
σ = volume conductivity of normal conductor
ϵ = dielectric constant of transmission-line insulation
ϵ_0 = permittivity of free space $= (1/36\pi) \times 10^{-9}$ fd/m
β_n $(n = 1, 2, 3, \cdots)$ = reciprocal penetration depth in conductor n
$d_n (n = 1, 2, \cdots)$ = thickness of conductor n
$h_n (n = 1, 2, \cdots)$ = thickness of insulation layer immediately under conductor n
$\delta = (2/\omega\mu_0\sigma)^{1/2}$ = skin depth in a normal conductor
$F = (j\omega\mu_0\sigma)^{1/2}$ = complex reciprocal skin depth in normal conductor
G = any complex field or transmission-line quantity
J = volume density of conduction current (amps/m^2)
Z = series transmission-line impedance per unit length
Y = shunt transmission-line admittance per unit length
r = transmission-line series resistance per unit length
l = transmission-line series inductance per unit length
c = transmission-line shunt capacitance per unit length
λ_n = magnetic flux per unit length linking conductor n
i_n = conduction current in conductor n
X_1 = an arbitrary but particular value of position coordinate x_1
X_2 = an arbitrary but particular value of position coordinate x_2

H^s = surface value of magnetic-field intensity
α = ratio of surface field on one face to surface field on other face
W = width of transmission line
Re = take the real part of
K = magnetic free energy per unit length
K_h = magnetic free energy per unit length in dielectric
K_s = magnetic free energy per unit length in superconductor
K_n = magnetic free energy per unit length in normal conductor
$k_s = [\mu_0 |\boldsymbol{H}|^2 + \mu_0 \beta^{-2} |\boldsymbol{J}|^2]/2$ = magnetic free-energy density in superconductor
$k_n = k_h = \mu_0 |\boldsymbol{H}|^2/2$ = magnetic free-energy density in dielectric or normal conductor
b_n = effective penetration distance in superconductor n for self-current
c_n = effective penetration distance in superconductor n for induced current
$[L_s]$ = inductance matrix with all conductors in the superstate
$[L_n]$ = inductance matrix with one or more conductors in the normal state
$\lambda(0)$ = penetration depth at absolute zero temperature
θ = temperature normalized with respect to critical temperature.

Strip-Line Field Solution

Consider the strip-transmission-line structure shown in Fig. 2. It consists of a dielectric layer sandwiched between a normal conductor and a superconductor. Both conductors are of width W in the y direction, which is large enough compared with total thickness $(h+d_1+d_2)$ so that fringing may be neglected, but small enough compared with a wavelength at the highest frequencies of interest so that there is no appreciable variation of field quantities in the y direction $(\partial/\partial y = 0)$.



Fig. 2—A thin-film strip line consisting of one normal conductor and one superconductor.

The normal conductor is characterized by a conductivity σ which is assumed to be large enough that conduction current dominates over displacement current, even at the highest frequencies of interest. Similarly the superconductor is characterized by a reciprocal penetration depth β which is large enough that the supercurrent dominates over the conduction current of the normal electrons and over the displacement current. The dielectric is assumed lossless so that only displacement current flows through it. Thus, the magnetic-field intensity $\boldsymbol{H}$ satisfies the following equations in each region.

Normal conductor—the skin-effect equation:[5]

$$\nabla^2 \boldsymbol{H} = j\omega\mu_0\sigma \boldsymbol{H}. \tag{1}$$

Superconductor—the static London equation:[6]

$$\nabla^2 \boldsymbol{H} = \beta^2 \boldsymbol{H}. \tag{2}$$

Dielectric—the wave equation:[7]

$$\nabla^2 \boldsymbol{H} = -\omega^2 \mu_0 \epsilon \boldsymbol{H}. \tag{3}$$

The most interesting and questionable assumption involves the use of the static London equation to describe the superconductor. First let us consider neglecting the normal conduction current compared with the supercurrent.[8] This can readily be shown to be equivalent to the requirement that at each point in the material

$$\omega\mu_0\sigma\lambda^2(0)(1-\theta^4)^{-1} \ll 1, \tag{4}$$

where $\lambda(0)$ is the penetration depth at absolute zero temperature, σ is the conductivity of the normal electrons at the temperature in question, and θ is temperature normalized with respect to the critical temperature of the material. Clearly, the assumption falls apart if the frequency is too high or the temperature too close to the critical value. If one takes as typical values for tin,

$$\lambda(0) = 500 \text{ Å}$$

and

$$\sigma = 4.26 \times 10^8 \text{ mhos/m},$$

it is a straightforward matter to show that the normal conduction current is less than 1 per cent of the supercurrent at a frequency of 1 kMc so long as the reduced temperature remains below 0.95. At the same frequency but at a reduced temperature of 0.995 the normal conduction current has risen to only 10 per cent of the supercurrent. At lower frequencies the temperature limit is still less severe.

Next arises the question of how meaningful it is to work with the London theory at all in view of the more modern nonlocal theories. Ittner[9] has examined the

[5] See, for example, S. Ramo and J. R. Whinnery, "Fields and Waves in Modern Radio," John Wiley and Sons., Inc., New York, N. Y., 2nd ed., ch. 6; 1953.
[6] London, *op. cit.*, ch. B.
[7] Ramo, *op. cit.*, ch. 7.
[8] London, *op. cit.*, sec. 3, p. 32.
[9] W. B. Ittner, III, "The critical fields of thin superconducting films," *Phys. Rev.*, vol. 119, pp. 1591; 1960.

situation in detail and has arrived at some helpful conclusions. He has shown that it is possible to define an effective penetration depth such that the spatial variation of magnetic field in a thin film as predicted by the London theory differs by less than $\frac{1}{2}$ per cent from that predicted by the BCS theory. This effective penetration depth, as defined by Ittner, differs from the London penetration depth in that it is a function of film thickness and purity. If either the film thickness or mean-free path becomes less than the coherence length, the effective penetration depth rises rapidly. Using this effective penetration depth, Ittner[9] has further shown that the measured critical fields of thin tin films are in reasonable agreement with the predictions of London. This last point is significant since it indicates that it makes sense to calculate the field-associated free energy of a film on the basis of the London theory so long as the London penetration depth is replaced by the effective penetration depth. Consequently, one may understand the influence of the nonlocal theories on the inductance formulas derived in this paper simply by using the value of effective penetration depth corresponding to the film thickness and purity in question.

In the Appendix an approximate traveling-wave solution to the field problem just described is given. For parameters and dimensions typical of those currently encountered in practice the solution given is shown to hold over the frequency range from dc up to nearly 1 kMc. This lowest-order field configuration is a TM mode or E wave with non-negligible axial electric field. It may be characterized by an equivalent distributed network consisting of series resistance r, series inductance l, and shunt capacitance c. These per-unit-length transmission-line parameters are shown to be given by the expressions

$$r = (\sigma d_1 W)^{-1} \tag{5}$$

$$l = \mu_0[h + (d_1/3) + \beta^{-1} \coth \beta d_2]/W \tag{6}$$

and

$$c = \epsilon W/h. \tag{7}$$

The per-unit-length resistance and capacitance are exactly what one expects on the basis of static considerations. However, the inductance is clearly influenced by field penetration into each conductor.

The inductance expression is made up of three parts, one associated with the dielectric region, one associated with the normal conductor, and a final contribution from the superconductor. The contribution to the inductance from the dielectric region is just what one would expect from low-frequency considerations. The contribution from the normal conductor is what one would expect from low-frequency field-energy considerations but differs from what would be predicted on the basis of *flux linkages per unit current*. This will be explained in detail shortly. The contribution to inductance from the superconductor is very interesting. If the superconductor is thick compared with a penetration depth the strip-line inductance behaves as though the insulation were one penetration depth thicker than it actually is. On the other hand, if the superconductor is made thin compared with a penetration depth, the inductance rises rapidly. This is due to the kinetic energy of the superelectrons which is part of the free electromagnetic energy of the system, as will be shown shortly. This effect of rising inductance with decreasing film thickness is actually enhanced by nonlocal considerations since the effective penetration depth increases with decreasing thickness.

If the normal conductor were replaced by a second superconductor and the field problem solved anew and again reduced to an equivalent transmission line, the capacitance would be unchanged, the resistance would vanish, and the inductance would be modified such that the term $d_1/3$ of (6) would be replaced by the term $\beta_1^{-1} \coth \beta_1 d_1$. The velocity of propagation on such a line would be completely dispersionless, and there would be no attenuation for the frequencies, temperature, and dimensions considered here. The velocity of propagation, normalized with respect to the velocity of a plane unbounded wave in the dielectric, would be

$$v/v_0 = (lc)^{-1/2}/v_0$$
$$= [1 + (h\beta_1)^{-1} \coth \beta_1 d_1 + (h\beta_2)^{-1} \coth \beta_2 d_2]^{-1/2}. \tag{8}$$

The velocity can be made small by making d_1 and d_2 small compared with β_1^{-1} and β_2^{-1}, respectively. It can also be made small by making h small compared with a penetration depth in each conductor. Perhaps this lossless slow wave can be utilized eventually in a delay-line memory.

Inductance by Static-Field Energy and by Flux-per-Unit Current

In the Introduction it was pointed out that emphasis in this paper is to be placed on the inductance parameter. The correct expression for inductance has been established by means of a fairly detailed field analysis, presented in the Appendix, and backed up by Swihart's more extensive treatment. In this section it will be demonstrated that the same inductance can readily be obtained by evaluating the static magnetic-field energy if the kinetic energy of the superelectrons in the superconductor is included. It will also be shown that the flux-linkage-per-unit-current definition of inductance leads to a different and incorrect result. The reason is that the lowest-order mode in the wave-guiding structure under consideration is a TM or E wave rather than the more familiar TEM wave, for which the two inductance definitions are equivalent. By taking the axial electric field into account, the flux-linkage approach can be reconciled with the static-field-energy approach and hence made to agree with the inductance expression obtained from the field analysis.

The static- or low-frequency magnetic-field distribution in the structure of Fig. 2 is sketched in Fig. 3. The field expressions in each region are as follows.

Normal conductor:

$$H_y(x_1) = -Ix_1/Wd_1. \tag{9}$$

Dielectric:

$$H_y(x) = I/W. \tag{10}$$

Superconductor:

$$H_y(x_2) = I \sinh \beta x_2/W \sinh \beta d_2. \tag{11}$$

From the Maxwell equation curl $\boldsymbol{H}=\boldsymbol{J}$, one can obtain the expression for volume density of the supercurrent in the superconductor:

$$J_z(x_2) = \partial H_y(x_2)/\partial x_2 = I\beta \cosh \beta x_2/W \sinh \beta d_2. \tag{12}$$

In the normal conductor and dielectric regions the magnetic free-energy density is just $\mu_0|\boldsymbol{H}|^2/2$, while in the superconducting region the magnetic free-energy density is $\mu_0|\boldsymbol{H}|^2/2+\mu_0|\boldsymbol{J}|^2/2\beta^2$,[10] since the kinetic energy of the superelectrons must be included. Integrating these energy-density expressions throughout the thickness and width of the structure and over a unit length gives the total low-frequency magnetic free energy per unit length K:

$$K = \mu_0 I^2[h + (d_1/3) + \beta^{-1} \coth \beta d_2]/2W. \tag{13}$$

By requiring that the inductance per unit length l account for this free energy, l may be evaluated.

Since

$$K = lI^2/2 \tag{14}$$

$$l = \mu_0[h + (d_1/3) + \beta^{-1} \coth \beta d_2]/W. \tag{15}$$

This expression agrees with that given in (6) taken from the field analysis in the Appendix.

The magnetic flux linkage per unit length at low frequencies λ is simply

$$\lambda/\mu_0 = \int_0^{d_2} H_y(x_2)dx_2 + \int_{-h/2}^{h/2} H_y(x)dx + \int_{-d_1}^{0} H_y(x_1)dx_1, \tag{16}$$

where the various magnetic-field variations are given in (9)–(11). Evaluating the integral and assuming that inductance per unit length is simply flux linkage per unit length per unit current yields the "incorrect" result

$$l = \mu_0[h + (d_1/2) + \beta^{-1}(\coth \beta d_2 - \operatorname{csch} \beta d_2)]/W. \tag{17}$$

Only the term arising from the dielectric region agrees with the correct result obtained by the energy approach.

[10] London, *op. cit.*, p. 66.



Fig. 3—Low-frequency magnetic-field distribution in a thin-film strip line.

The inconsistency can be reconciled by recognizing that there is a non-negligible axial electric field in both conducting regions. The flux-linkage-per-unit-current definition of inductance cannot be applied without taking this longitudinal E field into account. To demonstrate this, consider the process of converting the Maxwell equation curl $\boldsymbol{E}=-j\omega\mu_0\boldsymbol{H}$, into the transmission-line voltage equation $dV(z)/dz=-ZI(z)$. In integral form the Maxwell equation is

$$\oint_C \boldsymbol{E}\cdot\boldsymbol{dl} = -j\omega\mu_0 \int_A \boldsymbol{H}\cdot\boldsymbol{da}. \tag{18}$$

The contour C to be used is shown in Fig. 2 as the dotted path *abcdefgha*. As pointed out in defining voltage in the Appendix, the contributions to the line integral of electric field along the portions of the path C associated with transverse electric field in the conductors are negligible for a wide range of frequencies and dimensions. Hence, neglect contributions from *bc*, *de*, *fg*, and *ha*. There remains

$$\int_a^b E_x dx - \int_d^c E_z(X_1)dz - \int_f^e E_x dx + \int_g^h E_z(X_2)dz = -j\omega\mu_0 \int_A H_y dxdz. \tag{19}$$

The right-hand side of (19) is the negative time derivative of the magnetic flux linking the path. If the portion of path C from e to f is assumed to be at z and the portion from a to b is assumed to be at $z+dz$ so that the loop is only dz wide, then the first term on the left side of (19) is $V(z+dz)$, while the third term is $-V(z)$. Furthermore, since the path C is only dz wide, the longitudinal variations of E_z in each conductor along the path may be neglected. Similarly, the longitudinal variations of H_y may also be neglected. Eq. (19) then becomes

$$dV(z)/dz = -j\omega\mu_0 \int_{X_2}^{X_1} H_y dx + E_z(X_1) - E_z(X_2). \tag{20}$$

Comparing (20) with the transmission-line voltage equation shows that the series impedance per unit length is

$$Z = \left[j\omega\mu_0 \int_{X_2}^{X_1} H_y dx + E_z(X_2) - E_z(X_1) \right] \mathrm{I}^{-1}. \quad (21)$$

It is now clear that the inductance per unit length cannot be evaluated as the flux linkage per unit current if the axial electric field in either conductor has a non-negligible imaginary part. Eq. (21) can be evaluated in general for arbitrary values of X_2 and X_1 and the resulting impedance can be shown to agree with that derived in the Appendix (76).

Inductance in In-Line Superconducting Structures

Thus far it has been shown that the inductance in a thin-film strip-line structure may be evaluated correctly solely by consideration of the static magnetic-field energy, including the kinetic energy of the superelectrons. A sufficiently detailed field analysis has shown this approach to be valid over a wide range of frequencies and dimensions. It is desirable now to extend this approach to a structure of current practical interest. The geometry chosen involves a number of long, parallel, superimposed conductors of equal width above a ground plane, as shown in Fig. 4. The self and mutual inductances in this structure will be calculated in general terms with any conductor or combination of conductors in either the superconducting or normal state.

The assumptions to be made are as follows.

1) All conductors are parallel, of equal width, perfectly registered, and infinitely long.

2) Width W is much greater than the total thickness T, so that fringing is negligible.

3) Width W is narrow compared with a quarter wavelength at the highest frequencies of interest, so that the structure is effectively lumped in the transverse plane and coupled transmission-line notions apply.

4) All excitation currents return in the ground plane.

5) All regions are linear, so that superposition applies.

6) The frequency is low enough so that all the assumptions of the field analysis in the Appendix apply.

In summary they are:

a) Displacement current is negligible in normal conductors.

b) Displacement currents and normal conduction currents in superconductors are negligible compared with the supercurrents, so that the *two-fluid* model need not be applied.

c) Only displacement currents exist in dielectric regions.

d) Inequalities (60)–(63) of the Appendix are effectively satisfied, and inequality (75) holds in each normal conductor.

Self and mutual inductances must be defined such that they correctly account for the magnetic free energy for any excitation. If the structure shown in Fig. 4 has



Fig. 4—Cross-sectional view of an in-line superconducting structure of n long, parallel, superimposed conductors. (Distorted scale; actually $W \gg T$.)

3 conductors and a ground plane, it is, in effect, three coupled loops. Under the assumptions made, it may be characterized magnetically by the coupled circuit equations,

$$\left.\begin{aligned} \lambda_1 &= l_{11}i_1 + l_{12}i_2 + l_{13}i_3 \quad \text{(a)} \\ \lambda_2 &= l_{21}i_1 + l_{22}i_2 + l_{23}i_3 \quad \text{(b)} \\ \lambda_3 &= l_{31}i_1 + l_{32}i_2 + l_{33}i_3 \quad \text{(c)} \end{aligned}\right\} \quad (22)$$

The diagonal terms are self inductances per unit length and the off-diagonal terms are mutual inductances per unit length. The reciprocity theorem applies, so that the inductance matrix is symmetrical; *i.e.*, $l_{12} = l_{21}$ etc.

The energy required to build up currents i_1, i_2, and i_3 from zero is

$$K = \int_0^{\lambda_1} i_1 d\lambda_1 + \int_0^{\lambda_2} i_2 d\lambda_2 + \int_0^{\lambda_3} i_3 d\lambda_3. \quad (23)$$

Eq. (23) is evaluated by differentiating (22), multiplying each by the appropriate current and carrying out the integrations. Note that the off-diagonal terms integrate in pairs rather than individually, so the result is

$$\begin{aligned} K = {} & (l_{11}i_1^2 + l_{22}i_2^2 + l_{33}i_3^2)/2 \text{ self-inductance} \\ & \text{energy terms,} \\ & + (l_{12}i_1i_2 + l_{13}i_1i_3 + l_{23}i_2i_3) \text{ mutual-inductance} \\ & \text{energy terms.} \end{aligned} \quad (24)$$

This magnetic free energy K expressed in network terms can be equated to the magnetic-field and superelectron free-energy densities integrated throughout a unit length of the structure, irrespective of the excitation.

Ampere's circuital law establishes the uniform fields in each dielectric region in terms of the arbitrary excitation currents. These are also the known surface fields for evaluation of the free energy in the superconductors:

$$\left.\begin{aligned} H_1 &= (i_1 + i_2 + i_3)/W \quad \text{(a)} \\ H_2 &= (i_2 + i_3)/W \quad \text{(b)} \\ H_3 &= i_3/W \quad \text{(c)} \end{aligned}\right\} \quad (25)$$

Evaluation of the magnetic free energy per unit length in each dielectric region can now be carried out. The combined result for all dielectric regions is

$$K_h = \int_V k_h dV = \int_V [\mu_0 |\, \boldsymbol{H}\,|^2/2] dV$$
$$= \mu_0[h_1 i_1^2 + (h_1 + h_2) i_2^2 + (h_1 + h_2 + h_3) i_3^2]/2W$$
$$+ \mu_0[h_1 i_1 i_2 + h_1 i_1 i_3 + (h_1 + h_2) i_2 i_3]/W. \quad (26)$$

Consider next the general problem of an arbitrary superconducting region in the structure under discussion. The situation is shown in Fig. 5. The surface field on one side of the conductor is H^s, while on the other side it is αH^s, where α is a real constant of proportionality which may be either plus or minus. The solution of London's equations at low frequencies gives the field- and current-density distributions in the general superconductor under discussion:

$$H(x) = [(\alpha + 1) H^s/2 \cosh(\beta d/2)] \cosh \beta x$$
$$+ [(\alpha - 1) H^s/2 \sinh(\beta d/2)] \sinh \beta x, \quad (27)$$
$$J(x)/\beta = [(\alpha + 1) H^s/2 \cosh(\beta d/2)] \sinh \beta x$$
$$+ [(\alpha - 1) H^s/2 \sinh(\beta d/2)] \cosh \beta x. \quad (28)$$

Using these distributions, one can evaluate the magnetic free energy per unit length, including the kinetic energy of the superelectrons:

$$K_s = \int_V k_s dV = \mu_0 \int_V \{[\,|\,\boldsymbol{H}\,|^2 + \beta^{-2} |\,\boldsymbol{J}\,|^2]/2\} dV$$
$$= [\mu_0 W (H^s)^2/8\beta][(\alpha + 1)^2/\cosh^2(\beta d/2)$$
$$+ (\alpha - 1)^2 \sinh^2/(\beta d/2)] \sinh \beta d. \quad (29)$$

For the various superconducting regions it is clear from Fig. 4 and (25) that the pertinent values of H^s and α are given in Table I.



Fig. 5—Sketch of the magnetic-field distribution in an arbitrary conductor of the structure of Fig. 4.

TABLE I

Superconducting Region	H^s	α
0	$(i_1+i_2+i_3)/W$	0
1	$(i_2+i_3)/W$	$1+i_1/(i_2+i_3)$
2	i_3/W	$1+i_2/i_3$
3	i_3/W	0

All of the magnetic free-energy expressions may now be combined.

$$K = K_h + K_{s0} + K_{s1} + K_{s2} + K_{s3} \quad (36)$$

K: total free energy per unit length; K_h: from (26); K_{s0}: from (30); K_{s1}: from (31); K_{s2}: from (32); K_{s3}: from (33).

The total free energy in terms of dimensions and physical constants of materials from (36) may next be equated to the total free energy in terms of inductances from (24). Each self- and mutual-inductance term can readily be identified since the two energy expressions must be equal for any arbitrary combination of independent currents. Thus, with all conductors superconducting, the inductance matrix of the structure of Fig. 4 is

$$[L_s] = \frac{\mu_0}{W} \begin{bmatrix} (h_1 + b_0 + b_1) & (h_1 + b_0 + c_1) & (h_1 + b_0 + c_1) \\ (h_1 + b_0 + c_1) & (h_1 + h_2 + b_0 + b_2 + 2c_1) & (h_1 + h_2 + b_0 + 2c_1 + c_2) \\ (h_1 + b_0 + c_1) & (h_1 + h_2 + b_0 + 2c_1 + c_2) & (h_1 + h_2 + h_3 + b_0 + b_3 + 2c_1 + 2c_2) \end{bmatrix}. \quad (37)$$

Evaluating (29) for each region,

$$K_{s0} = (\mu_0/2W)(i_1 + i_2 + i_3)^2 b_0, \quad (30)$$
$$K_{s1} = (\mu_0/2W)[i_1^2 b_1 + 2(i_2 + i_3)(i_1 + i_2 + i_3) c_1], \quad (31)$$
$$K_{s2} = (\mu_0/2W)[i_2^2 b_2 + 2 i_3 (i_2 + i_3) c_2] \quad (32)$$
$$K_{s3} = (\mu_0/2W) i_3^2 b_3, \quad (33)$$

where, for convenience,

$$b_n (n = 1, 2, 3 \cdots) = \beta_n^{-1} \coth \beta_n d_n \quad (34)$$

and

$$c_n (n = 1, 2, 3 \cdots) = \beta_n^{-1} \tanh(\beta_n d_n/2). \quad (35)$$

Note that the mutual inductance between any two conductors is close to, but not equal to, the smaller self inductance of the pair.

Careful study of matrix (37) reveals the manner of extending this result to an arbitrary number of conductors without further analysis. The self inductance of the Nth conductor, counting upward away from the ground plane, is

$$l_{NN} = \mu_0 \left\{ \sum_{n=1}^{N} h_n + b_0 + b_N + 2 \sum_{n=1}^{N-1} c_n \right\} \Big/ W. \quad (38)$$

The mutual inductance between the Mth conductor and the Nth conductor when M is less than N is

$$l_{MN} = \mu_0 \left\{ \sum_{n=1}^{M} h_n + b_0 + c_M + 2 \sum_{n=1}^{M-1} c_n \right\} \Big/ W, \quad \text{for } M < N. \tag{39}$$

It is interesting to note that this result is independent of N. This is a consequence of the fact that current in the Mth conductor produces no appreciable field in the space between conductors M and N, and thus there is no interaction energy associated with this space when both conductors are excited by source currents.

It is now possible to attach some limited physical significance to the terms b_n and c_n. Dimensionally, each is a distance. The quantity b_n is a penetration distance associated with self current in conductor n. Hence it appears only in the self-inductance term of conductor n. The term b_0 is an exception since every source current always returns through the ground plane. The quantity c_n, on the other hand, is a penetration distance associated with induced current in conductor n. If, for example, conductor two is excited, as it would be in evaluating its self-inductance, the term c_1 appears twice since a field is applied to each face of conductor one and penetrates a distance into each face determined by the induced screening currents. On the other hand, if the mutual inductance between conductors one and two is to be evaluated, think of conductors one and two as each driven by a source current and then ponder over what space to evaluate the energy associated with both loop one and loop two. Evidently it is legitimate to regard the space of loop one, extending a distance c_1 into conductor one from the loop-one side, as the appropriate region over which to evaluate the mutual energy. This same rule, although not rigorous or at all obvious, gives the correct answer in the case of the other mutual-inductance terms.

If one of the conductors, for example conductor one, is in the normal state, its magnetic free energy is different from when it is in the superconducting state. Every surface field is still given correctly in terms of the independent currents by (25). Consequently, the free-energy expressions all remain valid, except for conductor one. In the normal state

$$K_{n1} = \int_V k_{n1} dV = (W\mu_0/2) \int_{x=0}^{x=d_1} |H|^2 dx, \tag{40}$$

where

$$H = (i_2 + i_3 + i_1 x/d_1)/W. \tag{41}$$

Evaluating the integral, one obtains

$$K_{n1} = (\mu_0/2W) d_1 \{ i_1^2/3 + (i_2 + i_3)(i_1 + i_2 + i_3) \}. \tag{42}$$

Comparison of this expression with the free energy in the superconducting state, K_{s1} from (31), is very interesting. The term involving i_1^2 does not correctly pass over from the super to normal states by letting the penetration depth go to infinity ($\beta_1 \to 0$). All the remaining energy terms, however, do correctly follow in the limit as β_1 vanishes. Hence, all the results except l_{11} follow directly from the superconducting case already calculated, and l_{11} is obtained merely by replacing the term b_1 by the term $d_1/3$.

With conductor one in the normal state the inductance matrix (37) becomes

$$[L_{n1}] = \frac{\mu_0}{W} \begin{bmatrix} (h_1 + b_0 + d_1/3) & (h_1 + b_0 + d_1/2) & (h_1 + b_0 + d_1/2) \\ (h_1 + b_0 + d_1/2) & (h_1 + h_2 + b_0 + b_2 + d_1) & (h_1 + h_2 + b_0 + d_1 + c_2) \\ (h_1 + b_0 + d_1/2) & (h_1 + h_2 + b_0 + d_1 + c_2) & (h_1 + h_2 + h_3 + b_0 + b_3 + d_1 + 2c_2) \end{bmatrix}. \tag{43}$$

Again it is a simple matter to generalize this result to any number of conductors. Furthermore, the case of any number or combination of conductors in the normal state also follows directly. Modifying (37)–(39) to take normal conductors into account is a two-step process. For each normal conductor

1) replace b_n by $d_n/3$,

and

2) replace c_n by $d_n/2$.

Conclusions

Inductances in thin-film superconducting structures can be evaluated up to about 1 kMc simply by consideration of the static magnetic-field energy, including the kinetic energy of the super electrons. The flux-linkage-per-unit-current definition of inductance cannot be used because the lowest-order mode which can exist on the structures in question is a TM or E wave with a non-negligible axial electric field. All the self- and mutual inductances in coupled strip-line structures are strongly influenced by penetration effects. In the case of parallel, superimposed strips above a common ground plane, the mutual inductance between any pair of strips is close to, but not equal to, the smaller self-inductance of the pair.

Appendix

Reduction of Field Solution to Equivalent Transmission Line

An approximate traveling-wave field solution is first given for the strip-line structure of Fig. 2. At low frequencies this is shown to reduce to an equivalent transmission line. For typical dimensions and parameters, frequency limits are set on the validity of this procedure.

Strip-Line Field Solution

Eqs. (1)–(3) govern the behavior of the magnetic field in each region. Naturally, the full set of Maxwell equations applies in each region, subject to the assumptions already discussed concerning the relative magnitudes of displacement, normal-conduction, and super-currents.

The sinusoidal steady state is assumed and is characterized by angular frequency ω. The fields are assumed to be driven by a current of complex amplitude I which flows in the positive z direction in the superconductor and in the negative z direction in the normal conductor. A forward traveling-wave solution is sought. Hence, each field component or equivalent transmission-line quantity is assumed to have a longitudinal variation characterized by the factor $\exp(-jaz)$, where a is the complex propagation constant. Thus, one obtains

$$\partial G(z)/\partial z = -jaG(z), \tag{44}$$

where $G(z)$ is any complex field or transmission-line quantity.

Experience shows[11] that a solution of the type sought can be obtained if field components E_x, E_z, and H_y are assumed to exist in each region. The axial electric field is necessary in order to account for the flow of field energy into the normal conductor for conversion to Joule heat and also to account for the flow of magnetic-field energy into and out of both conductors because of penetration effects.

The boundary conditions are interesting. First it is assumed that there is no appreciable magnetic field outside the strip line. Hence,

$$H_y = 0 \quad \text{at} \quad x_1 = x_2 = 0. \tag{45}$$

Since displacement currents are negligible in each conductor, the change in magnetic-field intensity with position as one passes through either conductor is just equal to the conduction current per unit width. Hence,

$$H_y = I/W \quad \text{at} \quad x_1 = -d_1. \tag{46}$$

and

$$H_y = I/W \quad \text{at} \quad x_2 = d_2. \tag{47}$$

At the boundaries between the dielectric and the conductors, the tangential components of electric and magnetic-field intensity must be continuous. The normal electric field at these interfaces may be discontinuous since field lines may terminate in or originate from surface charges just inside the conductors. Because the tangential field components must be continuous across the strip-line interfaces there is one and only one longitudinal propagation factor a for the complete structure.

Subject to all these assumptions and boundary conditions, the approximate field solution in the structure of Fig. 2 is shown below.

[11] Ramo, *op. cit.*, p. 323.

Low-Frequency Strip-Line Field Solution

Normal Conductor:

$$H_y(x_1) = -I \sinh Fx_1/W \sinh Fd_1 \tag{48}$$

$$E_x(x_1) = -Ija \sinh Fx_1/W\sigma \sinh Fd_1 \tag{49}$$

$$E_z(x_1) = -I(j\omega\mu_0)^{1/2} \cosh Fx_1/W\sigma^{1/2} \sinh Fd_1. \tag{50}$$

Dielectric:

$$H_y(x) = I/W \tag{51}$$

$$E_x(x) = Ia/W\omega\epsilon \tag{52}$$

$$E_z(x) = Ij\omega\mu_0[(\beta^{-1} \coth \beta d_2 - F^{-1} \coth Fd_1) - 2x(\beta^{-1} \coth \beta d_2 + F^{-1} \coth Fd_1)/h]/2W. \tag{53}$$

Superconductor:

$$H_y(x_2) = I \sinh \beta x_2/W \sinh \beta d_2 \tag{54}$$

$$E_x(x_2) = -Ia\omega\mu_0 \sinh \beta x_2/W\beta^2 \sinh \beta d_2 \tag{55}$$

$$E_z(x_2) = Ij\omega\mu_0 \cosh \beta x_2/W\beta \sinh \beta d_2 \tag{56}$$

where

$$F = (j\omega\mu_0\sigma)^{1/2} \tag{57}$$

and

$$a = \omega(\mu_0\epsilon)^{1/2}[1 + (Fh)^{-1} \coth Fd_1 + (\beta h)^{-1} \coth \beta d_2]^{1/2}. \tag{58}$$

Remember that the notation used here assumes the sinusoidal steady state in time, and that the longitudinal dependence is characterized by the complex propagation factor, so that each instantaneous field quantity is obtained from (48)–(56) in the following manner:

$$H_y(x_1, z, t) = \text{Re}\{H_y(x_1) \exp j(\omega t - az)\}. \tag{59}$$

The field solution given here is readily seen to satisfy the prescribed boundary conditions. Note, however, that the axial electric field E_z does not vanish at $x_1 = x_2 = 0$. Consequently, the assumption that there is no field outside the strip-line structure is not completely valid. It is not too difficult, however, to take external fields into account in a more nearly exact solution, as Swihart has done. The results at low frequencies are essentially unaltered from the simpler version given in this paper.

If the field quantities of (48)–(56) are substituted into the Maxwell equations and into (1)–(3) identities are obtained subject to the following approximations.

Normal Conductor:

$$a^2/\omega\mu_0\sigma \ll 1. \tag{60}$$

Dielectric:

$$\omega^2\mu_0\epsilon h\beta^{-1} \coth \beta d_2/2 \ll 1 \tag{61}$$

and

$$\omega^2\mu_0\epsilon hF^{-1} \coth Fd_1/2 \ll 1. \tag{62}$$

Superconductor:

$$a^2\beta^{-2} \ll 1. \tag{63}$$

Assume the following typical dimensions and parameters:

$$d_1 = d_2 = 5000 \text{ Å}$$
$$\epsilon/\epsilon_0 = 4$$
$$\sigma = 4.26 \times 10^6 \text{ mhos/cm (for tin film at 4.2°K)}$$
$$\lambda = \beta^{-1} = 1500 \text{ Å}.$$

Using these values, and assuming that much less than unity means equal to or less than 0.01, one can show that inequalities (60)–(63) are satisfied for the range of frequencies from dc up to about 10^{13} cps.

Equivalent Transmission Line

A well-defined series conduction current was assumed to exist in each conductor in the preceding field solution. This current $I(z)$ was used to establish boundary conditions on magnetic field H_y in each region. Consequently, the axial variation of the conduction current must be characterized by the same propagation factor a as the field quantities.

$$I(z) = I \exp(-jaz). \tag{64}$$

In order to reduce the approximate field solution to an equivalent transmission-line representation, it is necessary to be able to define unambiguously a voltage $V(z)$. Toward this end let us examine the transverse electric field E_x in the structure. Voltage must be defined as the line integral of this transverse electric field across the strip-line structure. There is some uncertainty as to just what two points should be chosen as the end points of the integration. If one integrates only across the dielectric,

$$V = \int_{-h/2}^{h/2} E_x(x)dx = Iah/W\omega\epsilon. \tag{65}$$

The line integral of transverse electric field through each conductor can be separately evaluated and compared with (65). Using the parameter values already assumed, it is found that the contribution to voltage arising from transverse electric field in the normal conductor is completely negligible over a wider frequency range than that for which inequality (62) is satisfied. Similarly, the contribution to voltage arising from transverse electric field in the superconductor is negligible compared with the voltage of (65) over a wider frequency range than that for which inequality (61) is satisfied. If, however, the insulation thickness should become very small compared with a penetration depth in the superconductor or compared with the skin depth in the normal conductor, then the frequency range over which a voltage can be defined unambiguously is reduced.

Having suitably defined a voltage and current, one can determine the per-unit-length series impedance Z and shunt admittance Y of the equivalent transmission line. This is done by substituting the voltage and current expressions into the transmission-line equations.

$$dV(z)/dz = -ZI(z)$$

or

$$jaV(z) = ZI(z) \tag{66}$$

and

$$dI(z)/dz = -YV(z)$$

or

$$jaI(z) = YV(z). \tag{67}$$

Substituting (64) and (65) into (66) and (67),

$$Z = ja^2h/\omega\epsilon W \tag{68}$$

and

$$Y = j\omega\epsilon W/h. \tag{69}$$

The admittance is clearly that due to the capacitance between conductors and is independent of any penetration effects. The series impedance can be put in a more meaningful form by reference to (58).

$$Z = j\omega\mu_0(h + F^{-1}\coth Fd_1 + \beta^{-1}\coth \beta d_2)/W. \tag{70}$$

The impedance has both real and reactive parts since the second term in brackets, involving F, is complex. This term may be separated into its real and imaginary parts. With the aid of (57),

$$F^{-1}\coth Fd_1 = \delta\{\sinh\gamma - \sin\gamma) - j(\sinh\gamma + \sin\gamma)\}/2(\cosh\gamma - \cos\gamma), \tag{71}$$

where

$$\gamma = 2l_1/\delta \tag{72}$$

and

$$\delta = (2/\omega\mu_0\sigma)^{1/2}, \tag{73}$$

the normal skin depth. For sufficiently low frequencies δ becomes large, γ becomes small, and the power series expansions of the various functions in (71) converge rapidly. It can be shown directly that

$$F^{-1}\coth Fd_1 = (d_1/3) - j(\omega\mu_0\sigma d_1)^{-1} \tag{74}$$

if

$$d_1^4(\omega\mu_0\sigma)^2/30 \ll 1. \tag{75}$$

Using the values previously assumed, this inequality will be satisfied from dc up to a frequency of nearly 1 kMc. Under these conditions, the per-unit-length series impedance may be written as

$$Z = (\sigma d_1 W)^{-1} + j\omega\mu_0[h + (d_1/3) + \beta^{-1}\coth \beta d_2]/W. \tag{76}$$

Acknowledgment

The author is indebted to N. Rochester and Dr. J. C. Swihart for their stimulation and encouragement.

Reduction of the Frequency-Temperature Shift of Piezoelectric Resonators by Mechanical Stress*

E. A. GERBER†, FELLOW, IRE, AND M. H. MILES†

Summary—**A method is described which allows a reduction of the frequency-temperature shift of piezoelectric crystals by the use of bimetal elements applying temperature-dependent pressure to selected spots on the circumference of the resonator disk. A decrease in the frequency change from ±15 to ±1 parts per million can be achieved for the AT cut of quartz over a wide temperature range by using one pair of bimetallic elements for the upper and one pair for the lower temperature range. This is accomplished without any increase in the resonance resistance of the crystal. Equations and curves are developed which enable one to obtain the optimum parameters of the bimetallic elements for a given frequency-temperature curve of the crystal. An experimental device, and results achieved with it under various conditions are described in detail. It is expected that in many cases this technique will make power- and space-consuming crystal ovens unnecessary.**

Introduction

IT HAS been known for some time that the frequency of piezoelectric resonators is affected by externally applied stress. Bottom[1] reports that the frequency change of a quartz resonator plate is proportional to a compressional stress applied in one specific direction in the plane of the plate. The frequency change is positive for AT-cut and negative for BT-cut plates. Bottom further observed that a quartz plate compressed along its X-axis exhibits a much larger frequency change than if compressed along its Z'-axis. Michels and Pérez[2] have studied the effects of hydrostatic pressure upon the frequency of AT- and BT-cut plates. Their results are similar in several aspects to those obtained by the application of linear tensile stresses. More complete measurements of the frequency change of quartz resonators vibrating in thickness shear as a function of the orientation of the mechanical stress have been published by Gerber[3] and Ballato and Bechmann.[4] Fig. 1 shows the effect of compressional force on an AT-cut resonator. The relative frequency change per Newton is plotted as a function of the azimuth. When the compressional force, measured from the X-axis, is applied at about 60°, the frequency change is zero. The frequency change reaches the extreme values of $+17 \cdot 10^{-6}$ per Newton for a force parallel to the X-axis and $-8 \cdot 10^{-6}$ per Newton for a force parallel to the Z'-axis. As has been shown,[5,6] the stress sensitivity of vibrating quartz crystals can be used to reduce their frequency-temperature shift considerably if the applied force is made temperature-dependent and applied to selected spots on the circumference of the crystal plate. The necessary force can be supplied, for instance, by bimetal strips, as shown in Fig. 2 and discussed previously.[5] This technique will enable one to dispense, in many cases, with power- and space-consuming crystal ovens, an important factor in the light of requirements for higher degrees of frequency stability coupled with the trend towards the utmost in miniaturization. It is the purpose of this paper to expand the preliminary results given previously[5,6] and to discuss the possibilities



Fig. 1—Relative frequency change per unit of applied force of an AT-cut plate as a function of the azimuth ψ.



Fig. 2—Quartz crystal unit with two compensating bimetal strips.

* Received by the IRE, July 18, 1961; revised manuscript received, August 30, 1961.

† U. S. Army Signal Research and Development Lab., Fort Monmouth, N. J.

[1] V. E. Bottom, "Mounting techniques for improved heat dissipation in quartz crystal units," Physics Dept., Colorado Agricu tural and Mechanical College, Fort Collins, Colorado, Final Rept. on Contract No. DA36-039 SC-5485; February 28, 1951, to February 29, 1952.

[2] A. Michels and J. P. Pérez, "Déplacement de la fréquence piézoelectrique du quartz sous haute pression," *Physica*, vol. 17, pp. 563–564; May, 1951.

[3] E. A. Gerber, "Precision frequency control for guided missiles," *Proc. 1st IRE Natl. Convention on Military Electronics*, pp. 91–98; June 17–19, 1957.

[4] A. D. Ballato and R. Bechmann, "Effect of initial stress in vibrating quartz plates," PROC. IRE, vol. 48, pp. 261–262; February, 1960.

[5] E. A. Gerber, "Reduction of frequency-temperature shift of piezoelectric crystals by application of temperature-dependent pressure," PROC. IRE, vol. 48, pp. 244–245; February, 1960.

[6] E. A. Gerber and J. M. Havel, "Precision frequency control for military applications," IRE TRANS. ON MILITARY ELECTRONICS, vol. MIL-4, pp. 424–437; October, 1960.

and limits of this compensation method analytically and experimentally.

Analysis

The well-known frequency-temperature characteristics of an AT-cut quartz resonator are shown in Fig. 3.[7] The minimum frequency change which can be obtained for a temperature range from $-40°$ to $+100°C$ is approximately ± 15 parts per million. This total frequency change can easily be compensated for by using bimetals, applying a force of approximately 1.9 Newtons at high temperatures and 0.9 Newtons at low temperatures, respectively. The difficulty is, however, that the frequency change effected by the bimetals is a linear function of the applied force, and therefore of the temperature, whereas the dependence of frequency upon temperature for an AT cut is represented by a polynomial of the third order. Therefore, in order to obtain a better compensation, it is desirable to use two, or even more, bimetals on the warm and on the cold end of the temperature range, in order to approach the polynomial by a group of straight lines. Obviously, it is conceivable that other orientations $(YXl)\theta$ of the quartz plate could be selected which would exhibit a linear relationship between frequency and temperature and which would use only one bimetal to compensate for the entire temperature range. However, the disadvantages of this arrangement would be that: 1) extremely large forces in the order of 20 Newtons would be required, and 2) accuracy of the crystal would be influenced by the stability of the bimetal. On the other hand, in the AT cut the necessary forces are much lower and compensation is only effected at the two ends of the temperature range, whereas the frequency at the center of the curve, close to the inflection point, is not influenced by the bimetals at all. Thus, the accuracy of the crystal is not changed by using bimetal compensation since only a corrective action takes place near the upper and lower temperature extremes.



Fig. 3—Frequency-temperature characteristics of a fifth overtone, 29-Mc AT-cut resonator.

[7] D. L. Hammond, A. R. Chi, and J. M. Stanley, "Effects of Impurities on the Resonator and Lattice Properties of Quartz," Signal Corps Engrg. Labs., Fort Monmouth, N. J., Engrg. Rept. E-1162; November 3, 1955.

The relationship between frequency and temperature of an AT-cut crystal can be described by a polynomial containing only linear and third-order terms, if the inflection point is chosen as the origin:[8]

$$\frac{\Delta f}{f} = a_0 T + c_0 T^3. \tag{1}$$

The constant a_0 is a function of the orientation angle θ, whereas c_0 changes very little with the angle. Its value is $+109.5\times10^{-12}(°C)^{-3}$.[9] It is therefore possible to determine the shape of AT frequency-temperature curves for different values of the constant a_0 (or for different orientation angles) and calculate the equations for the bimetals represented by straight lines which match the polynomial closest for a given maximum permissible frequency deviation $\pm(\Delta f/f)_m$. Polynomial (1) is used in the normalized form

$$y = kx + x^3, \tag{2a}$$

where

$$y = \frac{\Delta f}{f}\cdot\frac{1}{|a_0|}\sqrt{\frac{c_0}{|a_0|}},$$

$$x = T\cdot\sqrt{\frac{c_0}{|a_0|}}, \text{ and } k = +1, 0, \text{ and } -1. \tag{2b}$$

Fig. 4 shows a plot of (2a) for $x\geq 0$ and $k=-1$. This case is considered first and solved for the application of two bimetals. Since the inflection point of the curve is in the origin, the solution is also valid for $x<0$ (lower temperatures). It also can be applied for the case of one bimetal only. Since we have, with increasing x, first a negative frequency deviation in the amount of $y=2/3\sqrt{3}$, the first bimetal will be set to start operating at the point $x=2/\sqrt{3}$, which gives the same amount of frequency deviation but with a positive sign. The equations for the two bimetals will then be chosen in such a way that the frequency deviation from zero does not exceed the value of $\pm(2/3\sqrt{3})$ anywhere in the prescribed operating range. If the equations for the two straight lines (see Fig. 4) are

$$y_1 = d\left(x - \frac{2}{\sqrt{3}}\right) \tag{3}$$

and

$$y_2 = b(x - c), \tag{4}$$

then the values for the constants b, c, d, and a (the latter being the maximum value for the abscissa), can be obtained by equating

$$\frac{2}{3\sqrt{3}} = |\alpha|, = |\beta|, = |\gamma|, = |\delta|.$$

[8] R. Bechmann, "Frequency-temperature-angle characteristics of AT-type resonators made of natural and synthetic quartz," Proc. IRE, vol. 44, pp. 1600–1607; November, 1956.

[9] R. Bechmann, "Frequency-temperature-angle characteristics of AT- and BT-type quartz oscillators in an extended temperature range," Proc. IRE, vol. 48, p. 1494; August, 1960.



Fig. 4—Plot of the polynomial $y=-x+x^3$ and of the two straight lines which approximate it with an error $\leq(2/3\sqrt{3})$.

α and γ are obtained by setting the first derivatives of the functions $y-y_1$ and $y-y_2$ equal to zero. β is obtained by calculating the coordinates of the intersection of y_1 and y_2, and the difference between y and the ordinate of the intersection. δ is the difference between y and y_2 at $x=a$. The equations for these four quantities are

$$|\alpha| = \frac{2}{3\sqrt{3}}(1+d)^{3/2} - \frac{2}{\sqrt{3}}d, \tag{5}$$

$$|\beta| = -\frac{\frac{2}{\sqrt{3}}d - bc}{d-b} + \left(\frac{\frac{2}{\sqrt{3}}d - bc}{d-b}\right)^3 - bd\frac{\frac{2}{\sqrt{3}} - c}{d-b}, \tag{6}$$

$$|\gamma| = \frac{2}{3\sqrt{3}}(1+b)^{3/2} - bc, \tag{7}$$

$$|\delta| = a(a^2-1) - b(a-c), \tag{8}$$

$$|\alpha| = |\beta| = |\gamma| = |\delta| = \frac{2}{3\sqrt{3}}. \tag{9}$$

These equations are solved numerically for a, b, c and d with the help of a computer. The values of a_0 used for the computation are listed in the right-hand table of Fig. 5. The relationship between $-a_0$, $(\Delta f/f)_m$ and θ has been calculated according to Bechmann.[8] The constants b and d give information as to the necessary sensitivity of the bimetals. However, since bimetal 1 continues to operate after bimetal 2 has made contact, the sensitivity of bimetal 2 must actually be $b-d$. The abscissa value $(=\xi)$ of the intersection of the two straight lines, which corresponds to the temperature at which the second bimetal has to make contact, is obtained by

Curves No.	$a_0 \cdot 10^6$	θ
1	-.05696 to-18807	35°20.7' to 35°22.2'
2	0	35°20'
3	.05696	35°19.3'
4	.09042	35°18.9'
5	.14353	35°18.3'
6	18807	35°17.8'

FOR $a_0<0$ ONLY		
$(\frac{\Delta f}{f})_m 10^6$	$a_0 \cdot 10^6$	θ
± 0.5	-.05696	35°20.7'
± 1	-.09042	35°21.1'
± 2	-.14353	35°21.7'
± 3	-.18807	35°22.2'



Fig. 5—Sensitivity of bimetals as a function of the desired frequency tolerance. Parameter of the curves is the orientation angle θ of the crystal plate.

$$\xi = c\,\frac{b - d/c}{b - d}. \tag{10}$$

The calculated data enable us finally to draw curves which give the sensitivity of the two bimetals (Fig. 5), the maximum temperature range obtainable, and the contact temperatures of the bimetals (Fig. 6), as a function of a maximum permissible frequency deviation $\pm(\Delta f/f)_m$. The parameter is the constant $-a_0$ which, in turn, is a function of the angle of orientation θ. Note that for each value of $\pm(\Delta f/f)_m$, a different orientation θ is required, since $(\Delta f/f)_m$ is given by the minimum ordinate value of (1) which changes with the orientation angle θ. In examining the No. 1 curves of Fig. 6, it is noted that a frequency tolerance $(\Delta f/f)_m$ of ± 1 part in 10^6 can be maintained for a temperature range of ± 56°C by using one bimetal each at the higher and lower temperature, and of ± 75°C by using two bimetals each. Compared with the best uncompensated curve, this represents an improvement by the factor 15.

The data for the bimetals in the cases of $a_0=0$ and $a_0>0$ are calculated in a similar manner. They are likewise plotted in Figs. 5 and 6. In these two latter cases, however, different values of $(\Delta f/f)_m$ can be chosen for each different crystal orientation, since no negative ordinate values exist above $x=0$.

Finally, dimensional data for the bimetals can be obtained by combining the fundamental force-temperature relation[5]

$$\frac{F}{\Delta T} = A\,\frac{wt^2}{l} \tag{11}$$



Fig. 6—Maximum temperature range obtainable and contact temperatures of the bimetals as a function of the desired frequency tolerance. Parameter is the orientation angle θ of the crystal plate. Refer to Fig. 5 for the meaning of the numbers ascribed to curves.

with the force-frequency coefficient $(\Delta f/f)/F$ (Fig. 1)

$$\frac{\Delta f/f}{F} \cdot A \frac{wt^2}{l} = \frac{\Delta f/f}{\Delta T} \cdot \tag{12}$$

F is the force applied to the crystal plate by the bimetal; t, w, and l are the thickness, width, and length of the bimetallic element; the factor A contains Young's modulus, and the expansion coefficients of the bimetallic materials. $(\Delta f/f)/F$ and $(\Delta f/f)/\Delta T$ can be taken from the graphs in Figs. 1 and 5.

Experimental Results

Fig. 7 shows the crystal holder that was used in the experiments. It is made entirely of brass and has three main parts: the base on which the crystal is mounted, the vise-like frame on which the bimetal holders are mounted, and a cover (not shown) to seal the entire unit. The crystal is mounted in the channel of the base with silver bonding cement. This insures that the crystal will remain stationary under pressure of the bimetals. The bimetals are soldered into holders which are held tightly by the vise grip of the frame. A projecting arm from the bimetal holder allows the use of a screw to set the gap between the first bimetal and the crystal. The gap between the two bimetals is adjusted by lapping after the two bimetals have been soldered into the bimetal holders.

Some difficulty has arisen in the mounting operation of the crystal. The bonding cement is placed at the two points where the crystal touches the edges of the channel. This cement, when dried, sets up a stress between the two points and causes the temperature-frequency characteristic curve of the crystal to change slightly. However, after the initial change due to the bonding cement has taken place, no additional change occurs. At the present time, a new crystal base is under development which will prevent stresses from forming in the crystal due to the bonding cement.



Fig. 7—Experimental crystal holder.

For the experiments, 29-Mc third-overtone AT-cut crystals with an orientation angle θ of 35°20′ and a diameter of 0.45 inch were mounted, with the X-axis 77° off the center line of the holder. The bimetal used was "Highflex."[10] It was chosen among other samples because it combines relatively high sensitivity with a high elastic limit. The dimensions of all the bimetals were 0.33 inch, 0.056 inch, and 0.031 inch in length, width, and thickness, respectively.

Fig. 8 shows how the reduction in the frequency-temperature shift is varied by changing the temperature at which the bimetal makes contact. The measurement has only been made above the inflection point since the behavior below the inflection point is identical. The rate of compensation for each gap setting is constant, due to the fact that the azimuth angle ψ (angle between the X axis and the line of applied force, 82° in this case) is the same for each run. The temperature at which the bimetal makes contact with the crystal can be predetermined by adjusting the gap setting with a measuring microscope. As can be noted from the curve, a variation in gap setting of ± 5 microns will result in a deviation of approximately ± 1.5 parts per million from the desired compensation.

The variation in compensation resulting from a change in the azimuth angle, keeping the gap between the first bimetal and the crystal constant, is shown in Fig. 9. The width of the gap was 10 microns at 25°C. For this test, one pair of bimetals was used in the upper temperature range. The gap was set so that compensation began at the same temperature for each run. The setting of the azimuth angle is not as critical as the gap setting. A tolerance of $\pm 2°$ in the range of $\psi = 80°$ to $\psi = 90°$, and $\pm 1°$ between $\psi = 60°$ and $\psi = 80°$, will result in no appreciable error. By using a shadowgraph for setting the bimetals, tolerances can be maintained within $\pm \frac{1}{2}°$.

The results of compensation over the temperature range of -30°C to $+80$°C are illustrated in Fig. 10. For this test, two pairs of bimetals were used (see Fig. 7).

[10] H. A. Wilson Co., Div., of Engelhard Industries, Inc., Union, N. J.



Fig. 8—Frequency-temperature curves of a crystal with and without compensation by one bimetallic element. Parameter of the curves is the gap between tip of bimetal and edge of crystal at 25°C.



Fig. 9—Frequency-temperature curves of a crystal with and without compensation by a pair of bimetals. Parameter of the curves is the azimuth angle ψ.

The frequency deviation is reduced from ± 25 parts per million to ± 2.5 parts per million, *i.e.*, by a factor of 10. The theoretical results given in Fig. 6 would yield, for a maximum temperature range of 110°C (± 55°C with the inflection point at 25°C) and an a_0 value of 0.134×10^{-6} (curve No. 5 in Fig. 6), a frequency tolerance $(\Delta f/f)_m$ of ± 0.75 part per million. The measured data in Fig. 9 show that this optimum result was obtained for the upper temperature range while the lower temperature range fell short of the optimum. To have achieved optimum results in the lower temperature range, the second bimetal should have made contact at approximately -10°C rather than at 0°C. Also, the second bimetal should have had increased width to give greater sensitivity $(\Delta f/f)/$°C, whereas, for the sake of simplicity of the experiment, all bimetals were made with identical dimensions.

In order to test the reproducibility of the bimetal compensation, a rerun of the upper temperature range was made (see Fig. 11) and the reproducibility obtained was well within 3 parts in 10^7.



Fig. 10—Compensation by two pairs of bimetals over a temperature range of -30° to $+80$°C.



Fig. 11—Reproducibility of compensation with one pair of bimetals.

The resonance resistance of the crystal was measured as a function of temperature during all tests, and there was no change observed which was not within the accuracy of measurement of the crystal impedance meter, type TS-683/TSM.

Conclusions

It has been shown that the frequency-temperature shift of piezoelectric crystals can be drastically reduced by mechanically applied pressure. This pressure must be a function of the environmental temperature and is applied by bimetallic strips at selected spots on the circumference of the crystal disk. Ahead lies the task of reducing the experimental devices to production-line models by decreasing the size of the entire holder, by working out simple methods for setting the bimetals, and by studying the aging of the device and its behavior under rugged environmental conditions.

Acknowledgment

The authors wish to thank Joseph Weinstein and Dr. Richard K. Brown of the U. S. Army Signal Research and Development Laboratory, Fort Monmouth, N. J., for their assistance in the computations leading to Figs. 5 and 6.

Fundamental Limitations to Optical Doppler Measurements for Space Navigation*

R. H. NORTON† AND R. L. WILDEY‡

Summary—Theoretical consideration is given to the problem of optical Doppler velocity determination of the high accuracy (about 1 ft/sec) required to be useful for space navigation. From the physical theory of line-broadening and -shifting mechanisms in stellar atmospheres, it is concluded that an intrinsic variability of ±200 ft/sec may be expected in the measurement of an observer's Doppler velocity. Examination of the current state of the art in measuring equipment suggests that it does not set the limits on accuracy.

Introduction

It has been suggested that a useful portion of the information needed to make orbit corrections for a spacecraft undergoing the maneuvers of midcourse or approach guidance can be obtained from the determination of the spacecraft's velocity, by measuring the Doppler shift of absorption lines in the spectra of astronomical objects.[1] Noton has shown that the present state of the art for injection guidance is sufficient to permit the treatment of departures of the spacecraft's true orbit from the standard trajectory by linear perturbation theory.[2] He computed that an error in the range rate determination of 1 ft/sec during midcourse guidance would lead to a 4000-mile miss at Mars. Hence, velocity information, in order to be useful, must be accurate to about 1 ft/sec. For a representative wavelength of 4000 angstroms, the corresponding Doppler shift is 4×10^{-6} angstroms.

The physical mechanisms affecting the shapes and positions of spectral lines will be discussed, and limitations on the accuracy of observed Doppler velocities will be found to be caused by the inconstancy of these mechanisms. Of the available celestial sources to be considered, the only practical one is the sun, since the flux from the brightest star is only 10^{-10} that from the sun.

In addition, present spectroscopic techniques and instrumentation will be discussed, with emphasis upon the accuracy obtainable within the state of the art as imposed by the restrictions encountered in space-borne missions.

* Received by the IRE, April 10, 1961; revised manuscript received, July 21, 1961. This paper presents results of one phase of research carried out at the Jet Propulsion Lab. under Contract NASw-6, sponsored by the Natl. Aeronautics and Space Admin.

† Guidance and Control Research Section, Jet Propulsion Lab., Calif. Inst. Tech., Pasadena, Calif.

‡ Formerly with the Guidance and Control Research Section, Jet Propulsion Lab., Calif. Inst. Tech., Pasadena, Calif.

[1] R. G. Franklin and D. L. Birx, "A study of natural electromagnetic phenomena for space navigation," PROC. IRE, vol. 48, pp. 532–541; April, 1960.

[2] A. R. M. Noton, "Interplanetary Post-Injection Guidance," presented at Am. Rocket Soc. Meeting, San Diego, Calif., June 10, 1959, Jet Propulsion Lab., Pasadena, Calif., External Publication No. 653; June 4, 1959.

Physical Nature of Stellar Absorption Lines

Absorption lines in stellar spectra, for example as in the spectrum of the sun, are fundamentally affected by the physical conditions existing in the region of the stellar atmosphere where the absorption takes place. The general result of these effects is to broaden an otherwise monochromatic absorption line into a feature from which the physical conditions in the star's atmosphere may be induced. Line-broadening mechanisms may be divided into two classes: those that produce symmetric broadening, and those that produce asymmetric lines. It is the latter class that is of particular interest for the line profile for an asymmetric line will exhibit a wavelength difference between the line centroid and the point of greatest absorption. It will be wise to investigate whether these mechanisms are constant with time, for if not, a natural variability will be introduced in the observer's Doppler velocity which cannot be removed.

Symmetric Line-Broadening Mechanisms

Let us briefly discuss those line-broadening mechanisms which produce symmetric lines; they are:

1) Doppler broadening, characterized by a bell-shaped absorption coefficient $\exp[-\text{const}\ (\Delta\lambda)^2]$. Fig. 1(a) illustrates the line profile of Ca II, $\lambda_0=3934$ angstroms, for varying abundances in the solar atmosphere.
2) Radiation and collisional broadening, characterized by an absorption coefficient with a deep, narrow core and broad wings, in accordance with the dispersion formula $A/[B+(\Delta\lambda)^2]$. Fig. 1(b) illustrates the line profile for radiation damping only, for 1.8×10^{18} atom/gm of Ca II, $\lambda_0=3934$ angstroms. The line profile for collisional broadening will be similar to radiation damping. Fig. 2 shows the line profile (computed and observed) for the Ca II K line in the sun, with $T=5700°$ and $N=1.8\times10^{18}$ atom/gm.
3) Linear Stark effect, which produces components spaced symmetrically about the unperturbed line center.
4) Hyperfine structure, which, though not necessarily symmetric, is the same for a reference laboratory source as for a stellar source.
5) Linear Zeeman effect, which can be derived from a linear perturbation of the Hamiltonian in Schroedinger's equation, is symmetric for weak magnetic fields, both in line splitting and intensity distribution.



Fig. 1—Computed spectral line profiles for Ca II, 3934 angstroms.



Fig. 2—Computed and observed solar line profiles for Ca II, 3934 angstroms, including Doppler broadening, radiation damping, and collision damping.

6) Rotational broadening, from rapidly rotating stars, which produces a broad, shallow dish-shaped line profile, symmetric about the line center.

Asymmetric Line-Broadening Mechanisms

There is no direct information on the variation of average solar electric fields, but if we adopt, as an average field, the field of a single ion at a distance equal to the mean separation of particles at the mean level of absorption in the solar atmosphere and allow a relative variation in this field equal to the relative variation observed in the general solar magnetic field, we obtain a variation of approximately 1 to 9 v/cm. The interaction energy in a hydrogen-like atom is given by[3]

$$\Delta T = 6.42 \times 10^{-5} n(n_2 - n_1)F + 5.22 \times 10^{-16} n^4 \left\{17n^2 - 3(n_2 - n_1) - 9m_l^2 + 19\right\} F^2 + \cdots \quad (1)$$

where ΔT represents the shift in the energy level in wave numbers from the field-free state due to the presence of the electric field, and F is the field strength in v/cm. n is the usual total quantum number, and n_1, n_2, and n_l are electric quantum numbers subject to the condition

$$m_l = n - n_1 - n_2 - 1. \quad (1a)$$

The first observations of the second-order Stark effect in hydrogen were made by Takamine and Kokubu in the Stark pattern of $H\gamma$ when the spectrum was produced in a field of 147,000 v/cm, and they observed a shift to the red of the middle component of $H\gamma$ of 0.8 angstrom.[4] Therefore, we would expect for the assumed variation of the general solar electric field a maximum shift of the centroid wavelength of $H\gamma$ of 3×10^{-9} angstroms. It appears that the quadratic Stark effect, at least in this form, will not prevent measurements of optical Doppler velocities to 1 ft/sec.

However, the other form of quadratic Stark effect, known as pressure shift, has a much more appreciable effect. Due to the polarization of one atom by the close approach of another, an excited or outer state will be lowered more than a tightly-bound lower state. The frequency distribution during this time of close approach is added to the collision damping distribution, with the result that the observed spectral line is spread out more on the long wavelength side than on the short. The shift observed depends on the foreign gas used; it is also proportional to the relative density, defined as the ratio of the density under existing conditions to the density at STP.

For an order of magnitude example, consider as a typical line the mercury resonance line $\lambda = 2537$ angstroms. The empirical pressure-shift relationship with H_2 as the foreign gas (atomic hydrogen would be the most abundant foreign gas in all but the hottest stars) is:[5]

$$\Delta\lambda = 0.004\left[\frac{\rho}{\rho_0}\right] \quad (2)$$

where $\Delta\lambda$ is in angstroms and ρ_0 = density at STP.

[3] H. E. White, "Introduction to Atomic Spectra," McGraw-Hill Book Co., New York, N. Y., p. 402; 1934.

[4] T. Takamine and H. Kokubu, "Further studies on the Stark effect in Helium and Hydrogen," *Proc. Tokyo Math. Phys. Soc.*, vol. 9, pp. 394–404; August, 1918.

[5] White, *op. cit.*, p. 433.

If we assume that this relationship holds for atomic hydrogen as the foreign gas and extrapolate to densities in the solar atmosphere, taking as an example the density at about the level of formation of a moderately strong line from the model solar atmosphere of Chandrasekhar and Munch:[6]

$$\tau = \text{optical depth} = 0.3$$

$$P_g = \text{antilog } 4.67 = 4.68 \times 10^4 \text{ dyne/cm}^2$$

$$T = 5850^\circ \text{ K}$$

$$\frac{\rho}{\rho_0} = \frac{P}{P_0}\frac{T_0}{T} = 2.2 \times 10^{-3}$$

$$\Delta\lambda = 9 \times 10^{-6} \text{ angstroms.} \tag{2a}$$

We must also consider the variability of this effect. Flares, sunspots, plages, and other phenomena exhibiting markedly different densities from their surroundings will have profound effects over limited regions of the sun, but they are most unpredictable. In addition, for that small part of the absorption line formed in the chromosphere or outer atmosphere, the variation of the spicule pattern, those hot and dense spire-like cells of photospheric material thrusting up into the chromosphere, will have an appreciable effect. Also, the granule pattern in the photosphere, which is closer to the mean level of absorption, is not constant. It is, therefore, estimated that the above shift can vary by about its own magnitude, or produce a variability in the observed velocity of 0 to 4 ft/sec.

Let us now consider the second-order Zeeman effect. A linear perturbation of the Hamiltonian in Schroedinger's equation yields, for light circularly polarized perpendicular to the magnetic field,

$$\nu = \nu_0 \pm \frac{eH}{4\pi mc^2} + \frac{e^2H^2a_0n^4}{4mc^3} \tag{3}$$

The second-order term, giving the shift in the line centroid relative to the unperturbed line centroid, is

$$\Delta\nu = \frac{e^2H^2a_0n^4}{4mc^3} = 1.24 \times 10^{-32}H^2 \tag{4}$$

where $\Delta\nu$ is in wavenumbers, cm^{-1}, and all physical constants are in electrostatic cgs units. H is the magnetic-field strength in oersteds, and n is the refractive index in the solar atmosphere. It is obvious that no reasonable variation in the general solar magnetic field will produce a centroid shift sufficient to preclude optical Doppler velocity measurement accurate to 1 ft/sec.

Turning now to the variability of stars, we can, upon making simple assumptions, estimate the contribution of this effect to the variability of a measured Doppler velocity. At present, it is not possible to measure the brightness of a star to better than about 1 per cent, and it has been suggested that all stars are variable to some degree, the vast majority having a variability of less than 1 per cent. When a star varies in brightness, its radius and temperature change, giving rise to a true Doppler shift. The change in radius and temperature also have profound effects upon the pressure and density in its outer layers, in turn affecting all line broadening mechanisms.

Let us estimate the magnitude of the Doppler shift due to the change of radius of a star similar in mass, radius, and temperature to the sun. For such a small variation, less than 1 per cent, we may assume that the pulsation is an adiabatic process; further, we will assume the perfect gas law, and these assumptions are embodied in the two relations:

$$P = K\rho^\gamma$$

$$P = \frac{k}{\mu H}\rho T \tag{5}$$

where K = constant, γ = ratio of specific heats (5/3 for a monatomic perfect gas), μ = mean molecular weight in units of the mass of a hydrogen atom, and H = mass of hydrogen atom. We will also employ the relation between the luminosity, radius, and effective temperature of a star:

$$L = 4\pi R^2\sigma T^4. \tag{6}$$

For a variation in brightness $\delta L/L$, we have

$$\frac{\delta L}{L} = 2\frac{\delta R}{R} + 4\frac{\delta T}{T}. \tag{7}$$

It can easily be shown that the temperature and radius variations for a monatomic perfect gas undergoing an adiabatic pulsation are given by

$$\frac{\delta T}{T} = -2\frac{\delta R}{R}. \tag{8}$$

Hence,

$$\frac{\delta L}{L} = -6\frac{\delta R}{R}. \tag{9}$$

If, for a star like the sun, the brightness changes by 0.1 per cent, the radius variation will be

$$\delta R = 1.2 \times 10^7 \text{ cm} = 3.8 \times 10^5 \text{ ft.}$$

The theory of adiabatic pulsations predicts that the product of the period of pulsation and the square root of the mean density of the star be a constant, and this is substantiated by observation. If we adopt the value of this constant as determined observationally, we have:[7]

$$p\left[\frac{\bar{\rho}}{\bar{\rho}_\odot}\right]^{1/2} = 0.04 \tag{10}$$

[6] S. Chandrasekhar and G. Munch, "The continuous spectrum of the sun and the stars," *Astrophys. J.*, vol. 104, pp. 446–457; November, 1946.

[7] G. H. Herbig, Ed., "Non-Stable Stars," IAU Symp. No. 3, Cambridge University Press, Cambridge, Eng., p. 187; 1957.

where p = period in days, and $\bar{\rho}_{\odot}$ = mean density of the sun. Thus, for a star similar to the sun, the period of pulsation is approximately one hour. It then follows that the mean velocity of the pulsation wave will be 210 ft/sec. The observed shift in the spectral lines, however, is made up of contributions from all points on the disk, so that the observed velocity will be related to the pulsation wave velocity by

$$v_{obs} = 0.707 \text{ v}. \tag{11}$$

Here we also included the effects of limb darkening.

Thus we may expect, if the sun has a variation in brightness of 0.1 per cent, a mean shift in an observer's measured velocity of ± 150 ft/sec. Of course, the maximum velocity of the pulsation will be higher than the mean velocity.

The fourth source of line asymmetry to be considered is the "sunspot effect." The largest sunspot group ever observed covered 0.0054 of the visible solar surface.[8] The effect of such a spot group as the one above can be estimated from the following simple model. The best compromise, in the maximization of line shift, between the component of velocity in the observer's line of sight and the projected area of the spot group, places the spot group 0.707 of the way from the center of the disk to the limb. The radial velocity here, at the equator, is 4700 ft/sec. We assume the solar disk to be evenly illuminated; in fact, it shows pronounced limb darkening, but not enough to effect order of magnitude estimates. By the same token we assume the sunspots to be completely black; we can compute the effect of the sunspot group on the centroid wavelength due to Doppler effect alone. It will be the zero shift of the vast majority of the disk weighted by its intensity, which would be [1–2(0.0054)] plus the shift of 4700 ft/sec of the portion of the disk on the opposite side of the disk from the sunspot group, which the group fails to balance in oppositely shifted radiation, weighted by its intensity of 0.0054. The shift of the centroid of the line in the emergent solar flux is ± 25 ft/sec.

The effects of the foregoing mechanisms are summarized in Table 1, from which one may conclude that a natural variation in the measurement of a spacecraft's optical Doppler velocity of approximately ± 200 ft/sec may be expected.

TABLE I

Effect	Expected Maximum Optical Doppler Variation
Second-order Zeeman effect	10^{-24} ft/sec
Quadratic Stark effect	10^{-3} ft/sec
Pressure shift	4 ft/sec
Sunspot effect	25 ft/sec
Variability of radius	150* ft/sec

* Mean value given; maximum value incalculable, since explicit mathematical form of variation is not presently known.

[8] S. B. Nicholson and J. Hickox, "The great sunspot group of February, 1946," *Pubs Astron. Soc. Pacific*, vol. 58, pp. 86–88; April, 1946.

It must be emphasized here that the values given in the tabulation represent the maximum expected Doppler variations, under certain assumptions. In the case of the variability in the luminosity of the sun, it may be argued that the sun is not variable. However, we are here dealing with a change in brightness an order of magnitude less than the precision with which the observations can at present be made. This phenomenon has such a profound influence on the accuracy of optical Doppler velocity measurements that the question of its existence should provide sufficient heuristic grounds for a program whose objectives are to settle the issue.

Minimum values of the expected Doppler variations for each phenomenon can be set equal to zero, but the conditions necessary to obtain minimum values are considered extremely improbable.

The question now remaining is whether these variations can be averaged to zero by a suitable integration time. From the observations that the granule pattern presents a randomly changing appearance over a period of a few minutes, it seems likely that the variability due to pressure shift could be smoothed in a matter of minutes. For the Doppler variation arising from a true variability of the sun, the expected period is of the order of an hour, which appears to be too long an integration time for a mid-course guidance maneuver. Finally, since the period of rotation of the sun is 27 days, a sunspot group remains visible for 12–13 days, during which time the associated Doppler shift will swing its full value. It is expected that at most times the general sunspot pattern will create an average Doppler shift less than the maximum value which has been computed, but the possibility of such a large variation which cannot be removed still remains.

Instrumentation State of the Art

The state of the art in optical Doppler shift measurements today is exemplified by the Babcock magnetograph at the Mt. Wilson observatory. A 17-in image of the sun is formed by an off-axis Cassegrain reflecting system with a focal length of 150 ft located in a large steel tower.[9] The spectrograph, a vertical Littrow instrument employing a large plane grating, is located in a 75-foot pit under the tower, obtaining a dispersion in the green of 11 mm/angstrom with a 75-ft-focal-length lens. The grating, used in the fifth order, has a ruled area of $5\frac{1}{4} \times 8$ in, with 15,000 grooves/in and a resolving power in the green of 600,000. Using the Rayleigh criterion for resolution, two sharp lines 0.009 angstrom apart may just be resolved in the green, but by working into the diffraction pattern much better precision is obtained in centroid measurements.

In front of the entrance slit to the spectrograph is placed an electro-optic retardation plate in the form of a Z-cut crystal of ammonium dihydrogen phosphate.

[9] H. W. Babcock, "The solar magnetograph," *Astrophys. J.*, vol. 118, pp. 387–396; November, 1953.

Upon the application of an alternating voltage the retardation oscillates at the applied frequency, 120 cps, between plus and minus a quarter wave. A Nicol prism follows this plate, the two fixed elements thus constituting an oscillating circular analyzer.

Two slits are used at the exit of the spectrograph just before the detectors, each slit being placed at the point of steepest slope on each side of a spectral line. Thus, as the retardation of the quarter wave plate is oscillated, one measures the difference between the two exit slits first for the right-hand and then the left-hand circularly polarized components of solar line radiation. Magnetic fields of one gauss, causing a Zeeman splitting of 10^{-5} angstroms, can be measured accurately, and the rms shot noise of the system corresponds to about 0.1 gauss.

However, it is readily apparent that such an instrument as the Babcock magnetograph, capable of measuring an optical Doppler velocity with a precision of perhaps 3 to 5 ft/sec, is hardly practical from the standpoint of space-borne missions, because of its enormous weight and size. Limitations of instruments have been discussed by Franklin and Birx;[1] the best velocity resolution to be hoped for on the basis of detector noise considerations is 60 ft/sec. Possibilities exist for the use of interferometric techniques in order to obtain high dispersion and narrow instrumental profiles with nonbulky equipment; such an instrument might consist of a fixed-plate Fabry-Perot interferometer crossed with a small spectrograph, whose function is to separate the orders. It is interesting to note, however, that the original Fabry-Perot interferometer designed for the Babcock magnetograph was replaced by the present plane grating spectrograph because it was found impossible to maintain the temperature equilibrium necessary. Such an instrument would have to withstand the rigors of space-borne guidance maneuvers.

Conclusions

Calculations have been made on the assumption that the physical characteristics of stellar electromagnetic sources, as for example the sun, vary in such a manner that a variability of approximately ± 200 ft/sec may be expected in the observer's measured optical Doppler velocity. It is the authors' opinion that it is this that imposes a fundamental limitation on the accuracy with which Doppler measurements may be made optically, rather than the instrumentation.

Timing Potentials of Loran-C*

R. H. DOHERTY†, senior member, ire, G. HEFLEY†, and R. F. LINFIELD†, senior member, ire

Summary—**The Loran-C navigation system is capable of synchronizing and setting clocks to a relative accuracy of better than 1 μsec throughout the system's service area. A Loran-C receiver functions as a slaved oscillator and a trigger generator. The generated triggers bear a time relationship to the triggers at the master transmitter, which is known to within a microsecond. Clocks operating from these sources are compared with clocks operating from independent free-running oscillators.**

A fundamental relationship between time and position is considered. Loran-C as a navigation and timing system can provide both position and time simultaneously. The East Coast Loran-C chain will be time synchronized. The national frequency standards and uniform time source located at Boulder will be used to monitor these signals. Time synchronization and time distribution have been demonstrated on the Atlantic Missile Range. Inter-range time synchronization and precise time for large areas of the world could be provided in the future.

Appendix I describes briefly the results of ground wave measurements made on the Loran-C (Cytac) system. Appendix II describes the results of sky wave measurements made with the system.

* Received by the IRE, June 30, 1960; revised manuscript received, August 28, 1961.

† Radio Systems Division, National Bureau of Standards, Boulder, Colo.

I. Introduction

In the majority of timing applications a problem exists in setting two or more clocks to agree with one another. The greater the requirement for precise agreement between these clocks, the more difficult the problem becomes and, if the clocks are in widely separated locations, the difficulty is further increased. The reading of a single clock is meaningful only as it relates to its own frame of reference. For example, a clock may gain or lose with respect to the periodicity of the earth as it revolves about its own axis or about the sun.

Accurate astronomical time depends on long-term observations, but is ultimately limited by unpredictable variations in the earth's rotation. Furthermore, any astronomical time can be determined only to an accuracy of several milliseconds for a single set of observations. The initial settings of individual clocks may, therefore, differ by amounts of the order of milliseconds. These differences combined with the gains or losses of individual clocks are of such magnitude that

independently operating clocks or clocks synchronized by existing radio timing signals are unable to make measurements more precise than a millisecond at different locations.

When it is necessary to measure time at two or more locations to an accuracy of 1 μsec or better, such measurements must all be made within the same frame of reference, that is within a single clock system. The term "clock system" as used in this paper means a master clock at a convenient central location and other clocks at widely separated locations which are slaved to the master in such a way that each will track the master. Such a clock system must also provide for a means to synchronize or set each slave clock to agree accurately with the master clock. A number of Loran-C clocks will function as such a clock system with initial setting or synchronizing accuracies of 1 μsec or better using ground wave reception. Accuracies of 10 μsec or better should be obtainable using sky wave reception. Other methods may be used to set remote clocks, such as flying atomic standards from place to place, but they do not offer the convenience or reliability of Loran-C.[1]

The National Bureau of Standards at Boulder, Colo., maintains the nation's primary frequency standard. A fail safe clock operating from this standard would provide an extremely uniform time source that could be related in retrospect to any astronomical time measurements. This uniform time source is the proposed means for monitoring the aforementioned master clock.

II. Loran-C Operation and Its Timing Application

Loran-C[2] is a pulse navigation system operating on a basic frequency of 100 kc and normally consisting of a master station and two or more slave stations. Several Loran-C chains are operational or under construction. The presently operating U. S. East Coast Loran-C chain, and the previously operated Cytac (later named Loran-C) chain are shown in Fig. 1. The master station is located at Cape Fear, N. C., and the two slave stations at Martha's Vineyard, Mass., and Jupiter Inlet, Fla. The area over which a ground wave could be received for timing purposes would extend approximately 3000 km seaward or 2000 km landward from any one transmitter.

The Loran-C system utilizes synchronous detection techniques for measuring phase, and methods for determining a fixed sampling point early on the pulse, independent of pulse amplitude. By this means the ground wave is completely resolved from the sky waves. See Fig. 2. To a first approximation the ground wave transmission time is proportional to distance. Secondary corrections, however, usually have a magnitude in the range of 1 to 10 μsec. These corrections are determined



Fig. 1—Loran-C and Cytac locations.



Fig. 2—Ground wave resolution with Loran-C.

largely by the conductivity of the path and to a much smaller extent by the dielectric constant and the index of atmospheric refraction.[3,4] Both the conductivity and the dielectric constant of sea water are accurately known. Consequently, the transmission time over sea water can be computed accurately. Transmission times over paths involving land cannot be as accurately calculated since the conductivity of land is not well known. However, by correlating time difference measurements[5]

[1] F. H. Reder, M. R. Winkler and C. Vickart, "Results of a long range clock synchronization experiment," Proc. IRE, vol. 49, pp. 1028–1042; June, 1961.

[2] W. P. Frantz, W Dean and R. L. Frank, "A precision multipurpose radio navigation system," 1957 IRE National Convention Record, pt. 8, pp. 79–97.

[3] J. R. Johler, W. J. Kellar and L. C. Walters, "Phase of the Low Radiofrequency Ground Wave," Natl. Bureau of Standards, Boulder, Colo., NBS Circular No. 573; June, 1956.

[4] K. A. Norton, "The propagation of radio waves over the surface of the earth and in the upper atmosphere," Proc. IRE, vol. 25, pp. 1203–1236; September, 1937.

[5] All time difference measurements are determined by phase differences at 100 kc.

with generalized assumptions of ground conductivity, individual path conductivities may be deduced. For example, it has been demonstrated that the best single value of conductivity which can be assigned to the eastern half of the U. S. is 0.005 mho/meter. The average error between time differences computed using this conductivity and those measured in a test program (see Appendix I) was approximately 0.8 μsec. The algebraic average was nearly zero and the maximum error among all sites was 2.5 μsec. The largest errors were associated with sites located in mountainous terrain. Until better prediction methods are developed it must be assumed that systematic errors of the order of 1 μsec may exist for land and mixed paths unless the transmission time has been measured by the use of two transmitters, such as is done over the Loran-C baselines.

The East Coast Loran-C chain operates on a basic repetition rate of twenty pulse groups per second.[6] A pulse group consists of eight phase coded pulses with a uniform spacing of 1 msec. The Loran-C system, as presently operated, does not resolve time increments larger than the repetition period or 50 msec. Larger increments could be resolved without interference to the system, but at this time there appears to be no pressing requirement for such a change. The 50-msec interval between pulse groups can be resolved conveniently by the WWV seconds' pulses. In order to use WWV and Loran-C in such a manner the two transmitting systems must be synchronized, as they would be since WWV is transmitting uniform time.[7] See Fig. 3.

The Loran-C navigation system operating on a basic frequency of 100 kc performs the vitally important function of slaving all oscillators in the system to the oscillator at the master transmitter. By virtue of the technique of slaving a number of relatively cheap oscillators to a master oscillator, all clocks operated from such oscillators will, by definition, have an average drift rate of zero. The instantaneous deviation of any one clock from the average is primarily determined by the factors listed below:

1) Signal-to-noise ratio.
2) Relative and absolute quality of slave and master oscillators.
3) Integration time.
4) Tightness of coupling of the slave oscillator.

The positioning system requires a means for selecting a given cycle and a point on that cycle. It is obvious that this criteria for the positioning system satisfies the requirements for synchronizing a timing system. The instrumentation being utilized in the navigation system has a resolution of a few hundredths of

[6] Fractional Loran rates can also be used for the operation of a clock by gating the received pulses and using only those transmitted on the second to set the clock.

[7] A. H. Morgan, "Precise Time Synchronization of Widely Separated Clocks," Natl. Bureau of Standards, Boulder, Colo., NBS Tech. Note No. 22; July, 1959.



Fig. 3—Synchronization of Loran-C with WWV time signals.

1 μsec. The time variations in propagation due to changes in refractive index, conductivity, etc. are substantially less for all times than the previously mentioned prediction capability. Standard deviations of 0.2 to 0.3 μsec may be expected. (See Appendix I.)

In order to relate the Loran-C system to the primary frequency standard it has been proposed that an extremely high quality secondary frequency standard be installed at the Loran-C master station, and that the master transmissions be monitored at Boulder and that corrections be published periodically.

Measurements of Loran-C sky wave signals from the East Coast made in Boulder in 1955 and 1961 (Appendix II) showed that the propagation time can be determined to an absolute accuracy of about 1 μsec with an integration time of less than one minute. The standard deviation of such measurements (daytime) is less than 0.5 μsec. A better receiving antenna has made it possible to use the ground wave signal and achieve a substantially better measurement of the Loran-C master oscillator frequency.

III. Setting a Loran-C Clock

In order to set a slave clock to agree with the master clock it is first necessary to determine the amount by which the apparent time at the slave is slow with respect to the master.

After the signal has reached the antenna, additional time is required for it to pass through the receiver and produce a trigger suitable for starting or synchronizing the clock. This time depends solely on the receiver design. For timing purposes the Loran-C receiver should be designed in such a way that the transmission time through it remains constant over a wide range of environmental conditions.

The apparent time at the receiver is slow by the amount of time required for the signal to propagate from the master transmitter and through the Loran system to the receiver, plus the transmission time through the receiver plus any additional systematic delays such as the coding delay normally used in a Loran system. This is illustrated by the following example:

Given: 1) Receiver 2000 km from slave transmitter.
2) Sea water path.
3) Receiver delay 25.0 μsec.

Propagation time 2000 km sea water	6,675.3
Propagation time Master to Slave	2,711.8
Slave coding delay	12,000.0
Receiver delay	25.0
Total Delay	21,412.1

It is assumed that a pulse is transmitted from the master station precisely at each second. The corresponding pulse from the slave station would produce a time trigger at the receiver output 21,412.1 μsec later. Therefore, the clock at the receiver should read 0.021412 second when this time trigger is used as a read command. The calibration of this clock to read the correct fraction of a second is accomplished by adding counts to the divider chain, and the clock will maintain the same uniform time as the master clock. A one second or one minute output from the clock will occur within 1 μsec of the respective output from any other Loran-C clock in the system.

Fig. 4 is a front view of the developmental model of a Loran-C clock.[8] The panel immediately above the oscilloscope contains a 15-digit visual display covering from 1 μsec to 1000 days. When the clock is given a read command this display reads out the time and holds the reading until the next read command is received.

IV. Slaved Clocks vs Independent Clocks

The comparison of Loran-C clocks (slaved clocks) with independent clocks running from oscillators of different qualities is shown in Fig. 5. This comparison assumes that two independent clocks are drifting apart at a drift rate equal to the maximum rate indicated. The independent clocks must be initially synchronized and must run continuously without interruption. The Loran-C clocks may be interrupted and resynchronized at random without affecting the accuracy.

If a clock operating from the slaved oscillator of a Loran-C receiver is correctly set and if that clock and receiver are moved a distance of 300 meters toward the Loran-C transmitter, the clock will then be 1 μsec fast. Similarly, if the clock is moved 300 meters in the opposite direction it will be 1 μsec slow. In contrast, if the same clock were operating from an independent oscillator it would neither gain nor lose as a result of motion.

If a Loran-C clock is used in a moving vehicle its position must always be taken into account. In either ships or aircraft the fixes available from the Loran-C navigation system can provide the necessary information. However, the computations required to convert the time difference readings to distance from the transmitters are rather involved and may necessitate the use of a separate computer. An independent clock may be more satisfactory than a slaved clock in a moving vehicle if the clock does not have to maintain the correct time for a long period. Even the best clocks (or oscillators) will drift with respect to other clocks. In cases where drifts of the order of a microsecond are important, the slaved clock is a virtual necessity.



Fig. 4—Loran-C clock.



Fig. 5—Comparison of slaved and independent clocks.

As the accuracy of clocks within a timing system is increased, the location of each clock becomes correspondingly more important. Fig. 6 illustrates this simple relationship. The timing precision of Loran-C and WWV are also shown for an integration time of approximately one minute. Much longer integration times would improve the accuracies obtainable with WWV.[7]

V. Missile Range Timing

The National Bureau of Standards demonstrated Loran-C timing potentials on the Atlantic Missile Range in October, 1960. These tests were conducted using two experimental Loran-C clocks and a UHF timing distribution system.[8] The clocks were rather complex devices consisting of modified Loran-C receivers and counting and read-out circuits. The two clocks were synchronized on two separate transmitters and an external read command was used to check any variation

[8] T. L. Davis and R. H. Doherty, "Widely separated clocks with microsecond synchronization and independent distribution systems," IRE Trans. on Space Electronics and Telemetry, vol. SET-6, pp. 138–146; December, 1960.



Fig. 6—Time-position accuracy relationship.



Fig. 7—UHF time distribution system.



Fig. 8—Trajectory determination by precise timing.

between the clocks. When a large number of equipments requiring time are operated in close proximity, a single clock can serve them all by means of an appropriate UHF timing distribution system.[8] This basic system of time measurement and distribution could be duplicated at any number of locations within the coverage area of a Loran-C chain. See Fig. 7.

Loran-C ground wave coverage extends down range as far as Trinidad. The various down-range sites to that distance can be provided with absolute timing accuracy of approximately 1 μsec. Beyond Trinidad and down to Ascension Island the Loran-C clocks must be synchronized on sky waves. It is important to note that the absolute accuracy involves an allowance for *systematic* propagation errors which cannot be measured independently by any existing system or method. The repeatability of time measurements at any one station, however, will in general be better than 0.1 μsec. In some cases, repeatability may be at least as important as absolute accuracy. For example, the trajectory of a missile or the position of a satellite[9] could be determined by transmitting very short pulses at UHF or microwave frequencies from the missile and recording their time of arrival at a number of time synchronized stations. See Fig. 8. Systematic time errors among the observing stations would result in a corresponding error in the absolute position of the trajectory, but the changes from reading to reading would be influenced only by the stability of the individual clocks and the stability of the propagation medium between the missile and the ground stations.

On the basis of theory[10] and measurements (Appendix II) there is little doubt that Loran-C clocks can be quite accurately synchronized even on second and/or third hop sky waves. Second hop sky wave time differences from the Cytac (Loran-C) transmitters (Forestport, N. Y., Cape Fear, N. C., and Carrabelle, Fla.) were measured at distances up to 5000 km. Standard deviations of these differences were less than 2 μsec day or night. Sunrise and sunset effects corresponding to 18 to 20 km change in ionospheric height were observed. When only the first reflected signal was utilized these sunrise and sunset effects rarely lasted more than 30 minutes. The height variations agree well with other observations for oblique incidence.[11,12] At distances beyond ground wave range there is no satisfactory way to accurately measure sky wave delays. But there is no reason to distrust computed values based on theoretical calculations, former observations and recent electron density rocket information.[10–13] Based on this information, it should be possible to establish time at ranges from 2000 to 8000 km at least within 10 μsec.

The Atlantic and Pacific missile ranges can be linked with a common timing system which will provide 1 μsec accuracy. The link between the two ranges requires the

[9] G. Hefley, R. F. Linfield and R. H. Doherty, "Timing and Space Navigation with an Existing Ground Based System," presented at AGARD 10th General Assembly, Istanbul, Turkey, October, 1960, Pergamon Press Inc., New York, N. Y.; 1961.

[10] J. R. Johler and L. C. Walters, "On the theory of reflection of low and very-low radiofrequency waves from the ionosophere," *J. Res. NBS*, vol. 64D, pp. 269–285; May–June, 1960.

[11] J. R. Wait, "Diurnal change of ionospheric heights deduced from phase velocity measurements at VLF," PROC. IRE (Correspondence), vol. 47, p. 998; May, 1959.

[12] J. M. Watts, "Oblique incidence propagation at 300 kc using pulse techniques," *J. Geophys. Res.*, vol. 57, pp. 487–498; December, 1952.

[13] A. H. Waynick, "The present state of knowledge concerning the lower ionosphere," PROC. IRE, vol. 45, pp. 741–749; June, 1957.

installation of additional Loran-C stations in a generally east-west direction across the Continental U. S. Possible locations for these stations are shown in Fig. 9. Such a configuration would provide inter-range synchronization as well as excellent navigational coverage over the Continental U. S.



Fig. 9—Possible transmitter locations.

The inter-range synchronization only could be obtained on a very reliable basis by providing a transmitter in Illinois and another transmitter and secondary frequency standard near the West Coast. The western transmitter would be located within ground wave range of Boulder and could be steered by the primary frequency standard. If a number of Loran-C chains were synchronized, one to another, in order to provide coverage over very long ranges, the synchronization accuracy would be degraded to some extent. As far as is known, synchronization errors are of a random nature and therefore can be expected to add as the root-sum-square. For example, if the synchronization error in each transmitter is 0.03 μsec, the accumulated error in synchronizing six stations would be $\sqrt{6(0.03)^2}$ or 0.073 μsec.

The synchronization accuracy of the present Loran-C system could be improved by the use of better oscillators and longer integration times. It is not obvious, however, how much improvement could be achieved before reaching the point of diminishing returns.

The total noise or synchronization errors which can be expected in synchronizing a chain in the Hawaiian Islands from the U. S. should be substantially less than the prediction error in a land or mixed path.

VI. Additional Uses of Precise Time

Some scientific and commercial uses of a precise timing system that may have direct or indirect military applications are:

1) The positioning of high-altitude aircraft from the ground by using the UHF pulse technique.

2) The location of thunderstorms by precisely measuring the location of the lightning discharge.

3) The accurate position-fixing of nuclear detonations by a similar means.

4) A precise evaluation of the fluctuations of the periodicity of the earth's rotation and other astronomical phenomena by relating observations made at widely separated points.

5) The precise measurement of time variations on high-frequency transmissions such as WWV as an aid to better understanding of propagation phenomena.

6) Similar measurements on forward scatter communication links and other types of communication could also be made.

7) The surveying of offshore islands and remote areas.

8) The investigation of Loran-C sky waves to give a better understanding of ionospheric conditions.

9) The precise time from a single Loran-C clock could be made economically feasible for a variety of users in industry and research by the application of a VHF or UHF distribution system. Relatively inexpensive distribution would result if sufficient users were located within range of the distribution system. Existing facilities such as television transmitters could be utilized for this purpose.

Appendix I

Loran-C Ground Wave Measurements

The data presented in this appendix have been abstracted from a report concerned with the position fixing aspects of the Loran-C (formerly Cytac) system.[14]

The data were obtained primarily in the service area (see Fig. 1) during 1954 and 1955. The data are presented in the form of time difference measurements, since the position-fixing information was of prime concern. Although individual propagation paths were not resolved, these measurements were entirely consistent with the individual round-trip paths observed at the transmitters. Since no appreciable differences were detected, the time difference data in the service area were considered to be representative of single path propagation times. Data presented in Appendix II, comparing various sky wave time modes with the ground wave signal, are also consistent with this assumption.

These time-difference (TD) measurements were made in two stages. An envelope measurement was made automatically by subtracting the derivative of the envelope from the envelope and detecting an axis crossing with a servo loop. A cycle measurement was made automatically using synchronous detection techniques and a null seeking servo system. In all cases, the master signal was used to control the reference frequency, and the time differences (X − M and Y − M) were measured with respect to the master. The difference between the envelope TD readings and the cycle TD readings was denoted as the discrepancy. If this discrepancy did not exceed plus or minus 5 μsec, cycle identification was assured by the envelope reading. A typical plot of the cumulative distribution of this reading is illustrated in Fig. 10. Within ground wave recep-

[14] R. F. Linfield, R. H. Doherty, and G. Hefley, "Evaluation of the Propagation Aspects of the Cytac System," private communication; March 18, 1957. (Originally classified confidential.)

tion, the discrepancy was always well within reasonable limits.

The differences between observed and predicted readings were either position dependent or time dependent. The variations related to the position are thought to be caused by an incorrect assumption of the value of the conductivity. Fig. 11 shows a plot of data from locations where the signals arrived over land path. It appears that 0.005 mho/meter is a good average for the M-X pair, but that a higher value of conductivity from the Y transmitter would better approximate the M-Y paths.

The mean of the observed phase readings was compared to predicted phase readings calculated using an assumed conductivity of 0.005 mho/meter for land and 5 mhos/meter for sea water. Differences between the mean and the calculated readings are listed in Table I. Also shown are the distances from the transmitters, the hours of observation, and the standard deviations of the two time differences. The hours of observation were distributed randomly, day or night, throughout the period of operation at each location.



Fig. 10—Cumulative distribution of discrepancy readings—Wisconsin.



Fig. 11—Comparison of theoretical phase of secondary field difference corrections and measured data.

TABLE I

RESULTS OF CYTAC MONITORING PROGRAM

Receiver Location	Distance to Transmitters km			Total Observations	Days At Site	Mean (all Observations) Minus Predicted (μsec)		Std. Deviation of the Observations	
	M	X	Y	(hours)		M-X	M-Y	M-X	M-Y
Miss.—1	1187	753	1704	800	341	+0.10	−0.47	0.11	0.47
N. C.—1	84	756	1028	750	316	+0.35	+1.01	0.16	0.53
Ohio	670	993	825	200	102	+0.48	−1.20	0.10	0.21
Texas—1	2055	1312	2781	98	64	−1.25		0.15	
Maine	1322	2051	437	92	11		−0.07		0.23
Tenn	663	630	1214	58	5	−0.76	+0.78	0.10	0.24
Missouri	1339	1120	1556	52	5	−0.04	−2.88	0.14	0.25
Penn.—1	666	1252	472	52	3	+1.30	−0.09	0.12	0.05
Indiana	1039	1294	839	51	5	+0.29	−1.04	0.07	0.09
Wisconsin	1324	1430	1101	46	5	−0.13	−1.33	0.11	0.13
Florida	656	401	1717	34	7	−0.51	+0.89	0.16	0.27
Kansas	1939	1696	2010	30	5	−0.60	−2.22	0.17	0.19
N. C.—2	499	670	1084	27	2	+0.54	+2.24	0.05	0.09
Iowa	1573	1469	1542	22	2	+0.28	−1.58	0.11	0.10
Penn.—2	681	1314	409	17	3	−0.15	−0.43	0.09	0.07
Virginia	545	1184	544	16	2	+0.63	−0.33	0.26	0.06
Georgia—1	412	368	1408	16	3	+0.32	+0.14	0.12	0.15
Georgia—2	440	359	1371	14	2	−0.05	+0.38	0.11	0.07
Florida—2	816	37	1754	9	1	−0.01	+0.65	0.06	0.17
Louisiana	1414	780	2063	9	2	−0.81	−1.59	0.05	0.23
Arkansas	1519	1015	1990	8	2	+0.48	−1.37	0.04	0.22
Florida—3	1118	655	2182	8	2	−0.03	−0.03	0.08	0.12
Miss.—2	1079	449	1818	8	2	+0.43	+0.07	0.10	0.18
Florida—4	927	454	1983	7	2	+0.02	+0.02	0.06	0.10
Texas—2	1669	1133	2141	7	1	+0.80	−1.19	0.03	0.16

The standard deviation of the mean minus the predicted values listed in Table I for the M-X pair is 0.5 μsec, the mean deviation is 0.43 μsec and the algebraic average is +0.06 μsec. For the M-Y pair the standard deviation is 1.17 μsec, the mean deviation is 0.92 μsec, and the algebraic average is −0.41 μsec. The Millington[15] method for combining conductivities was used for evaluating predictions for 13 sites, but this did not appreciably improve the standard deviations. However, the only conductivity values[16] that were available were measured at broadcast frequencies and over limited areas and are, therefore, not considered applicable at 100 kc. By assuming conductivities for the Y path ranging from 0.004 to 0.008 mho/meter, the standard deviation of the mean-predicted values for the M-Y pair was reduced to 0.69 μsec, and the average error was reduced to 0.51 μsec. Even though the two paths (receiver to M and receiver to X or Y) cannot be separated this method could provide a means for empirically evaluating conductivity at 100 kc in areas where Loran-C measurements are available.

Figs. 12–16 present cumulative distributions of the time difference readings taken at 2.5 minute intervals for sites where the total observation time was limited. Figs. 17–20 present cumulative distributions of the daily average readings for sites where observations were made for several months.

From these figures it can be seen that variations were within 1 μsec during a very high percentage of the time. It may be noted that the M-Y (northern) pair generally had greater deviations than the M-X (southern) pair. This is also quite obvious from Figs. 21–24 where the daily averages are plotted for the fixed sites. Figs. 25 and 26 indicate some typical diurnal variations on the M-X and M-Y pairs. Again it can be seen that the M-Y variations were greater than the M-X variations.

The reason for the larger time variation associated with the northern path was never completely resolved although many contributing factors can be listed. Errors of this magnitude do not exist on the northern pair of the present east-coast Loran-C system.

Most of the data presented here were obtained from signals that were not phase coded. Multihop sky wave contamination was not eliminated and could contribute toward time variations (see Fig. 27). During the first few months of operation some variations were probably due to inexperience of operating personnel.

The operation was not continuous and evidently instabilities accompanied shut down periods. Fig. 28 shows such changes recorded at four stations when the operating periods were compressed into a single plot. Correlation coefficients were calculated using simultaneous data from these four sites. The correlation coefficients are shown in Table II.

In a further investigation, the variations were divided into two categories or components: 1) purely random variations and 2) variations which would produce correlation at the observation points. Since servos in the different pieces of equipment were not adjusted to have identical damping characteristics, the data were normalized to the average characteristics of the four equipments. The results indicated in Table III demonstrate that the maximum variations that could positively be attributed to propagation did not exceed 0.03 to 0.04 μsec.

Although the time fluctuations have sometimes been shown to correlate with weather phenomena, particularly temperature, it has not been conclusively established that the variations were not partially within the antenna system. The typical Loran-C installation includes a 600-foot top loaded transmitting antenna, and a 30- to 90-foot receiving whip within a few hundred meters of the transmitting antenna. Impedance changes of the transmitting antenna would affect the phase characteristics of the receiving antenna. An attempt to check this effect was made by using a receiver on the base-line extension. Any effect due to the antenna impedance change was evidently masked by larger variations.

The large time variations on the northern pair (M and Y) were probably the result of a combination of multihop sky wave contamination, and the first-hop sky wave contamination. The first-hop contamination could occur if the signal were sampled too late, that is, after the first-hop sky wave had started to arrive. The base-line path of the northern pair during the Cytac tests was quite long (over 1000 km); it was all over land (causing maximum delay of the ground wave), and it was at a high geomagnetic latitude.

A subsequent Loran-C chain located in the arctic (high geomagnetic latitude) has encountered trouble with very short first-hop sky wave delays because of the lower ionospheric heights at these latitudes. This situation was encountered even though the base lines were over sea water.

The Loran-C chain located on the East Coast of the United States has been relocated since 1955. The northern base line is now partially over sea water and the northern station is at a slightly lower geomagnetic latitude. With continuous operation and the new locations, the variations have been reduced by an order of magnitude.

Amplitudes of the ground wave signal out to ranges as great as 3700 km are shown in Fig. 29. The paths that the signals traversed were partially land, but primarily sea water. The agreement between predicted and measured values is fairly good in the range of 2400 to 3700 km. The deviation from the predictions at ranges less than 2400 km is greater than can be explained by experimental error.

[15] G. Millington, "Ground wave propagation over an inhomogeneous smooth earth," *Proc. IEE*, vol. 96, pt. III, pp. 53–64; January, 1949.

[16] R. S. Kirby, *et al.*, "Effective Radio Ground Conductivity Measurements in the United States," Natl. Bureau of Standards, Boulder, Colo., NBS Circular No. 546; February, 1954.



Fig. 12—Cumulative distribution of time difference readings—Tennessee Site 1 (2.5 minute intervals).



Fig. 13—Cumulative distribution of time difference readings—Wisconsin (2.5 minute intervals).



Fig. 14—Cumulative distribution of time difference readings—Kansas (2.5 minute intervals).



Fig. 15—Cumulative distribution of time difference readings—Georgia Site (2.5 minute intervals).



Fig. 16—Cumulative distribution of time difference readings—Kentucky (2.5 minute intervals).



Fig. 17—Cumulative distribution of daily averages —Mississippi Site 1 (November 1954–1955).



Fig. 18—Cumulative distribution of daily averages —North Carolina Site (January–October 1955).



Fig. 19—Cumulative distribution of daily averages —Ohio (January–February 1955).



Fig. 20—Cumulative distribution of daily average —Tennessee Site 1 (March–November 1955).



Fig. 21—Daily average X and Y cycle readings—Mississippi Site 1.



Fig. 22—Daily average X and Y cycle readings —North Carolina Site 1.



Fig. 23—Daily average X and Y cycle readings—Ohio.



Fig. 24—Daily average X and Y cycle readings—Tennessee Site 1.



Fig. 25—Running average of Y time difference—North Carolina Site 1 (November 30–December 1, 1954).



Fig. 26—Running average of X time difference—North Carolina Site 1 (November 30–December 1, 1954).



Fig. 27—Cycle readings with and without phase coding—Mississippi Site 1.



Fig. 28—37.5 minute running averages of X readings (13.1 hours of data, September 1–13, 1955).

TABLE II

CORRELATION OF S_1 PAIR

	Tenn. Site 1	Tenn. Site 2	Miss. Site 1	N. C. Site 1
Tenn. Site 1		0.930	0.934	0.901
Tenn. Site 2	0.930		0.934	0.855
Miss. Site 1	0.934	0.934		0.870
N. C. Site 1	0.901	0.855	0.870	

CORRELATION OF S_2 PAIR

Tenn. Site 1		0.526	0.658	0.620
Tenn. Site 2	0.526		0.543	0.442
Miss. Site 1	0.648	0.543		0.669
N. C. Site 1	0.620	0.442	0.669	

TABLE III

	Measured	Normalized	Noise Component	Synchronous Component
		S_1 PAIR		
Tenn. Site 1	0.107	0.077	0.011	0.076
Tenn. Site 2	0.081	0.081	0.009	0.076
Miss. Site 1	0.092	0.081	0.003	0.076
N. C. Site 1	0.068	0.082	0.032	0.076
		S_2 PAIR		
Tenn. Site 1	0.057	0.038	0.024	0.029
Tenn. Site 2	0.043	0.043	0.032	0.029
Miss. Site 1	0.043	0.035	0.019	0.029
N. C. Site 1	0.105	0.037	0.022	0.029



Fig. 29—Predicted and measured ground wave signal amplitude.

Appendix II

Loran-C Sky Wave Measurements

Loran-C is a pulse navigation system utilizing sampling techniques to select the ground wave and discriminate against the sky wave signal. These same sampling techniques can be utilized to select one sky wave signal and discriminate against all other sky wave signals at ranges beyond ground wave reception. This provides a means for measuring the phase and amplitude of a particular sky wave time mode rather than a composite signal as is done in CW measurements. Many measurements that have been made with Loran-C indicate that the phase of a particular time mode is very stable, but the amplitude of that time mode is quite unstable. Furthermore, the variations occurring on one time mode do not necessarily correlate with variations occurring on another time mode.

If a number of vectors of different fixed phases but of variable amplitudes are added together, the phase of the resultant will change as a result of the amplitude variations. Similarly, the phase of a CW signal varies in accordance with the amplitudes of the different time modes. Consequently, the phase variations do not necessarily indicate phase changes in the individual time modes nor changes in ionospheric height.

At ranges beyond ground wave reception the first signal arriving via the ionosphere was normally observed. At shorter ranges uncontaminated higher order multihop sky wave signals were observed. Sky wave signals have been observed at distances as great as 12,000 km (Johannesburg, S. A. from Jupiter, Fla.). A large number of measurements listed in Table IV have been made between 3000 and 5000 km. Multihop measurements listed in Table V have been made at ranges as short as 500 km.

Figs. 30–31 illustrate typical daytime first-hop sky waves observed at Boulder, Colo. (about 3000 km from the transmitters). All of the data available suggest an excellent sky wave phase stability when a single propagation mode is studied. The Boulder data recorded over a period of more than one month had short term variations of only 0.25 μsec and day to day variations of only 0.5 μsec. This data was obtained by comparing a first-hop sky wave from one transmitter with the ground wave from another (southern pair). Nighttime measurements were not made in 1955 because the transmitters did not operate on a 24-hour basis during September and October. Similar measurements made at Boulder in 1961 indicate nighttime stabilities to be at least within 5 μsec (see Fig. 32).

TABLE IV

Mode	Distance (Kilometers)	Time (Day or Night)	Delay (μsec)	σ Standard Deviation (μsec)
Belize, British Honduras				
X Gnd. Y Gnd.	1425 3133	D	− 0.4	0.944
X Gnd. Y 1st	1425 3133	D	+ 29.9	1.012
X Gnd. Y 1st	1425 3133	N	+ 43.1	1.219
X Gnd. Y 3rd	1425 3133	D	+102.8	0.541
X Gnd. Y 2nd	1425 3133	N	+103.9	1.460
X Gnd. Y 4th	1425 3133	N	+267.7	0.904
Kingston, Jamaica				
M Gnd. X Gnd.	1786 1539	D	− 0.7	0.551
X Gnd. Y Gnd.	1539 3829	N	+ 0.3	0.366
M Gnd. Y Gnd.	1786 3829	D	+ 1.0	0.356
Puerto Cabezas, Nicaragua				
X Gnd. Y Gnd.	1763 3356	D	− 2.21	1.235
X Gnd. Y 1st	1763 3356	D	+ 30.0	1.436
X Gnd. Y 1st	1763 3356	N	+ 49.7	1.234
X Gnd. Y 3rd	1763 3356	D	+211.4	1.018
M Gnd. X Gnd.	2286 1763	N	− 1.9	0.255
Buenaventura, Colombia				
M Gnd. X Gnd.	3339 2983	D	− 2.64	0.590
M 1st X 1st	3339 2983	N	− 2.06	0.415
M 1st Y 1st	3339 4385	N	+ 0.0	0.936
M Gnd. Y 2nd	3339 4385	D	+ 37.5	1.864
M Gnd. Y 3rd	3339 4385	D	+105.3	0.909
X 1st Y 4th	2983 4385	D	+222.7	1.309
X Gnd. Y 4th	2983 4385	D	+235.9	1.015
Guayaquil, Eduador				
M 1st X 1st	4024 3574	N	− 1.98	0.299
M 1st Y 2nd	4024 5086	N	+ 56.6	0.527
M 1st X 1st	4024 3574	D	− 0.50	1.812

TABLE V

Distance Kilometers	Transmitter	Total Delay (μsec)	Amplitude (in μv/m)	Most Probable Hop	Corresponding Layer Height km
Woodstock, Kentucky					
817	X	304	9.6	3rd	65.0
817		Nothing could be observed for 4th			
817	X	784	10.3	5th	65.5
817	X	1024	10.8	6th	63.6
1051	Y	285	19.2	3rd	69.5
1051	Y	505	14.4	4th	71.8
1051	Y	753	11.2	5th	71.7
1051	Y	993	9.6	6th	69.6
Spring Creek, North Carolina					
496	M	815	24.4	4th	68.0
496	M	1050	20.0	5th	64.0
676	X	454	—	3rd	74.2
676	X	752	13.2	4th	74.0
1078	Y	1083	—	6th	74.0
Boulder, Colorado					
2526	Y	32	—	1st	*
2526	Y	448	—	5th	78.8
2526	Y	618	—	6th	78.3
2518	Y	34	—	1st	*
2518	Y	298	2.0	4th	77.4
2518	Y	440	—	5th	77.5
2510	M	34	—	1st	*

* Since the apparent heights are obtained from a graph based on geometrical-optical considerations, and the distance for first-hop sky wave is far beyond that obtainable by geometrical-optical theory, any apparent heights assigned to these first-hop reflections would be completely meaningless.



Fig. 30—Envelope and cycle readings, first-hop sky wave—Boulder, Colo. (September 13, 1955).



Fig. 31—First-hop sky wave measurements—Boulder, Colo. (October 6, 1955).



Fig. 32—First-hop sky wave from Cape Fear, N. C.—Boulder, Colo. (1961). Approximately 3000 km.



Fig. 33—Phase and amplitude of Loran-C sky wave referred to ground wave.

The standard deviations listed in Table IV were typical of observations for an entire day or night made in Central and South America in 1956. These standard deviations again suggest excellent stability of the sky wave phase. The delays listed are delays as compared to the predicted arrival time of the ground wave signal. These delays seem to be quite reasonable for the propagation mode being measured. Fig. 32 illustrates the phase change resulting from an S.I.D. occurring on July 11, 1961. The event was rated at about $3\frac{1}{2}$ on a scale of 4. VLF records indicated a change of up to 30 μsec. This first-hop sky wave signal showed a total phase change of 4.5 μsec. This phase decrease was accompanied by an amplitude increase of more than 12 db. The slower sunset effect seems to be related to the flare and the magnetic storm that followed the event. On July 13th and 14th (dotted curves) a magnetic storm occurred that disturbed the phase of VLF CW measurements.

Fig. 33 presents a three-day plot of both the phase and amplitude of a first-hop sky wave signal, the upper plot representing the T.D. between a first-hop sky wave signal from 3200 km and the ground wave signal from 1440 km. Again rather good phase stability is suggested. The lower plots are the measured amplitudes of the two signals. The amplitude of the sky wave signal is quite variable and not obviously correlated with any phase changes.

The amplitudes of the various time modes present vary relative to one another, often quite rapidly. Fig. 34 illustrates several time modes of the Loran-C master pulses observed at Boulder. The relative amplitudes of the several time modes obviously do not correlate. A CW measurement made at this frequency would show phase changes due to these relative amplitude changes alone.



Fig. 34—Multihop sky waves master signal observed at Boulder, Colo.



Fig. 35—Field strength of Loran-C sky wave on north-south paths.

Fig. 35 represents average amplitudes observed on a predominantly north-south path. Since these plots are strictly amplitude versus distance and the Y transmitter was about 15° farther north than the X transmitter, a strong latitude effect on signals propagated by the ionosphere is suggested. The average nighttime sky wave field intensity was about 20 db larger than the average daytime field intensity.

Table V presents other interesting observations made at relatively short ranges. It was noted that high-order multihop sky waves were present at most locations. It was further noted as can be seen from the tabulations that often the amplitude of the nth hop would be as great as or greater than the amplitude of the nth-1 hop. Assumptions made as to predominant time modes or negligible time modes for CW measurements may be somewhat questionable in view of these observations.

VII. Acknowledgment

Special acknowledgment is given to P. J. Kiser, of the Air Force Eastern GEEIA Region, for his engineering contributions to the Loran-C clock and his assistance in the preparation of this paper.

The entire Loran-C clock and UHF distribution system has been developed by the National Bureau of Standards, Boulder Laboratories under the sponsorship of Headquarters, Eastern GEEIA Region.

A Provisional Ground Conductivity Map for Canada*

G. CLEMENT IRELAND†, MEMBER, IRE

Summary—**The Department of Transport promulgated a new ground conductivity map for Canada as of January 1, 1961. The derivation of this map is discussed. Included is a brief account of propagation measurements at broadcast frequencies carried out by the Department in the Great Lakes region.**

Introduction

AS OF January 1, 1961, a new ground conductivity map for Canada was promulgated by the Department of Transport. This map replaces the one promulgated in 1948 as part of the Department's Broadcast Specification No. 14 and subsequently included in the North American Regional Broadcasting Agreement (NARBA) of 1950. Although derived from the best available data existing at the time, the old map had proved to contain many inaccuracies since it had been based on a few field measurements generalized for fairly large areas. With respect to the allocation of standard radio broadcasting stations, these inadequacies were responsible for extra administrative work since many notifications had to be cleared by individual field measurements.

Since 1948, additional ground conductivity data has been acquired by the Department in the radial path field measurements submitted in proofs of performance which, in Canada, are required for both directional and omnidirectional standard radio antenna systems. When submitting the radial measurements for these proofs, the Department's specifications require sufficient field intensity readings to determine not only the efficiency of the antenna, but the day-time and night-time protected contours as well. As a result many radials have been run for a considerable distance giving an indication of the conductivity in the immediate vicinity of the station and any trend to a change at the greater distances. Soon after joining the Department in 1957, the author began a study of this data to determine a more accurate picture of ground conductivity in Canada and to derive an up-to-date map. In this regard, the procedure used in deriving the current U. S. map was noted.[1]

Conductivity Values for Land Areas

One of the main concepts used in deriving the current U. S. ground conductivity map was to have an "effective" map giving values of conductivity which would "result in the over-all median field strength for the path or segment of path under consideration when used in conjunction with groundwave field strength versus distance curves." Considering the variables that are present when measuring conductivity over any given path, there appeared to be no point in having a map with conductivity classifications closer than 2 to 1. The following conductivity classes were therefore established for land areas: 0.5, 1, 2, 4, 8, 15 and 30 millimhos per meter. The range of conductivities for each class was determined by calculating the geometric mean with adjacent values in the scale.

After some consideration, it was decided to draw up a Canadian map using much the same concept. However, the field measurement data in the Department and the nature of the terrain in certain large areas of Canada where average values of 40 millimhos per meter can be expected, favored the adoption of a somewhat different conductivity scale. This scale, with the ranges of conductivity for each class, is given in Table I.

TABLE I

Conductivity Class (millimhos per meter)	Range of Conductivities
1	1.414
2	1.414– 2.828
4	2.828– 4.889
6	4.889– 7.746
10	7.746–14.14
20	14.14 –28.28
40	28.28 –56.56

Although some overlap of a 2 to 1 ratio occurs in the "4-6-10" portion of the scale, graph values for NARBA field intensity curves are used throughout. While the actual values of conductivity may vary over the indicated range in any one conductivity area, the theory would indicate that these values should average out to approximately the scale value for any given distance.

In order to arrange the available data in a form

* Received by the IRE, March 31, 1961; revised manuscript received, July 5, 1961.

† Radio Regulations Division, Department of Transport, Ottawa, Ontario, Canada.

[1] H. Fine, "An effective ground conductivity map for continental United States," PROC. IRE, vol. 42, pp. 1405–1408; September, 1954.

which could be interpreted, map overlays for various sections of the country were prepared. By means of a system of color coding in which specific conductivity values were assigned different colors, the radials from all outstanding proofs of performance in the Department were plotted. Any one color, or a group of colors, on the overlay which seemed to predominate in a particular area gave some indication of the measured conductivity in that area.

As may be expected, there were areas where field measurement data was sparse. In an attempt to find a basis for suitable values in these areas, the overlays were compared with different types of maps, *i.e.*, geological, forest classification, gravity anomaly, soils, topographical, etc., to see if any correlation could be determined. This approach left much to be desired and no definite findings could be established. Nevertheless, predicting values on soil data appeared to have some merit and this method was used in areas where little or no field measurement information was available.

To avoid too much "extrapolation" and to allow for additional data becoming available in the future, three types of conductivity designations are used. In a section of the country along the United States boundary, where almost all of the Canadian broadcasting stations are concentrated, the conductivity values have been predicted either solely on a basis of field measurement data or on a combination of field measurement data and soil data. Field intensity calculations based on these values should be of an accuracy sufficient to fulfill international treaty obligations and domestic regulations. In a second section the conductivity values have been predicated almost wholly on soil studies alone. The values shown in these areas have been encircled. While there appears to be some justification for the values assigned, they are to be regarded as an approximation only, and if used, must be confirmed. In a third section, which consists for the most part of the far northern areas, the values of conductivity are designated as being "unknown" since there appears to be no field measurement data or soil data upon which values can be predicated. If values for these areas are required, they will have to be determined.

Conductivity Values for Bodies of Water

Although the generally accepted value of conductivity for fresh water is 10 millimhos per meter, few propagation measurements at broadcast frequencies have been made over any sizeable fresh water bodies. Since Canada contains many large fresh water lakes, a problem is presented in assigning them conductivity values. This problem is accentuated in the Great Lakes, where the Federal Communications Commission and the Department have used different conductivity values over the American and Canadian sectors respectively.

In view of the lack of data, it was decided in the Department to take propagation measurements over Lake Ontario to determine how close the accepted values were to actual conditions. The National Research Council's motor vessel "Radel II" was made available for this purpose, position fixes being obtained by means of the ship's radar. Since the transmitter of Radio Station CFRB, Toronto, was ideally located at one end of the lake, it was used as the source of radiation, CFRB kindly agreeing to operate with an omnidirectional pattern for the duration of the measurements. With this arrangement, a radial was run the length of the lake.

The results of these measurements indicated the conductivity of Lake Ontario to be about 15 millimhos per meter, which was higher than any value previously used in allocations. It was concluded that contamination could be responsible for this high value since Lake Ontario was the lowest lake in the system. It was therefore arranged for the "Radel" to make quick conductivity checks on the remainder of the Great Lakes (excluding Lake Michigan), a mobile broadcast transmitter being used as the source of radiation. These results showed that the conductivity from lake to lake tended to vary in accordance with position in the system.

In an attempt to determine the validity of the contamination theory, water samples were taken from the four lakes concerned for analysis by the National Research Council. This analysis indicated that the lakes having the higher measured conductivities also had the higher amounts of contamination.

As a result of these tests, values have been assigned to the Canadian sectors of these lakes as follows:

Lake Ontario—	15 millimhos per meter
Lake Erie—	10 millimhos per meter
Lake Huron and Georgian Bay —	10 millimhos per meter
Lake Superior—	8 millimhos per meter

For other Canadian fresh water bodies, a value of 10 millimhos per meter is used. For sea water the value is 5000 millimhos per meter.

Discussion

Determining conductivity over land areas by field measurement is subject to some approximation due to the effect of climate and terrain. Therefore, any conductivity map based on this type of information could give a general conductivity picture only. In addition, the density of field measurements will vary widely in different parts of the country resulting in a tendency for the map to vary in accuracy to the same extent. Even where the density of measurements is fairly high, *i.e.*, southwestern Ontario, it is often necessary to define conductivity areas somewhat arbitrarily. The main value of this type of map is as an acceptable standard upon which satisfactory allocations may be made.

Within the above-mentioned limitations, it is considered that the new Canadian map gives a good general outline of conductivity as it exists in the country. Too much approximation is avoided by having the three types of conductivity designations. The map as a whole has been accepted by the Canadian Association of Broadcast Consultants as being fairly indicative of



TELECOMMUNICATIONS AND ELECTRONICS BRANCH
DEPARTMENT OF TRANSPORT
OTTAWA
-CANADA-

PROVISIONAL GROUND CONDUCTIVITY MAP
SHEET-1- CANADA
SHEET-2- SOUTHERN ONTARIO

IN THE APPLICABLE AREA, SHEET 2 WILL TAKE PRECEDENCE.

WHERE CONDUCTIVITY VALUES ARE NOT CIRCLED, INDICATED VALUES WILL APPLY.

WHERE CONDUCTIVITY VALUES ARE CIRCLED, INDICATED VALUE IS BASED ON LIMITED DATA ONLY AND SHOULD BE CONFIRMED

WHERE CONDUCTIVITY VALUE IS INDICATED AS UNKNOWN, NO ACCURATE INFORMATION IS AVAILABLE AT PRESENT

JUNE 1, 1960

CONDUCTIVITY OVER WATER	
SEA WATER	5000
FRESH WATER LAKES (EXCEPT GREAT LAKES)	10
GREAT LAKES:	
LAKE SUPERIOR	3
LAKE HURON AND GEORGIAN BAY	10
LAKE ERIE	10
LAKE ONTARIO	15

Fig. 1.



SOUTHERN ONTARIO

TELECOMMUNICATIONS AND ELECTRONICS BRANCH
DEPARTMENT OF TRANSPORT
OTTAWA
-CANADA-

PROVISIONAL GROUND CONDUCTIVITY MAP

SHEET 1- CANADA
SHEET 2- SOUTHERN ONTARIO

IN THE APPLICABLE AREA, SHEET 2 WILL TAKE PRECEDENCE

JUNE 1, 1960

Fig. 2.

actual conditions. The unit, millimhos per meter, is used for values of conductivity throughout.

Since a body of water is practically homogeneous and there is very little scattering effect on a radio wave at broadcast frequencies, it seemed a reasonable assumption that conductivities over water could be measured more accurately than a 2 to 1 ratio. This was confirmed in the radials obtained on the lakes which followed the theoretical propagation curves very closely. Thus, the binary scale was abandoned for over-water propagation and the values as measured were assigned.

The new map is published in two sheets. The first sheet (Fig. 1) is on a scale of 1:6,336,000 and includes Canada as a whole. This scale was used because it appeared to be adequate and a base map was already available, thus facilitating immediate promulgation. However, a large portion of Canada's broadcasting stations are located in Southern Ontario and it had been past experience that a special need existed for agreed values in this area. Therefore, a second sheet (Fig. 2) showing Southern Ontario on a scale of 1:1,000,000 is also published. This sheet takes precedence over the first sheet in the applicable area. Specimens only of the two sheets are shown in Figs. 1 and 2.

It is admitted that use of this new Canadian map, in conjunction with the U. S. map, produces anomalous situations along the international boundary. This is a result of the two maps being drawn up by two different agencies evaluating information independently of one another. (It may be noted that other types of maps, *i.e.*, soil maps, contain similar anomalies.) While it may be argued that conductivity anomalies of this nature are impossible in a practical sense, satisfactory allocations should result if the anomalies are treated simply as conductivity boundaries. It is anticipated that, eventually, negotiations between the F.C.C. and the Department of Transport will result in these anomalies being removed or minimized; this is why the present map is designated as "provisional." Until such time as these negotiations are completed and promulgated, the provisional designation will apply.

Due to the provisional status of the map, wide circulation will not be encouraged. However, agencies and individuals who have a need for copies may obtain them at $5.00 per copy (one copy comprising both sheets) by writing the Controller of Radio Regulations, Department of Transport, Ottawa, Canada. Checks or money orders should be made payable to the Receiver General of Canada.

Acknowledgment

The author wishes to thank the following persons for their generous assistance and co-operation: W. B. Smith and J. T. Chrome of Radio Regulations Engineering Section, Department of Transport; Radio Station CFRB, Toronto; Clive Eastwood, Chief Engineer, CFRB; J. F. Edwards, Civil Defence Division, Department of National Health and Welfare, for arranging the loan of a mobile transmitter for the "over-water" measurements; Captain H. Ross Smyth, Navigational Aids Section, National Research Council, for arranging the use of Radel II for the over-water measurements; Dr. L. H. Doherty, National Research Council, for arranging the chemical analysis of the Great Lakes water samples, and for many helpful suggestions; Captain J. A. Hehir, Master of "Radel II," and his crew.

Correspondence

Tunnel-Diode Series Resistance*

The purposes of this note are 1) to describe a source of large error in the usual method of measuring the tunnel-diode series resistance, and 2) to indicate alternative measuring techniques.

The series resistance r_s of a tunnel diode is determined generally by measuring the incremental slope of the V-I characteristic at some large value of reverse current. The diode resistance actually measured r_m is the sum of r_s and the incremental resistance for the p-n junction r_d:

$$r_m = r_s + r_d. \tag{1}$$

Typical characteristics of r_m, r_d, and r_s as a function of reverse bias current I are shown in Fig. 1.



Fig. 1

Generally Used Technique for Determining r_s

With increasing reverse current, the incremental resistance for the p-n junction r_d decreases (see Fig. 1). Therefore, for some large value of reverse current, the measured incremental resistance r_m is essentially equal to r_s. This is the basis of the usual technique for determining r_s. But frequently an insufficiently large value of measuring current is used, either because of unfamiliarity with what is involved or because an adequately large value of reverse current will cause excessive heating of the diodes. As is evident from Fig. 1, the measurement actually determines r_m, and this may be *many times larger* than r_s for the particular measuring current.

One common error is to define the value of measuring current in terms of the forward *peak* current I_p. However, it is our experience that the required measuring current cannot be related generally to I_p and that such an attempt only blankets the type of error described.

In many cases heating of a diode is a limitation of the *test circuit* and *not* of the diode. When reverse bias is established with a narrow current pulse of low duty cycle, excessive heating usually can be avoided by simply reducing the width of the current pulse. If heating occurs and the width of the pulse cannot be conveniently reduced, then r_s may not be accurately determined by the generally used technique.

Techniques for Determining r_s with Reduced Currents

For values of reverse current smaller than required in the above technique, r_s may be accurately determined only by correcting for r_d.

Except for small currents, conduction in the reverse-bias region is by Zener emission, for which Chynoweth, *et al.*,[1-3] have suggested the following equation. Neglecting series resistance,

$$I = AV^p(V_i + V)^{q/2}\exp[-B/(V_i + V)^{1/2}], \tag{2}$$

where I is the measured current, V is the voltage applied to the p-n junction, being positive for reverse bias, V_i is the built-in voltage (internal-contact potential), and A, B, p, and q are constants (p is usually about unity).

From the derivative of (2) we may solve for $r_d(=dV/dI)$, the incremental resistance of the V-I characteristic for the p-n junction:

$$r_d = \frac{1}{I\left[\dfrac{p}{V} + \dfrac{B + q(V_i + V)^{1/2}}{2(V_i + V)^{3/2}}\right]}. \tag{3}$$

Two-Measurement Technique

With increasing reverse current, the voltage V applied to the p-n junction approaches a constant value. From (3) we see that, with V essentially constant, r_d is inversely proportional to current. The measured incremental resistance is then given by

$$r_m = r_s + \frac{k}{I}, \tag{4}$$

where k is a dimensional constant. Since in (4) there are two unknowns (r_s and k), r_s may be determined with measurements of r_m at two currents for which this equation holds.

Multiple-Measurement Technique

Alternatively, for a range of relatively *small* currents, the quantity $(V_i + V)$ is essentially constant, so that the value of the second term within the brackets of (3) may be considered constant. For this range of current the measured incremental resistance is given by

$$r_m = r_s + \frac{1}{I\left(\dfrac{p}{V} + N\right)}, \tag{5}$$

where N is a constant. Since in (5) there are three unknowns (r_s, p, and N), r_s may be determined with measurements of the incremental resistance r_m and the total voltage applied to the device $V_M(=V + r_sI)$ at three values of current. Calculation is especially easy if $p=1$, which fortunately is a reasonably valid assumption for most diodes.

Measurements

The series resistance of several experimental GaAs tunnel diodes was measured by the three techniques described with good agreement between results of each measurement for most diodes. In some cases results for a diode with the multiple-measurement technique differed from results with the other techniques by more than 10 per cent. This was possibly due to incorrectly assuming $p=1$ to simplify the calculations.

While the latter two techniques require additional and more accurate measurements, this in many cases more than offsets the requirement of a large measuring current for the single-measurement technique.

E. L. Bonin
J. R. Biard
Research and Engineering Dept.
Components Division
Texas Instruments, Inc.
Dallas, Tex.

* Received by the IRE, August 28, 1961.

[1] A. G. Chynoweth, *et al.*, "Internal field emission at narrow silicon and germanium P-N junctions," *Phys. Rev.*, vol. 118, pp. 425–434; April 15, 1960.

[2] A. G. Chynoweth and R. A. Logan, "Internal field emission at narrow P-N junctions in indium antimonide," *Phys. Rev.*, vol. 118, pp. 1470–1473; June 15, 1960.

[3] A. G. Chynoweth, "Physics of Esaki Diodes," Special Summer Session on New Devices for Amplification and Switching, The Moore School of Elec. Engrg., University of Pennsylvania, Philadelphia; 1960.

Some Measurements on an Iris Beam Waveguide*

The resonance in a parallel plate resonator which has first been investigated by King, Scheibe, and Tatsuguchi,[1] led to the conclusion that an array of uniformly spaced identical irises should guide a wave beam with relatively little diffraction loss, provided the apertures of the irises are sufficiently large compared to the wavelength. Assuming circular irises and uniformly directed field, one can formulate the condition for a beam whose field repeats from iris to iris by the following integral equation:

$$f(x) = q\int_0^a f(\xi)J_0(x\xi)e^{-j/2(x^2+\xi^2)}\xi d\xi \tag{1}$$

with

$$x = \sqrt{k/D}\,\rho, \qquad \xi = \sqrt{k/D}\,\eta,$$

$$a = \sqrt{k/D}\,R, \qquad k = \frac{2\pi}{\lambda},$$

* Received by the IRE, July 26, 1961; revised manuscript received, August 22, 1961.

[1] For references to the literature see E. Scheibe, "Measurements of resonators formed from circular plane and confocal paraboloidal mirrors," Proc. IRE (Correspondence), vol. 49, p. 1079; June, 1961.

where J_0 is the Bessel function of zero order, R the aperture radius of the irises, and D their spacing. ρ, η are radial coordinates at two adjacent irises. The eigenfunctions describe the radial distribution of the field and the eigenvalues q the amplitude ratio between the fields at two successive irises.

Early measurements by the authors with irises of 20 cm aperture and various spacings at a frequency of 25 Gc indicated that a large number of irises is necessary to obtain a repetitive field. However, when a phase transformation was introduced at each iris which removed the phase term $e^{-j\beta/2(x^2+\xi^2)}$ in the integral equation, only a few passages were necessary to obtain a substantially repetitive field. Furthermore, the loss was much smaller for the same size of aperture and iris spacing. The results were in good agreement with the then available solution of (1) with compensated phase term.[2]

Recently, Fox and Li[3] have evaluated (1) with the inclusion of the phase term. If the derivation of the equation is based upon Huygens' principle, one makes the assumption that $(R^4/\lambda D^3)\ll 1$. The equation can also be derived by expressing the field in terms of a bundle of plane waves whose directions of propagation are limited to small angles θ against the beam axis.[4] In this case, the limitation $D/\lambda(\theta/2)^4\ll 1$ applies. Therefore, one should expect that the restriction $R^4/\lambda D^3\ll 1$ is not necessary for the validity of (1) if the reiterative beam comprises only small propagation angles.



Fig. 1—Measured diffraction loss per iris in an iris beam waveguide:

□ = measured at 35 Gc.
○ = measured at 70 Gc.
△ = measured by Scheibe, King, and Tatsuguchi[1] from measurements on a parallel plate resonator with circular reflector plates.
Curve = theoretical curve by Fox and Li[4] for a parallel plate resonator of circular reflector plates.



Fig. 2—Multiply-reflected pulse train from experimental setup.

In order to verify this, pulse measurements have been performed with a setup consisting of two plane aluminum reflector plates approximately 56 cm square and facing each other at a distance S. Various numbers of identical plywood frames, with square apertures of the size of the reflectors were aligned equally spaced between the reflectors as indicated in Fig. 1. The reflectors were provided with a small coupling hole in the center for injecting and receiving the multiply-reflected pulse. Measurements were first made at a frequency of 35 Gc with a reflector spacing of 2.2 m. Since the travel time of the pulses was much shorter than the pulse duration, the pulses overlapped. The attenuation of the fundamental beam mode was determined from the rate of decay of the exponential tail of the oscilloscope display. The results, plotted in Fig. 1 as squares, show the diffraction loss caused by one frame as a function of a quantity A which is defined as aperture area divided by $\pi\lambda D$.

A second set of measurements was made at 70 Gc. The spacing S was increased to about 10 m so that the multiply-reflected pulses were separated in time. A typical pulse trail observed with this setup is shown in the photograph (Fig. 2). Each pulse represents a round trip down the line and back. Since there were 16 frames equally spaced between the reflectors the number of iterations between two successive pulses was 34. Almost 2500 iterations were required before all the higher beam modes were damped out and the exponential decrease of the pulse train was established. The results are indicated in Fig. 1 as circles. The triangular point in the plot is the value obtained by Scheibe, *et al.*,[1] from resonance measurements on a parallel plate resonator with circular reflector plates. The curve shown in the figure has been calculated by Fox and Li[3] for the parallel plate resonator but with circular reflector plates.

Although our measurements have been made with irises of square aperture, while the calculated curve by Fox and Li applies to circular reflectors, it can be concluded from the results that the condition $R^4/\lambda D^3\ll 1$ is not required for the validity of (1), at least so far as the lode mode is concerned. The values of $R^4/\lambda D^3$ in the measurements range from 0.07 to 11.

J. R. Christian
G. Goubau
Institute for Exploratory Research
U. S. Army Signal Research
and Development Labs.
Fort Monmouth, N. J.

[2] J. R. Christian and G. Goubau, "Experimental studies on a beam waveguide for millimeter waves," IRE Trans. on Antennas and Propagation, vol. AP-9, pp. 256–263; May, 1961.
[3] A. G. Fox and T. Li, "Resonant modes in an optical maser," Proc. IRE, vol. 48, pp. 1904–1905; November, 1960.
[4] G. Goubau and F. Schwering, "On the guided propagation of electromagnetic wave beams," IRE Trans. on Antennas and Propagation, vol. AP-9, pp. 248–263; May, 1961.

Ionospheric Contributions to the Doppler Shift at VHF from Near-Earth Satellites*

The ionospheric contributions to the Doppler shift at VHF arising from satellites sensibly above the ionosphere have been considered to $0(1/f_s^3)$, where f_s is the satellite transmitter frequency, and the vacuum Doppler shift is considered of $0(f_s)$. To this order, the phase (whose time derivative is the Doppler shift) cannot be approximated by the usual Fermat integral of geometrical optics. Through a consideration of the characteristics of an ideal Doppler tracking receiver, boundary conditions can be imposed upon the solution of the wave equation containing an arbitrary ionosphere electron contribution to the refractive index (including the earth's magnetic field) such that the solution is valid to $0(1/f_s^3)$ in the phase. The resulting nonrelativistic refracted Doppler shift corresponding to circularly polarized radiation is

$$\Delta f(t) = -\frac{f_s}{c}\frac{d}{dt_0}\phi(f_s, t_0) + 0\left(\frac{v^2}{c^2}\right),$$

$$\phi(f_s, t_0) = \int_0^{\vec{r}_s(t_0)} d\vec{r}' \cdot \hat{s}(\vec{r}') N(\vec{r}', t_0 \mid f_s) + 0\left(\frac{1}{f_s^5}\right),$$

$$t_0 = t - \frac{\partial}{\partial f_s}\left[\frac{f_s}{c}\phi(f_s, t)\right] + 0\left(\frac{v^2}{c^2}\right),$$

where

$\vec{r}_s(t_0)$ = satellite position vector at the time t_0 in a coordinate system where the receiving station is at the origin,

$\hat{s}(\vec{r}')$ = unit vector tangent to the path at $\vec{r}'$ which makes $\phi(f_s, t_0)$ an extremum,

$$\hat{R} = \frac{\vec{r}_s(t_0)}{|\vec{r}_s(t_0)|},$$

$\vec{\xi}(R)$ = normal to $\vec{r}_s(t_0)$ and is the vector difference between the extremum path and the geometric path, $\vec{\xi}(0) = \vec{\xi}(R) = 0$,

$\vec{r}' = R\hat{R} + \vec{\xi}(R)$, $0 \le R \le |\vec{r}_s(t_0)|$ = vector from origin to extremum path,

$$N(\vec{r}', t_0 \mid f_s) = n(\vec{r}', t_0 \mid f_s) + \frac{2\pi^2 c^2}{f_s^2}\frac{\hat{R}\cdot\vec{\nabla}n + \vec{\nabla}\cdot\dfrac{d\vec{\xi}(R)}{dR}}{R} + 0\left(\frac{1}{f_s^6}\right),$$

$n(\vec{r}', t_0 \mid f_s)$ = ionospheric refractive index appropriate to the circularly polarized component received.[1]

* Received by the IRE, September 8, 1961. This work was supported by the U. S. Dept. of the Navy, Bureau of Naval Weapons, under Contract NOrd 7386.

[1] J. A. Stratton, "Electromagnetic Theory," McGraw-Hill Book Co., Inc., New York, N. Y., pp. 327 ff.; 1941.

The above equations express the fact that to $0\,(1/f_s^3)$, the phase is given by a modified Fermat principle in which the index of refraction n is replaced by the function N given above. Since $\vec{\nabla}n$ and the deviation of the extremum path from the geometric path $\vec{\xi}$ are of $0\,(1/f_s^2)$, the difference between n and N is of $0\,(1/f_s^4)$.

After expanding the index of refraction in a power series in $1/f_s$, the above equations for the refracted Doppler shift were used to estimate upper bounds on the various contributions. First, it was found that, while the contribution of the difference $N-n$ is of $0\,(1/f_s^3)$, its magnitude was sufficiently small to be negligible in all cases of interest in the VHF region. Consequently Fermat's principle and the consequent optical approximation are valid to $0\,(1/f_s^3)$ at VHF. Second, numerical upper bounds were established for the various orders in $1/f_s$ using the above equations. The results are summarized in Table I. During periods where the ionosphere is not seriously disturbed, the magnitude of the various refraction terms are most likely a factor of 3–10 lower. It can be seen that for frequencies above about 100 mc the use of two frequency Doppler data to eliminate refraction effects is adequate.[2]

TABLE I
MAXIMUM IONOSPHERIC CONTRIBUTIONS TO THE SATELLITE DOPPLER SHIFT
(ENTRIES ARE IN CPS)

f_s(Mc)	Vacuum Doppler	$0(1/f_s)$	$0(1/f_s^2)$	$0(1/f_s^3)$
50	1200	20	0.6	2
100	2500	10	0.2	0.3
150	3700	6.7	0.07	0.04
200	5000	5	0.04	0.03
300	7500	3.3	0.02	0.01
400	10000	2.5	0.01	—
500	12500	2	—	—

A detailed report is being submitted for publication.

WILLIAM H. GUIER
Applied Physics Lab.
The Johns Hopkins University
Silver Spring, Md.

[2] W. H. Guier and G. C. Weiffenbach, "A satellite Doppler navigation system," PROC. IRE, vol. 48, pp. 507–516; April, 1960.

WWV and WWVH Standard Frequency and Time Transmissions*

The frequencies of the National Bureau of Standards radio stations WWV and WWVH are kept in agreement with respect to each other and have been maintained as constant as possible with respect to an improved United States Frequency Standard (USFS) since December 1, 1957.

The nominal broadcast frequencies should for the purpose of highly accurate scientific measurements, or of establishing high uniformity among frequencies, or for removing unavoidable variations in the broadcast frequencies, be corrected to the value of USFS, as indicated in the table below. The corrections reported have been arrived at by means of improved measurement methods based on LF and VLF transmissions.

The characteristics of the USFS, and its relation to time scales such as ET and UT2, have been described in a previous issue,[1] to which the reader is referred for a complete discussion.

The WWV and WWVH time signals are also kept in agreement with each other. Also they are locked to the nominal frequency of the transmissions and consequently may depart continuously from UT2. Corrections are determined and published by the U. S. Naval Observatory. The broadcast signals are maintained in close agreement with UT2 by properly offsetting the broadcast frequency from the USFS at the beginning of each year when necessary. This new system was commenced on January 1, 1960. A retardation time adjustment of 20 msec was made on December 16, 1959; another retardation adjustment of 5 msec was made at 0000 UT on January 1, 1961; and a time advancement of 50 msec was made at 0000 UT on August 1, 1961.

WWV FREQUENCY
WITH RESPECT TO U. S. FREQUENCY STANDARD

August, 1961	Parts in 10^{10}†
1	−150.6
2	−150.3
3	−150.1
4	−150.0
5	−150.1
6	−149.6
7‡	−149.6
8	−150.9
9	−151.0
10	−151.5
11	−151.4
12	−151.5
13	−151.5
14	−151.5
15	−151.4
16	−151.3
17	−151.2
18	−151.2
19	−151.1
20	−150.9
21	−150.8
22	−150.7
23‖	−150.9
24	−149.5
25§	−149.8
26	−151.2
27	−151.4
28	−151.7
29	−151.9
30	−152.2
31	−152.1

† A minus sign indicates that the broadcast frequency was low. The uncertainty associated with these values is $\pm 5\times10^{-11}$.

‡ The frequency was adjusted -1.3×10^{-10} on August 7.

‖ The frequency changed $+1.7\times10^{-10}$ on August 23.

§ The frequency was adjusted -0.9×10^{-10} on August 25.

NATIONAL BUREAU OF STANDARDS
Boulder, Colo.

[1] Refer to "National Standards of Time and Frequency in the United States," PROC. IRE (Correspondence), vo . 48, pp. 105–106; January, 1960.

* Received by the IRE, September 25, 1961.

Persistent-Current Memory Circuit*

Crittenden, *et al.*, state (page 1244)[1] that lead films have "large critical currents at working temperatures (2° to 5°K), and large heat evolution occurs in the normal state. This leads to long recovery times determined by thermal relaxation and tends to make lead unsuitable for Persistor switch elements." Experiments with persistatron[2] circuits made entirely from evaporated lead and operating at 4.2°K have demonstrated that this opinion is pessimistic. We have observed complete switching (denoting total reversal of the magnetic flux linking a superconducting circuit) in less than 10 nsec, several times faster than in the tin and indium persistor circuits. Fig. 1 shows a lead persistatron on a 1-inch×0.4-inch glass substrate.



Fig. 1—Thin-film persistatron made of lead evaporated onto a glass substrate. Terminals *ab* are for current input; *cd* are for voltage sense. The self-inductance of the loop is 0.02 μh.

Our results are quite reasonable in light of a circuit analysis that includes the conservation of flux in a multiply-connected superconductor.[3] The persistor (or persistatron, the same circuit by a different name) is considered to be a superconducting loop, rather than a nonlinear resistor and inductor driven in parallel. The flux linking the loop may change only when some portion of the loop becomes normally conducting. This analysis does not restrict the switch element to a smaller self inductance than the remaining part of the loop.

If one assumes that there is negligible electric field within the superconducting portion of the loop—the usual low-frequency approximation to one of London's equations—then the output voltage developed across the switch element is comprised of two parts:

1) $L(dI/dt)$ voltage from the inductance seen across the current input terminals, even though the net flux *linking the loop* remains constant,
2) $d\phi/dt$ voltage arising from a change in the net flux linking the loop and appearing as an IR drop across the switch element, even though input current is constant.

* Received by the IRE, August 28, 1961. This work was performed under AEC Contract No. AT-(40-1)-2430.

[1] E. C. Crittenden, Jr., J. N. Cooper and F. W. Schmidlin, "The 'persistor'—a superconducting memory element," PROC. IRE, vol. 48, pp. 1233–1246; July, 1960.

[2] M. J. Buckingham, "The persistatron—a superconducting element for computers," *Proc. 5th Internatl. Conf. on Low Temperature Physics and Chemistry*, Madison, Wis., August, 26–30, 1957; University of Wisconsin Press, Madison, 1958.

[3] F. London, "Superfluids," John Wiley and Sons, Inc., New York, N. Y.; 1950.

As Crittenden, *et al.*, pointed out, it is the $d\phi/dt$ portion of the output signal that is significant in determining the sense of the stored flux. Fig. 2 shows the superposition of switching and nonswitching output waveforms from a persistatron.



Fig. 2—Two superimposed output waveforms from a persistatron showing LdI/dt nonswitching signal (lower trace), and the switching signal plus LdI/dt (upper trace). The large deflection on the left corresponds in time to the leading edge of the 250-ma input current pulse. Vertical scale is 0.5 v per large division; horizontal scale is 2 nsec per large division.

The amount of energy dissipated as heat during switching depends *only* upon the quantity of flux that is changed, and not upon the resistance of the switch element. The switching speed (for a given circuit configuration and stored flux level) will be faster for a switch element that develops high resistance in a short time—a characteristic of thin lead films—with a correspondingly larger output signal. The relatively large critical current of a lead film provides higher stored flux levels and also yields an increase in output signal level.

Our analysis shows further that it is *not* necessary to terminate the input current pulse immediately after switching occurs in order to establish a persistent current. A lead persistatron has stored the same quantity of flux with current pulses of 10-nsec duration and of 1-μsec duration. The necessity for terminating input pulses just after switching, as reported by Crittenden, *et al.* (page 1234), suggests that thermal relaxation may be a more serious problem in tin and indium switch elements operated only slightly below critical temperature.

W. C. Stewart
H. A. Owen
M. S. P. Lucas
C. R. Vail
Superconducting Circuits Laboratory
Electrical Engineering Department
Duke University
Durham, N. C.

A C-Band Parametric Amplifier with Large Bandwidth*

A bandwidth of 700 Mc has been obtained from a nondegenerate parametric amplifier built to operate at *C* band. This amplifier, utilizing a single silicon-varactor diode, has a measured gain of 13 db and a noise figure of 2.4 db. Band-pass response of the amplifier is shown in Fig. 1; other operating conditions obtained are pictured in Figs. 2–4.

To enhance bandwidth, multituning techniques[1] similar to those used with good success on degenerate parametric amplifiers[2–5] were employed. The approximate equivalent circuit for the signal and idler frequencies is depicted in Fig. 5. The elements used to double-tune the circuit (represented by C_1 and L_1), while not physically located at the diode terminals, do present, to the first approximation, the same impedance function to the terminals. The manner in which the idler susceptance is made to transform into the signal circuit is believed to account for the quadruply tuned response indicated in some of the band-pass sketches. The L_2, C_2 combination was resonant at approximately 8 Gc; this was also the approximate self-resonant frequency of the diode (which had a junction capacitance of 0.63 pf). The pump frequency was approximately 16.6 Gc. The circulator used with the amplifier was a broad-band 3-port circulator with isolation of 25 db and insertion loss of 0.3 db maximum.

Both the unusually large bandwidth and the good noise-figure performance of the amplifier are attributed in part to large C_1/C_0 values, presumably explained by the phenomenon of multiplication of stored carriers.[6] The sensitivity of amplifier gain to pump-power variations is dependent upon circuit adjustments and the value of C_1/C_0 realized. Under most adjustments this amplifier appeared more sensitive to changes in pump power than amplifiers incorporating GaAs diodes. This is believed due to circuit detuning, which is caused by the average capacitance of the silicon varactor being a stronger function of pump power at high C_1/C_0 values than the GaAs varactor.



Fig. 1.



Fig. 3.



Fig. 2.



Fig. 4.



Fig. 5.

The author wishes to thank K. M. Johnson for his many helpful comments and suggestions.

B. T. Vincent, Jr.
Apparatus Div.
Texas Instruments, Inc.
Dallas, Tex.

* Received by the IRE, August 21, 1961. Research sponsored by Bureau of Naval Weapons, Contract No. NOw 61-0283-d.

[1] H. Seidel and G. F. Herman, "Circuit aspects of parametric amplifiers," 1959 IRE WESCON Convention Record, pt. 2, pp. 83–90.
[2] A. G. Little, "A wide-band single-diode parametric amplifier using filter techniques," Proc. IRE, vol. 49, pp. 821–822; April, 1961.
[3] Advertisement, Airborne Instrument Lab., "C-band degenerate parametric amplifier," Proc. IRE, vol. 49, p. 4A; February, 1961.
[4] M. Gilden and G. L. Matthaei, "A nearly optimum wide-band degenerate parametric amplifier," Proc. IRE, vol. 49, pp. 833–834; April, 1961.
[5] B. T. Vincent, "A high-performance *X*-band parametric amplifier," Proc. IRE, vol. 49, pp. 511–512; February, 1961.
[6] K. Siegel, "Comparative figures of merit for available varactor diodes," Proc. IRE, vol. 49, pp. 809–810; April, 1961.

Multiple Reflections of Microwaves Propagating Through a Semiconductor Medium*

In considering the transmission of microwave energy through a semiconductor medium such as high-resistivity germanium or silicon, an analysis has been made of the role of absorption and multiple internal reflections in the medium. In this problem the microwave radiation is assumed to be propagated through three media: air, a semiconductor slab, and air. The physical arrangement is suggested in Fig. 1.

As a result of this study, a new family of devices, useful as modulators, has been suggested. In this case, excess carriers are injected by forward-biased contacts made to the semiconductor. Carrier densities could alternatively be increased by incident light.



Fig. 1—Equivalent circuit for microwave propagation in three media. The regions indicated by the propagation constant and impedance Γ_1 and Z_{01} represent the waveguide in air. The terms Γ_2 and Z_{02} represent the waveguide completely filled with a semiconductor plate, l_2 being the thickness of this plate.

In changing the conductivity of the semiconductor, the transmission, reflection and absorption of carrier-frequency energy can be significantly changed. Modulation experiments have been previously described as well as detailed computer calculations for waveguide and free-space conditions[1] at carrier frequencies of 10,000 Mc.

The results of further calculations at various frequencies have now been tabulated in normalized form and it appears that there may be several dimensionless constants, which having been determined, will allow a simplified design procedure for devices such as described above.

For slightly lossy material ($\sigma \ll \omega\epsilon$) it is well known that at one-half wavelength in thickness maximum transmission is attained. In this case, we refer to the wavelength in the nonlossy medium. In germanium, where $\epsilon_R = 16$, the wavelength in the semiconductor medium is one-fourth the wavelength in air. In a waveguide, the wavelength is further modified and given by

$$\lambda_p = \frac{\lambda_1}{\sqrt{1 - \left(\frac{\lambda_1}{\lambda_0}\right)^2}}, \qquad (1)$$

where λ_p is the wavelength in the medium in the waveguide, λ_1 is the wavelength in the infinite, lossless dielectric and λ_0 is the cutoff wavelength for the waveguide.

What has not been established to date is the role of multiple internal reflections on the phase shift of the transmitted or reflected waves. From the calculated data, if one considers the ratio of the thickness of the semiconductor (medium 2) to the guide wavelength in the lossless medium l_2/λ, constant values exist for which there is no change in the phase of the transmission coefficient E_o/E_{in}. The constant ratios are still maintained even if waveguides are not present, as in the case of air, large area semiconductor plate, and air, if one considers λ as the wavelength in the infinite lossless dielectric medium. This would be useful in the design of devices which provide amplitude modulation with little or no change in phase shift. With respect to the reflection coefficient E_R/E_{in}, other nearly constant values of l_2/λ exist where amplitude modulation can occur with no phase shift. In Table I we see the results of calculations which support the thesis that there are specific critical values of the ratio of thickness of the semiconductor to the wavelength in the lossless medium, where nodes occur such that the phase shift of the reflected wave does not vary even as the conductivity of the semiconductor is varied, and the amplitude of the reflected wave is caused to change. Similarly, at other critical thicknesses, the amplitude of the reflected wave is constant as the conductivity of the material and phase of the reflected wave is changed.

The values have been determined for germanium and silicon in free space and in a waveguide at various frequencies. It is hopefully expected that the constants will hold for all semiconductors in a similar physical arrangement. The range of frequencies for which this effect occurs would be determined as follows. The lower frequency limit would exist at the condition $\sigma \ll \omega\epsilon$. That is, the conductivity must be less than the product of the angular frequency and the permittivity of the dielectric in medium 2. The upper-frequency limit for which the table of constants may be applied depends upon ϵ remaining constant and $\omega\tau \ll 1$, as was assumed in the calculations. Experimental evidence at room temperature indicates that,

TABLE I

NORMALIZED CONSTANTS FOR PROPAGATION OF MICROWAVES THROUGH SEMICONDUCTORS*

Experimental Conditions	A Wavelength in the Medium in Millimeters	B Thickness of Sample for Maximum Change in Attenuation by Transmission per a Unit Change in Conductivity	C Transmission Mode, Thickness for No Phase Shift as Conductivity is Changed	D Reflection Mode, Thickness for No Change in Reflection Amplitude as Conductivity and Reflection-Coefficient Phase is Varied	E Reflection Mode, Thickness for No Change in Reflection Coefficient Phase as Conductivity and Reflection Amplitude is Varied
I. Air, Germanium Slab, Air Unbounded $f=10^{10}$ $(l_2/\lambda)\rightarrow$	7.5	0.5, 1.0, 1.5	0.28, 0.51, 0.64	0.45, 0.64, 1.15	0.32, 0.51, 0.82, 1.0
II. Air, Germanium Slab, Air all in X-Band Waveguide $f=10^{10}$ $(l_2/\lambda)\rightarrow$	7.6	0.5, 1.0, 1.5	0.31, 0.49, 0.76		
III. Air, Silicon Slab, Air Unbounded $f=10^{10}$ $(l_2/\lambda)\rightarrow$	8.6	0.5, 1.0, 1.5	0.31, 0.51, 0.77	0.39, 0.65	0.27, 0.50, 0.76
IV. Air, Silicon Slab, Air all in X-Band Waveguide $f=9.549\times10^{9}$ $(l_2/\lambda)\rightarrow$	9.2	0.5, 1.0, 1.5	0.31, 0.50, 0.77, 1.0		
V. Air, Germanium Slab, Air Unbounded $f=2.4\times10^{10}$ $(l_2/\lambda)\rightarrow$	3.1	0.5, 1.0, 1.5	0.32, 0.50, 0.77		
VI. Best Estimate		0.5, 1.0, 1.5	0.31, 0.50, 0.77, 1.0	0.39, 0.65, 1.15	0.29, 0.50, 0.79, 1.0

* All thickness constants are in terms of l_2/λ. The term l_2 refers to the thickness of the semiconductor plate. For free-space propagation, λ is the wavelength in a large lossless semiconductor plate. In the case of the waveguide filled with the semiconductor, λ is the guide wavelength in the material. The constants are more precise as the conductivity σ becomes smaller.

* Received by the IRE, February 8, 1961; revised manuscript received, July 10, 1961.

[1] H. Jacobs, F. A. Brand, J. D. Meindl, M. Benanti and R. Benjamin, "Some device aspects of multiple microwave reflections in semiconductors," 1960 IRE WESCON CONVENTION RECORD, pt. 3, pp. 42–48.

H. Jacobs, F. A. Brand, J. D. Meindl, M. Benanti and R. Benjamin, "Electrodeless measurement of semiconductor resistivity at microwave frequencies," PROC. IRE, vol. 49, pp. 928–932; May, 1961.

for high-resistivity germanium and silicon, this assumption is generally valid throughout the microwave region[2] with rare exceptions.[3]

Acknowledgments should be made to Dr. Leonard Hatkin and Dr. G. Goubau for theoretical discussions, to Mrs. M. Tate in the application of the computer and calculation of numerical values, and to Charles LoCascio for his part in the experimental work involved in checking parts of the theoretical predictions at the frequency of 10,000 Mc with high-resistivity germanium plates of various thickness.

H. Jacobs
F. A. Brand
J. D. Meindl
U. S. Army Signal Res. and Dev. Lab.
Fort Monmouth, N. J.
R. Benjamin
Monmouth College
West Long Branch, N. J.

[2] A. F. Gibson, "Infrared and microwave modulation using free carriers in semiconductors," *J. Sci. Instr.*, vol. 35, p. 274; August, 1958.
[3] A. C. Baynham, A. F. Gibson and J. W. Granville, "On the dielectric constant of germanium at microwave frequencies," *Proc. Phys. Soc.*, vol. 75, pt. 2, pp. 309–311; February, 1960.

Correlation Optical Radar*

Recently, considerable attention has been given to ranging systems which employ optical masers as pulsed oscillators.[1] To date, the devices have used a fluorescent line in ruby of wavelength 6943 Å (in the visible red) which corresponds to a frequency of about 4.3×10^{14} cps. The standard practice has been to pulse the maser in such fashion that the output is a narrow beam which, as measured, radiates one or a few joules of the desired frequency in a period, typically of order 10^{-4} to 10^{-3} seconds. This energy at the red wavelength corresponds to 10^{19} photons. Of course, a millisecond pulse radar is of rather restricted use but could be considered quasi-CW for many tactical situations. In ruby the light output during this rather long quasi-CW pulse actually consists of many random spikes of about 10^{-7} to 10^{-6} seconds duration. This randomness of the spikes evidences the difficulty in designing a coherent radar, since the spike-to-spike uncertainty allows no single value of phase to be remembered for coherent detection unless it is decided to use one or a few individual spikes. Under these circumstances, the only efficient way to achieve coherent data processing is to delay a portion of the transmitted wave and beat it with the echo before integrating; in short, it is desirable to build a correlation optical radar.

In a correlation optical radar the mixing may occur at photosensitive surfaces illuminated by the diffraction pattern from



Fig 1.

two slits. One slit projects a delayed portion of the emitted light, and the other projects light reflected from targets (Fig. 1). The photosensitive surface will be made up of a mosaic of several segments per fringe. It is easily seen that a change in target range of $\lambda/2$ will reverse positions of light and dark fringes. Thus, two segments per light fringe will detect target motion, and four segments per light fringe will provide information as to increase or decrease in range. It should be pointed out that the scheme could suffer from too much information. For example, with a carrier of 4.3×10^{14} cps, the radar Doppler is about 1.3×10^{6} cps for a 1-mph target. Thus, moving target indication will require more involved processing and detection than microwave radars where display of the Doppler output may require no more than a pair of earphones.

An additional problem will be to provide a low-loss delay mechanism for the replica of the transmitted pulse. Losses here will, at least until better systems are achieved, limit the range more severely than beam spreading—the ultimate limit in ranging systems. One possible storage device for such a radar is a fiber optic waveguide of optical path length equal to the round trip target distance. Present fiber optic waveguide is reported to have losses of nearly 10 db in 20 feet,[2] or round trip (radar) losses of about a db/foot for wavelengths in the visible region. This will be somewhat improved by the actual slowing of the light by the waveguide. However, if we assume 10^{19} photons are available for signal processing at the transmitter, and find that 10^{4} photons are needed to beat the echo, we obviously have a range limited to not much more than 150 feet. The choice of 10^{4} photons is based on the number of quanta required to remove an eightfold uncertainty about the target at the output of the signal processing and integrating circuitry. Thus, a fourfold uncertainty must be resolved to get phase information adequate for velocity determination, that is, to 90°, and a further twofold uncertainty as to the existence of a target must be removed at any given phase. Treating this signal from a wave standpoint requires 8[4] photons.[3] Of these 4×10^{3} photons, 2×10^{3} are from the target and 2×10^{3} are the delayed and attenuated portion of the emitted pulse. Therefore, 10^{4} photons should be adequate, assuming photoelectric surfaces of good quantum efficiency and low system noise. Improving the loss factor by one order of magnitude[4] gives a radar range in the order of 1500 feet, which begins to look interesting tactically. Inserting fiber optic amplifiers[2] or other negative resistances along the delay path will allow for a small increase in range. Our calculations indicate that one or two octaves may be expected if spurious responses produced by reflections in the system are kept to 10 db or more below the desired signal. If the system can be approached from a coded pulse rather than from a quasi-CW basis, the spurious response due to reflections may be reduced by gating the negative resistances. The development of unilateral light amplification will, it is hoped, result in devices limited in range only by the conventional radar range equation.

In summary it is felt that optical maser radars can be built which will accurately measure target velocity as well as range, and which will accomplish this by a coherent radar technique. This method will resemble an interferometer in which one path will be through an optical path in dielectric waveguide of known length. Although the losses in present fiber optics at 6943 Å severely limit range capabilities, it may be possible to develop tactical optical maser radars with ranges of one to a few miles.

M. Katzman
E. Frost
U. S. Army Signal Research and Development Lab.
Fort Monmouth, N. J.

[4] E. Snitzer, "Optical Dielectric Wave-Guides," presented at 2nd Internatl. Conf. on Quantum Electronics, University of California, Berkeley; March 23–25, 1961. (To be published.)

Unidirectional Lower Sideband Parametric Amplifier Without Circulator*

A method is presented of obtaining the characteristics of a traveling-wave parametric amplifier, *i.e.*, matched input and nonreciprocity of amplification, using a structure containing only two variable reactance units operating in the lower sideband mode.[1] A circulator is not required.

The matched input in a negative conductance traveling-wave device can be attributed to the cancellation of the backward waves excited by successive sections of the line. In a lumped structure this can be achieved simply by using a quarter wave separation of the negative conductance units. Fig. 1 illustrates one section of a ladder network matched to a load of $G-G_n$.

The nonreciprocity of a traveling-wave parametric amplifier is determined by the direction in which the pump power is sup-

* Received by the IRE, August 28, 1961.
[1] D. A. Budenhagen, *et al.*, "An experimental Laser ranging system," 1961 IRE International Convention Record, pt. 5, pp. 185–193.

[2] E. Snitzer, "Proposed fiber cavities for optical masers," *J. Appl. Phys.*, vol. 32, pp. 36–39; January, 1961.
[3] D. Gabor, "Communication theory and physics," *Phil. Mag.*, vol. 41, pp. 1161–1187; November, 1950.

* Received by the IRE, July 21, 1961; revised manuscript received. August 29, 1961.
[1] Since this letter was submitted, it has come to the attention of the author that a similar device has been described by L. D. Baldwin, "Nonreciprocal parametric amplifier circuits," Proc. IRE (Correspondence), vol. 49, p. 1075; June, 1961. A somewhat differing layout has also been disclosed independently, by K. H. Locherer and R. Mauer, *Electronics*, vol. 34, p. 21; March, 1961.



Fig. 1—Section of repetitive negative conductance amplifier.



Fig. 2—Unidirectional twin varactor parametric amplifiers. (a) Shunt-tuned parametric units (schematic). (b) Series-tuned parametric units.

plied. The condition that the sum of the propagation coefficients of the signal and the idler waves be equal to that of the pump can usually only be satisfied in one direction. However, if parametric elements are situated at intervals of half the pump wavelength there is no means of sensing the direction of the pump supply. For maximum nonreciprocity with the fewest number of elements, the separation should be a quarter wavelength at the pump frequency, or approximately an eighth of a wavelength at the signal and idler frequencies.

Although similar principles can be used in a twin-diode amplifier, the transition from many diodes to only two is not perfectly straightforward. The difficulty lies in the fact that, ideally, for uniform operation a traveling-wave device should be supplied with power at both the signal and idler terminals. In a multi-element device any unbalance in the supply disappears after a few sections. This obviously does not apply when only two elements are present.

A circuit (and its dual) which gets over the difficulty is illustrated in Fig. 2. Parametric units M_1 and M_2 are represented by two terminal pair junctions with a line dividing the terminal pairs to indicate that frequency conversion takes place between them. It must be understood that these junctions are assumed to contain all the filters and tuning elements necessary for the operation of the amplifier.

To obtain maximum nonreciprocity the pump supply is applied in quadrature to the two units, and the condition that the sum of the phase changes of the signal and the idler should equal that of the pump is satisfied by making the idler phase change zero (*i.e.*, by connecting the two pairs of idler terminals) and by introducing a quarter wave separation at the signal. This arrangement is susceptible to simple analysis and a simple matching procedure because no reactive effects are introduced by the parametric units. The quadrature phase of the signal voltage at the terminals of the parametric units, in conjunction with the quarature phase of the pump, ensure that the idler currents generated in each are in phase for forward propagation and in antiphase for backward propagation (analysis shows that they are equal and opposite in the latter case). The common voltage at the two pairs of idler terminals means that equal current will be supplied to the signal terminals of each unit with a quadrature phase delay, or phase advance, determined by the relative pump phases. Analysis shows that for forward operation the current is of the correct phase to produce amplification and that for reverse operation the current is zero since the idler voltage is zero. The latter result means that the amplifier produces no effect on the backward wave, which passes without amplification or attenuation. The foward wave is amplified, and it is easy to show that equal currents injected in quadrature at a quarter wave interval couple no energy in the reverse direction, and therefore introduce no mismatch. Analysis shows that the amplification is identical to what would be obtained using one of the parametric units as a reflection amplifier on one arm of a circulator with input and output loading of the same characteristic impedance as for the twin diode layout.

It can also be shown that the noise power contributed by losses in the diodes is the same as in the circulator layout. It will be assumed that the noise appears to come from a generator in shunt with the diode with admittance G_t. Noise contributed by the second diode will not be amplified, passing back through the device in the same way as a signal injected in the reverse direction. If the source admittance is G_1 noise current from the first diode, of magnitude $2(kTBG_t)^{1/2}$, is loaded by $2G_1$ when the amplifier is matched, and therefore produces a voltage at the input of $(kTBG_t)^{1/2}/G_1$ compared with the voltage of $(kTB/G_1)^{1/2}$ produced by noise in the input signal (assuming the same temperature). The noise figure is therefore $1+G_t/G_1$ which is the same as for a similar diode in the circulator layout. In single-sideband operation the inevitable idler noise will, of course, also be present.

The amplifier therefore reproduces the behavior of the circulator unit in respect to match, amplification, noise figure, and nonreciprocity, but is inferior in respect to bandwidth because of the frequency sensitivity of the quarter wave line.

Note: Since submitting this note, it has come to the author's attention that a similar device has been described by L. D. Baldwin, "Nonreciprocal parametric amplifier circuits," PROC. IRE (Correspondence), vol. 49, p. 1075; June, 1961. A somewhat differing layout has also been independently disclosed by Locherer and Maurer.[1]

G. H. B. THOMPSON
Standard Telecommunication Labs. Ltd.
London, England

One-Tunnel-Diode Flip-Flop HF Behavior*

In a note by Kaenel[1] and subsequent comments by Flowerday and McKibbin,[2] the one-tunnel-diode flip-flop was discussed. It is the purpose of this paper to offer an analysis of the approximate switching speed of the circuit and thereby show that this type of circuit may be used as a frequency divider with a fixed pulse length output, that is to say, that the normal scale of two divisions associated with a flip-flop will be modified to a much higher value under suitable trigger conditions (Fig. 1).



Fig. 1.

It is assumed that the triggering signal is injected through R_1 long enough to shift the diode from A to P along $\overline{AP}$. The value of L is chosen so that the current i_A remains essentially constant. The equivalent during triggering is then approximately as shown in Fig. 2, so that the voltage across the diode is given by (1).

$$v = v_A + \frac{rv_{in}}{r+R_1}\left\{1-\exp\left\{-\frac{t}{\dfrac{R_1 r}{R_1+r}C}\right\}\right\}$$

$$v_p \geq v \geq v_A. \quad (1)$$



Fig. 2.

In most applications the inequality $R_1 \gg r$ is satisfied, which yields a time constant $\tau = rC$, or a waiting time of about 200 μsec for a fast tunnel diode. After obtaining the peak current the diode will switch. Since the triggering signal is removed the current i will be very nearly i_A so that conditions are given by point B. The characteristic will now be approximated by (2).

$$i = \frac{1}{r'}\quad v - \frac{1}{r'}v_0. \quad (2)$$

* Received by the IRE, August 23, 1961.

[1] R. A. Kaenel, "One-tunnel-diode flip-flop," PROC. IRE (Correspondence), vol. 49, p. 622; March, 1961.

[2] T. W. Flowerday and D. D. McKibbin, "Tunnel diode one-shot and triggered oscillator," PROC. IRE (Correspondence), vol. 49, p. 1315; August, 1961.

This yields a current response of the form:

$$i = \frac{U - v_0}{R + r_1}(1 - \epsilon^{[-(R+r')/L]t}) + i_1\epsilon^{[-(R+r')/L]t}. \quad (3)$$

The relaxation time is therefore controlled by the time constant L/R. The implication is that the sensitivity to the negative voltage reset trigger is modified from $v_C - v_M$ to a value as high as $v_B - v_M$, so that a circuit with a negative input only slightly higher than $v_C - v_M$ will act as a frequency divider. The division ratio for a given input signal depends therefore on the time constant and the amount of input signal.

The assertions of the preceding analysis were tested experimentally with some very fast tunnel diodes. It was found that the circuit operated for frequencies up to 3000 Mc; 100 per cent modulation of the RF input yielded an output which could be used to recover the audio signal. The circuit, with perhaps slight modification, therefore offers the additional uses of RF detector and high scale counter, which indeed is surprising for such a simple arrangement.

HENRY GUCKEL
Digital Computer Lab.
University of Illinois
Urbana, Ill.

Additional Information on "An Interaction Circuit for Traveling-Wave Tubes"*

The purpose of this note is to present several important facts regarding the class of traveling-wave tube interaction structures described by Crepeau and Itzkan.[1] These additional observations are as follows: 1) circuits of the type described by Crepeau and Itzkan can support a multiplicity of propagating modes in the lowest pass band which may interfere with proper circuit operation in linear beam tubes. 2) The Crepeau and Itzkan structures (which might be termed "ring-line" circuits) can be made entirely self-supporting and can also be effectively cooled by the substitution of conducting plates for the wire lines which connect successive rings. The resulting circuits might be called "ring-plane" circuits. 3) Low-velocity circuits of this family can be fabricated conveniently from plane-supported helices ("helix-plane" circuits).

The most crucial observation is the first, the existence of several modes having nearly equal phase velocities in the lowest pass band. Two modes have been observed in circuits similar to the two-wire circuits of Crepeau and Itzkan, three modes in a three-wire version, and so on. These modes were observed in cold tests several years ago at the General Electric Traveling-Wave Tube Product Section and at the University of California at Berkeley.[2] In recent hot tests of an X-band plane-supported helical structure at the University of California, backward-wave oscillation was obtained by interaction with the spatial harmonics of the two distinct modes.

Several members of the plane-supported ring family are shown in Fig. 1. The lowest-order ($n = \frac{1}{2}$) member is the plane-supported ring structure of Fig. 1(a). On this circuit,[3,4] a single mode propagates in the z direction; it has primarily z-directed electric fields having their maximum amplitude at the top of the rings, and a zero amplitude at the plane itself. The angular dependence of the field is $E_z \sim \sin(n\phi)$, where $n = \frac{1}{2}$, and ϕ is the angular coordinate. The next-higher-order plane-supported ring circuit, the $n = 1$ member, is similar in behavior to the ring-line circuit previously mentioned.[1] The circuit, shown in Fig. 1(b), has a vanishing electric field along the support planes which serve both as mechanical supports and as thermal conductors. Two modes have been observed on this circuit [as indicated in Fig. 1(d)], both having an angular dependence $|E_z| \sim |\sin\phi|$. In one mode, both wires at any transverse section are excited in phase, so that predominantly longitudinal electric fields exist between successive rings and on the axis. In the other mode, the "transverse" mode, the two wires at any cross section are oppositely charged, and strong transverse electric fields cross the center of the circuit. In this second mode there are also longitudinal fields between successive rings.



Fig. 1—Several members of the family of plane-supported ring circuits. Axial electric field dependence on the angular coordinate is as sin ($n\phi$). For circuit (a), $n = \frac{1}{2}$; for (b), $n = 1$; for (c), $n = 2$. Fig. 1(d) shows the ω-β diagram for the plane-supported ring ($n = 1$) circuit of Fig. 1(b). The circuit pitch is p, the inside ring diameter is a; the straight line represents propagation at the velocity of light. The transverse and longitudinal modes are represented by curves T and L, respectively.

Support of this general mode picture was obtained at the GE Traveling-Wave Tube Product Section in cold tests of the four-wire structure of Fig. 2. This structure,



Fig. 2—Photograph of a four-ring (or four-ladder) circuit.

when tested without any supporting planes, showed clearly that there were at least three modes closely spaced in frequency; it is possible that a fourth mode went undetected because of the close mode spacing. At certain frequencies, a length of this circuit resonated with strong fields on two opposing slots and zero fields at the centers of the slots on either side of the excited slots. At other frequencies, only three of the four sets of slots were excited, the set nearest the exciting probe being the most strongly excited. These tests indicated the need for great care in measuring propagation characteristics and in evaluating mode suppression schemes applied to these circuits.

The upper cutoff frequency for the longitudinal mode of circuits of this sort can be calculated approximately by assuming that cutoff occurs when the circumferential length of a slot is one-half a free-space wavelength. Such a simple consideration is plausible if one considers these circuits as members of the ladder structure family which obey this rule very well.[5] This family includes the Easitron, on which strong electric fields exist at only the frequency for which the rung length is exactly equal to $\lambda_0/2$, the unsupported slotted plane, the Karp circuit, and the ring structures described here. To be sure, additional inductance in the conducting member which joins successive rings alters the cutoff condition somewhat. However, the entries in Table I show that this simple condition is adequate for estimation of the upper cutoff frequency, and hence, approximation of the ω-β diagram.

* Received by the IRE, April 17, 1961; revised manuscript received, May 1, 1961.

[1] P. J. Crepeau and I. Itzkan, "An interaction circuit for traveling-wave tubes," PROC. IRE (Correspondence), vol. 49, p. 525; February, 1961.

[2] C. K. Birdsall and D. E. Chaffee, work supported in part under contract AF 33(616)6139.

[3] H. Heffner, "Traveling-Wave Amplification of Millimeter Waves," Stanford University, Stanford, Calif., Tech. Rept. No. 51, Contract N6onr251, ERL; July 31, 1952. See especially Fig. 57 for $n = \frac{1}{2}$ circuit.

[4] C. K. Birdsall and T. E. Everhart, "Modified Contra-Wound Helix Circuits for High-Power Traveling-Wave Tubes," Hughes Aircraft Co., Culver City, Calif., Tech. Memo. No. 400; 1955. See especially Fig. 19 for $n = \frac{1}{2}$ circuits; Fig. 14 for $n = 1$ circuits.

[5] R. M. White, C. K. Birdsall, and R. W. Grow, "Multiple ladder circuits for millimeter wavelength traveling-wave tubes," *Proc. Symp. Millimeter Waves*, Brooklyn Polytech. Inst., Brooklyn, N. Y.; March 31–April 2, 1959.

TABLE I

Comparison of calculated and observed upper cutoff frequencies f_c of the longitudinal mode for various ladder-type circuits. Calculated value obtained by assuming the length of the conduction path for one element of the periodic circuit equals $\lambda_0/2$ at the upper cutoff frequency.

Circuit	Reference	Calculated Upper f_c / Observed Upper f_c
Easitron	4	1.00
Plane ladder	4	1.12
Double ring-on-wire	1 [Fig. 2(a)]	1.09
Double ring-on-wire	1 [Fig. 2(b)]	1.08
Double ring-on-wire	1 [Fig. 2(c)]	0.93
Quadruple ring-on-meander line	1 [Fig. 2(d)]	0.83

To summarize, even though these circular ladder structures can support undesired modes of propagation, they still represent an excellent means of making well-cooled and well-supported periodic structures having both a large interaction impedance and a diameter comparable with or larger than $\lambda_0/2$.

R. M. White
Traveling-Wave Product Section
General Electric Co.
Palo Alto, Calif.
C. K. Birdsall
D. E. Chaffee
University of California
Berkeley, Calif.

Authors' Reply[6]

The comments of White, Birdsall, and Chaffee are correct; however, the problem of interfering modes is more acute in circuits with rings connected to planes or straight wires than in circuits with rings connected to meandered wires. Fig. 1(d) shows the transverse and longitudinal modes for rings connected to planes. For rings connected to meander lines, the transverse mode is essentially unaffected, but the upper cutoff frequency of the longitudinal mode is appreciably decreased. [This decrease of the longitudinal mode can be seen by comparing curves (a) and (b) of Fig. 2 in Crepeau and Itzkan.[1]]

In practical traveling-wave tube applications, the interaction circuit is usually surrounded by a cylindrical conducting shell. There is strong coupling between the transverse circuit mode and the TE_{11} circular cylindrical waveguide mode; this is a result of the similarity between the field configurations for these two modes. The coupling raises the lower cutoff frequency of the transverse mode from zero to very nearly that of the TE_{11} cutoff. This is shown in Fig. 3.

The composite transverse electric mode intersects the velocity line for an operating beam at a frequency greater than 1.5 times the upper cutoff of the useful band. This condition makes mode suppression easy, and, in fact, a high-power broad-band tube



Fig. 3—Dispersion curve for ring-loaded meander line with outer conducting shell.

has been operated with absolutely no interference from competing modes.[7]

The essential virtue of the ring-loaded meander line is this freedom from interfering modes. The authors, however, in no way wish to imply that this is an inherent property of all "ring-line" circuits.

P. J. Crepeau
I. Itzkan
Electronic Tube Div.
Sperry Gyroscope Co.
Great Neck, N. Y.

Comments on "Design Theory of Optimum Negative-Resistance Amplifiers"*

In a recent article[1] Kuh and Patterson state in the second paragraph of the Introduction that, prior to their work which was first submitted to the IRE on December 8, 1960, and finally on February 27, 1961, no general theory had been found for the limitations and synthesis of amplifiers incorporating tunnel diodes.

We wish to point out that in this respect they are in error since the three papers,

1) "Network Synthesis with Negative Resistors," by H. J. Carlin and D. C. Youla,
2) "Optimum Negative-Resistance Amplifiers," by D. C. Youla and L. I. Smilen,
3) "Gain Bandwidth Performance of Maximally Flat Negative-Conductance Amplifiers," by E. W. Sard,

which were submitted to the Brooklyn Polytechnic Symposium on Active Networks and Feedback Systems and read April 19–21, 1960, predated their efforts by at least seven months. These later appeared in the published Polytechnic Institute of Brooklyn Symposium Proceedings. Moreover, the paper,

4) "Exact Theory and Synthesis of a Class of Tunnel Diode Amplifiers," by L. I. Smilen and D. C. Youla,

appeared in complete printed form in the *Proc. NEC*, vol. 16, October, 1960, this time predating them by two months.

The second paper quoted gave: 1) A complete, rigorous and systematic account of the gain-bandwidth limitations of amplifiers constructed with either one or many tunnel diodes embedded in a lossless, passive-reciprocal or nonreciprocal environment, together with appropriate synthesis procedures. 2) Exact and explicit formulas were presented for both Butterworth and Tchebycheff insertion-loss characteristics of arbitrary order for both optimum-nonreciprocal and transmission amplifiers employing a single diode. 3) The stability, noise figures and sensitivities of the various configurations were also explicitly determined and discussed.

Some of these results were also obtained by Sard 3) using an entirely different approach.

The NEC paper 4) contains a careful study of the reflection amplifier. Its gain-bandwidth performance is summarized in (133), its noise figure in (147) and (150), and its sensitivity and stability in (161) and (152), and (153), respectively. Again a full account of the associated synthesis procedures is given. Section II of this same paper also includes an exhaustive treatment of the transmission amplifier [Figs. 1(a) and (b)]. Its gain-bandwidth restriction appears in (16), the gains of the Butterworth and Tchebycheff responses in (20) and (23), and the sensitivity and stability formulas in (44), (45), (47), (86) and (88), respectively. The noise figure relations are compactly expressed in (68) and (82). As before, the pertinent synthesis techniques are treated fully.

We also wish to take issue with some of the technical statements which appear in the Kuh-Patterson paper. In their treatment[2] these authors find it necessary to describe their 3-port N_a in terms of a scattering matrix normalized to G_S at port #1, G_L at port #2 and Y_0 at port #3, where Y_0 is an arbitrary passive admittance at their disposal. Then they proceed to assert on the following page that since S_{21a}, S_{31a} and S_{23a} are the scattering coefficients of a lossless network with passive reference admittances, their magnitudes must all be bounded by unity. The normalization technique they employ is implied to be the one developed in their [6]. Unfortunately their assertion is false, as a simple counterexample shows. Let Y be an arbitrary Foster function and y any passive admittance. According to the definition in their [6] [p. 215, (146)], the scattering coefficient s of the lossless 1-port

[6] Received by the IRE, July 14, 1961.

* Received by the IRE, June 21, 1961.

[1] E. S. Kuh and J. D. Patterson, Proc. IRE, pp. 1043–1050; June, 1961.

[2] *Ibid.*, p. 1403, Fig. 2.

[7] C. Burklund, "A broadband megawatt TWT using a ring-loaded meander line interaction circuit," to be published.

Y normalized to y is

$$s = \frac{Y - y}{Y + y}. \tag{1}$$

For $p=jw$ set $Y=jB$ and $y=g+jb$. Then

$$|s(jw)|^2 = \frac{(B-b)^2 + g^2}{(B+b)^2 + g^2}.$$

Clearly, if $B>0$ and $b<0$, $|s(jw)|>1$. Their statement is also incorrect even if Y is passive but not Foster.

Actually, the correct way to normalize is by means of the old and familiar Bode formula,

$$s = \frac{Y - \bar{y}}{Y + y}, \tag{2}$$

where $\bar{y}$ is the complex conjugate of y. A proper normalization procedure for n-ports is also available and automatically leads to a unitary scattering matrix S whenever these structures are lossless.[3] Eq. (1) only succeeds when y is real and positive. Thus the authors' artifice of inserting a parallel-tuned circuit for the purposes of making Y_{33} real (p. 1044) may be dispensed with if it is understood that the normalization has been carried out in the correct manner.

Nevertheless, the entire question of complex normalization may be completely avoided by the simple and natural expedient of lumping the diode parasitic capacitance C in with the 3-port equalizer and normalizing port #1 to G_S, port #2 to G_L and port #3 to $G=1/R$, where $-R$ is the negative resistance appearing in the tunnel-diode equivalent circuit. This leads immediately to the transducer power-gain expression

$$G_T(w^2) = \left| \frac{s_{12}(jw)}{s_{33}(jw)} \right|^2 \tag{3}$$

and involves only magnitudes. Formula (3), which appeared for the first time as (16) in Youla and Smilen [2], p. 250], should be contrasted with Kuh and Patterson's (3), (p. 1044) which is both magnitude and phase sensitive.

Lastly, Kuh and Patterson fail to mention that the main advantage of optimum nonreciprocal over-reciprocal equalization is not the additional gain, which can never exceed 6 db, but the significantly reduced noise figure. It has been shown in Youla and Smilen [2], (160), p. 292] that, for equal load and generator temperatures, $(F_{\text{opt}})_{\text{recip}} = 2(F_{\text{opt}})_{\text{non recip}}$, *i.e.*, a difference of 3 db.

H. J. Carlin
L. I. Smilen
D. C. Youla
Electrophysics Dept.
Polytechnic Inst. of Brooklyn
Brooklyn, N. Y.

Authors' Comment[4]

We wish to thank Carlin, Smilen and Youla for their comments on our paper. The omission of the references is unfortunate. However, some of the results in our paper were disclosed to Professor Carlin in August, 1960, when none of the papers quoted were available. Our paper was first submitted in early September, 1960, to the *Journal of Applied Physics*. The reviewer of *JAP* recommended in December that the paper should be published in PROCEEDINGS OF THE IRE. References 1), 2), and 3) quoted above did not appear until April, 1961.

The paper of Youla and Smilen 2) contains certain results we have obtained. However, the proof of the optimum-gain bandwidth and the synthesis procedures are completely different. We feel that our presentation is simpler, and we include amplifier configurations and synthesis procedures not treated elsewhere.

Their comments on the normalization of the scattering matrix is immaterial as far as the proof of the optimum-gain bandwidth is concerned. The arbitrary passive admittance Y_0 is introduced as one of the reference admittances only in the preliminary step. It is then justified that Y_0 can be made real without losing any generality. The unitary property of the scattering matrix with real reference admittance is used to prove the optimum-gain bandwidth formula. Youla's conjugate impedance normalization would be helpful, but was not needed in the proof.

We appreciate their pointing out the sentence regarding the boundedness of the scattering coefficient as being correct only in terms of the conjugate impedance normalization, but incorrect in terms of the usual impedance normalization.

Finally, following the suggestion of the reviewer, we did not include a section on noise figure. However, it is mentioned in the introduction that, except for the circulator and hybrid types, other amplifiers have large reflection coefficients at the input and output.

E. S. Kuh
J. D. Patterson
Dept. of Elec. Engrg.
University of California
Berkeley, Calif.

Noise in Tunnel-Diode Mixers*

An expression for the noise figure of the tunnel diode mixer, derived by Breitzer,[1] includes the noise of the load conductance of the mixer. It is the aim of this note to modify Breitzer's result and obtain the noise figure of the mixer itself. The results are of interest for the following reasons:

1) Since the noise of the load is only part of the IF amplifier noise, it is often undesirable to count its noise as part of the tunnel diode mixer circuit.

2) Friis' formula for stages in cascade, if it can be applied, uses the noise figure of the mixer itself, not that of the mixer plus the load.

3) Friis' formula cannot be applied if the output conductance g_{out} of the mixer circuit is negative. Nevertheless, it is still not right to ignore the noise of the first IF stage unless the gain of that stage is large.

4) The results can be put in a simple form if $g_{\text{out}}>0$.

The noise figure of the tunnel diode mixer stage itself can be obtained by eliminating the contribution of the load conductance g_L to the noise figure in Breitzer's result.[2] This yields

$$F = 1 + \frac{e}{2kT}\frac{I_{e0}}{g_1^2}\left[g_s + \frac{1}{g_s}(g_0^2 - 2g_0g_1\frac{I_{e1}}{I_{e0}} + g_1^2) + 2(g_0 - g_1\frac{I_{e1}}{I_{e0}})\right]. \tag{1}$$

In (1), e is the electronic charge, k is Boltzmann's constant, T is room temperature, g_s is the source conductance, I_{e0} and I_{e1} are Fourier components of the instantaneous equivalent shot noise current $I_{eq}(t)$, and g_0 and g_1 are Fourier components of the instantaneous conductance $g(t)$ of the tunnel diode, defined by the equations

$$I_{eq}(t) = I_{e0} + 2I_{e1}\cos\omega_h t + 2I_{e2}\cos 2\omega_h t + \cdots \tag{2}$$

$$g(t) = g_0 + 2g_1\cos\omega_h t + 2g_2\cos 2\omega_h t + \cdots. \tag{3}$$

Eq. (1) shows that the correlation between the RF and IF noise currents can either enhance or decrease the noise figure of the mixer depending upon both the magnitude and the sign of the parameters I_{e0}, I_{e1}, g_0 and g_1.[3] Eq. (1) has the minimum value

$$F = F_{\min} = 1 + \frac{e}{2kT}\frac{I_{e0}}{g_1^2}\left[2\sqrt{g_0^2 - 2g_0g_1\frac{I_{e1}}{I_{e0}} + g_1^2} + 2(g_0 - g_1\frac{I_{e1}}{I_{e0}})\right] \tag{4}$$

for

$$g_s^2 = (g_s^2)_{\text{opt}} = g_0^2 - 2g_0g_1\frac{I_{e1}}{I_{e0}} + g_1^2. \tag{5}$$

The right-hand side of (5) is always positive since $I_{eq}(t)>0$ at all times; this implies $|I_{e1}| \le I_{e0}$.

If $g_{\text{out}}>0$, the over-all noise figure F_{tot} of the system can be obtained by Friis' formula

$$F_{\text{tot}} = F_{\min} + \frac{(F_{\text{IF}} - 1)}{G_{\text{av}}}; \tag{6}$$

[2] $g_L = 1/r_2$ in Breitzer's paper. Our (1) can be obtained by omitting the third term of (5) in Breitzer's paper and substituting the notations $I_{e0} = I_{0f} + I_{or}$, $I_{e1} = I_{1f} + I_{1r}$, $g_s = 1/r_1$, $e = q$ and $T = T_1$.

[3] Neglecting the correlation means putting $I_{e1} = 0$; (1) then becomes

$$F = 1 + \frac{e}{2kT}\frac{I_{e0}}{g_s} + \frac{e}{2kT}\frac{I_{e0}}{g_s}\left(\frac{g_s + g_0}{g_1}\right)^2.$$

This equation is identical to (26) of the paper: K. K. N. Chang, G. H. Heilmeier, and H. J. Prager, "Low-noise tunnel-diode down converter having conversion gain," PROC. IRE, vol. 48, pp. 854–858, May, 1960, if this equation is modified as follows:

Omit the noise contributions due to the loss conductances G_1 and G_2 and the load conductance G_L, and substitute $T_0 = T$, $G_g = g_s$, $G_0 = g_0$, $G_{V3} = g_1$ and $G = eI_{e0}/2kT$.

[3] D. C. Youla, "Solution to the Problem of Complex Normalization," Microwave Res. Inst., PIBMRI-891-61; January 30, 1961. Polytechnic Inst. of Brooklyn, N. Y.

[4] Received by the IRE, July 10, 1961.

* Received by the IRE, July 31, 1961.

[1] D. I. Breitzer, "Noise figure of tunnel-diode mixer," PROC. IRE, vol. 48, pp. 935–936; May, 1960.

here F_{IF} is the noise figure of the IF amplifier and G_{av} is the available gain of the mixer. It is difficult to give a general expression for F_{tot} if $g_{out}<0$; especially since one has to satisfy the condition $(g_{out}+g_L)>0$ in that case in order to have stability.

The output conductance g_{out} of the mixer is

$$g_{out} = g_0 - \frac{g_1^2}{g_0 + g_s}, \tag{7}$$

and the power gain of the mixer is

$$G = \frac{4g_s g_L g_1^2}{[(g_0 + g_s)(g_0 + g_L) - g_1^2]^2}. \tag{8}$$

If g_{out} is positive, G can be optimized by putting $g_L=g_{out}$; one then obtains the available gain

$$G_{av} = \frac{g_s}{g_{out}}\left(\frac{g_1}{g_0 + g_s}\right)^2. \tag{9}$$

The conditions $g_s=(g_s)_{opt}$ and $g_{out}>0$ are not always satisfied simultaneously. If one keeps $g_s=(g_s)_{opt}$, the relation $g_{out}>0$ is only satisfied if g_0 and g_1 meet certain requirements.

If $g_1^2>g_0^2$, the mixer circuit is not unconditionally stable, since G can be made infinitely large by proper choice of g_s and g_L. The circuit is unconditionally stable if $g_1^2<g_0^2$ and $g_0>0$; G can then be optimized as a function of g_s and g_L.

The latter is the case for the ordinary diode mixer,[4] for which

$$\frac{I_{c1}}{I_{c0}} = \frac{g_1}{g_0}. \tag{10}$$

The optimized values of F and G,

$$G = G_{max} = \frac{g_1^2/g_0^2}{(1 + \sqrt{1 - g_1^2/g_0^2})^2} \tag{11}$$

$$F = F_{min} = 1 + \frac{e}{2kT}\frac{I_{c0}}{g_1^2}\,2\sqrt{g_0^2 - g_1^2}\cdot\left(1 + \sqrt{1 - \frac{g_1^2}{g_0^2}}\right), \tag{12}$$

are then obtained for

$$g_s = g_L = g_0\sqrt{1 - \frac{g_1^2}{g_0^2}}. \tag{13}$$

It is seen that $G_{max}\leq 1$, since $g_1^2\leq g_0^2$; G_{max} and F_{min} approach unity if g_1^2 approaches g_0^2. This is generally not the case for the tunnel diode mixer because the relation (10) is not satisfied here, so that the condition $|g_1|\rightarrow|g_0|$ does not lead to $F_{min}\rightarrow 1$.

The case $g_{out}<0$ will be dealt with in another paper. A study is under way to determine the influence of the correlation effect on the noise figure.

Very sincere thanks are due Prof. A. van der Ziel for his constant advice and encouragement.

Shih-Fang Lo
Elec. Engrg. Dept
Univ. of Minnesota
Minneapolis, Minn.

[4] A. van der Ziel, "Noise," Prentice-Hall, Inc., Englewood Cliffs, N. J., pp. 247–250; 1954.

Comments on "Tunnel-Diode Microwave Oscillators"*

We have read with great interest the above paper.[1] We would draw attention to an apparent error (printing or otherwise) in (25) and suggest that the imaginary part of this should be rewritten as

$$\left[\tan\beta l_2 + \frac{\{1 - (Z_0/Z_R)^2\}\sin\beta l_1\cos\beta l_1}{(Z_0/Z_R)^2\sin^2\beta l_1 + \cos^2\beta l_1}\right].$$

While initially calculating values for a practical circuit, some rather improbable solutions resulted which lead us to investigate the derivation of (25) and the subsequent realization that the brackets had been omitted from the numerator.

We are indebted, however, to the authors of this paper for their invaluable contribution to this new field of microwave oscillators.

G. Fuller
G. W. H. Wooding
Radar Div.
Elliott Brothers, Ltd.
Rochester, Kent, Eng.

Author's Comment[2]

The authors wish to thank Fuller and Wooding for pointing out the omission of brackets in (25). It should be noted that the correct form of (25) was used in plotting Fig. 14.

Another error occurs in (6): the plus sign before I in the left-hand side of the equation should be changed to a minus sign. This error does not affect the following equations.

We regret any inconvenience which has been caused by these errors.

D. Sterzer
D. E. Nelson
Electron Tube Div.
RCA Labs.
Princeton, N. J.

* Received by the IRE, June 12, 1961.
[1] F. Sterzer and D. E. Nelson, Proc. IRE, vol. 49, pp. 744–753; April, 1961.
[2] Received by the IRE, July 13, 1961.

Gravitational Fields*

Interest in the general theory of relativity has recently been renewed especially since the advent of the artificial earth satellites. It is well-known that there are gravitational analogies to the electromagnetic field in that theory. A recent paper in this journal[1] contains a good survey of the literature and the work done in that field.

However, it is interesting to notice that the gravitational and the "protational" field, obtained by linearizing the equations of the general theory of relativity are not completely analogous to the electric and the magnetic field. Namely, the Maxwell equations cannot be obtained strictly from the general theory of relativity.

Suppose now that the existence of the "protational" field, which may also be called the "antigravitational" field, since it acts in certain cases opposite to the gravitational field, is experimentally established by some means to a certain degree of accuracy. The "protational" field of a moving point mass must have the form

$$\boldsymbol{h} = \frac{1}{c^2}\boldsymbol{v}\times\boldsymbol{g}, \tag{1}$$

where $\boldsymbol{g}$ is the gravitational field. Eq. (1) is completely formally analogous to the Biot-Savart law for the magnetic field. The gravitational field of a point mass is given by the Newton law

$$\boldsymbol{g} = km\frac{\boldsymbol{r}}{r^3}. \tag{2}$$

The sign in this equation is chosen positive intentionally to stress the analogy, and, therefore, different symbols for the gravitational and the "protational" field are used here from those used in the paper mentioned; k is the gravitational constant. The force on a moving mass particle m in the gh field is

$$\boldsymbol{F} = -m'\boldsymbol{g} - m'\boldsymbol{v}'\times\boldsymbol{h}, \tag{3}$$

which is, except for the sign, completely formally analogous to the Lorentz force in the electromagnetic field.

In the case of the mass distribution ρ, we have instead of (1) and (2) the following equivalent field equations:

$$\nabla\cdot\boldsymbol{g} = 4\pi k\rho, \qquad \nabla\times\boldsymbol{h} = \frac{4\pi k}{c^2}\rho\boldsymbol{v}. \tag{4}$$

Provided now that in the general nonstationary case the equation of continuity

$$\frac{\partial\rho}{\partial t} + \nabla(\rho v) = 0 \tag{5}$$

holds, (4) may be generalized for the nonstationary case into the following set of equations:

$$\nabla\times\boldsymbol{h} = \frac{4\pi k}{c^2}\rho\boldsymbol{v} + \frac{1}{c^2}\cdot\frac{\partial\boldsymbol{g}}{\partial t}, \quad \nabla\times\boldsymbol{g} = -\frac{\partial\boldsymbol{h}}{\partial t}, \tag{6}$$

$$\nabla\cdot\boldsymbol{h} = 0 \qquad \nabla\cdot\boldsymbol{g} = 4\pi k\rho,$$

and those are the Maxwell equations for the gh field.

The conclusion from the above is that if someone experimentally proves the existence of the "protational" field, then it will be only the proof of the Maxwell equations, which are already proved for the electromagnetic field. It will not be a sufficient proof of the general validity of the general theory of relativity.

Jovan Djurić
Institute Mihailo Pupin[2]
Belgrade, Yugoslavia

* Received by the IRE, June 30, 1961.
[1] R. L. Forward, "General relativity for the experimentalist," Proc. IRE, vol. 49, pp. 892–904; May, 1961.

[2] On leave of absence 1961–1962; teaching in the Dept. of Elec. Engrg., University of New Mexico, Albuquerque, N. Mex.

The *gh*-Field Theory*

The *gh*-field theory has been defined in a recent communication[1] by the present author. It has been shown there that the *gh* field is defined by the Maxwell equations

$$\nabla \times \boldsymbol{h} = \frac{4\pi k}{c^2}\rho \boldsymbol{v} + \frac{1}{c^2}\cdot\frac{\partial \boldsymbol{g}}{\partial t}, \quad \nabla \times \boldsymbol{g} = -\frac{\partial \boldsymbol{h}}{\partial t}, \tag{1}$$

$$\nabla \cdot \boldsymbol{h} = 0 \qquad \nabla \cdot \boldsymbol{g} = 4\pi k\rho.$$

To these equations boundary conditions must be attached which are formally completely analogous to the boundary conditions of the electromagnetic theory.

It is obvious that the *gh*-field theory is a very close approximation to the classical mechanics and the Newton theory of gravitation with a straightforward physical meaning of all the quantities involved.

We shall now put forward a working hypothesis that light is of the *gh* nature instead of the electromagnetic nature. The consequence of this hypothesis is indeed a striking one.

It must be emphasized that due to the formal identity of the electromagnetic theory and the *gh*-field theory, numerous formulas, but by no means all, from the electromagnetic theory of light can be immediately transferred into the *gh*-field theory of light with a proper change of symbols.

It is well known that the classical electromagnetic theory of light breaks down at the fact that an atom, *e.g.*, a hydrogen atom to take the simplest form, does not radiate light in the stationary state. Even after the introduction of the quantization, that theory cannot explain this fact, unless further assumptions are introduced.

However, if we assume that the introduced hypothesis of the *gh* nature of light is correct, then we immediately arrive at the conclusion that a self-closed system of masses, subject only to internal forces, cannot radiate in a stationary state a time-varying *gh* field, provided that the forces which are acting between the masses of such a system are conservative. For such a system of masses the principle of the conservation of momentum is valid, and if one mass is accelerated in one direction, then the remaining masses are accelerated in the opposite direction to such an extent, so that the net effect is that the total radiation outside will cancel, since the partial radiations which leave the system will be out of phase. A static gravitational field will be observed outside the system, superimposed with an "induction" field which decreases much faster than the gravitational field, so that at a sufficient distance from the system only the static gravitational field will be observable.

A "naively" imagined atom approximates very closely a self-closed system of masses mentioned above, and the conclusion is that such an atom cannot radiate, in its stationary state, a time-varying *gh* field which is presumably light, unless that atom is excited by some external forces. Such a situation is exactly observed experimentally, and this is a direct consequence of the presumed *gh* nature of light. It provides a plausible explanation of a riddle which is a stumbling block in the classical physics, and corroborates the basic hypothesis. It is, however, obvious that the introduction of the quantization into the *gh*-field theory is imperative, if that theory is to be applied to various other problems of light.

It is interesting to point out that the gravitational deflection of light also corroborates the basic hypothesis of the *gh* nature of light. The actual difficulty lies, however, in the fact that even the $\boldsymbol{h}$ field is hypothetical. Nevertheless, the fact that molecules, *i.e.*, matter, radiate light if excited, gives credence to the basic hypothesis. The future research in that direction must give further evidence of the presumed validity, or incogency of the *gh*-field theory of light.

Jovan Djurić
Institute Mihailo Pupin[2]
Belgrade, Yugoslavia

[2] On leave of absence 1961–1962; teaching in the Dept. of Elec. Engrg., University of New Mexico, Albuquerque, N. Mex.

* Received by the IRE, July 26, 1961.

[1] J. Djurić, "Gravitational fields," Proc. IRE (Correspondence), this issue, p. 1689.

X-Band Electronically-Variable Attenuator*

An electronically variable attenuator has been developed and successfully operated in the *X*-band frequency range using a symmetrical stripline structure. The attenuator circuit is illustrated in Fig. 1. It consists of a 3-db branch-line hybrid with a balanced pair of Sylvania 1N832 diodes mounted on arms of equal length. The diodes were matched to a 50-ohm stripline as detectors of 9-kMc energy with no external bias applied. By applying an external bias in the negative direction, the reflection coefficient of the diodes and their power detection can be controlled over a wide range. At a power level of 1 mw, the voltage reflection coefficient of a stripline 1N832 diode mount can be varied from approximately 0 to 90 per cent by varying the external bias from 0 to −3.0 volts. (See Fig. 2.)

The operation of the attenuator of Fig. 1 is as follows:

1) At any bias setting, the reflected energy from the diodes will emerge from Arm 4 if Arms 2 and 3 are equal in length. Thus Arm 1 will be matched at the center frequency of the device.

2) With the control voltage V set to −3.0 V, the diodes are back biased and maximum output signal is obtained at Arm 4. As V is varied from −3.0 to 0 V, the diode reflection decreases, the power absorbed by the diodes increases, and the output signal is attenuated.

The insertion loss of the device at the minimum attenuation setting, *i.e.*, at −3.0 V, is approximately 1 db. The attenuation characteristic of the device at 9 kMc is illustrated in Fig. 3 for input powers of 1.0 and 5.2 mw. A summary of measured data on the attenuator is given in Table I.

The pulse measurement was made using a 9-kMc carrier pulse whose half-power width is 1 nsec. The detection of the pulse is accomplished by the use of a special-purpose sampling oscilloscope.[1] The results of the

* Received by the IRE, July 26, 1961.

[1] A. S. Farber, "Sampling oscilloscope for millimicrosecond pulses at a 30-Mc repetition rate," *Rev. Sci. Instr.*, vol. 31, no. 1, pp. 15–17; January, 1960.



Fig. 1—Attenuator circuit.



Fig. 2—Voltage reflection vs bias.



Fig. 3.

TABLE I

Measured Data on the Attenuator at 9 kMc

Input	Bias Change	Attenuation Range
1-mw CW signal	−3.0 v to 0 v	26 db
5.2-mw CW signal	−3.0 v to 0 v	20 db
1-mw peak pulse (1 nsec)	−3.0 v to +0.12 v	15 db

pulse measurements indicate that the device is usable for at least a 10 per cent bandwidth. In addition, the control voltage can be a very fast waveform since the low-pass filter at the video terminals of the diode mount was designed for transmission of 1-nsec video pulses.

P. L. Fleming
Res. Center IBM Corp.
Yorktown Heights, N. Y.

A Method of Displaying Ultra-Fast Limit Cycles or Three-Parameter Trajectories*

In studying the operation of nonlinear circuits with complex loads, there is often a need for determining trajectories of the instantaneous operating point when the circuit is in a dynamic state. The effects of different device parameters or circuit element values are usually such that computation of the trajectories is extremely tedious and time-consuming without the use of simplifying piece-wise approximations or the use of an electronic computer. Even with the aid of computers, however, it is desirable to check the solutions with experiment. Further, if the trajectories could be determined simply and accurately by experiment, experiment itself could serve as a useful design tool for many cases of interest. This correspondence describes a method of displaying, on an X-Y scope, trajectories for circuits switching as fast as 0.2 nanosecond. This method (Fig. 1) was devised in the course of a study to develop means of accurately predicting switching times of diodes, transistors and tunnel diodes. For present purposes, the method will be illustrated by the specific example of displaying I-V trajectories of a tunnel diode switch.

This author had independently derived the same solutions as Schuller and Gärtner[1] for switching of tunnel diodes, and used the circuitry of Fig. 1 to verify the results. The reader is therefore referred to Schuller and Gärtner's paper for the theory and background for the example to follow. For the same circuit as Fig. 3 of the reference, and conditions between cases 4 and 6 in Fig. 4, the I-V trajectories displayed by the circuit of Fig. 1 are shown in Fig. 2. Here the tunnel diode was pulsed with a triangular waveshape having a base width of 2.5 nsec. Using the methods discussed in the reference and superimposing the static current-voltage characteristics of the tunnel diode, these traces can aid considerably in detailed transient analysis.

An especially useful feature of the newer sampling scopes is the provision for shifting, under direct manual control, a "window" along the sweep and expanding time within the window. Thus one can examine any particular portion of a trajectory down to picosecond times. This is shown in Fig. 2(d)–(f) where the trajectory of Fig. 2(c) is broken into 5-nsec segments to provide a very clear insight into the dynamic processes in the circuit.

William T. Rhoades
Ground Systems Division
Hughes Aircraft Company
Fullerton, Calif.



Fig. 1—Test setup for display of I vs V plot of a tunnel diode.



Fig. 2 Trajectories on a V-I plot. (a) Top curve: current through the diode, 5 ma/cm. Bottom curve: voltage across the diode, 100 mv/cm. Time scale: 5 nsec/cm. The diode inductance was increased to 150 mμh by adding a small inductor to show ringing. Rise time and fall time of applied pulse ≃1 nsec. (b) I (2.5 ma/cm) vs V (100 mv/cm) without inserted inductance. (c) I (2.5 ma/cm) vs V (100 mv/cm) with 150 mμh series diode inductance. (d) I (2.5 ma/cm) vs V (100 mv/cm) for the first 5 nsec, with L = 150 mμh. (e) I (2.5 ma/cm) vs V (100 mv/cm) for the second 5 nsec, with L = 150 mμh. (f) I (2.5 ma/cm) vs V (100 mv/cm) for the third 5 nsec, with L = 150 mμh.

* Received by the IRE, August 25, 1961.

[1] M. Schuller and W. Gärtner, "Large-signal circuit theory for negative-resistance diodes, in particular tunnel diodes," Proc. IRE, vol. 49, pp. 1268–1278; August, 1961.

An Extension of Newtonian Relativity to Include Electromagnetic Phenomena*

The Newtonian relativity, together with the Galilean Transformation (the G.T.), when extended to include electromagnetic phenomena, predicts that the velocity of light with respect to the observer is not always a constant, but instead is a quadratic function of the purely relative velocity of its source. To understand this, we must consider the equivalence of two inertial frames of reference, X and Y, in terms of line elements in a Euclidean 4-space:

$$\delta_{ij}dx^i dx^j = \delta_{ij}dy^i dy^j, \qquad (1)$$

where

$$(\delta_{ij}) = \begin{vmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 1 \end{vmatrix}.$$

On account of the equivalence, the observer can arbitrarily be stationed in either isotropic frame; therefore, let $y_4 = itc/\alpha_{yy}$ and let $x_4 = itc/\alpha_{xy}$, where α_{xy} is to be regarded as a refractive index for light originating in the X frame when viewed by an observer stationary in the Y frame. In accordance with the G.T., and with Newton's definition, the time t is independent of the metrical considerations, and distances are invariant under the transformation.

Now a minimal statement of Poincaré's principle of relativity is that *the relative space of any arbitrarily selected observer whatsoever shall possess only a quadratic optical isotropy.* There is no physical justification for including linear optical effects in this principle, and recently several tests have been suggested whereby this matter may be more closely examined.[1–4] Regardless of the out-

* Received by the IRE, July 18, 1961.

[1] P. M. Rapier, "A proposed test of the constancy of the velocity of light," Proc. IRE (Correspondence), vol. 49, p. 1322; August, 1961.

[2] J. Palacios, "The postulates of a new theory of relativity," *Rev. Roy. Acad. Exact. Sci. Madrid*, vol. 54, pp. 313–330; July, 1960.

[3] M. Ruderfer, "Relativity: blessing or blindfold?" Proc. IRE, vol. 48, pp. 1661–1662; September, 1960.

[4] H. Dingle, "Relativity and electromagnetism: an epistemological appraisal," *Phil. Sci.*, vol. 27, pp. 233–253; July, 1960.

come of these experiments, however, the conditions for quadratic isotropy for the assumed observer in the Y frame must be

$$\sum_{1}^{3} dy_i^2 = 0, \qquad \text{and} \qquad \alpha_{yy} = 1,$$

with the latter requirement necessary because it has been well established that every observer will measure the two-way velocity of light from a source rigidly connected with his frame as the universal constant c. With these substitutions, (1) has a unique solution for the effect of relative motion upon the refractive index of free space

$$\alpha_{xy} = 1/(1 + V^2/c^2)^{1/2}. \tag{2}$$

The velocity of the light received from a relatively moving source, therefore, turns out to be c/α_{xy}, which is not a constant at all, but is a symmetrical quadratic function of the relative velocity. If this quantity is designated by C_{mn}, where m and n are dummy indices, (2) becomes

$$\alpha_{mn} = \alpha_{nm} = (1 - V^2/C^2_{mn})^{1/2}, \tag{3}$$

so that when m equals n, α_{mn} equals unity.

Now under the Lorentz Transformation, (the L.T.), α_{mn} is written as $(1-v^2/c^2)^{1/2}$, wherein v/c should have been written V/C_{mn}, or $V\alpha_{mn}/c$. Hence, it turns out that v, the relativistic velocity appearing in Einstein's equations, actually equals $V\alpha_{mn}$; since by definition of a velocity, $V \equiv dX/dt$, it follows that $v \equiv \alpha_{mn} dX/dt$, which is not a velocity at all, but is simply a mathematical abstraction.[4] Therefore, one result of the L.T. is to cause real physical quantities to appear as variants and purely abstract notions to appear as invariants in the physical equations. This might appear to be good mathematics, but it is certainly not good physics. In any satisfactory physical theory, we expect only those quantities to be invariant that have an objective significance, *e.g.*, that can be identified directly with the real properties of real bodies.

If we let β_{mn} equal V/C_{mn}, we can employ the 4-vector addition of velocities, *viz*,

$$\beta_{xz} = (\beta_{xy} + \beta_{yz})/(1 + \beta_{xy}\beta_{yz}), \tag{4}$$

whereby a single G.T. takes the place of two separate ones. This theorem explains at once Fizeau's results with moving liquids, Fresnel's dragging coefficient, $1/n^2$, and Airy's experiment. In the case of Ruderfer's experiment,[5] Townes' maser experiment,[6] and the Michelson-Morley experiments, the apparatus is moving along in space with the observer with an absolute velocity

$$\left(\sum_{1}^{3} dy_i^2 \right)^{1/2} / dt.$$

However, because of the isotropy of this frame we have already seen that

$$\sum_{1}^{3} dy_i^2$$

equals zero. Since this is a vector, it vanishes identically in all coordinate systems, along with all effects of the absolute motion on the apparatus. For these, and for all similar experiments, Newtonian relativity predicts precisely null results.

An important consequence of the principle of relativity presented herein is that it requires the existence of an aether which has a velocity-dependent index of refraction. The principle also admits the possibility that relative space may be linearly anisotropic with respect to the propagation of electromagnetic waves. Thus, experiments yielding first-order positive results, such as the Sagnac experiment, the aberration of starlight, Courvoisier's observations,[3] and the Pound-Rebka experiments,[7] which contradict Einstein's principle, are explained under Newtonian concepts in a classical manner. It is obvious from the foregoing discussion that the concepts presented herein do not admit the possibility of "action at a distance." Finally, they do not pretend to explain everything upon the elusive basis of two mutually contradictory postulates, as is the fad with modern theoreticians, but instead possess an inner consistency that renders them completely free from paradoxes.

The basic consequence that the velocity of light in the aether is a quadratic function of the relative velocity of its source has only recently been verified in a series of experiments by electronic techniques that will be the subject of a separate communication.

Pascal M. Rapier
Newtonian Science Found.
Richmond, Calif.

[5] M. Ruderfer, "First order terrestrial ether drift experiment," *Phys. Rev. Lett.*, vol. 5, pp. 191–192; September 1, 1960.
[6] C. H. Townes and J. Cedarholm, "A new experimental test of special relativity," *Nature*, vol. 184, pp. 1350–1351; October 31, 1959.
[7] C. W. Sherwin, "Some recent experimental tests of the clock paradox," *Phys. Rev.*, vol. 120, pp. 17–21; October 1, 1960.

Maser Terminology*

I would like to suggest a change in terminology for stimulated emission devices. Since devices operating in the optical and infrared spectra have been demonstrated recently, the terminology has become unwieldy and confusion reigns. At present there are masers, mosers, losers, lasers, irasers, presumably irosers, optical masers, infrared masers, etc., ad infinitum.

Since the term *maser* represents *M*icrowave *A*mplification by *S*timulated *E*mission of *R*adiation, it is a mistake to designate a device which does not amplify and does not operate in the microwave spectrum an *optical maser*. The term *loser* has been objectionable because no one wants to *lose*. In addition to these objections it would be much better to have a common name for devices which are identical in principle.

I believe the following names would be comprehensive enough to cover the entire group of devices, would be simple, and would show enough similarity to present terminology to permit recognition by persons not yet acquainted with the change.

E″ma′ser for *E*lectro*m*agnetic *a*mplification by *s*timulated *e*mission of *r*adiation.
E″mo′ser for *E*lectro*m*agnetic *o*scillation by *s*timulated *e*mission of *r*adiation
Or, to misquote Dr. A. L. Schawlow, Emaser can represent "*E*xtensive *m*oney *a*cquisition *s*chemes for *e*xpensive *r*esearch."

William R. Mallory
G.E. Advanced Electronics Ctr.
Ithaca, N. Y.

* Received by the IRE, July 26, 1961.

Technique for Amplitude Modulating a Van Atta Radar Reflector*

In Bauer's recent communication,[1] he discussed the possibility of designing a satellite which, through use of a Van Atta radar reflector and radar absorber material, would be undetectable by enemy radars. At the same time, this satellite could be tracked by friendly radars through illumination "with the appropriate coded signal which would be answered by coding the modulation of the Van Atta array. During the time when no interrogation was being effected the array would be biased to a zero state to reduce the radar cross section to a minimum."

The analysis of amplitude modulation of the reflector concerned itself with a monostatic radar illuminating the array from an arbitrary direction. By varying phase shift in the interconnecting transmission lines of the array, one can modulate the signal reradiated in the direction of the illuminating radar. The modulation is in fact the result of varying the direction of the reradiated signal and not its total energy. While it is easy to adjust phase shift so that monostatic echo in a given direction is minimized, it is impossible to do this for all incidence angles simultaneously. Unless energy incident on the array was absorbed in some manner, it always would be possible to choose positions for an illuminating radar which would provide the radar with the maximum echo of which the array was capable.

William F. Bahret
Reconnaissance Laboratory
Aeronautical Systems Div.
Wright-Patterson AFB, Ohio

* Received by the IRE, May 3, 1961.
[1] L. H. Bauer, Proc. IRE (Correspondence), vol. 49, pp. 634–635; March, 1961.

Some Ladder Networks Representing Certain Transcendental Numbers—Classroom Note*

The numerical computation of important irrational and transcendental numbers such as $\sqrt{2}$, π, e and Log 2 has been the subject of historical mathematical investigations. It may be of some recreational and possibly practical interest to scientists and engineers to suggest sequences of simple resistive circuits whose resistances asymptotically approach the values of such numbers.

For an applied voltage of 1 volt, the input current of the circuit of Fig. 1, asympotically approaches the value of $1\sqrt{2}$ amperes if a larger and larger number of ladder sections are considered.

Similarly, the input resistances of the networks in Figs. 2–4 approach the values of $\pi/2$, e and Log 2, respectively. In all four cases, appropriate continued fractions have been chosen leading to familiar grounded ladder circuits. It was thought that the suggested network realization might be considered as an electrical engineering method for the evaluation of these basic numbers. The students in a laboratory course, for instance, may find this an interesting exercise. In each of the given four cases, the mathematical computation involved is rather trivial, but it can be further pursued by referring to classical work on continued fractions.[1,2] The derivation of the foregoing expansions are given in Wall or Perron. Admittedly, we have selected expansions leading to resistive grounded ladder with simple numerical values for resistors. No effort has been made to arrive at particularly rapidly converging resistive structures. This can be done by selecting faster converging expansions if so desired.

The more enthusiastic reader may wish to pursue this matter further by synthesizing other well-known expansions in resistor-capacitor or resistor-inductor ladder



Fig. 1— $\sqrt{2} = 1 + \cfrac{1}{2 + \cfrac{1}{2 + \cfrac{1}{2 + \cdots}}}$



Fig. 2— $\dfrac{\pi}{2} = 1 + \cfrac{1}{1 + \cfrac{1.2}{1 + \cfrac{2.3}{1 + \cfrac{3.4}{1 + \cdots}}}}$



Fig. 3— $e = 2 + \cfrac{2}{2 + \cfrac{3}{3 + \cfrac{4}{4 + \cfrac{5}{5 + \cdots}}}}$



Fig. 4— $\log 2 = \cfrac{1}{1 + \cfrac{1}{1 + \cfrac{4}{1 + \cfrac{9}{1 + \cfrac{16}{1 + \cdots}}}}}$

circuits. The following expansions are cited for those who wish to undertake such exercises. The pertinent mathematical discussions (convergence, etc.) can be found in Wall.[1]

F. Reza
Dept. of Elec. Engrg.
Syracuse University
Syracuse, N. Y.

* Received by the IRE, July 26, 1961.

[1] H. S. Wall, "Analytic Theory of Continued Fractions," D. Van Nostrand Co., Inc., New York, N. Y.; 1948.

[2] O. Perron, "Die Lehre von den Kettenbrüchen," B. G. Teubner, Leipzig and Berlin, Ger., 2nd ed.; 1929.

$$\log(1+s) = \cfrac{s}{1 + \cfrac{1^2 s}{2 + \cfrac{1^2 s}{3 + \cfrac{2^2 s}{4 + \cfrac{2^2 s}{5 + \cfrac{3^2 s}{6 + \cdots}}}}}}$$

$$\int_0^\infty \frac{e^{-u}\,du}{(1+su)^a} = \cfrac{1}{1 + \cfrac{as}{1 + \cfrac{1 \cdot s}{1 + \cfrac{(a+1)s}{1 + \cfrac{2 \cdot s}{1 + \cfrac{(a+2)s}{1 + \cfrac{3 \cdot s}{1 + \cdots}}}}}}}$$

Performance Degradation of Linear FM-Pulse-Compression Systems Due to the Doppler Effect*

In a recent correspondence[1] Cook has presented an analysis of linear FM pulse compression. It is possible to perform a similar analysis based on a more exact model of the Doppler effect. In doing so, a fundamental limitation of the linear FM pulse-compression technique becomes apparent.

Using the transmitted waveform as it leaves the antenna for phase and time reference, one can write for the transmitted waveform

$$S(\omega) = \text{rect}\,\frac{\omega - \omega_c}{\Omega} \exp j[a(\omega - \omega_c)^2]. \quad (1)$$

In (1), rect $(\omega - \omega_c/\Omega)$ denotes a rectangular amplitude spectrum centered around ω_c having a bandwidth Ω. The corresponding phase-matched[2] filter (the compression filter) is described by

$$F(\omega) = \text{rect}\,\frac{\omega - \omega_c}{(1+\epsilon)\Omega} \cdot \exp j[b_0 + b_1(\omega - \omega_c) - a(\omega - \omega_c)^2]. \quad (2)$$

The factor $1+\epsilon$ implies that the phase-matched filter is wide enough to accept Doppler-shifted signals without reducing the signal bandwidth.

When a moving target is radar-illuminated, each frequency component in the transmitted waveform suffers a frequency shift due to the Doppler effect. A frequency ω is, upon return, observed as a frequency

$$\omega \frac{1 + \nu/2}{1 - \nu/2}.$$

The quantity ν equals $2v_r/c$, where v_r is the relative velocity between radar and target along their connecting line and c is the speed of light. The expression given above for the Doppler-shifted return is exact except for relativistic effects. Since ν, however, is always much smaller than 1 even for orbital velocities, one can write for the Doppler effect, $\omega(1+\nu)$ or, as well, $\omega/(1-\nu)$. In many cases it is sufficient to treat the return as if it were translated in frequency by an amount $\omega_d = \nu\omega_c$, the Doppler shift of the center frequency. This was the procedure used by Cook. The present analysis takes into account that in fact each frequency component is shifted by an amount $\nu\omega$, and thus an expression for the radar return from a moving target is

* Received by the IRE, July 14, 1961; revised manuscript received, July 25, 1961.

[1] C. E. Cook, "General matched-filter analysis of linear FM-pulse compression," Proc. IRE (Correspondence), vol. 49, p. 831; April, 1961.

[2] H. O. Ramp and E. R. Wingrove "Principles of pulse compression," IRE Trans. on Military Electronics, vol. MIL-5, pp. 109–116; April, 1961.

$$R(\omega) = \text{rect}\,\frac{(1-\nu)\omega-\omega_c}{\Omega}\cdot\exp j\{c_0+c_1[(1-\nu)\omega-\omega_c]+a[(1-\nu)\omega-\omega_c]^2\}. \quad (3)$$

The output, given by $R(\omega)\cdot F(\omega)$, is

$$0(\omega) = \text{rect}\,\frac{\omega-(1+\nu)\omega_c}{(1+\nu)\Omega}\cdot\exp j\{d_0-d_1\omega_c+(d_1-c_1\nu+2a\nu\omega_c)\omega-a\nu(2-\nu)\omega^2\}, \quad (4)$$

where $d_0=b_0+c_0$ and $d_1=b_1+c_1$. Interpreting (4), one finds that

1) The center frequency of the output spectrum is $(1+\nu)\omega_c$, compared to $(1+\nu/2)\omega_c$ in Cook's treatment. This difference occurs because different receiving filter bandwidths were assumed in each case.
2) The bandwidth of the signal has changed to $(1+\nu)\Omega$, *i.e.*, is wider or narrower, depending on the sign of ν (ν is positive for decreasing range, negative for increasing range).
3) The constant phase is the same as in the case of a stationary target.
4) The coefficient of the linear term, $(d_1-c_1\nu+2a\nu\omega_c)$, gives the position of the output signal on the time axis. In particular d_1 is the round-trip time to target plus phase-matched filter delay and $-c_1\nu$ is a range- and velocity-dependent time shift, encountered with any radar waveform. The latter term is very small and can for all practical purposes be neglected. The term $2a\nu\omega_c$ is a time shift dependent on the waveform parameters and carrier-frequency Doppler shift. This shift is typical for linear FM pulse-compression systems and was also noted by Cook.
5) The last term, $-a\nu(2-\nu)\omega^2$, is of particular interest. It indicates that a phase-slope dispersion[2] exists in the output signal. A consequence of this dispersion is a widening of the output pulse, *i.e.*, the output pulse due to a moving target is wider than the output pulse due to a stationary target.

Time did not permit continuing the above analysis to obtain the pulse widening quantitatively. An estimate can be obtained quickly, however, by performing a similar analysis[3] starting with a transmitted waveform having a Gaussian-amplitude spectrum and parabolic-phase spectrum $S(\omega)$, with corresponding phase-matched filter response $F(\omega)$; thus

$$S(\omega) = e^{-b\omega^2}e^{ja\omega^2}$$

$$F(\omega) = \text{rect}\,\frac{\omega}{(1+\epsilon)\Omega}\,e^{-ja\omega^2}. \quad (5)$$

The analysis yields a compressed pulse length (between $1/e$-points) of

$$\bar{\tau} = 4\sqrt{b}\,\sqrt{1+\left(\nu\,\frac{\pi K}{2}\right)^2}, \quad (6)$$

where $2\pi K=T\cdot\Omega$, with T and Ω the phase-slope dispersion and bandwidth of $S(\omega)$ between $1/e$-points. Investigation of (6) shows the following: 1) $4\sqrt{b}$ is the shortest possible output pulse length and is obtained in case of ideal pulse compression, *i.e.*, for $\nu=0$. 2) The pulse widening factor,

$$w = \sqrt{1+\left(\nu\,\frac{\pi K}{2}\right)^2} \quad (7)$$

depends, as expected, on ν; furthermore, it depends on only one more variable K, the compression ratio.

Eq. (7) can be used to obtain numerical values for the pulse widening due to the dispersive effects of target velocity. Assuming the case of two earth orbiting vehicles on collision course, v_r can approach 31,000 knots, *i.e.*, ν becomes 10^{-4}. For this speed and a compression ratio $K=10{,}000$, the pulse widening factor is found to be 1.87. This means the actual compression ratio is $K_{act}=5900$, which is a sizeable reduction from the original $K=10{,}000$. With the pulse widening there also occurs an amplitude reduction, thus the SNR is reduced. This numerical example is based on a special waveform, but for other linear FM waveforms widening effects of the same order of magnitude can be expected.

The above analysis shows that a degradation of the performance of linear FM pulse-compression systems takes place when moving targets are illuminated. The degradation, which is in form of a pulse widening and loss in SNR is minor for present-day systems and targets. However, for advanced pulse-compression systems in a space environment, the degradation can become serious.

H. O. Ramp
E. R. Wingrove, Jr.
Electronics Lab.
General Electric Co.
Syracuse, N. Y.

Doppler-Shift Effects in Space Propagation*

Space propagation involves propagation within an ionosphere for great distances. Unlike common experience, however, the ionosphere is the ionosphere of the sun, and the ion and electron concentration is very low near the earth's orbit.

"Steady-state" propagation in this type of field has been examined in several papers.[1] This note examines approximately the effect of non-steady-state conditions on Doppler shift to obtain an estimate of the magnitude of possible effects. The non-steady-state conditions may result from a change in electron concentration, or from the motion of a plasma stream, or from both, these being characteristic of disturbed solar conditions.

The dielectric constant in the presence of free electrons is

$$k^2 = 1 - \frac{81N}{f^2} \quad (1)$$

where N=concentration, electrons per cc, f=frequency, kc. The phase of a radio signal at a receiver, referred to the transmitter, is

$$\varphi_r = \omega t - \frac{2\pi}{\lambda_0}\int_T^R k\,ds, \quad (2)$$

where ω=transmitter frequency, and λ_0=vacuum wavelength.

The instantaneous received frequency is

$$2\pi f_r = \frac{d\phi_r}{dt} = \omega - \frac{2\pi}{\lambda_0}\frac{d}{dt}\left(\int_T^R k\,ds\right), \quad (3)$$

which may be written as

$$\frac{\Delta f}{f} = \frac{1}{C}\frac{d}{dt}\left(\int_T^R k\,dx\right) \quad (4)$$

for straight-line propagation. R and T are receiver and transmitter locations. C is the velocity of light.

In order to evaluate this expression, consider several specific cases.

Case 1): Moving constant-width and constant-density electron cloud between R and T. Let x_1, x_2 be the boundaries of the cloud. Then (4) becomes

$$\frac{\Delta f}{f}=\frac{1}{C}\frac{d}{dt}\left[\int_T^{x_1}dx+\int_{x_2}^{x_2}k\,dx+\int_{x_0}^{R}dx\right]\cdot \quad (5)$$

Since the sum of the first and last terms is constant, and the middle term is also constant, there is no Doppler shift.

Case 2): Moving constant-density electron cloud surrounding R. Let x be the position of the edge of the cloud. Then (4) may be written as

$$\frac{\Delta f}{f} = \frac{1}{C}\frac{d}{dt}\left[\int_T^x dx+\int_x^R k\,dx\right]\cdot \quad (6)$$

The magnitude of the term in brackets changes linearly with the velocity of the edge of the cloud, the slope being equal to $(1-k)$. Therefore,

$$\frac{\Delta f}{f} = \frac{1}{C}\,(1-k)\,\frac{dx}{dt}. \quad (7)$$

Case 3): Stationary, constant-width cloud of variable density. In this case the middle term in brackets of (5) is not a constant, and (5) becomes

$$\frac{\Delta f}{f} = \frac{1}{C}\,(x_2-x_1)\,\frac{dk}{dt} \quad (8)$$

$$= \frac{x_2-x_1}{C}\cdot\frac{81}{2f^2}\cdot\frac{dN}{dt}. \quad (9)$$

Case 4): Expanding cloud of constant density between R and T. This can be evaluated by assuming that an auxiliary receiver-transmitter unit is located at the center of the cloud. Then, assuming that both edges are moving at the same rate,

$$\frac{\Delta f}{f} = \frac{2}{C}\,(1-k)\,\frac{dx}{dt}. \quad (10)$$

Case 5): An electron cloud expanding so that the total number of electrons is con-

[2] H. A. Wheeler, "The solution of unsymmetrical-sideband problems with the aid of the zero-frequency carrier," Proc. IRE, vol. 29, pp. 446–458; August, 1941.

* Received by the IRE, July 26, 1961.

[1] C. N. Lee, "Space-to-space propagation phenomena," in "Advances in Astronautical Sciences," vol. 3, Plenum Press, New York, N. Y.; 1958.
G. Kuiper, "The Sun," University of Chicago Press, Chicago, Ill.; 1953.

stant. This may be solved by introducing the linear assumption

$$\Delta f \text{ (total)} = \Delta f \text{ (width change)} + \Delta f \text{ (density change)}, \quad (11)$$

which combines cases 2) and 3).

The magnitude of these effects is of interest. Assume that

$f = 10^3$ kc
$N = 1000$ electrons/cc
$dN/dt = 1$ electron/sec
$x_2 - x_1 = 300{,}000$ km
$C = 300{,}000$ km/sec
$dx/dt = 50$ km/sec.

Then the Doppler shifts for the various cases are

Case 1) $f = 0$ cps
Case 2) $f = 70$ cps
Case 3) $f = 40$ cps
Case 4) $f = 140$ cps
Case 5) $f = 110$ cps.

These appear to be negligible, except in single-sideband transmission, or in precision tracking. Closer to the sun, where the electron concentration is greater and the gas clouds move more rapidly, the various effects of changes in the propagation medium would appear to become very important in most modes of communication.

R. P. Haviland
Missile and Space Vehicle Dept.
General Electric Co.
Philadelphia, Pa.

Comment on Shot-Noise Smoothing Mechanism Proposed by LaRosa and Wilhelmsen*

In a recent note to this department,[1] La Rosa and Wilhelmsen (L. and W.) advance a theory of noise smoothing in tunnel diodes. The theory is based on the argument that the tunneling probability p is approximately $\frac{1}{2}$, and therefore a binomial rather than a Poisson distribution should be used to describe the number of electrons tunneling during an interval of observation $(0, T)$. This change in distribution leads, according to L. and W., to a reduction of shot noise by a factor of $(1-p) \approx \frac{1}{2}$.

Although noise measurements of tunnel diodes[2,3] show full shot noise, the possibility of reduced shot noise would be of great theoretical and practical interest. We therefore wish to present arguments that the mechanism suggested by L. and W. will not lead to shot noise smoothing.

Consider an electron in the conduction band; it is rapidly being scattered by its interaction with the lattice, and every so often its momentum, after a scattering process, is such as to permit it to tunnel. In this manner we may speak of the electron impinging on the barrier so many times per second. Now if the probability of tunneling is of the order of $\frac{1}{2}$, as suggested by L. and W., then a binomial distribution is indeed appropriate to describe the number of successes resulting from a given number of trials. Unfortunately, measurement of the current is only sensitive to the number of successes in a given interval of observation, and we have no way of knowing how many failures there were or when they occurred. To observe the second moment of the binomial distribution, as suggested by L. and W., would require that this knowledge of the total number of trials at least be implicit in the measurement.

The quantity from which the power spectrum is correctly obtained is the correlation function of the current

$$\psi(\tau) = \langle I(t) I(t+\tau) \rangle.$$

Then, making the usual assumption that the current may be expressed as a superposition of impulses occuring independently at random times t_i,

$$I(t) = \sum_i F(t - t_i),$$

and if we also assume that the probability of the occurrence of an impulse in the interval dt is a constant independent of the time, it can be shown that[4]

$$\psi(\tau) = \nu \int_{-\infty}^{\infty} F(t) F(t+\tau) dt.$$

This expression for the correlation function[5] involves an average over the arrival times of the impulses and an average over the distribution of the number of impulses arriving in an interval of observation $(0, T)$. It should be noted that these assumptions are sufficient to determine uniquely a Poisson sequence for the times t_i. We now observe that only the first moment ν (the average number of particles per second) appears, and that white noise will be observed up to frequencies comparable to the inverse width of a current pulse.

It is consistent with the present view of direct tunneling processes that individual pulses should be uncorrelated (*i.e.*, the times t_i) for "intervals" much greater than the dielectric relaxation time of the semiconductor material. By "interval" we mean the time between successive particles within a volume where the space charge of a particle which has just made a tunneling transition will alter appreciably the tunneling probability of the succeeding particle.

It is now apparent that for independent tunneling events, full shot noise will be observed regardless of the magnitude of the tunneling probability[6] p. A large value of p can only lead to reduced noise insofar as it might induce a correlation between the times t_i; for example, the "interval" between particles may become comparable to the dielectric relaxation times.

An exception to these remarks probably should be made for "excess" current where tunneling involves intermediate states. Associated with this type of tunneling transition, time constants of the order of 10^{-8} to 10^{-9} seconds have been observed.[7] At frequencies whose periods are equal to or less than these time constants, something less than full shot noise might be observed, depending, of course, on the nature of the correlation between successive events which is associated with these time constants.

The authors wish to thank H. C. Montgomery and J. P. Gordon for helpful discussions.

C. A. Lee
A. Yariv
Bell Telephone Labs.
Murray Hill, N. J.

* Received by the IRE, April 11, 1961.

[1] R. La Rosa and C. R. Wilhelmsen, "Theoretical justification for shot-noise smoothing in the Esaki diode," Proc. IRE (Correspondence), vol. 48, p. 1903; November, 1960.

[2] J. Tieman, "Shot noise in tunnel diode amplifiers," Proc. IRE, vol. 48, pp. 1418–1423; August, 1960.

[3] C. A. Lee and H. Montgomery, *Bull. Am. Phys. Soc.*, vol. 5, p. 160; 1960.

[4] S. O. Rice, *Bell Sys. Tech. J.*, vol. 23, pp. 282–332; July, 1944.

[5] The term giving the dc power has been neglected.

[6] Estimates of the tunneling probability for the types of junctions described in the literature are many orders of magnitude less than 1/2.

[7] F. F. Fang, paper presented at Symp. on Electron Tunneling in Solids, Philadelphia, Pa.; January, 1961 (unpublished). A symposium report by E. O. Kane is to be published which contains Fang's remarks.

Vacuum-Tube Networks*

Some years after the paper by Llewellyn and Peterson under the above title was published,[1] I discovered an error in the equation for the anode current in a triode. At my suggestion, the senior author reviewed the derivation and found himself in agreement with my result. At that time I was outlining a paper in which the equation questioned would be used, and by agreement with Dr. Llewellyn the error was to be pointed out in my paper and the revised expression employed. The paper became too long, and before publication it was shortened by omitting any discussion of transit time effects. Meanwhile, my intention of calling attention to the necessary change was forgotten.

In view of the continued basic importance of the Llewellyn-Peterson paper, the equation mentioned should be corrected. Reference is to the last term in the denominator of (50a). As published, this is

$$-\zeta_2 \left(1 - \frac{\theta_2}{2\theta_1} + \frac{\theta_1}{2\theta_2}\right),$$

but should be

$$-\frac{\zeta_2}{2\theta_1\theta_2}(\theta_1 + \theta_2)^2.$$

The meanings of the letter symbols are the same as in the original paper.

George D. O'Neill
General Telephone & Electronics Labs. Inc.
Bayside, N. Y.

* Received by the IRE, August 10, 1961.

[1] F. B. Llewellyn and L. C. Peterson, "Vacuum-tube networks," Proc. IRE, vol. 32, pp. 144–166; March, 1944.

Flow Graphs and Tapered Transmission Lines*

If a transmission line with continuous taper is approximated by a cascade of short, separately uniform segments, the determination of the reflection coefficient is a problem in linear algebra; hence, the signal flow-graph technique[1] may be applied. In this instance, as in so many others, the flow graph reveals the "structure" of the problem clearly.

Suppose that a continuously nonuniform transmission line is approximated by a line with n uniform segments. The jth segment, centered at x_j, is to have a uniform characteristic impedance Z_j equal to $Z(x_j)$ of the original line. The reflection coefficient $r_{j,j+1}$ between the jth and $j+1$st segments is obtained from the Fresnel reflection formula

$$r_{j,j+1} = \frac{Z_{j+1} - Z_j}{Z_{j+1} + Z_j} \tag{1}$$

which, for short segments and moderate taper, becomes

$$r_{j,j+1} \cong \frac{\Delta Z_j}{2Z_j}. \tag{2}$$

The phase change across the jth segment is given by

$$\exp\{-\gamma_j(x_{j+1} - x_j)\} = \exp\{-\gamma_j \Delta_j x\}, \tag{3}$$

The behavior of a cascade of uniform segments is described by a set of linear simultaneous equations relating the forward and backward wave values at the segment boundaries. The signal flow-graph representation of this set of equations is shown in Fig. 1.

This graph may be simplified by noting that all "looped" paths (those which pass through any node more than once) are at least two orders higher in the reflection coefficients than the "direct" paths. Under the assumption that $|r_{jk}| \ll 1$, the looped paths may be ignored, which means that all of the upward-pointing transmittances may be removed. The resulting simplified graph is shown in Fig. 2.

The over-all reflection coefficient for n uniform segments,

$$R_n = \frac{E_g^-}{E_g^+}. \tag{4}$$

is found by summing all possible paths in Fig. 2 from node E_g^+ to node E_g^-. For this situation a further simplification of the graph is obtained by noting that every path except r_{01} involves at least one pair of transmittances of the form $1+r_{jk}$ (going across the top of the graph) and $1-r_{jk}$ (coming back across the bottom). Since these transmittances occur in pairs, whose product $1-r_{jk}^2$ is approximately unity for short segments, all transmittances of the form $1 \pm r_{jk}$ on the top and bottom of the graph may be replaced by unity. The resulting graph is shown in Fig. 3.

* Received by the IRE, April 3, 1961; revised manuscript received, August 14, 1961.

[1] S. J. Mason, "Feedback theory—some properties of signal flow graphs," PROC. IRE, vol. 41, pp. 1144–1156; September, 1953.



Fig. 1—Signal flow-graph for n-section transmission line.



Fig. 2—Simplified flow-graph.



Fig. 3—Flow-graph for computation of reflection coefficient.

All paths from the E_g^+-node to the E_g^--node are now summed, giving

$$R_n = r_{01} + [r_{12}\exp\{-2\gamma_1\Delta_1 x\} + r_{23}\exp\{-2(\gamma_1\Delta_1 x + \gamma_2\Delta_2 x)\} + \cdots + r_{n-1,n}\exp\{-2(\gamma_1\Delta_1 x + \cdots + \gamma_{n-1}\Delta_{n-1}x)\}] + r_t\exp\{-2(\gamma_1\Delta_1 x + \cdots + \gamma_n\Delta_n x)\}; \tag{5}$$

hence,

$$R_n = r_{01} + \sum_{j=1}^{n-1}\left[r_{j,j+1}\exp\left\{-2\sum_{i=1}^{j}\gamma_i\Delta_i x\right\}\right] + r_t\exp\left\{-2\sum_{k=1}^{n}\gamma_k\Delta_k x\right\}. \tag{6}$$

The number of segments is now permitted to increase in such a manner that the largest $\Delta_i x$ becomes vanishingly small; therefore, from (2),

$$r_{j,j+1} \to r(x) = \frac{dZ(x)}{2Z(x)} = \frac{1}{2}\frac{d}{dx}(\ln Z)dx \tag{7}$$

and

$$-\gamma_i\Delta_i x \to -\gamma(x)dx.$$

Hence, from (6) and the definition of the Riemann integral,

$$R = \lim_{n\to\infty} R_n = r_{01} + \left[\int_0^l \frac{1}{2}\frac{d}{dx}(\ln Z)\cdot\exp\left\{-2\int_0^x \gamma(s)ds\right\}dx\right] + \left[r_t\exp\left\{-2\int_0^l \gamma(x)dx\right\}\right]. \tag{8}$$

This result is the same as that obtained by Bolinder,[2] differing only in the presence of terms to account for the input and terminating discontinuities.

FRANK M. BROWN
Captain, USAF
Dept. of Elec. Engrg.
Institute of Technology
Wright-Patterson AF Base, Ohio

[2] E. F. Bolinder, "Fourier transforms and tapered transmission lines," PROC. IRE (Correspondence), vol. 44, p. 557; April, 1956.

Large Signal Interaction Between a Spiraling Electron Beam and the TE_{10} Rectangular Waveguide Mode*

In the attempt to push microwave devices to higher power levels and frequencies, several workers have proposed the use of periodic beams and smooth circuits (waveguides) rather than smooth beams and periodic circuits. The smooth circuits have greater power dissipation capabilities which are required for high powers or frequencies. One of the simplest embodiments of this proposal is that of a beam spinning about an axial dc magnetic field in a rectangular waveguide propagating the TE_{10} mode. This case will be considered here.

The success of a device of this sort depends on whether good bunching of the beam can be obtained. The bunching was investigated using the method of Webber[1] and Phillips,[2] where electron motion is observed in the presence of a constant RF circuit field. The equations of motion are used to find the position and velocity of injected electrons. Knowing the velocity of a group of electrons in an RF cycle, the efficiency can then be calculated using

$$\eta(t) = 1 - \frac{\sum_{i=1}^{N_0} v_i^2(t)}{N_0 v_0^2},$$

where v_0 is the initial electron velocity, $v_i(t)$ is the velocity of the ith electron at time t, and N_0 is the number of electrons considered per cycle. The equations were programmed on the Datatron 205-digital computer where eight electrons were considered under synchronous conditions at a 500-kw power level in S-band waveguide. The helical bunching described by Chow and Pantell[3] was not observed, because the transverse electric fields completed the energy exchange with the electrons *before* the transverse magnetic fields could accomplish any bunching. The efficiency was negative, reaching -36 per cent after three cycles. The large negative efficiency was due to the predominant effect of the unfavorable electrons.

If a device of this sort is to work at higher power levels, some method must be found to quickly move these unfavorable electrons into a favorable phase. Looking at the axial and transverse equations of motion separately, conditions can be set up where the electrons move very quickly through the accelerating phase and are trapped in the decelerating phase. A second computer run was made for these conditions, with a power level in the guide of 4 megw. The transverse velocity was 0.7 c, and the axial velocity was 0.2 c, corresponding to a considerable

* Received by the IRE, August 11, 1961.

[1] S. E. Webber, "Electron bunching and energy exchange in a traveling-wave tube," IRE TRANS. ON ELECTRON DEVICES, vol. ED-4, pp. 87–91; January, 1957.

[2] R. M. Phillips, "The Ubitron, a high power traveling-wave tube based on a periodic beam interaction in unloaded waveguide," IRE TRANS. ON ELECTRON DEVICES, vol. ED-7, pp. 231–241; October, 1960.

[3] K. K. Chow and R. H. Pantell, "The cyclotron resonance backward-wave oscillator," PROC. IRE, vol. 48, pp. 1865–1870; November, 1960.



Fig. 1.



Fig. 2.



Fig. 3.

amount of over-velocity. The total electron kinetic potential U is shown vs phase position in Fig. 1 for $N=0$, 1, 4, and 5 cycles. After one cycle the electrons have gained or lost energy according to their phase position. At four cycles a bunch has been formed and much energy has been extracted. At five cycles a saturation effect is expected as the bunch has now moved into the accelerating phase. An Applegate diagram for this process is shown in Fig. 2, where the formation of a bunch in the decelerating phase is evident. The efficiency is shown in Fig. 3. The curve is as expected from Fig. 1, and a peak efficiency of 35 per cent is obtained.

This large signal bunching mechanism can give good efficiency, but the gain available is limited to something like 10 db due to the initial negative efficiency present. Higher efficiencies and gains may be possible as the conditions used in this computer run may not be optimum.

Our results have shown that although helical bunching is not possible at higher power levels, a large signal bunching mechanism is available. This large signal bunching can be obtained for over-velocity conditions where the electrons are trapped in the decelerating phase. Good efficiencies are available with modest gains, indicating an application as a high-power output tube.

W. L. Dickson
C. C. Johnson
R. W. Grow
University of Utah
Salt Lake City, Utah

On Backward-Wave Oscillator Stabilization*

There has been and there will be an increasing need for a stable-tunable microwave source. These two requirements are generally incompatible in common microwave sources. The material herein reports the results of some preliminary work to provide a stable-tunable microwave source.

The experimental problem is specifically to stabilize a backward-wave oscillator (BWO) which is electrically tunable over an octave in S-band. In order to stabilize an oscillator, a frequency reference is needed. For an ideal stabilization system this is equivalent to putting the reference signal frequency through a high-gain amplifier with unity feedback; or, in other words, the stabilized microwave oscillator acts as a transfer network with a gain of one for the microwave reference. See Fig. 1. The loop gain of the stabilized system corresponds to the stabilization factor for the oscillator. The properties of the stabilization system will depend on whether an automatic frequency control (AFC) loop or an automatic phase control (APC) loop is used.[1–5] One serious limitation that appears to be present in this system is the additive or background noise which is introduced between the microwave mixer and the frequency discriminator or phase detector. See Fig. 2. This appears



Fig. 1—Block diagram of ideal stabilization system.



Fig. 2—Block diagram of actual stabilization system using AFC.

as an added input to the ideal system, shown in Fig. 1, and adds directly to the instability already present in the microwave oscillator frequency.

An S-band BWO (Sylvania 4198) with an inherent instability of at least 1 kc rms over a bandwidth of 5 kc, of which 200 cps is contributed by ripple from power supply, has been stabilized. An AFC loop with a bandwidth of 40 kc has been used to reduce the instabilities to 200–300 cps rms. The instabilities have been reduced further to 30 cps rms with the use of a 500 cps bandwidth low-pass filter in the AFC loop.

The reason for the improvement in stability with the addition of the low-pass filter appears to be the reduction of the background noise introduced in the mixer and preamplifier of the AFC loop. This corresponds to the phenomenon cited above as a limitation in the feasibility of providing a stabilized tunable microwave oscillator with a given microwave reference input.

R. B. Clark
W. D. Comstock
Syracuse Univ. Res. Corp.
Syracuse, N. Y.

Education and Creativity*

What Johnson[1] says bears repeating with great emphasis and not only for electronic engineering education.

In this age of swift and demanding technological progress, the learning of old tricks devised by our predecessors may preserve our present know-how by copy-cat techniques, but it will never advance the state of our science and arts in a world where others, advancing by leaps and bounds, leave us in relative obsolescence.

* Received by the IRE, August 16, 1961.

[1] K. V. Pound, "Frequency stabilization of microwave oscillator," Proc. IRE, vol. 35, pp. 1405–1415; December, 1947.
[2] W. G. Tuller, *et al.*, "Recent developments in frequency stabilization of microwave oscillators," Proc. IRE, vol. 36, pp. 794–800; June, 1948.
[3] M. Peter and M. W. P. Strandberg, "Phase stabilization of microwave oscillators," Proc. IRE, vol. 43, pp. 869–873; July, 1955.
[4] T. J. Rey, "Automatic phase control: theory and design," Proc. IRE, vol. 48, pp. 1760–1771; October, 1960.
[5] H. G. Pascalar, "An investigation of frequency stabilization techniques for backward-wave oscillators," M.I.T. Lincoln Lab., Lexington, Mass., Group Rept. No. 48.7; August, 1959.

* Received by the IRE, August 19, 1961.

[1] R. W. Johnson, "Are Electronic Engineers Educated," Proc. IRE, vol. 49, p. 1319; August, 1961.

When the text and reference books provide no answers for the myriads of challenging new problems, only creativity can find the answers. When the facts of science and engineering are taught, not as final dictums of design, but only as stepping stones to new methods and designs, then each student engineer will come to the realization that when he cannot find a way, he must *make* one!

Instead of placing his reliance on knowledge found or created by others in the past, he must learn that nothing man or nature ever created is perfect, that vast room for improvement exists in all things, that entirely new things and methods for accomplishing old ones are being created every day by those no better qualified than he; he must learn to think *synthetically* instead of only analytically, as Johnson suggests.

Creativity has *not* been taught, but I believe firmly that it *can* be. This involves the development of a highly critical state of mind, which sees imperfections in every object with which it comes in contact, instead of accepting these objects as the "last word" of creation by others. Once he has developed a jaundiced eye, he then can begin to synthesize other solutions from his mental and library storehouse of elementary components to meet the purposes of these imperfect designs, and, if some of those components are absent, he must create new ones which fit his purpose.

Student design problems, rather than being planned to test his digestion of previously taught theory, should set entirely new problems which demand exercise of his imagination and which test the variety and number of his "vocabulary" of ideas and elementary building blocks available for synthesis into new and useful objects.

A few self-reliant engineers and scientists develop these abilities early in life, and they expand with use. All creative people have them in varying degrees. All engineers could be trained in their development if our institutions of learning placed strong emphasis on creativity instead of on mimicry in engineering design.

B. F. Miessner
Miessner Inventions, Inc.
680 N.E. 105th St.
Miami Shores, Fla.

A Simple Method for the Supervision of the Orbital Period of Artificial Satellites*

Last year U. S. and Russian sources reported that the orbital constants of Sputnik IV (Epsilon 1960) had been altered on May 17, 1960, in an attempt to return this satellite to earth. These efforts failed and the satellite assumed a new orbit. The purpose of this letter is to call attention to a simple method of observing such orbital changes.



Fig. 1—Progression charts, Sputnik III, Delta 1958.

Stations that make continuous satellite observations use progression charts, which consist of a time diagram that uses the 24 hours of the day as abscissa and the datum of the days as ordinate. When the passage of a satellite is recorded, the center time of this passage is noted by a point on the progression chart. Thus, the various passages observed on one day form a line of horizontally-distributed points on that date, and the distance between the points is an average measure of the period of the satellite's orbit. The same procedure is repeated on the next day; this new line of points representing the passages observed is shifted in time with respect to the previous day, because the period of the satellite is not a submultiple of the earth's revolution. The equator crossings of corresponding orbits are shifted. As long as the orbital constants of the satellite do not change, however, this shift of equator crossings remains constant, and the picture on the progression chart consists of rows of dots that can be connected by a system of parallel straight lines. The progression charts of long-living, steady satellites are characterized by such a system of straight lines, the slope of which remains constant over many months.

In contrast, the progression charts of short-living satellites and of satellites near the ends of their lives are quite different. The centers of passage times of corresponding orbits of these satellites represent lines of different slopes (see Fig. 1). When a satellite approaches the end of its orbital life, its orbital velocity is increased. The closer the satellite approaches the earth, the higher its velocity becomes, until a dense atmosphere is reached and strong braking effects are developed, at which time the acceleration is reduced again. Since the radio beacons in most of the satellites become silent long before the re-entry period, the observed changes in the progression charts refer only to the acceleration period mentioned.

Fig. 1 shows the progression charts of Sputnik III, Delta 1958, during the last four months of its life. Because of the increasing orbital velocity, corresponding orbits appear a little earlier in true time each day than predicted by means of a system of parallel lines. The total amount of this shift becomes larger as the satellite comes closer to the earth; consequently, the slope of the connecting lines becomes flatter day by day.

These progression charts cannot be used for precise measurement of the alteration of the orbital period from each orbit to the next one, because the graphical method lacks the precision for such measurement. Moreover, the observation times do not refer to the same position in the orbital trajectory, nor is the apparent altitude accounted for. However, a sudden change in a satellite's orbital constants will obviously be indicated by these progression charts in a manner comparable to the indication given by the continuous alterations during the last weeks of a satellite.

During the early life of the satellite represented in Fig. 2, the progression chart followed the system of straight lines shown in the upper part of the figure. The undisturbed configuration is seen for orbits 5 through 58. However, beginning with orbit 68, we see a new scheme of time sequences working: the inclination of the lines has changed. Thus, after the observation of orbit 69, the station reported a change in the orbital behavior. Confirmation was later received that the Russian attempt to return

* Received by the IRE, August 11, 1961.



Fig. 2—Progression chart, Sputnik IV, Epsilon 1, 1960.

the satellite to earth had been made between orbits 58 and 68, namely during orbit 63, which was entirely over Russia for its northern part. This change had already been observed by means of the progression chart of Fig. 2, during the second orbit that could have been observed by our station at the Deal Astro-Observation Center, USASRDL.

This simple method of timing the passages of satellites has been found to be a valuable tool for indicating alterations of a satellite's orbital data. In addition, this method is of great practical value in making local predictions of expected passage times and in differentiating between the passages of various satellites that use the same radio frequency.

P. R. Arendt
L. H. Manamon
Institute for Exploratory Research
U. S. Army Signal Research and Development Lab.
Fort Monmouth, N. J.

Comment on "A Theoretical Comparison of Average- and Spot-Noise Figure in Transistor Amplifiers"*

Ekiss and Halligan[1] make use of the common error that the high-frequency corner at which a transistor's noise figure starts rising at 6 db per octave is given by $\sqrt{1-\alpha_0}f_{\alpha b}$. Cooke[2] has shown the serious errors resulting from the use of this approximation. The results of Case 2 in Ekiss and Halligan are therefore not generally correct.

Paul J. Bénéteau
Analog Circuits Group
Fairchild Semiconductor Corp.
Mountain View, Calif.

* Received by the IRE, July 30, 1961.

[1] J. A. Ekiss and J. W. Halligan, "A theoretical comparison of average- and spot-noise figure in transistor amplifiers," Proc. IRE (Correspondence), vol. 49, p. 1216; July, 1961.

[2] H. F. Cooke, "Transistor upper noise corner frequency." Proc. IRE (Correspondence), vol. 49, p. 648; March, 1961.

The Directional Coupler Core of an Arbitrary, Lossless, Reciprocal 4-Port*

The arbitrary, lossless 4-port was the subject of an early study by one of the authors.[1] The result of this study was the demonstration that "any arbitrary junction of four transmission lines (lossless reciprocal 4-port) can be represented either as a directional coupler with transformers in three of the lines or as a junction consisting of two-interconnected T-junctions." The ideal directional coupler which might lurk within a particular 4-port has appeared somewhat reluctant in the sense that no formula was available which would yield the characteristics of this coupler in terms of the conventional parameters of the given 4-port. We now present the necessary formulas, and note the generalizations of the original result which become apparent in the derivation.

A 4-port, Fig. 1, may be described by its normalized voltage-scattering matrix, $S=[S_{ij}]$,

$$b_i = \sum_j S_{ij}a_j \qquad (1)$$

or, equivalently, by a scattering-transfer matrix, $T=[T_{ij}]$,

$$\begin{bmatrix} b_3 \\ a_3 \\ \hline b_4 \\ a_4 \end{bmatrix} = T \begin{bmatrix} a_1 \\ b_1 \\ \hline a_2 \\ b_2 \end{bmatrix}. \qquad (2)$$

Both Fig. 1 and (2) indicate a particular grouping of the four ports of (1) into in-ports and out-ports: other groupings are, of course, possible; one formal way of obtaining these is a simple renumbering of terminals.

Now consider the scattering-transfer matrix representation (2) of an ideal directional coupler. There are three possible



Fig. 1—General 4-port.

* Received by the IRE, June 27, 1961; revised manuscript received, July 18, 1961.
This work was supported in part by the U. S. Army Signal Corps, the Air Force Office of Scientific Res., and the Office of Naval Res.; Contract AF-18(600)-1505.

[1] C. G. Montgomery, *et al.*, "Principles of Microwave Circuits," McGraw-Hill Book Co., Inc., New York, N. Y., ch. 9, pp. 303–306; 1948.

combinations of decoupled ports. Corresponding to the three possible forms of the scattering matrix for these ideal cases (at suitable reference planes),

$$S_1 = \begin{bmatrix} 0 & 0 & \alpha & j\beta \\ 0 & 0 & j\beta & \alpha \\ \alpha & j\beta & 0 & 0 \\ j\beta & \alpha & 0 & 0 \end{bmatrix},$$

$$S_2 = \begin{bmatrix} 0 & \alpha & 0 & j\beta \\ \alpha & 0 & j\beta & 0 \\ 0 & j\beta & 0 & \alpha \\ j\beta & 0 & \alpha & 0 \end{bmatrix},$$

$$S_3 = \begin{bmatrix} 0 & j\beta & \alpha & 0 \\ j\beta & 0 & 0 & \alpha \\ \alpha & 0 & 0 & j\beta \\ 0 & \alpha & j\beta & 0 \end{bmatrix}; \qquad (3)$$

one has three forms of T.

$$T_1 = \left[\begin{array}{cc|cc} \alpha & 0 & j\beta & 0 \\ 0 & \alpha & 0 & -j\beta \\ \hline j\beta & 0 & \alpha & 0 \\ 0 & -j\beta & 0 & \alpha \end{array}\right],$$

$$T_2 = \left[\begin{array}{cc|cc} 0 & -j\frac{\alpha}{\beta} & j\left(\beta+\frac{\alpha^2}{\beta}\right) & 0 \\ j\frac{\alpha}{\beta} & 0 & 0 & -j\frac{1}{\beta} \\ \hline j\left(\beta+\frac{\alpha^2}{\beta}\right) & 0 & 0 & -j\frac{\alpha}{\beta} \\ 0 & -j\frac{1}{\beta} & j\frac{\alpha}{\beta} & 0 \end{array}\right],$$

$$T_3 = \left[\begin{array}{cc|cc} \frac{\alpha^2+\beta^2}{\alpha} & 0 & 0 & j\frac{\beta}{\alpha} \\ 0 & \frac{1}{\alpha} & -j\frac{\beta}{\alpha} & 0 \\ \hline 0 & j\frac{\beta}{\alpha} & \frac{\alpha^2+\beta^2}{\alpha} & 0 \\ -j\frac{\beta}{\alpha} & 0 & 0 & \frac{1}{\alpha} \end{array}\right]. \qquad (4)$$

Conservation of energy would imply $\alpha^2+\beta^2=1$. Now it is clear that on interconnection with 2-ports at each port a transfer matrix, partitioned as shown,

$$T_i = \left[\begin{array}{c|c} t_{11} & t_{12} \\ \hline t_{21} & t_{22} \end{array}\right] \qquad (5)$$

$$\frac{1}{S_{13}S_{24}-S_{14}S_{23}}\left|\begin{array}{cccc|cccc}
+S_{31} & S_{13} & S_{24} & +S_{33} & S_{24} & +S_{32} & S_{13} & S_{24} & -S_{33} & S_{14} \\
-S_{31} & S_{14} & S_{23} & -S_{34} & S_{23} & -S_{32} & S_{14} & S_{23} & +S_{34} & S_{13} \\
-S_{11} & S_{33} & S_{24} & & & -S_{12} & S_{33} & S_{24} & & \\
+S_{11} & S_{34} & S_{23} & & & +S_{12} & S_{34} & S_{23} & & \\
+S_{21} & S_{33} & S_{14} & & & +S_{22} & S_{33} & S_{14} & & \\
-S_{21} & S_{34} & S_{13} & & & -S_{22} & S_{34} & S_{13} & & \\
 & & & & & & & & & \\
-S_{24} & S_{11} & & +S_{24} & & -S_{24} & S_{12} & & -S_{14} & \\
+S_{14} & S_{21} & & & & +S_{14} & S_{22} & & & \\
\hline
+S_{41} & S_{13} & S_{24} & +S_{43} & S_{24} & +S_{42} & S_{13} & S_{24} & -S_{43} & S_{14} \\
-S_{41} & S_{14} & S_{23} & -S_{44} & S_{23} & -S_{42} & S_{14} & S_{23} & +S_{44} & S_{13} \\
-S_{11} & S_{43} & S_{24} & & & -S_{12} & S_{43} & S_{24} & & \\
+S_{11} & S_{44} & S_{23} & & & +S_{12} & S_{44} & S_{23} & & \\
+S_{21} & S_{43} & S_{14} & & & +S_{22} & S_{43} & S_{14} & & \\
-S_{21} & S_{44} & S_{13} & & & -S_{22} & S_{44} & S_{13} & & \\
 & & & & & & & & & \\
+S_{23} & S_{11} & & -S_{23} & & +S_{23} & S_{12} & & +S_{13} & \\
-S_{13} & S_{21} & & & & -S_{13} & S_{22} & & &
\end{array}\right|, \tag{8}$$

goes over into

$$T=\left|\begin{array}{c|c} At_{11}C & At_{12}D \\ \hline Bt_{21}C & Bt_{22}D \end{array}\right|, \tag{6}$$

wherein A, B, C and D are transfer representations of the 2-ports. Thus, the subdeterminants are invariants provided $\det\{AC\}=\det\{AD\}=\det\{BC\}=\det\{BD\}=1$. The latter is true for any *reciprocal* 2-ports, lossless or dissipative.[2] The invariants are, by inspection,

$$\alpha^2,\ \beta^2=1-\alpha^2; \tag{7a}$$

$$\left(\frac{\alpha}{\beta}\right)^2=\frac{\alpha^2}{1-\alpha^2},\quad 1+\left(\frac{\alpha}{\beta}\right)^2=\frac{1}{1-\alpha^2}; \tag{7b}$$

$$\frac{a^2+\beta^2}{\alpha^2}=\frac{1}{\alpha^2},\qquad \left(\frac{\beta}{\alpha}\right)^2=\frac{1-\alpha^2}{\alpha^2}. \tag{7c}$$

On the other hand, the absolute value of the determinant of the transfer representation of a lossless $2N$-port, reciprocal or nonreciprocal, is also unity. Hence, the absolute values of the invariants are significant as well for nonreciprocal lossless tuning in the arms of the 4-port.

Evidently the transfer matrices corresponding to a general scattering matrix have subdeterminants which correspond to the invariants (7). For the grouping of the ports indicated in (2), the transfer matrix T is

from which the determinants of the submatrices are

$$\frac{S_{24}S_{31}-S_{21}S_{34}}{S_{24}S_{13}-S_{23}S_{14}},\qquad \frac{S_{14}S_{32}-S_{12}S_{34}}{S_{14}S_{23}-S_{13}S_{24}},$$
$$\frac{S_{23}S_{41}-S_{21}S_{43}}{S_{23}S_{14}-S_{24}S_{13}},\qquad \frac{S_{13}S_{42}-S_{12}S_{43}}{S_{13}S_{24}-S_{14}S_{23}}. \tag{9}$$

These expressions are of the general form

$$\frac{S_{ij}S_{kl}-S_{il}S_{kj}}{S_{ij}S_{lk}-S_{ik}S_{lj}}.$$

The above relations are valid for arbitrary 4-ports, but the interpretation in terms of an imbedded ideal directional coupler is limited to the lossless reciprocal case. As previously mentioned, the analogous forms for the different groupings of ports may be obtained formally by permuting the port designations. The new expressions thus obtained are also invariant. The magnitudes of the several invariants in a specific case, in particular whether sums or differences equal unity, determine the proper choice of directional coupler terminals [see (7)].

Of the 2-ports A, B, C, D which convert the lossless, reciprocal 4-port to an ideal directional coupler, one may be chosen arbitrarily. The other three may then be obtained from (6) and the standard forms shown in (4). In particular one port may remain untuned.

W. K. Kahn
Polytechnic Inst. of Brooklyn
Brooklyn, N. Y.
R. L. Kyhl
Res. Lab. of Electronics
Mass. Inst. Tech.
Cambridge, Mass.

[2] L. B. Felsen and W. K. Kahn, "Transfer characteristics of $2N$-port networks," *Proc. Symp. on Millimeter Waves*, New York, N. Y., March 31, April 1–2, 1959, Polytechnic Press, Brooklyn, N. Y., pp. 477–512; 1959.

Spectral Response of a Nonlinear Device*

It is frequently desirable to be able to determine the spectral output of a nonlinear device when it is driven by a periodic input. If the device and the input signal satisfy certain conditions, the output may be specified. These conditions are that 1) the output is a single-valued function of the input which is constant over the frequency range of the input, and that 2) the input may be represented by a finite sum of terms. If the device satisfies these conditions, it may be expanded by a Fourier series over the interval $-e_m \leq e \leq e_m$, where e_m is greater than the maximum absolute value of the input.

$$e_0=f(e_{in})=\sum_{n=1}^{\infty}\left[a_n\sin\left(\frac{n\pi e_{in}}{e_m}\right)+b_n\cos\left(\frac{n\pi e_{in}}{e_m}\right)\right]\quad -e_m\leqq e\leqq e_m \tag{1}$$

where as usual

$$a_n=\frac{1}{\pi}\int_{-\pi}^{\pi}f(e_{in})\sin\left(\frac{n\pi e_{in}}{e_m}\right)de_{in}$$
$$b_n=\frac{1}{\pi}\int_{-\pi}^{\pi}f(e_{in})\cos\left(\frac{n\pi e_{in}}{e_m}\right)de_{in}.$$

It is assumed that the input may be represented by a finite sum of terms,

$$e_{in}=\sum_{i=1}^{N}\alpha_i\sin\omega_i t. \tag{2}$$

Then each term in the Fourier expansion is of the form,

$$\cos\left(\frac{n\pi e_{in}}{e_m}\right)=\cos\left(\frac{n\pi}{e_m}\sum_{i=1}^{N}\alpha_i\sin\omega_i t\right). \tag{3}$$

The argument of each term in the expansion contains all N harmonics of the input. By repeated use of the trigonometric identity for the sum of two arguments, (3) may be written as a sum of 2^{N-1} terms. Each of these terms will be the product of N factors of the form

$$\prod_{i=1}^{N}T\left(\frac{n\pi}{e_m}\alpha_i\sin\omega_i t\right), \tag{4}$$

where T may be either sin or cos:

$$\left\{\begin{array}{l}\cos\left(\dfrac{n\pi e_{in}}{e_m}\right)\\ \sin\left(\dfrac{n\pi e_{in}}{e_m}\right)\end{array}\right\}=\sum_{j=1}^{2^{N+1}}{}_R\left\{\pm\prod_{i=1}^{N}{}_j\ T_i\left(\frac{n\pi}{e_m}\alpha_i\sin\omega_i t\right)\right\}. \tag{5}$$

$\sum_R$ refers to the sum of all possible combinations of

$$\prod_{i=1}^{N}T_i$$

formed using either sin or cos for T, which satisfy the following rule: If the product

$$\prod_{i=1}^{N}T_i$$

were written from $\cos(n\pi e_{in}/e_m)$, there must be an even or odd number of cos functions,

* Received by the IRE, August 3, 1961; revised manuscript received, August 21, 1961.

depending upon whether N were even or odd. The opposite would be true if $\sin(n\pi e_{in}/e_m)$ were being expanded.

The rule for the sign of the product is rather complicated, and since only the magnitude of the output is required, this rule is omitted. When $a_n \sin(n\pi e_{in}/e_m) + b_n \cos(n\pi e_{in}/e_m)$ is expanded in this way, all possible combinations of

$$\prod_{i=1}^{N} T_i$$

appear. Half of the terms come from $\sin(n\pi e_{in}/e_m)$ and half come from $\cos(n\pi e_{in}/e_m)$. The distribution of these terms comes from the above rule.

Then the well-known Bessel function series may be substituted for T:

$$\cos\left(\frac{n\pi\alpha_i}{e_m}\sin\omega_i t\right) = J_0\left(\frac{n\pi\alpha_i}{e_m}\right) + 2\sum_{k=1}^{\infty} J_2\left(\frac{n\pi\alpha_i}{e_m}\right)\cos 2k\omega_i t$$

$$\sin\left(\frac{n\pi\alpha_i}{e_m}\sin\omega_i t\right) = 2\sum_{k=1}^{\infty} J_{2k-1}\left(\frac{n\pi\alpha_i}{e_m}\right)\sin((2k-1)\omega_i t).$$

Then these substitutions may be made and the products evaluated and simplified by repeated application of the trigonometric identities:

$$\cos a\cos b = \tfrac{1}{2}[\cos(a+b) + \cos(a-b)],$$
$$\sin a\cos b = \tfrac{1}{2}[\sin(a+b) + \sin(a-b)],$$

whichever is applicable. If this is done, there results an expression

$$\left\{\begin{matrix}\cos\left(\frac{n\pi e_{in}}{e_m}\right)\\ \sin\left(\frac{n\pi e_{in}}{e_m}\right)\end{matrix}\right\} = 2^r \sum_{k_1=1}^{\infty}\sum_{k_2=1}^{\infty}\cdots\sum_{k_N=1}^{\infty}\left[\prod_{i=1}^{\infty} J_{l_i}\left(\frac{n\pi\alpha_i}{e_m}\right)\right] \cdot T[(l,\omega, \pm l_2\omega_2 \pm \cdots l_N\omega_N)t] \quad (6)$$

r = the number of components for which $l_i \neq 0$

$l_i = 2k_i, \quad 2k_i - 1, 0,$

where, if $l_i = 0$, the sum over k_i is not performed, and where α_i is the ith component of input, $T = \sin$ if argument of T contains an odd number of odd harmonics, and $T = \cos$ if argument of T contains an even number of odd harmonics. It is necessary to retain the distinction between even and odd harmonics of the components of the input to determine whether T is sin or cos.

Thus, it has been shown that a nonlinear device produces all possible harmonics of each input component plus all possible sums and differences of these harmonics. The magnitude of any component of the output may be determined by returning to the original expansion of $f(e_{in})$ and summing over n. Thus, if e_{io} is a component of the output whose frequency is

$$\omega_e = \sum_{i=1}^{N} l_i\omega_i,$$

then

$$e_{io} = m_e \sin(\omega_e t + \phi) \quad \phi = 0, \pm\frac{\pi}{2}$$

where

$$m_e = \frac{2^{r+1}}{\pi}\sum_{n=1}^{\infty}\left[\prod_{i=1}^{N} J_{l_i}\left(\frac{n\pi\alpha_i}{e_m}\right)\right] \cdot \int_{-\pi}^{\pi} f(e_{in})T\left(\frac{n\pi e_{in}}{e_m}\right) de_{in}. \quad (7)$$

The l_i in the expression for m_e must be the same as l_i in the expansion for ω_e. $T = \cos$ if an even number of odd harmonics appear in ω_e, and $T = \sin$ if an odd number of odd harmonics appear in ω_e.

The form of the solution will always be the same. The product of Bessel functions is independent of shape in that the number of factors is equal to the number of components of the input. There will be one Bessel function factor for each input component. The argument of the Bessel functions is only dependent on the relative magnitude of the input components and the location of e_m. The effect of the shape of $f(e_i)$ is contained entirely in the integral.

This technique is quite general and may be applied to any nonlinear device which satisfies the conditions listed at the beginning of this letter. A computer could be used to evaluate the components of the output if more than a few components are in the region of interest. If $f(e_i)$ may be approximated by only a few terms of a power series, it may be described more easily by evaluating the resulting polynomial products. However, a piecewise continuous $f(e_i)$ may be expanded in a Fourier series quite efficiently, and so devices which may be described by this type of curve are best analyzed by the technique of this letter.

William B. Ribbens
Dept. of Elec. Engrg.
University of Michigan
Ann Arbor, Mich.

On a Mathematical Description of Noisy Measurement System Performance*

There are many practical measurement systems for which internal noise is the factor which limits the quality of system performance. Such systems, which might be termed noisy measurement systems, have many features in common with the type of random experiments which have been the subject of much discussion in the literature of mathematical statistics.[1] In spite of the available mathematical work, quantitative expressions for the performance of noisy measurement systems do not seem to be commonly used in the engineering literature.

The purposes of this note are: 1) to call attention to the precise definitions of two statistical parameters which can be used as measures of the performance of certain noisy measurement systems; and 2) to formulate quantitative expressions for measurement-system performance in terms of these quantities.

Consider a noisy measurement system with an input $r_S(t)$, an output $R(x, t)$, and internal noise $n(x, t)$. All of the parameters of $r_S(t)$ but one, denoted by $S(t)$, are assumed to be known. This parameter is the quantity to be measured. The nature of the internal noise is such that it can be best represented mathematically as a stochastic process. The presence of $n(x, t)$ in the system thus makes the output $R(x, t)$ also a stochastic process.

Stochastic processes have been discussed extensively in both mathematical and engineering literature, and the use of such processes as mathematical models for physical noise is well known.[2] In the notation chosen here, the double argument (x, t) has been adopted to emphasize the fact that the stochastic variables n and R depend not only on the time variable t, but also on the chance state of the internal noise generators represented by the variable x. If x is fixed to correspond to a particular measurement with the measurement system, the functions $n(x, t)$ and $R(x, t)$ thus restrained are commonly called sample functions from the corresponding noise processes. On the other hand, a large number of measurements could be made in such a way that the system output is recorded at a fixed time after exciting the measurement system with the quantity to be measured. If these measurements are performed under identical conditions, except for the chance state of the noise generators, then the collection of values $\{n(x, t)\}$ or $\{R(x, t)\}$, where x varies and t is fixed, would be termed an ensemble of values from the appropriate processes. Moments of the random variables may be defined either as averages over the variable t or as averages over the ensemble. Frequently the averages defined in these two ways are equal, but this is not true in general for measurement systems. Here the ensemble average, denoted $En(x, t)$ or $ER(x, t)$, will be used.

The purpose of a measurement system is to produce in a given measurement (*i.e.*, with x fixed) a function $R(x, t)$ which is an estimate of the unknown parameter $S(t)$ that is being measured. The question naturally arises as to the quality of the estimate produced by a measurement system. If the results of a particular measurement are in hand, and if the true values of the parameter to be measured are known, then the quality of the estimate can be precisely determined. This is seldom the case, however, and a much more interesting question concerns the potential quality of an estimate to be formed by a particular measurement system with the calculation being made prior to the measurement. Thus, *a priori*, $R(x, t)$ can be regarded as a random variable. In fact the ensemble of values of $R(x, t)$ is

* Received by the IRE, August 14, 1961.

[1] See, for example, H. Cramér, "Mathematical Methods of Statistics," Princeton University Press, Princeton, N. J., 1945; or H. B. Mann, "Analysis and Design of Experiments," Dover Publications, Inc., New York, N. Y., 1949.

[2] The book by J. L. Doob, "Stochastic Processes," John Wiley and Sons, Inc., New York, N. Y., 1952, is representative of the mathematical literature on the subject of stochastic processes, while the paper by W. R. Bennett, "Methods of solving noise problems," Proc. IRE, vol. 44, pp. 609–638, May, 1956, is typical of the engineering literature on stochastic processes and applications to physical systems.

just the collection of all possible measurement system outputs which result from all possible values of the input $S(t)$ and internal noise $n(x, t)$. If the statistical properties of $n(x, t)$ are known, it is then possible to compute the statistical properties of $R(x, t)$ in terms of $S(t)$. Certain of these statistical properties of $R(x, t)$ can then be used to formulate a probabilistic expression for the quality of the estimate of $S(t)$ formed by the measurement system.

In order to be more specific, the discussion will be restricted to those measurement systems having the following properties: 1) $En(x, t)$ equals zero; 2) $S(t)$ is a constant, S; and 3) the elements of the system are linear. Such systems are commonly designed to satisfy the specific condition

$$ER(x, \infty) = kS, \tag{1}$$

where k is a constant scale factor, and the symbol ∞ in the argument of R indicates that t is very large so that the measurement system is in the steady state. This condition is usually met by designing the system so that

$$ER(x, t) = w(t)S,$$

where $w(t)$ accounts for the transient behavior of the system, and

$$\lim_{t \to \infty} w(t) = k.$$

For systems thus restricted there are two distinct types of error, namely: 1) statistical fluctuation errors caused by internal noise, and 2) errors caused by the fact that $ER(x, t)$ is not proportional to S. Quantitatively these two types of error can be defined as follows:[3]

$$\text{Bias error} = \epsilon_b(t) = ER(x, t) - kS; \tag{2}$$

$$\text{Mean-square error} = \epsilon_{ms}(t) = E[R(x, t) - kS]^2. \tag{3}$$

Bias error, taken from the statistical use of the term "bias," thus measures the amount by which the ensemble average of the measurement-system output differs from the true value of the quantity being measured. Similarly mean-square error measures the statistical fluctuation about the true value to be expected in the results of a large number of measurements taken with the same instrument.

Now consider the use of these error terms in describing measurement-system performance. Eq. (2) expresses clearly the quantitative effect of bias error. A relation which elucidates the effect of mean-square error can be derived as follows. Eq. (3) for mean-square error can be written as

$$\epsilon_{ms}(t) = \int_{-\infty}^{\infty} [R(x, t) - kS]^2 dF(x) = \int_{-\infty}^{\infty} \gamma^2 dF(x),$$

where F is the probability distribution function of $R(x, t)$, and $\gamma^2 = [R(x, t) - kS]^2$. The chain of inequalities,

$$\epsilon_{ms}(t) \geq \int_A \gamma^2 dF(x) \geq c^2 \epsilon_{ms}(t) \int_A dF(x), \tag{4}$$

where A denotes the set of values of x such that $|\gamma| \geq c\sqrt{\epsilon_{ms}(t)}$, can be easily verified. Eq. (4) leads immediately to an upper bound on the probability of the event $[|R(x, t) - kS| \geq c\sqrt{\epsilon_{ms}(t)}]$, or what is more useful here, the relation[4]

$$P[|R(x,t) - kS| < c\sqrt{\epsilon_{ms}(t)}] > 1 - 1/c^2. \tag{5}$$

Eq. (5) is equivalent to the following statement: "With probability greater than $1 - 1/c^2$, a single reading of a measurement-system output differs in magnitude from the true value of the quantity being measured by no more than c times the root of its mean-square error."

It may be noted that the above discussion again takes cognizance of the well-known fact that at least two different types of error arise from the use of noisy measurement systems. The terms "accuracy" and "reliability"[5] or "accuracy" and "precision"[6] seem to be used more frequently than others in identifying these two types of error. Thus (2) calls attention to a mathematical measure of "accuracy" for the class of systems to which it applies, and similarly, (3) calls attention to a measure of "reliability" (or "precision") for the same class of systems. Eq. (5) gives a quantitative relation between a single reading of the output of a measurement system and the true value of the quantity which the system is designed to estimate.

J. L. Hammond, Jr.
School of Elec. Engrg.
Georgia Inst. of Tech.
Atlanta, Ga.

[3] In arriving at these definitions, it has been assumed that the scale factor k is known so that in effect kS is the true value of the quantity being measured. If for some reason k is not known, alternative definitions of $\epsilon_b(t)$ and $\epsilon_{ms}(t)$ could be made. For example, these quantities could be defined by replacing kS in (3) and (4) by simply S.

[4] This relation is similar to the Bienaymé-Tchebycheff inequality.

[5] L. Brillouin, "Science and Information Theory," Academic Press, Inc., New York, N. Y.; 1956.

[6] Y. Beers, "Introduction to the Theory of Error," Addison-Wesley Publishing Co., Reading, Mass.; 1953.

The Delta Function and the Fourier Integral*

A rather interesting result can be obtained from the use of the delta "function" (to use the word loosely) in the Fourier integral. The delta function is often said to be 1) an even function, and 2) zero everywhere except at the origin, where it is so large that

$$\int_{-\infty}^{\infty} \delta(x)dx = \int_{-e}^{e} \delta(x)dx = 1. \qquad e > 0. \tag{1}$$

In its use in communications engineering the Fourier integral is written as

$$F(w) = \int_{-\infty}^{\infty} f(t)e^{-iwt}dt, \tag{2}$$

"the direct transform," and

$$f(t) = \frac{1}{2\pi}\int_{-\infty}^{\infty} F(w)e^{iwt}dw, \tag{3}$$

"the inverse transform," where always

$$w = 2\pi f \tag{4}$$

and

$$i = \sqrt{-1}. \tag{5}$$

Consider now a delta function of frequency, from which will be obtained the corresponding time function through the use of (3).

$$f(t) = \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(w)e^{iwt}dw, \tag{6}$$

which, from the stated property of the delta function in (1), can be reduced immediately to yield

$$\begin{aligned} f(t) &= \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(w)e^{iwt}dw \\ &= \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(0)e^{i(0)t}dw \\ &= \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(0)dw \\ &= \frac{1}{2\pi}. \end{aligned} \tag{7}$$

Now consider exactly the same equation (6) with the introduction of the apparently trivial change of variable shown in (4).

$$\begin{aligned} f(t) &= \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(w)e^{iwt}dw \\ &= \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(2\pi f)e^{i2\pi ft}(2\pi)df \\ &= \int_{-\infty}^{\infty} \delta(2\pi f)e^{i2\pi ft}df. \end{aligned} \tag{8}$$

Evaluation of the final result shown in (8) by the same method used in evaluation of (7) leads to

$$\begin{aligned} f(t) &= \frac{1}{2\pi}\int_{-\infty}^{\infty} \delta(w)e^{iwt}dw \\ &= \frac{1}{2\pi}\int_{\infty}^{\infty} \delta(2\pi f)e^{i2\pi ft}(2\pi)df \\ &= \int_{-\infty}^{\infty} \delta(2\pi f)e^{i2\pi ft}df \\ &= \int_{-\infty}^{\infty} \delta(2\pi(0))e^{i2\pi(0)t}df \\ &= \int_{-\infty}^{\infty} \delta(0)df \\ &= 1. \end{aligned} \tag{9}$$

From (7) and (9) come the two different numbers $1/2\pi$ and 1, respectively, as the values of the same definite integral. Perhaps either $1/2\pi$ or 1 is the value of the definite integral, but who can say that $1/2\pi$ and 1 are equal?

The answer, or answers, or neither, obtained above are perhaps no better or no worse than another expression commonly as-

* Received by the IRE, June 9, 1961.

sociated with a delta function of time:

$$\begin{aligned} F(w) &= \int_{-\infty}^{\infty} \delta(t) e^{-iwt} dt \\ &= \int_{-\infty}^{\infty} \delta(0) e^{-iw(0)} dt \\ &= \int_{-\infty}^{\infty} \delta(0) dt \\ &= 1. \end{aligned} \tag{10}$$

There is no "2π-trick" in (10); that is,

$$\begin{aligned} F(w) &= \int_{-\infty}^{\infty} \delta(t) e^{-iwt} dt, \text{ or} \\ F(2\pi f) &= \int_{-\infty}^{\infty} \delta(t) e^{-i2\pi ft} dt \\ &= \int_{-\infty}^{\infty} \delta(0) e^{-i2\pi f(0)} dt \\ &= \int_{-\infty}^{\infty} \delta(0) dt \\ &= 1. \end{aligned} \tag{11}$$

Now to apply the inverse transform of (3) to the common result of (10) and (11):

$$\begin{aligned} f(t) &= \frac{1}{2\pi} \int_{-\infty}^{\infty} F(w) e^{iwt} dw \\ &= \frac{1}{2\pi} \int_{-\infty}^{\infty} 1 e^{iwt} dw \\ &= \frac{1}{2\pi} \int_{-\infty}^{\infty} \cos wt dw + i \frac{1}{2\pi} \int_{-\infty}^{\infty} \sin wt dw \\ &= \frac{1}{2\pi} \int_{-\infty}^{\infty} \cos wt dw, \end{aligned}$$

since sin wt is an odd function. (12)

Alternatively,

$$\begin{aligned} f(t) &= \frac{1}{2\pi} \int_{-\infty}^{\infty} F(w) e^{iwt} dw \\ &= \int_{-\infty}^{\infty} F(2\pi f) e^{i2\pi ft} df \\ &= \int_{-\infty}^{\infty} 1 e^{i2\pi ft} df \\ &= \int_{-\infty}^{\infty} \cos 2\pi ft df + i \int_{-\infty}^{\infty} \sin 2\pi ft df \\ &= \int_{-\infty}^{\infty} \cos 2\pi ft df, \end{aligned} \tag{13}$$

which agrees with the result of (12), again with no "2π-trick." However, the $f(t)$ of (12) and (13) is the delta function, so that the common result obtained above is

$$\delta(t) = \frac{1}{2\pi} \int_{-\infty}^{\infty} \cos wt dw = \int_{-\infty}^{\infty} \cos 2\pi ft df. \tag{14}$$

This is a rather interesting result, because the integral of (14) does not converge for *any* value of t. Let $t=0$ in (14). Then,

$$\begin{aligned} \delta(0) &= \int_{-\infty}^{\infty} \cos 2\pi f(0) df \\ &= \int_{-\infty}^{\infty} 1 df. \end{aligned} \tag{15}$$

Both sides of (15) seem to agree since $\delta(0)$ is commonly said to be "infinite" and the integral of (15) also appears to be infinite. Next let $t=1$ in (14). Then

$$\begin{aligned} \delta(1) &= \int_{-\infty}^{\infty} \cos 2\pi f df \\ &= \frac{1}{2\pi} [\sin 2\pi f]_{-\infty}^{\infty} \end{aligned} \tag{16}$$

formally at least.

Now $\delta(1)$ is supposed to be zero. However, the right side of (16) does not converge to any number, and, in approaching the limits $-\infty$ and ∞, it varies between the lower bound $-1/2\pi$ and the upper bound $+1/2\pi$; similar results are obtained from other values of $t \neq 0$ in (14).

Is (14) the delta "function?"

A. W. McMurtrey
Conduction Corp.
Ann Arbor, Mich.

An Electronically Tunable Up-Converter*

The device to be described in this letter is a lower-sideband up-converter with a single varactor diode. Two-resonator broadbanding filters are used at the signal-input and pump-input ports, and a single-resonator *narrow-band* filter is used at the lower-sideband output port. Defining f as the input frequency, f^p as the pump frequency, and f_0' as the *fixed* frequency passed by the narrow-band output filter, for a signal to be amplified, the relation

$$f = f^p - f_0' \tag{1}$$

must be satisfied. Thus, using a voltage-tunable pump oscillator to vary f^p, fast electronic tuning is possible. The design of devices of this type was discussed in a recent paper.[1]

To test the previously developed theory, a strip transmission line up-converter of the general form shown in Fig. 1 was constructed. A Hughes 1N896 diode that has a computer-type package with 0.020-inch-diameter wire leads was used. The diode plus its leads makes a resonant circuit which exhibits series resonance at both the center of the signal input band and at the center of the pump input band. The two-resonator signal input broadbanding filter consists of the series resonator formed by the diode and its leads, along with the shunt resonator formed by the shunt capacitor block and the shunt inductor stub. The two-resonator pump input broadbanding filter consists of the diode circuit at its second series resonance, along with the quarter-wavelength-type second pump resonator shown in Fig. 1. The lower-sideband output filter consists of a half-wavelength resonator capacitively coupled to the diode circuit and to the output line. The band-stop resonators were introduced to prevent leakage of the output signal. In the device constructed, the pump input reflection loss is 3 ± 0.2 db across the pump band, which can be shown to be very nearly optimum for a two-resonator matching filter in this particular device.[1] With this amount of reflection loss, 67 mw of incident pump power were required for optimum operation.



Fig. 1—Simplified drawing of the strip-transmission-line electronically tunable up-converter.



Fig. 2—Measured tuning characteristics of the up-converter. (The output frequency was held fixed at 4037 Mc, while the pump frequency was varied for each input frequency; incident pump power was a constant 67 mw.)

Fig. 2 shows the measured tuning characteristic of the device. The 3-db-down fractional tuning bandwidth is 38.5 per cent, which compares favorably with the design value of 40 per cent. Since the gain has both negative-resistance and up-conversion components, it was possible to make the negative-resistance component relatively small, which makes the device relatively insensitive to small deviations from the design terminating impedances. The theoretical midband noise figure was 2.1 db, and the measured values ranged close to this value over much of the input frequency band, while reaching a peak of 3 db at the upper edge of the band. Of course, even lower noise figures are possible when using higher-Q diodes and larger f_0'/f ratios.

Theory shows that if the diode were lossless, the tuning range possible with devices of this type would be unlimited; with existing diodes, tuning ranges of the order of an octave should be practical.[1] Such up-converters should find application not only as low-noise preamplifiers with electronic tuning, but also as low-noise preamplifiers with manual tuning achieved by a single

* Received by the IRE, September 18, 1961. This research was supported by the U. S. Army Signal Res. and Dev. Lab., Fort Monmouth, N. J., under Contract DA-36-039 SC-87398.

[1] G. L. Matthaei, "Design theory of up-converters for use as electronically tunable filters," IRE Trans. on Microwave Theory and Techniques, vol. MTT-9, pp. 425–435; September, 1961.

knob on the pump oscillator. If desired, similar results can be obtained with absolutely stable upper-sideband up-converters,[1,2] but with less gain for a given f_0'/f ratio.

GEORGE L. MATTHAEI
Stanford Research Institute
Menlo Park, Calif.

[2] G. P. Shepherd and D. G. Kiely report gain of 7 db or greater over a range from 150 to 1800 Mc using an up-converter with a fixed upper-sideband output of 8600 Mc. [See PROC. IRE (Correspondence), vol. 49, p. 966; May, 1961.] They, however, appear to have varied their pump power as their pump frequency was varied. Adjusting the pump power for maximum gain at each frequency not only will overcome variations in pump circuit reflection, but also will vary the average capacitance of the diode so as to retune the diode circuit. The approach here assumes constant incident pump power.

The Linearized Transfer Function of a Phase-Locked Loop Containing an IF Amplifier*

Very commonly, phase-locked loops are constructed with an IF amplifier in the loop, as shown in the typical example of Fig. 1(a). This note will derive a method for finding the exact linear transfer function for such a loop. The effect of the IF transfer function is included. If the IF is narrow compared to the loop bandwidth, the IF transfer function cannot be neglected.

Consider the block diagrams of Fig. 2, and assume that $G(s)$ is a high-Q band-pass transfer function. If $F(s)$ is the Laplace transfer function of some input to $G(s)$ the output is, of course, $F(s)G(s)$. The expressions $F(s)$ and $G(s)$ may be rewritten as $F(s) = F_1(s)F_1^*(s)$ and $G(s) = G_1(s)G_1^*(s)$. This simply allows the upper s-plane singularities to be treated separately from their lower-plane conjugates. This output is multiplied by a cosine wave

$$\frac{E_{0_2}}{2\pi}\cos\omega_3 t.$$

The Fourier transform of this cosine is

$$\mathfrak{F}\left\{\frac{E_{0_2}}{2\pi}\cos(\omega_3 t-\theta_3)\right\}$$
$$=\frac{E_{0_2}}{2}[\delta(\omega-\omega_3)+\delta(\omega+\omega_3)],$$

where $\delta(\omega)$ is the well-known impulse or delta function. Since the Fourier transform of a time product is the convolution of the individual transforms, the transformed output of $h(t)$ of Fig. 2(a) is

$$\frac{K_n}{2}\int_{-\infty}^{\infty}F_1(\omega-\omega_0)F_1^*(\omega-\omega_0)G_1(\omega-\omega_0)$$
$$\cdot G_1^*(\omega-\omega_0)[\delta(\omega-\omega_3)+\delta(\omega+\omega_3]d\omega_0$$
$$=\frac{K_n}{2}[F_1(\omega-\omega_3)F_1^*(\omega-\omega_3)G_1(\omega-\omega_3)G_1^*(\omega-\omega_3)$$
$$+F_1(\omega+\omega_3)F_1^*(\omega+\omega_3)G_1(\omega+\omega_3)G_1^*(\omega+\omega_3)],$$

* Received by the IRE, August 7, 1961.



Fig. 1—(a) A typical phase-locked loop. (b) A loop with an equivalent transfer function. (c) The linearized equivalent.



Fig. 2—(a) Filter before the multiplier. (b) Filter after the multiplier.

where K_n is the constant associated with the multiplier. The higher harmonic frequency terms (outside the range of interest) are next evaluated and assumed to be constant in the low-pass range. Then

$$H(\omega)=\frac{K_n}{2}[K_HF_1(\omega-\omega_3)G_1(\omega-\omega_3)$$
$$+K_H^*F_1^*(\omega+\omega_3)G_1^*(\omega+\omega_3)].$$

This is, in effect, the lower half s plane moved up by ω_3 and the upper half s plane moved down by ω_3 with the high frequency components treated as complex constants. If one may assume that $F_1(\omega)$ and $G_1(\omega)$ are symmetrical about ω_3,

$$H(\omega)=K_n\,\mathrm{Re}\,[K_H]F_1(\omega-\omega_3)G_1(\omega-\omega_3),$$

or, in Laplace notation,

$$H(s)\propto F_1(s-j\omega_3)G_1(s-j\omega_3).$$

Referring to Fig. 2(b) it is now seen that after the multiplier, where $F(s)$ is shifted by $j\omega_3$, the filter must have the frequency translated dynamics of $G(s)$:

$$D(s)=G_1(s-j\omega_3).$$

The substitution in Fig. 1(b) may now be made. This low-frequency equivalent of $G(s)$ is shown in Fig. 3(b).



Fig. 3—(a) An example of $G(s)$. (b) $D(s)$, the low-frequency equivalent of $G(s)$.

The output of the multiplier of Fig. 1(b) is then

$$K_nK_mK_sE_sE_{0_1}E_{0_2}\,\mathrm{Re}\,[K_H]\sin(\theta_1-\theta_2).$$

K_m is the mixer constant. The linearization of the loop can now continue in the conventional manner.[1]

The completely linearized loop is shown in Fig. 1(c). The equivalent noise voltage will be the same as given in Weaver.[1] It is seen, for example, that if the low-frequency equivalent in Fig. 3(b) is not wide band compared to $B(s)$, $D(s)$ will definitely affect the compensation needed.

R. LAWHORN
C. S. WEAVER
Western Development Labs.
Philco Corp.
Palo Alto, Calif.

[1] C. S. Weaver, "A new approach to the linear design and analysis of phase-locked loops," IRE TRANS. ON SPACE ELECTRONICS AND TELEMETRY, vol. SET-5, pp. 166–178; December, 1959.

Infrared Fluorescence and Stimulated Emission of Nd^{+3} in $CaWO_4$*

Recently, several investigations have confirmed the predictions of Schawlow and Townes[1] concerning the character of stimulated emission in the optical region from an assembly of atoms in a suitable cavity prepared in a state of inverted population in excess of a certain critical number. This letter reports the observation of infrared fluores-

* Received by the IRE, September 20, 1961.

[1] A. L. Schawlow and C. H. Townes, "Infrared and optical masers," *Phys. Rev.*, vol. 112, pp. 1940–1949; December 15, 1958.



Fig. 1—Near infrared fluorescence spectrum of Nd^{+3} in $CaWO_4$ at 77°K, with transitions designated.

cence and stimulated emission at room temperature and 77°K in $CaWO_4$:Nd^{+3}. Trivalent neodymium is the active medium, and stimulated emission is produced in the infrared fluorescence line at 1.0646 microns (1.063 microns at 77°K).

Ultraviolet and visible absorption and emission spectra of trivalent neodymium ions in $LaCl_3$ have been analyzed in great detail by Carlson and Dieke.[2,3] While variations arising from a different crystal field are found in the corresponding energy level diagram for the $CaWO_4$ host lattice, the gross features are preserved. Indeed, the strongest infrared fluorescence line was found to occur at the same wavelength for both materials.

The infrared fluorescence spectrum at 77°K of a sample cut from a crystal of $CaWO_4$:Nd 0.14 per cent (ratio of neodymium to calcium atoms) is shown in Fig. 1. Emission was excited by an Osram HBO 200 mercury lamp and recorded by a PbS detector in conjunction with a Perkin-Elmer Model-12G grating spectrometer. Excitation is achieved most efficiently by pumping into Nd^{+3} levels lying below 25,000 cm^{-1}. The predominant emission arises from de-excitation processes to a resonance level corresponding to the $^4F_{3/2}$ state of the free ion. This is followed by radiative transitions to groups corresponding to $^4I_{13/2}$, $^4I_{11/2}$, and $^4I_{9/2}$ states of the free ion (see Carlson[3]). The strongest line in the $^4F_{3/2} \rightarrow {}^4I_{11/2}$ group at 1.063 microns has a normal fluorescence line width of about 7 cm^{-1} at 77°K and exhibits stimulated emission. The terminal state $^4I_{11/2}$ lies some 2000 cm^{-1} above the ground state $^4I_{9/2}$.

The remainder of the crystal was then cut into a cylindrical rod, and both ends were polished to spherical surfaces according to a confocal cavity geometry.[4] Silver was evaporated on both ends, one end being left with a transmission ≃5 per cent. The rod was mounted on one end of a Cu-Ni tube, a window cemented to the other end, and the assembly was placed inside a Pyrex Dewar. The Dewar was centered in a helical GE FT524 xenon flash tube. Measurements at both room temperature and 77°K were made with this configuration. The lamp was flashed by discharging a 100-μf condenser charged typically to 1 kv. Optics were arranged so as to examine the light emerging through the lightly silvered end of the rod up through the tube. An RCA 7102 photomultiplier was employed for oscilloscope display and the emission was detected in conjunction with filters, quartz prism, or grating, or a desired combination.

Shown in Fig. 2 are traces taken at room temperature at progressively higher levels of flash lamp intensity. For the series shown in Fig. 2(a)–(d), only filters were used between sample and detector so as to display simultaneously both the stimulated emission and the combination of normal fluorescence and stray light from the lamp. The upper trace, Fig. 2(a), illustrates behavior at threshold, a single burst of stimulated emission superimposed on a background which closely resembles the intensity variation of the flash lamp with time. The critical inverted population density is achieved after 250-μsec integration of the lamp intensity. The threshold for stimulated emission for this particular rod is estimated to be ~5 joules at room temperature and ~3 joules at 77°K. As the exciting intensity is



Fig. 2—Oscilloscope traces of stimulated emission at room temperature at progressively higher levels of pumping intensity above threshold. For traces (a) through (d), only wide-band filters were employed between sample and detector so as to display both stimulated emission and the combination of normal fluorescence and stray light from the flash lamp. The bottom trace of (a) illustrates behavior at threshold on a time scale of 100 μsec/division. The time scale for the top trace of (a) is expanded to 20 μsec/division. [similarly for (b)–(d)]. (b) 1 per cent above threshold. (c) 17 per cent above threshold. (d) 80 per cent above threshold. (e) Stimulated emission at 1.06 microns at room temperature. The 1.06-micron line has been isolated from normal fluorescence and stray light by means of a grating. One stimulated emission is displayed. Lower trace: 100 μsec/division. Upper trace: 20 μsec/division, 15 per cent above threshold.

[2] E. H. Carlson and G. H. Dieke, "Fluorescence spectrum and low levels of $NdCl_3$," *J. Chem. Phys.*, vol. 29, pp. 229–230; July, 1958.

[3] E. H. Carlson, "Absorption and Fuorescence Spectra of $NdCl_3$ and States of the Neodymium Ion," Johns Hopkins University Spectroscopic Rept. No. 16; March, 1960.

[4] G. D. Boyd and J. P. Gordon, "Confocal multimode resonator for millimeter through optical wavelength masers," *Bell Sys. Tech. J.*, vol. 40, pp. 489–508; March, 1961.

increased very slightly above threshold, the stimulated emission manifests itself as a series of damped oscillations, the number of such oscillations increasing rapidly with energy above threshold [Fig. 2(b), (c)], while the oscillation amplitude decay time remains roughly constant at about 35 μsec. At intensities well above threshold, the oscillations take on a "ringing" character [Fig. 2(d)], and occasionally bursts of oscillations follow the main train. At room temperature, the period between oscillations increases with time at all excitation levels employed, but at 77°K the period first increases at low levels above threshold, then decreases at higher intensities.

A more detailed presentation of the stimulated emission pattern as a function of time is obtained when the 1.06-micron line is isolated from the background of stray light and normal fluorescence by utilizing a grating. A typical example of such a pattern, shown in Fig. 2(e), is seen to consist of the relaxation oscillations superimposed on a continuum of stimulated emission which rises slowly as the oscillations decay. It is to be emphasized that the level of spontaneous emission (normal fluorescence) is too weak to be observed, and that the entire pattern consists solely of stimulated emission.

The authors would like to thank C. G. B. Garrett for several valuable discussions, and W. S. Boyle, whose early interest in the Nd^{+3} ion is gratefully acknowledged. They also wish to thank P. M. Ness for preparing the spherical ends, and R. A. Thomas and A. M. Broyer for valuable technical assistance.

L. F. Johnson
K. Nassau
Bell Telephone Laboratories, Inc.
Murray Hill, N. J.



Fig. 1—The line on top of the cavity response curve sustains oscillation as indicated by the beat phenomenon between maser and probing signal.

Fig. 2—The upper trace indicates the rectified component of the maser signal at the output of the 70-Mc amplifier. The lower trace is the reference level with the maser turned off. The difference between these two levels is 16 db.

Fig. 3—Display of the 70-Mc signal resulting from heterodyning the maser output with a klystron.

Fig. 4—Upper trace shows relative position of the two major emission lines. The two lower traces show the beat phenomenon between the maser output and the probing signal as one or the other line oscillates.

Maser Oscillation Observed from HCN Maser at 88.6 kMc*

In a previous publication,[1] the author reported observed stimulated emission from an HCN maser. At that time, no maser oscillation had been obtained.

Since the time of these earlier experiments, our HCN maser has been rebuilt. In its present form, the maser consists of a Fabry-Perot-type cavity with a plane and a spherically curved reflector ($Q=30{,}000$). The spacing between the two reflectors is arranged so that it results in a half confocal cavity.[2] This cavity is surrounded by two circular gas sources that shoot beams radially from many points of the periphery into the center of the circle, at which point the cavity is located. Each of these two planar beams passes through a state selector, which consists of two planes which are closely spaced and allow the gas beam to pass between them. Each plane is made of radially arranged rods which are charged alternatingly to positive and negative potentials of ±10,000 volts. The whole maser structure is contained in a copper cylinder which can be cooled by liquid nitrogen. Fastened on to this cylinder are copper fins that extend between the state selectors and freeze out that part of the gas beam that is rejected by them. The whole apparatus described above is mounted in a vacuum system.

As in the previous maser,[1] a probing signal can be sent through the transmission-type cavity. Two waveguides are coupled to the cavity by small holes in the flat reflector plate.

Fig. 1 shows the emission spectrum with the strongest line at 88.631 kMc tuned to the peak of the cavity response curve. This line actually sustains oscillation. The picture shows the beat note of the maser oscillation with the probing signal superimposed on the picture of the emission line. This phenomenon needs some further explanation. The cavity allows several different modes to be resonant simultaneously. The maser apparently does not oscillate in the mode that is excited by the probing signal. This explains why the maser breaks into oscillation before any appreciable gain can be observed. The electronic gain reaches only about 5 db at the point where the maser breaks into oscillation, while the insertion loss of the empty cavity is about 10 db.

The result of the maser output being heterodyned with a klystron is shown in Fig. 2. The resulting 70-Mc signal is amplified, rectified and displayed on the scope. No probing signal was passed through the cavity. The lower trace was obtained with the gas beam turned off and represents the rectified noise level. The upper trace shows the increase in level as a result of the maser output. The difference between the two levels is 16 db. The IF amplifier has a width of 20 Mc between 3-db points.

Fig. 3 shows a stroboscopic oscilloscope picture of the 70-Mc signal that is obtained by mixing the maser output with the signal from the klystron. Due to phase instability of the klystron, the scope did not achieve perfect synchronization, which explains the double trace.

Fig. 4, finally, demonstrates that both of the stronger emission lines at 88.631 kMc

* Received by the IRE, September 19, 1961.

[1] D. Marcuse, "Stimulated emission from HCN gas maser observed at 88.6 kmc," *J. Appl. Phys.*, vol. 32, p. 743; April, 1961.

[2] G. D. Boyd and J. P. Gordon, "Confocal multimode resonator for millimeter through optical wavelength masers," *Bell Sys. Tech. J.*, vol. 40, pp. 489–508; March, 1961.

and 88.633 kMc sustain maser oscillation. The upper trace shows both lines in their relative position on the cavity response curve. Subsequently, the cavity was tuned to each of the two lines in turn, and the beat note of the maser output with the probing signal (the latter at a much reduced level) is displayed in the two lower traces. As can be seen, both lines give rise to oscillation. The different traces in this picture were obtained by shifting the camera contrary to Fig. 2, where the camera stayed fixed.

Dietrich Marcuse
Bell Telephone Laboratories, Inc.
Holmdel, N. J.

High-Speed Silicon Computer Diodes as RF Switches*

The specifications of silicon computer diodes, of the type with switching speeds of less than 10 nsec, indicate the possibility of the use of these diodes as RF switches.

The use of germanium computer diodes as switches has previously been reported by Bloom;[1] at that time, the silicon computer diodes available were not suitable for this application. The low-capacitance, low-slope resistance of the forward characteristic, and high rectification efficiencies at 100 Mc, of present high-speed silicon computer diodes imply high Q and reasonable cutoff frequencies.

The Q of a number of diodes (types 1N914, 1N916, FD100, and FD200) were measured by a cavity perturbation method at 408 Mc, the measured values corresponding to cutoff frequencies of from 20 to 40 kMc at zero bias. The capacitance and capacitance-voltage characteristic were measured at $10/\pi$ Mc at an applied RF level of less than 10 mv. The capacitances at zero bias were considerably smaller than the manufacturer's specified nominal value; for example, the average value for twelve FD200 was 1.63 pf at zero bias (nominal value 5.5 pf), and for twelve 1N916 0.97 pf (nominal value 1.6 pf). The C-V characteristic was also much less nonlinear than expected.

A number of diodes were tested in a SPDT radiometer switch at a frequency of 408 Mc. The insertion loss of typical diodes was 0.3 db, and the isolation greater than 26 db, using appropriate external series and shunt reactances for tuning out the diode internal reactances in the ON and OFF directions.

The RF performance and Q were found to be correlated with the junction capacitance, in that high-capacitance samples gave inferior performance. Measurements of 50 diodes indicate that this type of diode can quite generally be used as an RF switch element at frequencies up to approximately 1.5 kMc, with over 80 per cent of diodes giving high performance comparable to special varactor diodes.

High-speed silicon computer diodes accordingly can be considered as an economic and efficient substitute for special-purpose silicon diodes for RF switching applications.

R. E. Aitchison
School of Elec. Engrg.
University of Sydney
Sydney, N.S.W., Australia

*Received by the IRE, August, 11, 1961.

[1] M. Bloom, "Microwave switching with computer diodes," *Electronics*, vol. 33, pp. 85–87; January 15, 1960.

Use of a Coherent Memory Filter in Spectral Measurements of Atmospheric Whistlers*

It is often of interest to know the spectrum of a signal. This measurement has been performed by devices which could be divided, with few exceptions, into two groups: the heterodyne type and the bank-of-filters type. The heterodyne type of spectrum analyzer utilizes a fixed narrow-band intermediate-frequency filter and a tunable local oscillator. This device does not analyze the spectrum in real time, *i.e.*, the read-out time of the device is very long compared to the duration of the signal. It is not possible to measure the entire spectrum without recording the signal and playing it back many times.

The second type of spectrum analyzer employs a bank of filters. The measurement of the spectrum with this device can take place in real time, so that this type of analyzer has an advantage over the previous one in this respect. However, it is cumbersome to implement a bank of filters, and, in addition, it yields only a gross approximation of the signal spectrum.

A different approach to the spectrum analysis measurement problem has been implemented. This approach utilizes a recirculating delay-line-heterodyner feedback loop to obtain an excellent approximation of the signal spectrum in real time, as pointed out previously.[1] This device is known as the coherent memory filter, and it has the advantages with respect to the bank of filters of being capable of observing rapid changes in the input spectrum that occur from one processing period to the next, and of providing continuous spectral coverage. In addition, the processing period, or integration time, of the coherent memory filter is easily adjustable so that variable-resolution analysis of nonstationary spectra is possible. This is the equivalent of continually changing the number of filters, and their bandwidths, in a filter bank consisting of hundreds of filters.

One class of signals whose spectra yield much valuable information is that of atmospheric whistlers. The coherent memory filter was used to analyze the spectra of these signals, and the experimental results are shown in Figs. 1 and 2. It was found experimentally that a processing time of about 20 msec is desirable for the measurement of the spectra of these signals. The frequency coverage of the spectral analysis was 0 to 8 kc since it was found that there was very little energy outside this band. The input signal was time-weighted with a symmetrical triangular function, so that an effective resolution of about 73 cps was obtained. Thus, roughly speaking, the equivalent of a filter bank with approximately 110 filters, each with an effective bandwidth of 73 cps, was synthesized.

Fig. 1—Spectral analysis illustrating the evolution of an atmospheric whistler.

Fig. 2.

* Received by the IRE, August 10, 1961. This paper was presented at the URSI Convention, Washington, D. C., May, 1961.

[1] J. Capon, "High-speed Fourier analysis with recirculating delay-line-heterodyner feedback loops," IRE Trans. on Instrumentation, vol. I-10, pp. 32–37; June, 1961.

Acknowledgment

The atmospheric whistler signals were supplied on a tape recording through the kindness of Prof. R. A. Helliwell of Stanford University.

J. Capon
M. R. Weiss
Federal Scientific Corp.
New York, N. Y.

Injection Efficiency in Double Diffused Transistors*

Emitters in double diffused transistors have a rapidly varying impurity distribution which causes a built-in electric field that opposes the flow of minority carriers injected into the emitter. As a result, the injected minority carrier concentration falls rapidly as a function of distance from the emitter-base junction toward the emitter contact, and it is already low within one diffusion length from the junction. Earlier calculations of injection efficiency neglecting either electric field or carrier lifetime are not adequate for this situation. An approximate formula including both is given in this note.

Consider an n-p-n transistor and define a common-emitter injection efficiency gain parameter by

$$\beta_\gamma = \left| \frac{J_{n1}}{J_{p1}} \right|$$

where J_{n1} is electron density in the base at the edge of the emitter-depletion region and J_{p1} is hole density in the emitter at the edge of the depletion region. In the base it is satisfactory to assume infinite lifetime and to calculate J_{n1} by the method of Moll and Ross.[1]

$$J_{n1} = q \frac{D_n N_{A1} n_1}{w \bar{N}_A}$$

where N_{A1} is acceptor concentration in the base at the edge of the depletion region, n_1 is electron concentration, $\bar{N}_A$ is average acceptor concentration in the base, w is base width, q is electron charge, and D_n is electron diffusion constant.

In the emitter, we have in the usual notation

$$\frac{1}{q}\frac{dJ_p}{dx} + \frac{p}{\tau p} = 0$$

$$J_p = q\mu_p \cdot pE - qD_p \frac{dp}{dx}.$$

Let

$$L_p = \sqrt{D_p \tau_p} \qquad Z = \frac{x}{L_p} \qquad \eta = \frac{qEL_p}{2kT}.$$

Combining the differential equations and using the Einstein relation, we have

$$\frac{d^2p}{dZ^2} - 2\frac{dp}{dZ} - p\left(2\frac{d\eta}{dZ} + 1\right) = 0.$$

The field parameter is obtained from the impurity profile by

$$\eta = -\frac{1}{2N_D}\frac{dN_D}{dZ}.$$

Now we represent the impurity profile by an approximate expression which is tractable in the differential equation. We choose

$$N_D = cx^a.$$

Then

$$\eta = -\frac{a}{2Z}.$$

Typical profiles can be represented satisfactorily with a suitable choice of a. For a practical silicon transistor design example, a value of a of about 2.8, with the origin for Z displaced slightly from the emitter junction, gave reasonable agreement with impurity densities and electric-field values calculated from the exact relations.[2]

The differential equation becomes

$$\frac{d^2p}{dZ^2} + \frac{a}{Z}\frac{dp}{dZ} - p\left(1 + \frac{a}{Z^2}\right) = 0,$$

which is a form of Bessel's equation. For cases where $(1+a)/2$ is not an integer, the solution is

$$p = Z^{(1-a)/2} A\left[J_{(1+a)/2}(-iZ) + BJ_{-(1+a)/2}(-iZ)\right]$$

where the J's are Bessel functions and $i = \sqrt{-1}$.

We must calculate the hole current in the emitter at the edge of the depletion region. With the junction forward biased, the depletion region extends about 10^{-5} cm from the junction. If the hole-diffusion constant is as small as 2 cm²/sec and the lifetime as small as 10 nsec, the diffusion length is 1.4×10^{-4} cm. Z is then 10^{-1} or smaller, and we may expand the Bessel functions as follows:[3]

$$p = Z^{(1-a)/2}\frac{A(-iZ)^{(1+a)/2}}{2^{(1+a)/2}\Gamma\left(\frac{3+a}{2}\right)}\left(1 - \frac{1}{1!\left(\frac{3+a}{2}\right)}\left(\frac{-iZ}{2}\right)^2 + \cdots\right)$$
$$+ \frac{B(-iZ)^{-(1+a)/2}}{2^{-(1+a)/2}\Gamma\left(\frac{1+a}{2}\right)}\left(1 - \frac{1}{1!\frac{(1-a)}{2}}\left(\frac{-iZ}{2}\right)^2 + \frac{1}{2!\left(\frac{1-a}{2}\right)\left(\frac{3-a}{2}\right)}\left(\frac{-iZ}{2}\right)^4 \cdots\right).$$

Redefining the arbitrary constants and retaining only the leading terms,

$$p \approx AZ + B\left[Z^{-a} + \frac{Z^{2-a}}{2(1-a)}\right]$$

We shall now assume that the boundary condition at the emitter contact is such that A is not large compared with B. (The solution to the differential equation can be written in closed form when the parameter a is an even integer. This has been done for $a=2$ and $a=4$ and the ratio $|A/B|$ has been evaluated for the case of an emitter contact with infinite recombination velocity. Provided that the emitter is several diffusion lengths wide, the magnitude of the ratio was found to be less than, or equal to, 1.) We may then drop the first term in p. At the edge of the depletion region,

$$Z = Z_1, \qquad p = p_1 \text{ so } B \approx p_1 Z_1^a$$

and

$$p \approx p_1 Z_1^a\left[Z^{-a} + \frac{Z^{2-a}}{2(1-a)}\right].$$

The first term in the bracket gives the equilibrium hole density at the edge of the depletion region; only the second term contributes to the current. Current density is found from

$$\frac{L_p J_p}{qD_p} = 2\eta p - \frac{dp}{dZ} = \frac{-ap}{Z} - \frac{dp}{dZ}.$$

Evaluating J_p at Z_1 and returning to the original variables we find

$$J_{p1} = \frac{-qD_p p_1}{\frac{q}{kT}E_1 L_p^2}\frac{1}{\left(1 - \frac{1}{a}\right)}.$$

Then

$$\beta_\gamma = \frac{D_n}{D_p}\frac{\frac{q}{kT}E_1 L_p^2 N_{A1} n_1}{w\bar{N}_A p_1}\left(1 - \frac{1}{a}\right)$$

$$\beta_\gamma = \frac{D_n N_{D1}\frac{q}{kT}E_1 \tau_p}{w\bar{N}_A}\left(1 - \frac{1}{a}\right).$$

This result differs from previous calculations by the proportionality to lifetime rather than to diffusion length in the emitter, and by the specification of field and donor concentration at the edge of the depletion region in the emitter. A very similar result is obtained for constant field in the emitter.[4]

Melvin Klein
Components Div.
International Business Machines Corp.
Poughkeepsie, N. Y.

* Received by the IRE, August 15, 1961.

[1] J. L. Moll and I. M. Ross, "The dependence of transistor parameters on the distribution of base layer resistivity," Proc. IRE, vol. 44, pp. 72–78; January, 1956.

[2] D. P. Kennedy provided machine calculations based on work that he is publishing.

[3] P. M. Morse and H. Feshback, "Methods of Theoretical Physics, Part I," McGraw-Hill Book Co., Inc., New York, N. Y., p. 619; 1953.

[4] W. E. Harding, private communication.

Antenna Size for a Space Vehicle*

Directional antennas on space vehicles have grown to the size where they have become a significant portion of the space vehicle. With their small beamwidth, they require a considerable amount of associated equipment and structure to control and power them. This letter shows that the weight of an area-limited directional-transmitting antenna, together with all of the associated gear and structure used to operate it, should weigh $\frac{2}{3}$ the weight of the transmitter and its associated gear and structure. Included in the definition of associated gear is everything which is directly needed to operate the device, such as solar panels, storage batteries, structural members for holding the solar panels and batteries, drive motors, control equipment, and heat sinks. It does not include such weights as are associated with data processing, scientific experiments, and receiving equipment.

* Received by the IRE, August 18, 1961.

The power P_t of the transmitter is assumed to be directly proportional to its size in terms of its weight W_t:

$$P_t = k_1 W_t.$$

It is assumed that a transmitter tube which is capable of putting out twice the power of another tube would require twice the weight in solar panels, structures, heat sinks, etc. The gain of the directional antenna G_a is assumed to be directly proportional to the area of the antenna. The area of the antenna is related to the volume, such that the gain G_a is a direct function of the weight to the $\frac{2}{3}$ power:

$$G_a = k_2 W_a^{2/3}.$$

That is, the weight is proportional to the dimension cubed, while the gain is proportional to the dimension squared. The weight of associated equipment to operate the antenna must be added to the actual weight of the antenna. It is assumed to be directly proportional to the weight of the antenna.

For a given weight W of the transmitter and antenna, it is desirable to have the maximum effective power radiated P. This is the product of the transmitter power and the antenna gain.

$$P = P_t G_a = k W_t W_a^{2/3}$$
$$W = W_t + W_a.$$

Maximization of P subject to the weight constraint produces the following result:

$$W_a = \tfrac{2}{3} W_t;$$

i.e., the weight of the antenna should be $\frac{2}{3}$ the weight of the transmitter.

C. S. Lorens
Space General Corp.
Glendale, Calif.

Input-Output Relationships for Multisampled Loop Systems*

In his recent note[1] Dr. Tou made a statement to which I wish to take exception. In referring to a paper that I co-authored,[2] he said, " . . . the methods proposed in the literature appear either quite involved or lack of generality." The method introduced in my two papers[2,3] is, I feel, simpler to use than Dr. Tou's, and, furthermore, is just as general an approach for determining the output of these systems in terms of their input(s) and system parameters.

So that the readers may judge for themselves, I will state the method here and illustrate it by solving the same example as Dr. Tou did in his note. Further, I will present a more complicated example and ask the reader to try both methods and then judge for himself which is simpler.

Generally speaking, the approach is to represent the given system block diagram by an appropriate signal-flow graph (I call it a sampled-signal-flow graph, he calls it a pulsed-signal-flow graph) to which Mason's theorem can be applied. Note, that in words, both of our techniques sound the same; however, the differences lie in the choice of the type of flow graph used and the procedure employed in going from the block diagram to this flow graph.

I propose a six step procedure for going directly from the block diagram to the sampled-signal-flow graph—no mathematics in between! After this sampled-signal-flow graph is completed, step seven is to apply Mason's theorem and to write the output by inspection. The following is the proposed procedure:

1) Eliminate all redundant samplers in the original block diagram. This step is not necessary for correct results, but it simplifies the resulting flow graph.
2) Number all samplers (in any fashion desired).
3) On a separate sheet of paper draw a node for each sampler indicated in step 2) and label these S_1^*, S_2^*, $\cdots$, S_n^*.
4) Open all samplers in the block diagram.
5) Start from sampler 1 and traverse all possible continuous paths from the output of sampler 1 to the input of all samplers. Where these exist, draw in a branch on the signal-flow graph from node S_1^* to the respective node S_k^* with the direction and the appropriate sampled transfer function indicated. Then start at sampler 2 and repeat procedure until all samplers are covered.
6) Now add two other nodes: one labeled with a 1 (the input), and one labeled with a C (the output). From the input node draw a branch to each of the nodes which has a corresponding continuous path in the block diagram, and label with the appropriate gain (RG_{io}' to the output, and $\overline{RG_{isk}}^*$ to the other nodes). Then draw a branch from each of the nodes S_k^* which has a corresponding continuous path in the block diagram to the output node C and label appropriately (G'_{sko}).
7) Then to obtain the output of the system, apply Mason's or Coates' method to the nodes marked C and 1 of this sampled-signal-flow graph.

If the sampled form of the output is desired, one may use the standard technique of starring the expression for C obtained in 7).

Let us now work out the example presented by Dr. Tou. After applying step 1) of our procedure, his block diagram reduces to that shown in Fig. 1(a). By applying rules 2–6 to this block diagram, the corresponding sampled-signal-flow graph [Fig. 1(b)] can be drawn directly. Then, by applying Mason's theorem to this flow graph, we can write the expression for the output

$$C(s) = R_1G_1G_2(s) + R_2G_2(s) + \frac{(\overline{R_1G_1G_2}^* + \overline{R_2G_2}^*)(G_1G_2H_1 + G_2H_2)}{1 + \overline{G_2H_2}^* + \overline{G_1G_2H_1}^*}. \quad (1)$$

This completes the example.

Let us now consider the system whose block diagram is shown in Fig. 2(a). There are no redundant samplers in this system, so step 1) may be skipped. By applying rules 2–6 to this block diagram, its corresponding sampled-signal-flow graph [Fig. 2(b)] can be drawn directly. Again, by applying Mason's theorem, the expression for the output may be written:

$$C(s) = \frac{R^*G_1^*G_2^*G_3}{1 + \overline{G_1H_1}^* + H_2^*\overline{G_2H_3}^* + G_1^*G_2^*\overline{G_3H_6}^*H_5^* + G_1^*G_2^*\overline{G_3H_4}^* + \overline{G_1H_1}^*H_2^*\overline{G_2H_3}^*}. \quad (2)$$

George G. Lendaris
Dept. of Elec. Engrg.
University of California
Berkeley, Calif.



Fig. 1—(a) Block diagram for the illustrative example 1. (b) Sampled-signal-flow graph for this system.



Fig. 2—(a) Block diagram for the illustrative example 2. (b) Sampled-signal-flow graph for this system.

* Received by the IRE, April, 14, 1961.

[1] J. T. Tou, "A simplified technique for the determination of output transforms of multiloop, multisampler, variable-rate discrete-data systems," Proc. IRE, vol. 49, pp. 646–647; March, 1961.

[2] G. G. Lendaris and E. I. Jury, "Input-output relationships for multisampled loop systems," *Trans. AIEE*, vol. 78 (*Applications and Industry*, no. 78), pp. 375–485; January, 1960.

[3] G. G. Lendaris, "Discussion on 'A general flow graph technique for the solution of multiloop sampled systems' R. Ash, W. H. Kim, and G. M. Kranc," *Trans. ASME, J. of Basic Engrg.*, vol. 82, pp. 360–370; June, 1960.

Contributors

W. S. Boyle

Willard S. Boyle was born in Nova Scotia, Canada, on August 19, 1924. He received the B.Sc., M.Sc., and Ph.D. degrees from McGill University, Montreal, Canada, in 1947, 1948, and 1950, respectively.

After joining the Technical Staff of Bell Telephone Laboratories, Murray Hill, N. J., he was concerned with electrical discharge phenomena in low-voltage contacts. He later studied optical properties of metals in the far infrared and at very low temperatures. For the past three years, he has headed a group studying optical properties of solids and microwave characteristics of semimetals. He has also been engaged in research in the infrared spectroscopy of solids.

Dr. Boyle is a member of the American Physical Society and Sigma Xi.

❖

R. H. Doherty

Robert H. Doherty (SM'59) was born in Albert Lea, Minn., on May 9, 1927. He received the B.S. degree from the University of Colorado, Boulder, in 1950.

In 1951 he joined the National Bureau of Standards, Boulder, Colo. In 1954 joined the Navigation Systems Section of the Radio Systems Division, where he is now an Electronic Engineer, and Project Leader of the Navigation Systems Analysis project, and the Loran-C Clock and Distribution System project. His work involves over-all concepts of navigation and timing systems.

Mr. Doherty is an associate member of Commission III of URSI, a member of Sigma Pi Sigma, and of Study Groups VI and XIII of CCIR.

❖

Eduard A. Gerber (A'50–SM'56–F'58) was born in Fuerth, Bavaria, Germany, on April 3, 1907. He received his education at the Institute of Technology in Munich and Berlin, Germany. From the former, he received the M.S. degree in 1930 and the Ph.D. degree in 1934, both in physics.

In 1935 he joined the Scientific Staff of the Carl Zeiss Works, Jena, Germany, and was in charge of research and development in piezoelectric crystals. From 1947 to 1954 he was a Consultant to the Signal Corps Engineering Laboratories, Fort Monmouth, N. J., on all matters pertaining to frequency control, and from 1954 to 1961 he served as Director of the Frequency Control Division, USASRDL. Since February, 1961, he has been Director of the newly organized Solid State and Frequency Control Division.



E. A. Gerber

Dr. Gerber is a member of the IRE Standards Committee and the IRE Committee on Piezoelectric and Ferroelectric Crystals. He was Chairman of the latter Committee from 1958–1960. He is also a member of Commission I of the International Scientific Radio Union and a Technical Advisor, Committee on Piezoelectric Crystals and Associated Devices, U. S. National Committee of the International Electrotechnical Commission.

❖



G. Hefley

Gifford Hefley was born in Norman, Okla., on September 12, 1915. He received the B.A. degree from the University of Oklahoma, Norman, in 1938.

He joined the National Bureau of Standards, Washington, D. C., in 1949, and transferred to the NBS Boulder Laboratories in 1951, where he is now Chief of the Navigation Systems Section of the Radio Systems Division. Prior to joining NBS, he was a radio engineer with the U. S. Signal Corps, a Loran Project Engineer with the Air Force at Wright Field, and a Development Engineer with Petty Laboratories. One of his major interests is in time-position relationships; he has supervised the development of the Loran-C clock, done research work on ground conductivity, and has also worked on propagation problems on VLF navigation systems.

Mr. Hedley is a member of RESA, and Study Group VII of CCIR.

❖

G. Clement Ireland (M'60) was born in Vancouver, British Columbia, Canada, on April 18, 1924. After serving in World War II with the Royal Canadian Artillery, he attended the University of Saskatchewan, Saskatoon, where he received the B.S. degree in electrical engineering in 1950.

G. C. Ireland

From 1950 to 1957, he was employed by the Department of National Defence, Ottawa, Canada, as a civilian electrical engineer, first with the Naval Services and then with Canadian Military Electronics Standards Agency. In 1957, he transferred to the Radio Regulations Division of the Canadian Department of Transport, in Ottawa, where he is presently employed in allocation studies for AM, FM, and TV broadcasting stations.

Mr. Ireland is a member of the Association of Professional Engineers of Ontario and of the Engineering Institute of Canada.

❖



P. P. Kisliuk

Paul P. Kisliuk was born in Philadelphia, Pa., on February 22, 1922. He received the B.S. degree in 1943 from Queens College, N. Y., and the M.A. and Ph.D. degrees from Columbia University, New York, N. Y., in 1947 and 1952, respectively.

He has been a member of the Technical Staff of Bell Telephone Laboratories, Murray Hill, N. J., since 1952, where he has been engaged in research in contact and surface physics. His studies have included problems at relay contacts and adsorption of gases on metals. Recently his work has been concerned with optical masers.

Dr. Kisliuk is a member of the American Physical Society and Sigma Xi.

❖



R. F. Linfield

Robert F. Linfield (SM'59) was born in Bozeman, Mont., on November 20, 1925. He received the B.S. degree in engineering physics from the University of Colorado, Boulder, in 1956.

He joined the National Bureau of Standards, Washington, D. C., in 1948, where he did missile development work; from 1951 to 1954 he was employed at the NBS Missile Division, Corona, Calif.; and from 1954 to 1961 he worked at the NBS Navigation Systems Section in Boulder, Colo. He was a

Project Leader in the NBS Radio Navigation Section and did intensive research on the Loran-C system. Prior to NBS, he was a U. S. Navy Radar Technician, and currently he is employed by DECO Electronics Inc., Boulder, Colo.

Mr. Linfield is an associate member of Commission III of URSI.

❖

Ivars Melngailis (M'59) was born in Riga, Latvia, on November 13, 1933. He received the B.S., M.S., and Ph.D. degrees in electrical engineering from Carnegie Institute of Technology, Pittsburgh, Pa., in 1956, 1957, and 1961, respectively. During the academic year 1957–1958, he studied physics at the University of Munich, Germany, under a Fulbright Fellowship.

I. Melngailis

In 1958–1959 he was an Instructor in electrical engineering at the Carnegie Institute of Technology, and in 1960, a Project Engineer studying low-temperature electrical properties of germanium. At present he is a member of the Applied Solid-State Physics staff at the M.I.T. Lincoln Laboratory, Lexington, Mass., engaged in research on electrical and magnetic phenomena in semiconductors and semiconductor devices.

Dr. Melngailis is a member of Tau Beta Pi, Eta Kappa Nu, and Sigma Xi.

❖

Norman H. Meyers (SM'59) was born in Buffalo, N. Y., on February 11, 1931. He received the B.E.E. degree from Rensselaer Polytechnic Institute, Troy, N. Y., in 1952, and the S.M. and Sc.D. degrees in electrical engineering from the Massachusetts Institute of Technology, Cambridge, in 1954 and 1957, respectively.

N. H. Meyers

He remained at M.I.T. as an Assistant Professor of Electrical Engineering from 1957 to 1958, and did research in the classical electrodynamics of moving media. In 1958 he joined the staff of the research laboratory of IBM Corporation, Yorktown Heights, N. Y., where he has been engaged in the research and development of high-speed thin-film superconducting circuitry.

Dr. Meyers is a member of Tau Beta Pi, Eta Kappa Nu, Sigma Xi, and the Scientific Research Society of America.

❖

M. H. Miles was born in Blount County, Ala., on December 26, 1935. He received the B.S. degree in electrical engineering from the University of Tennessee, Knoxville, in 1959. While in school he worked with Southern Bell Telephone and Telegraph Company, Memphis, Tenn.

M. H. Miles

After working briefly with Southern Bell in Nashville, Tenn., he served in the Army from 1959 to 1961 at the U. S. Army Signal Research and Development Laboratory, Fort Monmouth, N. J. In 1961 he returned to his former position as Assistant Engineer with Southern Bell in Nashville.

He has been a member of Eta Kappa Nu and a student member of AIEE.

❖

Arthur G. Milnes (SM'58) was born in England on July 30, 1922. He received the B.S. degree in electrical engineering in 1943, and the M.S. degree in 1947 from the University of Bristol, England. From 1947 to 1950 he carried out research work at the University on magnetic amplifiers. In 1956 for a book on this subject and for other research papers he was awarded the D.Sc. degree.

A. G. Milnes

From 1943 to 1957 he held Scientific Officer posts at the Royal Aircraft Establishment, Farnborough, Great Britain, apart from the academic year 1954–1955, which was spent on a Royal Society-National Academy of Science Fellowship at Carnegie Institute of Technology, Pittsburgh, Pa. In 1957 he returned to C.I.T. where he is now Professor of Electrical Engineering, with major research interests in the semiconductor device and solid-state fields.

Dr. Milnes is a member of the AIEE and the IEE (London).

Robert H. Norton was born in New York, N. Y., on February 5, 1935. He received the B.S. and M.S. degrees in astrophysics from the California Institute of Technology, Pasadena, in 1957 and 1958 respectively. He has been working on a doctoral program in astrophysics at C.I.T. and expects to complete his dissertation in 1962.

R. H. Norton

From 1958 to 1961 he has been employed part time at the Jet Propulsion Laboratories of the California Institute of Technology and has worked on such projects as the Deep Space Instrumentation Facility in the Telecommunications Division, and the gas bearing research conducted in the Guidance and Control Division. In 1961 he joined JPL full time as Research Engineer in the Guidance and Control Research section.

Mr. Norton is a member of the American Astronomical Society.

❖

Chih-Tang Sah (S'50–M'57), for a photograph and biography, please see page 651 of the March, 1961, issue of these Proceedings.

❖

Robert L. Wildey was born in Los Angeles, Calif. on August 22, 1934. He received the B.S. and M.S. degrees in astronomy from the California Institute of Technology, Pasadena, in 1957 and 1958, respectively. He is presently completing his doctorate at the Mount Wilson and Palomar Observatories, Pasadena.

R. L. Wildey

During the summers of 1958 and 1959, he worked in the Guidance Research Section at the Jet Propulsion Laboratory, C.I.T. His research has been in the fields of galactic structure and stellar evolution, photoelectric and photographic stellar photometry, line-blanketing effects in stellar atmospheres, solar corpuscular radiation and the interplanetary dust cloud, and the measurement of planetary diameters.

Mr. Wildey is a member of the American Astronomical Society and Sigma Xi.

Books

Adaptive Control Processes: A Guided Tour, by Richard Bellman

Published (1961) by Princeton University Press, Princeton, N. J. 247 pages+5 index pages+xvi pages +bibliography by chapter. Illus. 6¼×9¼. $6.50.

This reviewer should like to state at the outset that if he were asked to name an individual whose work is likely to have by far the greatest impact on the course of development of control theory in the years ahead, he would answer without a moment's hesitation: Richard Bellman.

Until the publication of the present volume, much of Bellman's work was inaccessible to a large body of scientific workers and engineers whose lack of mathematical sophistication prevented them from penetrating the barriers presented by such mathematical elements in Bellman's theory as functional equations, invariant imbedding, policy space, etc. Indeed, it is largely because of the presence of such barriers that there are still many control engineers who have not fully grasped the significance of Bellman's contributions and are only dimly aware of the potency of dynamic programming and related techniques.

On the surface, the book under review gives the appearance of a popularized and somewhat sketchy exposition of a wide gamut of ideas and techniques contributed by Bellman, together with a discussion of their relation to more classical approaches. In fact, it is much more than that. Upon careful perusal, one finds a wealth of incisive comments and enlightening observations which give the reader much insight into some of the most fundamental aspects of modern control theory. Throughout, the major aim is to lay clear the basic ideas and the motivation rather than to fill in the technical details. In this, the author succeeds admirably.

The range of topics covered by the text is extremely wide. Some are treated fairly completely, some are merely touched upon. Understandably enough, the subject that receives most attention is dynamic programming, its applications, and its relation to the calculus of variations.

To be more specific, Chapters 1 and 2 introduce the reader to the concept of state, the fundamentals of dynamical systems, and some variational problems. Chapter 3 is given over to an introductory discussion of multistage decision processes. Here the author states his "principle of optimality" and points out its connection with a basic property of the maximum, namely, Max $(x_1, x_2, \cdots, x_n) = \text{Max}\ (x_1, \text{Max}\ (x_2, \cdots, x_n))$. Chapters 4 and 6 present a very illuminating analysis of the relation between dynamic programming and the calculus of variations—especially the Lagrange multiplier method. The computational aspects of dynamic programming are discussed in Chapters 5 and 6, with the latter chapter treating the two-point boundary value problems. The application of dynamic programming to some problems in finite-state systems is discussed very briefly in Chapter 8. In the opinion of this reviewer, it is such systems, both of deterministic and stochastic types, that offer dynamic programming one of its most fruitful areas of application.

The remaining chapters are concerned in the main with stochastic systems and Markovian decision processes. Of particular interest here is a theory of adaptation—based on dynamic programming—which was developed by Bellman and his talented collaborator, R. Kalaba. In contrast with other theories of adaptation, the Bellman-Kalaba theory leads to systems which are optimally adaptive in a well-defined and very reasonable sense. Unfortunately, "the curse of dimensionality" makes the practical implementation of the Bellman-Kalaba theory rather difficult and frequently uneconomical.

The book closes with a chapter devoted to the subject of successive approximations. Such techniques, as well as iterative procedures based on the contraction principle, are particularly well suited for use with machine computers and, thus, are likely to gain increasing importance with advances in computer technology. Another important advantage of such techniques, particularly when they lead to monotone convergence, is that the iteration may be stopped as soon as the solution is judged to be "good enough" rather than truly optimal. In this way, one obtains, in effect, a "suboptimal" policy which is acceptably close to the optimal policy.

The book is written in a style which is Bellman's trademark—fresh, non-conformist, incisive and impatient with detail. It is replete with numerous comments, observations, quotations, anecdotes, references and, most important, carefully chosen examples. It is addressed to the neophyte and yet contains much that is new to the expert. In short, it is the work of a leading thinker of our time and a master of both oral and written exposition.

L. A. Zadeh
Dept. Elec. Engrg.
University of California
Berkeley, Calif.

The Physical Theory of Transistors, by Leopoldo B. Valdes

Published (1961) by McGraw-Hill Book Co., Inc., 330 W. 42 St., New York 36, N. Y. 358 pages+12 index pages+xiv pages. Illus. 6¼×9¼. $10.50.

This is a textbook which covers precisely the field stated in its title. It is unusually well organized to teach a well-defined subject. While providing the necessary background, diversions are carefully avoided. For the teacher, student, or practicing engineer entering the field, this book deserves first consideration. Although not intended as a reference work, the book will also be useful to the specialist who occasionally needs to refresh his memory on a textbook point.

Dr. Valdes has divided his book into three parts. Part I, Introductory Concepts, provides an easy entrance, a welcome mat, to the student. The student will encounter no difficulty here other than that imposed by new concepts. This sixty page, elementary but thorough, introduction will be very helpful. Problems are provided with each chapter.

Part II, Electronic Properties of Semiconductor Materials, occupies slightly more than one-half of the 360 pages of the book and is the "main course." Although the basic physics may be familiar to physics students, the detailed application to the electronic behavior of semiconductors will be new. The student lacking in physics background will find the text sympathetic but nature unmerciful. This book provides a clearer introduction to semiconductor physics than will be found among most books of comparable depth, but the electrical engineering student is well advised to cultivate in advance at least a liking for physics.

Electron energy levels in atoms and in crystals are discussed without actually giving Schrodinger's equation. Hence the mathematical tools and physics of quantum mechanics are not required although the pertinent results are given. The Fermi statistics is similarly treated. Following the universal practice, the approach to statistical equilibrium is treated as a topic unrelated to the statistical state of equilibrium. A better appreciation of the physical processes might be given by keeping these topics together. Also, the replacement of physical models by mathematical models in quantum theory does not justify the loss of mechanical visualization throughout physics. Specifically, the generation and recombination of carriers can better be taught in terms of probability theory, using models resembling the dog-flea problem, for special cases, rather than by a generalized, mathematical treatment. With an appropriate Fermi distribution of antisocial fleas, the dog-flea analogs for holes, electrons, and traps will provide unlimited material for visualization. The teacher will find no single source of good tutorial material on this topic.

Part II concludes with a lucid discussion of thermoelectric, optical, magnetic, and surface effects. The treatment of the first three of these phenomena is appropriately brief since they are peripheral topics in transistor physics.

Part III, Properties of Semiconductor Devices, applies the ideal p-n junction theory developed in detail in Part II to real diodes and transistors. Fabrication methods and limitations are mentioned. Some equivalent circuits are included to describe devices, but circuit analysis, as such, is not within the province of this text.

The teacher and student will find the book exceptionally well planned and rich in clear explanations of new concepts.

M. A. Clark
Pacific Semiconductors, Inc.
Culver City, Calif.

An Introduction to the Principles of Communication Theory, by John C. Hancock

Published (1961) by McGraw-Hill Book Co., Inc., 330 W. 42 St., New York 36, N. Y. 248 pages+5 index pages+x pages. Illus. 6¼×9¼. $9.50.

Those of us who have been out of touch with undergraduate engineering education for 20 years or more may have something of a shock in store if we have occasion to investigate what has happened in the meantime. For this reviewer, the first indication of the drastic change that has taken place came when his son reported having finished calculus in the first two terms of his freshman year and devoting the third term to differential equations. A further indication was the fact that the son's sophomore year included subjects the father studied in graduate school. Despite these forewarnings, it still comes as a shock to learn (on reviewing the current book) that undergraduates now learn at least the rudiments of Wiener filter theory as a minor sub-topic of a one semester, senior level, required course. Those who can recall the awe with which Wiener's original "Yellow Peril"[1] was regarded can appreciate the significance of this development.

Of course, the treatment of Wiener filters is by no means complete and neither is it rigorous. The essence is nevertheless there including the concept of spectrum factorization. Though the development does not exactly prove the result, it does have an element of plausibility that may satisfy the less critical student. The one real serious omission is the lack of any mention of Wiener's name. It is true that the undergraduate is likely to derive little benefit from a reference to the original work, but it does seem that the author of so important a contribution deserves some mention. Similar comments can be made about several other sections of the book, there being no mention of important contributors such as Nyquist, North, VanVleck and Middleton, etc., although their results are presented.

As indicated, Wiener filters are only a minor sub-topic in this book. The book is primarily an introduction to the use of probabalistic and statistical methods for handling noise and other nondeterministic problems. According to the author's preface, prerequisites include two semesters of electronics and a networks course which treats Fourier and Laplace transforms. A course in probability is regarded as helpful but not required. The book starts with a review of frequency and time domain relations and includes chapters on modulations, random signal theory, noise, and communication systems. The chapter titles are not too descriptive. The chapter on network analysis is actually concerned with operations on random signals and it is here that Wiener filters are treated as a sub-topic of the topic "Optimum Systems." Similarly, the chapter on communication systems includes a treatment of radar detection problems.

In such a book, one cannot, of course, expect great depth of treatment. Shannon's basic coding theorem, for example, is stated but not proved. The section on radar detection makes no mention of fluctuating targets. On the other hand, the student who completes this course will have had at least nodding acquaintance with a wide variety of topics including autocorrelation and spectral density; Gaussian and Rayleigh probability distributions; delta functions; Bessel and hypergeometric functions; the sampling theorem; entropy, redundancy, and equivocation; etc. The reviewer cannot help but approve of including this type of material in the undergraduate curriculum.

The author appears to have done a good job of matching the material to the capabilities of the students. He has also included a liberal supply of problems to be solved. These problems appear well designed to impress the basic points on the minds of the students. Perhaps the greatest danger of such a course is that the student will emerge unaware of his own ignorance or of how much there is yet to be learned. Reasonable precautions on the part of the instructor, however, will minimize this danger.

Warren D. White
Airborne Instruments Lab. Div.
Cutler-Hammer, Inc.
Melville, N. Y.

[1] Norbert Wiener, "The Extrapolation, Interpolation, and Smoothing of Stationary Time Series with Engineering Applications," John Wiley and Sons, Inc., New York, N. Y.; 1949. Originally published as a classified report to Section D_2, National Defense Research Committee.

Proceedings of URSI Thirteenth General Assembly, John P. Hagen, Ed.

Publication 880 (1961), National Academy of Sciences, Printing and Publishing Office, Washington 25, D. C. 595 pages+ii pages. Illus. 9×11. Paper Binding. $5.00.

For the first time, the Proceedings of a General Assembly of URSI are being made available to the general public in book form. The International Scientific Radio Union (abbreviated as URSI from the French title, Union Radio Scientifique Internationale), with several hundred delegates from some 20 different countries, holds its General Assembly every three years. Recent assemblies have been held in Zurich, Switzerland, Sydney, Australia, The Hague, Netherlands, Boulder, Colo.; and this one (the thirteenth) in London, England. The functions of a General Assembly are to review, on a worldwide basis, the progress of the past 3 years in radio science, and to plan for the future. This book, constituting the report of the USA National Committee of URSI, records the progress of radio science from 1957 to 1960, perhaps the most exciting three-year period in its history.

The fields of URSI are delineated by its seven commissions which are: I, Radio Standards and Methods of Measurement; II. Tropospheric Radio Propagation; III. Ionospheric Radio Propagation; IV. Radio Noise of Terrestrial Origin; V. Radio Astronomy; VI. Radio Waves and Circuits; VII. Radio Electronics. The book presents a wealth of up-to-the-minute research results in each of these areas. Of great value to the nonspecialist in a particular area will be the survey papers which introduce most of the sessions. Each survey paper, presented by an international authority in his field, undertakes to summarize the present state of recently acquired knowledge in the field, and to lay the groundwork and provide the understanding for the detailed papers which follow. Most of the survey papers are reproduced in full, but many of the specialized papers are reported in summary form only, to keep the size of the book within bounds.

The unifying theme that ties together these diverse fields is the absorbing story of nearly 3 years of concentrated research which was carried out during the International Geophysical Year and the succeeding International Geophysical Cooperation of 1959. This is the period that saw the successful launching of artificial earth satellites, and the consequent development of new techniques for the scientific exploration of our earth, its atmosphere and the space beyond. In this book, the major role played by radio science in space research is described by the men who directed much of the research. From the results of this research there now emerges a surprisingly coherent and comprehensive picture of the natural processes that encompass the earth and interplanetary space.

E. C. Jordan
Dept. Elec. Engrg.
University of Illinois
Urbana, Ill.

The Antenna, by H. Thourel

Published (1961) by John Wiley and Sons, Inc., 440 Fourth Ave., New York 16, N. Y. 378 pages+5 index pages+23 appendix pages. Illus. 6¼×9½. $12.50.

"The Antenna" was originally published in French in 1956, and the translation into English was performed by H. de Laistre Banting. American readers will find the text clearly written, with familiar terminology used throughout. There is heavy dependence upon American papers and books as sources of information, but, in addition, much worthwhile material has been obtained from the European literature.

This book is less theoretical and more practical in its approach than other textbooks commonly used for first-year graduate courses (for example, "Antennas," by J. D. Kraus). Its level would be more suitable for a one-semester senior-year course. However, the instructor should bear in mind that the book was intended for familiarizing the reader with important antenna types and design techniques, rather than for imparting fundamental knowledge.

Antennas for all frequency ranges are considered, from mammoth sheets of wires at 15 kc to reflectors and lenses used at microwave frequencies. The broadcast and short-wave bands, for example, receive more attention than has been customary in recent books on antennas.

The practical orientation of this book will make it a useful reference for the design engineer. The wide coverage of antenna types will assist him in making the correct choice for a given application, while the formulas, curves, and referenced literature will help him perform his design task.

Seymour B. Cohn
Rantec Corp.
Calabasas, Calif.

Antenna Engineering Handbook, Henry Jasik, Ed.

Published (1961) by the McGraw-Hill Book Co., Inc., 330 W. 42 St., New York 36, N. Y. 1010 pages +30 index pages +xx pages. Illus. 6¼×9¼. $22.00.

Antenna engineering is a field which has grown very rapidly in the last two or three decades, having received a great impetus from military applications in communications, radar, radio aids to navigation, etc. In the past, engineers who have been faced with antenna problems have had to search the extensive technical literature for design information, so there has existed a real need for a handbook. The editor and authors are to be commended for tackling the difficult task of collecting and organizing the material for this handbook.

As stated in the preface, "'The Antenna Engineering Handbook' is intended to serve as a compendium of antenna design data and principles. Although it is expected that it will prove most useful to the engineer who is actively engaged in designing antennas, it will also be of considerable use to the electronic systems engineer who desires to understand the capabilities and limitations of the antenna as a component. The treatment is at the engineering level and is directed toward an understanding of antenna problems . . . in addition to presenting an extensive collection of design data." Hence, being an engineer's handbook, it does not contain much in the way of detailed mechanical design data such as belongs more properly in a radio amateur's handbook.

The book is organized into four sections, comprising Introduction and Fundamentals, Antenna Types and Methods, Applications, and Topics Associated with Antennas. The first section, which is brief, contains basic definitions and fundamental formulas. The second section contains engineering design information and performance data on the basic types of antennas. The system of classification is somewhat arbitrary but appears to be quite comprehensive. The third section treats antennas for specific types of applications, and again the classification has been a bit arbitrary. The fourth section contains information on a variety of topics of interest to the antenna engineer such as transmission lines and waveguides, impedance matching, radomes, measurements, as well as a chapter on propagation and one on mechanical considerations in antenna design.

It is inevitable that, in a book written by thirty-nine authors, there should be some variation in the thoroughness with which the different topics are treated. The chapter on loop antennas is rather sketchy and does not contain even as much information on loops as may be found in textbooks such as Kraus's "Antennas." The chapter on Surface- and Leaky-Wave Antennas is quite comprehensive and represents an excellent summary of the state of the art in this field. The chapter on Frequency-Independent Antennas will be welcomed by many engineers. The chapter on Antenna Measurements is not as extensive as might be expected (and it was disappointing to find no reference to IRE Standards on Antennas: Method of Test).

The chapter on Methods of Obtaining Circular Polarization uses the term "ellipticity" to describe the polarization, whereas the chapter on Helical Antennas uses the more-commonly accepted term "axial ratio." The use of the term "ellipticity" is to be deprecated since it does not conform to the mathematical definition of the term (see IRE Standards on Antennas and Waveguides: Definitions of Terms, 1953). The chapter on Corner Reflector Antennas might have mentioned Cottony's empirical design data for corner reflector antennas. The handbook contains very little on the subject of noise, a topic what might well have constituted a separate chapter.

The main shortcoming of the handbook is its index. The index appears to be little more than an expansion of the Table of Contents, so it is necessary for the reader to be familiar with the particular organization of material used in the handbook in order to locate a specific item of information. For the antenna specialist this will not be important, but for the nonspecialist it could be frustrating. A few examples will illustrate the problem. One might reasonably expect the definition of "antenna temperature" to occur in the section on Fundamentals and be listed in the Index under "A" or "T." It actually is listed under Radio Telescope Antennas. Similarly, the topic "noise" is listed only under Radio Propagation. Dielectric rod antennas are not listed under "D" or "A," but under Surface Wave Antennas, Specific Structures. Friis' Transmission Formula occurs in at least three places in the book but does not rate a listing in the Index.

In the opinion of this reviewer, the "Antenna Engineering Handbook" represents an important contribution to the literature and will be welcomed by all antenna engineers. It should find a place on the bookshelf not only of antenna engineers but all engineers concerned with systems employing antennas. The editor and the authors are to be congratulated for producing such an excellent and complete summary of the present state of the art.

GEORGE SINCLAIR
University of Toronto
Toronto, Ont., Canada

Electronic Circuits, Signals, and Systems, by Samuel J. Mason and Henry J. Zimmerman

Published (1960) by John Wiley and Sons, Inc., 440 Fourth Ave., New York 16, N. Y. 611 pages +4 index pages +1 appendix page +xviii pages. Illus. 6¼×9¼. $12.50.

A more revealing title for the contents of this remarkable book might be, "Introductory System Theory with Applications to Electronic Circuits." The book is noteworthy for the inventiveness and originality of its approach and for the conceptual richness of its presentation. Although it is intended for use by undergraduates, it will provide rewarding, stimulating (and perhaps even difficult) reading for the older, experienced engineer and teacher who wishes to strengthen his comprehension of several major aspects of modern system theory.

System theory is primarily concerned not with the *things* which comprise the system but rather with the *relations* between the signals (*i.e.*, observables) that characterize these things. The recognition of system theory as a distinct engineering discipline has been slow in coming. A major obstacle has been that much of the traditional symbolization of engineering has denoted the things comprising the system rather than the signal relationships which are of importance for theoretical purposes. Thus, the description of the "things" has been made to seem concrete and real whereas the signal relationships, described in traditional mathematical notation, have seemed more abstract and difficult to comprehend.

With the publication nearly a decade ago of his paper on signal flow graphs,[1] Mason provided an explicit symbolism for representing these signal relationships. For linear and constant-parameter systems, Mason showed that the flow graph can be solved directly so as to permit one to write, by simple inspection, the solution of the system equations. For nonlinear and time-varying systems, where analytical solution usually becomes very difficult, the flow graph leads directly to the programming of analog or digital computers.

The merit of any notational innovation, such as this, can only be evaluated by examining its usefulness in practice. Flow graphs are used throughout this book to portray the signal relationships which are peculiar to the particular system property being illustrated. The reader is thus given an opportunity to evaluate the importance of signal flow graphs by seeing in detail how they have been used by their inventor. In my opinion, the signal flow graph is an important innovation—a kind of mathematical "esperanto"—which is particularly well suited to the modeling, simulation, and analysis of systems in many diverse fields. Although a discussion of flow graphs is now included in most recent books on linear systems analysis, none thus far has illustrated their usefulness as thoroughly as does the present book.

The emphasis on flow graphs is but one of many unusual features of this book. Prior to the flow graph development of Chapters 4 and 5, the authors give concise treatments of matrix and topological methods for the analysis of electric circuits. These early chapters are very tightly written and presume that the reader is already familiar with elementary notions of electric circuits.

Chapters 6 and 7 constitute the main bulk of the book. In Chapter 6 on Signal Analysis, an astonishing array of important concepts and results are set forth in 110 pages of beautifully written and clearly illustrated text. Pulsed, periodic, almost periodic, and random signals are introduced, in that order, to motivate a brief discussion of random processes. Next comes a discussion of the geometrical representation of

[1] S. J. Mason, "Feedback theory: some properties of signal flow graphs," PROC. IRE, vol. 41, pp. 1144–1156; September, 1953. Also, "Feedback theory: further properties of signal flow graphs," PROC. IRE, vol. 44, pp 920–926; July, 1956.

signals by vectors in some appropriate signal space and the geometrical interpretations of approximation and correlation. This leads easily to auto- and cross-correlation functions for stationary random signals. Only at this point is the trigonometric Fourier series introduced and extended to yield the Fourier integral. To estimate bounds on the Fourier spectrum of a signal, the "content," "variation," and "wiggliness" measures are defined. The chapter closes with specific examples of the application of Fourier theory to the analysis of a wide variety of signals.

Chapter 7 deals with the transmission of signals through linear systems. It contains more content in 163 pages than is usually found in entire books on this subject. An interesting feature is that the authors define the familiar system function $H(s)$ as the transmittance of a linear stationary operator H for the characteristic signal, $\exp(st)$, thus focusing attention upon the meaning of $H(s)$ rather than upon the mathematical formalism of the Laplace transformation.

The last two chapters deal respectively with nonlinear and time-varying linear systems and the negative-feedback concept.

The clear, precise, but rather terse style of writing demands and deserves a careful reading—each word counts. The discussion of each topic is complete but without the customary redundancy and occasional verbosity ordinarily found in books at this level. A large assortment of thought-provoking problems (342 in all) are given to illustrate and extend the material of each chapter. I found the book most rewarding—a rich source of new ideas, accurate and authoritative in its development of many of the major concepts needed in systems work. Perhaps it is because I learned so much from reading this book that it is difficult to believe that all of this material is accessible to juniors and seniors today. However, even if it should be a few years ahead of its time, the book will certainly have a major constructive influence on the future development of systems education.

W. H. Huggins
The Johns Hopkins University
Baltimore, Md.

Recent Books

Blanco, V. M. and McCluskey, S. W. *Basic Physics of the Solar System.* Addison-Wesley Publishing Co., Inc., Reading, Mass. $7.50. For the reader at the intermediate level not a specialist in astronomy who is interested in space technology. Examples of computations and practice problems are presented.

Bundy, F. P., Hibbard, W. R., Jr., and Strong, H. M., Eds. *Progress in Very High Pressure Research.* John Wiley and Sons, Inc., 440 Park Ave. S., New York 16, N. Y. $12.00. The book consists of papers and discussions presented at an International Conference held in June, 1960, under sponsorship of Materials Central, Wright Air Development Div., U. S. Air Force and the Research Lab. of the General Electric Co. It includes a review of high pressure work in the U.S.S.R.

Hocking, John G., and Young, Gail S. *Topology.* Addison-Wesley Publishing Co., Inc., Reading, Mass. $8.75. A book on abstract mathematical topology.

Scanning the Transactions

The Case of the Missing Bass has been causing a bit of a stir in audio circles lately. Several home loudspeaker systems have been marketed recently which sound very good, and yet, when subjected to careful measurements, apparently have shown a deficient bass response. Several theories have been advanced to account for this discrepancy. One explanation for the "apparent bass" effect is based on a psychoacoustic phenomenon in which a person listening to a complex tone thinks he hears the fundamental frequency even though it is absent. Experiments have been conducted in which a series of pulses, set to a periodic repetition rate lying within the audible band, is passed through a high-pass filter with a cutoff frequency higher than that of the pulse rate. Subjects listening to the pulse train have reported being able to hear a frequency corresponding to the pulse repetition frequency. Biophysicists, noting that this effect is present only at loud levels, have suggested that it might be attributed to neural and middle-ear distortion. It has also been noted that in small inexpensive loudspeakers, a large excursion of the voice coil will move it out of the gap of uniform flux density of the magnet, causing a nonlinear clipping action on the sound wave. This latter effect has now been explored further by means of listening tests. Twenty subjects were asked to listen to various kinds of high-quality tape-recorded music over a special circuit that simulated and introduced the clipping distortion of a small loudspeaker, and to compare what they heard with the undistorted rendition of the same music, especially with respect to the bass content. The results confirm that the "apparent bass" effect does indeed exist, and that it is due to some degree to loudspeaker distortion. The degree to which neural and middle-ear distortion also contribute is as yet unknown but will no doubt be investigated further. (J. D. Griffiths, "'Apparent bass' and nonlinear distortion," Ire Trans. on Audio, July–August, 1961.)

The slowness of light may prove to be a basic limitation on the speed of ultra-high-speed digital computers. For example, a computer with a one nanosecond access time must have an average radius of less than one foot simply because, at the speed of light, it takes at least one nanosecond for a piece of information to be transmitted over a distance of one foot. This restriction, which is inherent in all present-day serial computers where all information is passed through a central processing unit, might be somewhat overcome by "parallel" machines. Thus a digital computer of the future might contain a great many local processing units distributed uniformly throughout the memory storage area and under the control of a central processing unit, in order to reduce the distance over which information is required to flow. Whatever evolves, it is apparent that the phrase "with the speed of light" is rapidly losing its awesome reputation. (W. W. Bledsoe, "A basic limitation on the speed of digital computers," IRE Trans. on Electronic Computers, September, 1961.)

A radio-fed radio antenna may sound like too much of a good thing, even to radio engineers. Nevertheless, a new method of exciting dipole antennas by coupling them electromagnetically to a two-wire transmission line is showing considerable promise for high-power VHF–UHF communications. The array consists of several dipoles situated in a plane parallel to that of the two-wire line, with the dipole centers situated opposite positions of voltage maximum along the line. When the dipole axes are oriented in a direction other than parallel to the direction of the line, the antennas are excited by the charges on and currents in the line. The advantage of this arrangement is that only a single transmission line is required to feed the several dipoles, thus avoiding the problem of balancing a large member of interacting feed lines and minimizing the difficulty of obtaining the desired field pattern. (K. M. Chen and R. W. P. King, "Dipole antennas coupled electromagnetically to a two-wire transmission line,"

IRE Trans. on Antennas and Propagation, September, 1961.)

The use of capacitors as memory elements is being explored for a new semipermanent storage system, *i.e.*, a storage system in which the stored information will not be changed by the machine that is able to consult it. Present systems of this type are limited in speed, where rotating magnetic drums are used, or rely on expensive and complicated error detection and correction circuitry where use is made of destructively read magnetic stores. To overcome these shortcomings two systems were recently developed: the flying spot store, which makes use of cathode-ray access to information stored on photographic emulsion, and the permanent magnetic twistor, in which information is stored by magnetically biasing the twistor. A third system has now been developed in which the memory consists of a matrix of printed capacitors. Since there is a great need for reliable, economical, high-speed permanent stores for electronic telephone switching systems, as well as for modern digital computers, it is likely that this sytem will have a promising future. (D. H. Macpherson and R. K. York, "Semipermanent storage by capacitive coupling," IRE Trans. on Electronic Computers, September, 1961.)

Trouble-shooting the trouble shooters reveals some interesting statistics on the behavior of maintenance technicians in locating faults in equipment. In a recent study, detailed records were kept of each successive move which was made in trouble-shooting simple radio and radar circuits. When 422 of the records were analyzed later, it was found that in 87 per cent of the cases the technicians had accumulated enough information to identify the faulty stage, but only 3 per cent of them utilized this information immediately. The remainder went on making redundant or irrelevant checks before they finally identified the faulty stage. Similar results were found in finding the faulty component within the stage. Only 14 per cent of those who had accumulated sufficient information to identify the faulty component immediately recognized this fact. The study points up the fact that searching for symptoms and the correct interpretation of them occur on two different behavioral levels which are not necessarily closely coordinated. (J. W. Rigney, *et al.*, "Analysis of fault-location behavior in electronic equipment," IRE Trans. on Human Factors in Electronics, September, 1961.)

The simulation of cognitive processes has received a great deal of attention recently. Considerable effort is being devoted to developing machine with capabilities for self-organizing and cognitive behaviors previously thought to be exclusively the domain of organisms. At the same time, behaviorial and life scientists are very much interested in the analysis and synthesis of organic behaviors in terms of machines which can simulate them. The result has been a marked increase in the volume of papers on this subject. It seems safe to say that over two-thirds of the literature on the simulation of cognitive processes has been written just in the past four years. The appearance of an annotated bibliography covering 498 papers in this burgeoning field, therefore, comes at a most propitious time. (P. L. Simmons and R. F. Simmons, "The simulation of cognitive processes: An annotated bibliography," IRE Trans. on Electronic Computers, September, 1961.)

Abstracts of IRE Transactions

The following issues of Transactions have recently been published, and are now available from The Institute of Radio Engineers, Inc., 1 East 79 Street, New York 21, N. Y., at the following prices. The contents of each issue and, where available, abstracts of technical papers are given below.

Sponsoring Group	Publication	IRE Members	Libraries and Colleges	Non-Members
Antennas and Propagation	AP-9, No. 5	$2.25	$3.25	$4.50
Audio	AU-9, No. 4	2.25	3.25	4.50
Automatic Control	AC-6, No. 3	2.25	3.25	4.50
Broadcasting	BC-7, No. 3	2.25	3.25	4.50
Broadcast and Television Receivers	BTR-7, No. 2	2.25	3.25	4.50
Component Parts	CP-8, No. 3	2.25	3.25	4.50
Electronic Computers	EC-10, No. 3	2.25	3.25	4.50
Human Factors in Electronics	HFE-2, No. 2	2.25	3.25	4.50
Industrial Electronics	IE-8, No. 2	2.25	3.25	4.50
Radio Frequency Interference	RFI-3, No. 1	2.25	3.25	4.50
Reliability and Quality Control	RQC-10, No. 2	2.25	3.25	4.50
Space Electronics and Telemetry	SET-7, No. 3	2.25	3.25	4.50
Vehicular Communications	VC-10, No. 2	2.25	3.25	4.50

Antennas and Propagation

Vol. AP-9, No. 5, September, 1961

Philip S. Carter 1897–1961 (p. 424)

Dipole Antennas Coupled Electromagnetically by a Two-Wire Transmission Line—K. M. Chen and R. W. P. King (p. 425)

The circuit properties of a dipole antenna coupled electromagnetically to a two-wire transmission line are studied theoretically and experimentally. Some arrays constructed of a number of dipole antennas coupled electromagnetically to a two-wire line are considered and the radiation patterns are found.

Mutual-Coupling Effects in Scanning Dipole Arrays—L. A. Kurtz, R. S. Elliott, S. Wehn, and W. Flock (p. 433)

The perturbations in mutual coupling due to finiteness of a dipole array and its ground plane have been studied. Experimental procedures were evolved to measure these perturbations and their influence on antenna performance as a function of beam position. Data for one- and two-dimensional dipole arrays are presented and interpreted, particularly with reference to edge effects.

Optimum Feeds for All Three Modes of a Monopulse Antenna I: Theory—P. W. Hannan (p. 444)

In a monopulse antenna for use in a tracking radar, the requirements for the sum and difference modes are not the same. For the amplitude-comparison type of monopulse having an antenna whose main aperture is illuminated by

a feed, these independent requirements can be met by a feed designed to fulfill two conditions. One is that excitation of the feed aperture in the difference modes be effectively about twice as wide as in the sum mode. The other is that the shapes of all the feed excitations be free of any avoidable irregularities.

The amount of improvement available when these conditions are met depends on the optimization point desired for each mode, as well as the design of the reference antenna. In a typical case, the gains and slopes in the difference modes should increase by several db. Furthermore, the near sidelobes and the spillover radiation in the difference modes should decrease by an order of magnitude. A small increase of gain in the sum mode is also available, and finally, the criticalness of positioning the feed may be appreciably reduced.

Optimum Feeds for All Three Modes of a Monopulse Antenna II: Practice—P. W. Hannan (p. 454)

In an amplitude-monopulse antenna whose main aperture is illuminated by a feed, it is desired to control the feed excitation independently in the sum, azimuth difference, and elevation difference modes. It is possible to describe a feed system, comprising an infinite array of radiators and hybrid junctions, which demonstrates the principle of complete independent control of the three modes.

There are several practical feeds which approach a hypothetical ideal one in varying degrees. One representative type is the "twelve-horn feed;" although it has some disadvantages, it is versatile and quite useful. However the most attractive type for many applications appears to be one having a combination of multiple-horn excitation in one plane and multimode-waveguide excitation in the other. With a simple form of the "multihorn-multimode" feed, the ideal is substantially realized, and a major improvement in monopulse performance can be obtained.

A New Way of Solving Maxwell's Equations –V. H. Rumsey (p. 461)

A general solution of Maxwell's equations for a single frequency can be expressed as the combination of two types of solution, each of which is characterized by an electric vector which is equal to the magnetic vector times the intrinsic impedance of free space but a quarter cycle out of phase. These two types are mathematically orthogonal, and each can be conveniently expressed by means of a single scalar. The method leads to circularly polarized surface waves propagating along anisotropic sheets which are perfectly conducting in one tangential direction and perfectly transparent in the orthogonal tangential direction.

Correlation of Wind Shear with Tropospheric Scatter Signals –L. H. Bauer (p. 466)

Examination of the hourly values of the 10 90 per cent fading range of selected 915 Mc tropospheric scatter records of a 400-mile path have shown unusual behavior which correlates well with wind shear through the scatter volume. Although the meteorological data were of a gross nature and were collected at a point at least 70 miles from the common volume, correlation coefficients of 0.76 to 0.8 were obtained. The data indicate that the fading range (10–90 per cent in this case) increases by 1.4 db per meter/sec/km increase in average wind shear through the scatter volume.

Coherent and Incoherent Scattering of Microwaves from the Ocean –C. I. Beard (p. 470)

This report, the third in a series, summarizes experimental studies of microwave over-ocean propagation on line-of-sight paths. Measurements at 5.3, 3.2, and 0.86 cm wavelength in 1955, in the Gulf of Mexico, between two oil drilling platforms one mile apart are compared with the results of the phenomenological model developed earlier. The total field was measured at maxima and minima of the interference patterns using a sequence of receiver beam widths. The scattered field alone was measured by means of a narrow beam. The 1955, Gulf of Mexico, data are consistent with the previous 1953, Golden Gate data in regions of overlap of certain parameters, and provide extended coverage for other values under different conditions.

Specifically, some of the new findings are: a) The experimental values of the coherent reflected field are larger than exp $[-2(2\pi h\psi/1000\lambda)^2]$ for values of "apparent ocean roughness" $(h\psi/\lambda)$ greater than 110 milliradians. h = standard deviation of water surface, ψ = grazing angle in milliradians, and λ = electromagnetic wavelength. b) After rising from zero, the incoherent scattered power exhibits a downtrend for $h\psi/\lambda$ greater than 110. The incoherent power divided by the square of the smooth sea reflection coefficient shows no polarization dependence. c) The distribution along the surface as measured by the narrow-beam antenna shows that the coherent and incoherent power are markedly peaked in the specular direction. d) The ratios of coherent-to-incoherent power (m^2) obtained from the shapes of the probability distributions agree with the power ratios obtained by measurements of the magnitudes of the signals. e) Total signal spectra broaden with increasing $h\psi/\lambda$ as found at the Golden Gate; the relative shapes of spectra agree with those from the Golden Gate. Horizontally- and vertically-polarized total signal spectra are the same.

Electromagnetic Propagation in an Exponential Ionization Density—L. S. Taylor (p. 483)

The propagation of a plane electromagnetic (TE) wave into a plane stratified medium in which the ionization density varies as exp (z/z_0) is investigated. The solution of the wave equation appears as a combination of Bessel functions of imaginary order and complex argument, but the magnitude of the reflection coefficient (taken at $z = -\infty$) is given by the simple expression exp $\{-(4\pi z_0 \cos \theta_i/\lambda) \tan^{-1}(\nu_c/\omega)\}$, where θ_i is the angle of incidence, λ is the free-space wavelength and (ν_c/ω) is the ratio of electron collision frequency to the frequency of the field. In general, the field components must be obtained from a complex series, but at depths beyond the critical density asymptotic forms are given which display the rapid decay of the evanescent field in terms of elementary functions.

Some Propagation Characteristics of High UHF Signals in the Immediate Vicnity of Trees—A. H. LaGrone and C. W. Chapman (p. 487)

Results are reported of measurements made at very low angles of 2880-Mc vertically-polarized signals over wooded areas, with the elevation angle to the transmitter the principal variable. The effects of one tree and of many trees on the apparent location of a signal source, as determined with a narrow-beam antenna, are reported. A hypothetical direction-finding system is assumed and its pointing characteristics determined.

Tropospheric Scatter Propagation and Meteorological Conditions in the Caribbean—R. E. Gray (p. 492)

Results are given of radio propagation measurements which have recently been made in the Caribbean. The transmission loss on beyond-the-horizon paths in this region was found to be considerably less than that measured over paths of similar length in temperate climates.

The fact that the path loss is, in general, relatively low in the Caribbean is believed to be chiefly due to the large gradient of the refractive index of the atmosphere which normally prevails in the first few hundred feet above the earth's surface in that area.

Communications (p. 497)
Contributors (p. 503)
Papers to be Published in Future Issues (*Inside Back Cover*)

Audio

Vol. AU-9, No. 4, July-August, 1961

Message from the New Chairman—C. M. Harric (p. 97)
The Editor's Corner—M. Camras (p. 98)
National Officers of the PGA, 1961–1962 (p. 99)
PGA Awards for 1960 (p. 102)
Chapter News—W. M. Ihde (p. 102)
More on Nonlinear Distortion Correction—J. R. MacDonald (p. 103)

Further consideration is given to basic amplitude limitations which may apply to the complementary distortion method of nonlinear distortion correction. It is found, in disagreement with others, that points at which the differential gain is zero or infinite do not limit the amplitude over which complete correction is possible but that relative maxima, minima, gain zeros, and infinite-gain points in the characteristic do set limitations when the usual simply connected tandem configuration is employed. When the characteristic to be corrected is multiple valued or passes through points of zero or infinite gain within a given amplitude range, a multiply connected correction circuit must be used for perfect correction of distortion over the amplitude range in question.

A Simplified Noise Theory and Its Application to the Design of Low-Noise Amplifiers—A. E. Sanderson and R. G. Fulks (p. 106)

Any noisy amplifier can be represented by an equivalent noiseless amplifier plus two noise generators either at the input or the output of the amplifier. The choice of two particular noise generators (the equivalent short-circuit noise voltage and the open-circuit noise current) to characterize a noisy amplifier has a number of advantages over the concept of noise figure. The noise generators can easily be measured separately from the source noise, and the optimum source impedance and the noise figure at any source impedance can then be calculated. Since the amplifier noise is measured separately from the source noise, low noise figures can be easily measured. The optimum source impedance equals the quotient of the two noise generators, and the noise figure depends upon their product. Neither feedback nor input impedance is a consideration in determining noise figure and optimum source impedance.

Several transistor noise diagrams show how the two noise generators are affected by emitter current, collector voltage, and frequency. Noise diagrams can be used to select the most suitable amplifying devices and optimum operating conditions for various applications.

Average vs RMS Meters for Measuring Noise—J. J. Davidson (p. 108)

It appears that the controversy is still alive over whether average reading or root-mean-square reading meters should be specified as standard for the measurement of noise. This being the case, it is worthwhile to consider the entire subject from the standpoint of basic fundamentals, to determine what are the significant quantities involved, and then proceed to investigate which type of meter yields the most significant results.

The following is the result of such an investigation. The entire discussion rests on 1) an axiom, that energy transfer is the fundamental interaction within the universe, and 2) a premise, that for the type of measurements under discussion (audio), all significant processes are linear. Given these two starting points, the conclusion is reached that the meaningful quanti-

ties are found by rms measurements.

It is shown further, by concrete example, that measurements made with average reading meters can depart widely from those made with an rms meter. This being the case, it is necessary that *measurement standards* specify the use of rms meters. Those who elect to use average meters, then, bear the responsibility of determining the accuracy of their results in terms of the fundamentally important quantities.

An Adjustable Shelf-Type Equalizer with Separate Control of Frequency and Limiting Attenuation or Amplification—R. H. Rose (p. 112)

This device provides for control of the high-frequency content of an audio program, allowing the operator to choose independently:

1) the frequency above which equalization is to occur, and
2) the maximum correction in signal strength which results in the range of frequencies under correction.

Three operating controls are used. One control determines whether the high-frequency signals shall be increased, left unchanged, or decreased in strength relative to the low-frequency signals. A second control is calibrated in terms of the frequency above which correction shall occur. The third control adjusts the asymptote which represents the maximum correction which shall occur for frequencies considerably higher than that chosen by the frequency control described above.

The circuit can be described briefly as follows: for high-frequency attenuation, the operation employs a negative feedback amplifier whose output may have high-frequency loss inserted by an RC network following the amplifier; for high-frequency boost, the RC network is inserted in the amplifier feedback path so that the amplifier output (which now becomes the system output) has a rising high-frequency response which corresponds to the attenuation of the RC network. All three controls are continuously adjustable within their ranges of operation.

"Apparent Bass" and Nonlinear Distortion—J. D. Griffiths (p. 117)

A discrepancy between the "apparent bass" response heard by the average music listener and anechoic-chamber measurements has been noted for some small loudspeaker systems. This may be caused by the psychoacoustic response to the generation of harmonic distortion by the nonlinear suspension and the inhomogeneous flux gap density in a small speaker. An electrical analog, with controllable distortion, of such a speaker has been subjected to listener tests and evaluation to determine if this is the cause of the apparent bass effect. An analysis of the listener reactions to various music stimuli through the system indicates that this is the case.

The Concept of Linear Interpolation in Spectral Compensation—C. E. Maki and J. M. Chirnitch (p. 122)

Spectral compensation is usually achieved with equalizers cascaded so as to generate a desired response. In the concept of linear interpolation, a series of points are located along the desired response and linear interpolation provided between adjacent points. This is accomplished with contiguous band-pass filters arranged so as to minimize the effect of filter crossover. The performance limitations depend upon the filter characteristics, crossover ripple, and the type of response to be equalized. This approach to compensation has two advantages. First, automatic control of the spectrum can be achieved when the input signal is a random noise voltage. Second, discreet points on the frequency axis permit control using digital techniques. Data is presented for some cases of peak-notch resonances encountered in acoustic and vibration systems.

Contributors (p. 131)

Automatic Control

Vol. AC-6, No. 3, September, 1961

Rising Costs, ***Editorial*** (p. 249)
The Issue in Brief (p. 250)

The Sensitivity Problem in Sampled-Data Feedback Systems—I. M. Horowitz (p. 251)

This paper is devoted to a discussion of the effect of parameter variations on the system response in sampled-data feedback systems. It is shown that in any single degree of freedom feedback configuration, the system response and especially its overshoot are inherently very sensitive to parameter variation. By means of a suitable transformation, the properties of the sensitivity function can be studied in terms of the usual continuous system frequency concepts, *e.g.*, bandwidth and loop transmission shaping on the Bode plane. There is a basic limitation on the loop transmission bandwidth that can be obtained in any sampled-data feedback configuration. This limitation makes it impossible to secure the unlimited sensitivity reduction which is theoretically available in minimum phase continuous systems. It is shown how one must achieve a compromise between the values of the sampling period, the system response, and the sensitivity function. The design procedure is illustrated in detail with a numerical design problem in which there is substantial parameter variation.

Self-Optimization of a Control System by Means of a Logic Circuit—T. Isobe (p. 260)

The self-optimization of a control system has been tried by means of a logic circuit. The device makes successive trials by giving values of a parameter to the system and, on the basis of the resulting successive observations of the mean-square error, finally finds the value of the parameter giving the minimum error. The device is also able to follow the change of the system conditions to keep the system optimum. The optimum value of damping ratio of a second-order system with LF Gaussian noise input is also discussed on the basis of the data obtained with the device.

Stability Conditions of Pulse-Width-Modulated Systems Through the Second Method of Lyapunov—T. T. Kadota and H. C. Bourne, Jr. (p. 266)

PWM systems contain inherent nonlinearities which arise from their modulation scheme. Thus, for a legitimate study of stability, such systems must be treated as nonlinear sampled-data systems without initially resorting to linear approximations. For a nonlinear system whose dynamic behavior is described by a set of first-order difference equations, one of the theorems in the second method of Lyapunov gives, as a sufficient condition for asymptotic stability in the large, the existence in the whole space of a positive-definite Lyapunov's function V, whose difference ΔV is negative definite. Hence, by choosing a positive-definite quadratic form as V, the sufficient condition is reduced to the negative-definiteness in the whole space of ΔV. Upon this basis, a systematic procedure of obtaining analytically a sufficient condition for asymptotic stability in the large is developed for various types of PWM systems; the condition is stated as the negativeness of all the eigenvalues of three matrices associated with the PWM system.

Stability and Graphical Analysis of First-Order Pulse-Width-Modulated Sampled-Data Regulator Systems—E. Polak (p. 276)

Pulse-width-modulated sampled-data systems are described by nonlinear difference equations which do not lend themselves to an exact analytic treatment.

This paper presents a graphical technique for the analysis of PWM sampled-data systems with first-order plants. This technique provides a sufficient condition for asymptotic stability in the large, a method for examining the damping properties of the system, a method for computing the step response from any initial condition and, finally, a method for observing and interpreting the effect of varying the system parameters on the step response of the system.

Analysis of Pulse-Width-Modulated Control Systems—F. R. Delfeld and G. J. Murphy (p. 283)

Previous work on the analysis and design of pulse-width-modulated control systems is reviewed, and the limitations of some of the earlier contributions are discussed. A mathematical development of an orderly and relatively simple method for the exact determination of the response of closed-loop pulse-width-modulated control systems to arbitrary input is then presented. Through the use of difference equations and the separation of linear and nonlinear terms, the output at the sampling instants is expressed as a function of the sampled error, and z-transform theory is then employed to obtain an exact solution for the error at the sampling instants.

A technique for studying the stability and other performance characteristics of pulse-width-modulated feedback systems is next presented. The exact method of analysis developed earlier and a modified describing-function technique are utilized together to investigate stability without overlooking pulse-width saturation.

Three illustrative examples are also presented to demonstrate the relative simplicity of the methods described in the paper as well as the accuracy of the results obtained by the use of these methods.

Effects of Quantization on Feedback Systems with Stochastic Inputs—R. Kramer (p. 292)

An approximate analysis of the effects of quantization in a feedback system is made. The system input is a Gaussian random signal. The error autocorrelation as a function of the quantizer box size is the goal of the analysis. The approximation lies in the assumption that certain error joint distributions are Gaussian. In the limit as the quantizer box size approaches zero, these distributions do become Gaussian.

On the basis of the approximation, a nonlinear integral equation relating the error autocorrelation to the system parameters is developed. An iteration procedure for successive approximations to the solution is outlined, and several examples are presented. Finally, experimental results obtained on a digital computer are shown.

Minimizing Effects of Disturbing Signals Through a Minimum Square-Error Criterion—M. Sobral, Jr. (p. 306)

One of the reasons for using feedback is the improvement in the rejection of disturbing signals. This improvement can be obtained through an analytical design utilizing as a performance index the integral square-error criterion. In the usual technique the sum of the command signal plus the disturbing signal transferred to the input of the system is used as the input signal. When this is done, one of the two compensating transfer functions (for the particular case of a system with two degrees of freedom) has to be fixed arbitrarily. Then the optimum over-all transfer function, which minimizes the integral of the square of the error between the desired output and the actual one, is calculated and thus the remaining compensator can be obtained. As the technique does not provide a method for determining one of the compensators, and the transferred disturbing signal is a function of this compensator, a required rejection of the disturbing signal may not be satisfied. The purpose of the present paper is to suggest an analytical technique for determining both of the two compensators which have the

minimum bandwidth necessary to satisfy a desired over-all transfer function and a required rejection of a disturbing signal. In addition, the technique provides physically realizable compensating transmissions.

Discussion of Paper Above—O. J. M. Smith (p. 310)

Integral Transforms for a Class of Time-Varying Linear Systems—K. S. Narendra (p. 311)

This paper presents an extension of the transform method to systems having parameters which vary with time. By using the general λ domain approach suggested by Zadeh for the analysis and synthesis of linear time-varying systems, a system function $H(\lambda)$ independent of time may be defined for the linear system. Such a system function has many of the advantages of that obtained for stationary systems using the Laplace transformation. By making $H(\lambda)$ a ratio of polynomials in the complex variable λ the pole-zero synthesis technique used for fixed systems may be applied to the time-varying case as well. Recently, a "building block" for the synthesis of a class of time-varying systems was suggested by Kilmer and Johnson. A similar building block for systems with exponentially varying coefficients is suggested in this paper.

Signal Stabilization of Self-Oscillating Systems—R. Oldenburger and T. Nakada (p. 319)

The hunt (self-oscillations) of a physical system may often be removed by the introduction of an appropriate stabilizing signal which changes the open loop gain in a nonlinear manner. More generally, the performance of nonlinear systems in many cases may be improved by the introduction of extra signals. The theory of signal stabilization developed here extends the earlier work by Oldenburger and Liu involving an equivalent gain concept. It is shown that with the aid of the Fourier series the designer can determine the periodic signal to be inserted at one point in a loop to yield a desired stabilizing input to a nonlinear element in the loop. The use of sinusoidal and triangular inputs to a limiter are compared. An example where a limiter is the only nonlinearity is employed to illustrate the theory. The approach developed here explains experimental results previously reported by Oldenburger.

An Analytical Approach to Root Loci—K. Steiglitz (p. 326)

The general algebraic equations of root loci for real K are found in polar and Cartesian coordinates. A synthesis method is then suggested which leads to linear equations in the coefficients of the open-loop transfer function when closed-loop poles and their corresponding gains are specified. Equations are also found for the gain corresponding to a given point on the root locus.

A superposition theorem is presented which shows how the root loci for two open-loop functions place constraints on the locus for their product. With a knowledge of the simple lower-order loci, this theorem can be used in sketching and constructing root loci.

***s*-Plane Design of Compensators for Feedback Systems**—C. D. Pollak and G. J. Thaler (p. 333)

The poles and zeros of a compensator affect the s-plane gain and phase of the open-loop system at every point in the s-plane. These effects are studied for open-loop poles and zeros on the negative real axis, and a family of curves summarizes the results. A design technique is developed which permits compensation design to satisfy simultaneous specifications of root location and system gain. The method clearly defines the minimum number of compensator sections required and leads to a logical interpretation of relative needs for phase-lead and phase-lag compensators.

Correspondence (p. 341)
Recent PGAC Chapter Meetings (p. 363)
Contributors (p. 364)
Announcements (p. 367)

Broadcasting

Vol. BC-7, No. 3, August, 1961

N.A.B. Engineering Achievement Award (p. 1)

Scan Converter for Broadcast Use—A. W. Malang (p. 2)

Minimizing the Effects of Vidicon Lag with a Long Video Delay Line—W. L. Hughes (p. 8)

A common complaint among people who utilize vidicon cameras is the "stickiness" or "lag" effect which is encountered when these tubes are used at low light levels. This paper discusses a method of minimizing this effect using a wide band video delay line with a time length equal to 262 television lines. This technique is an outgrowth of an extensive color television systems research program carried on at Iowa State University for the last several years.

Improved Video Recording System—F. Gillette (p. 11)

Uniform terminology and a method of graphical representation are established. Factors affecting exposure uniformity are described by reviewing fundamental relations between the film exposure cycle and the television scan. Practical arrangements for recording television pictures on motion-picture film are described and analyzed. Effects of phosphor persistence are considered, and a detailed analysis of persistence effects in single-field recording is offered.

Recent Advances in Vidicons—M. Rome (p. 12)

The last few years have seen the introduction of many new vidicon types. Sensitivity, lag, response, resolution, and miniaturization of the new tubes are reviewed. In addition a brief discussion on the variation of gamma with dark current and light level of broadcast vidicons is included.

An Improved Loudness Indicator—J. L. Hathaway (p. 19)

The standard type VU meter has for many years been employed almost exclusively by broadcasters in the United States as a program level indicator. A new unit which should give better indication of peak loudness has now been developed and is being evaluated. This unit operates within the range of time constants specified by the FCC for transmitter aural modulation meters. A field test is now in progress, with a number of the new indicators in various studios throughout the country.

The International Broadcasting System of the Voice of America—G. Jacobs and E. T. Martin (p. 25)

The Voice of America, the international broadcasting service of the U. S. Information Agency, speaks for America in thirty-five different languages to a worldwide audience. The technical facilities that make this possible literally encircle the globe. Thirty shortwave transmitters at seven locations in the continental United States range in power from 25 to 200 kilowatts. Overseas, the VOA has nine relay stations with forty-seven transmitters ranging in power from 35 to 1000 kilowatts. This presentation discusses the development of this technical system from its war-time inception. Highlighted in the discussion are the problems encountered in the development of the system, the techniques designed to counteract these obstacles, and future plans for strengthening the signal of the Voice of America.

FCC Laboratory Observations of Precision Frequency Control of TV Stations—E. W. Chapin (p. 36)

Observations on the use of both high- and low-frequency precision offset for interference reduction have not indicated any severe problems due to propagation, at least for Channel 4. Arrangements are being made for further observations on high VHF channels.

The CBS NetALERT—A System for Network Signaling—A. A. Goldberg, A. Kaiser, G. D. Pollack, and D. Vorhes (p. 43)

Broadcasting and Television Receivers

Vol. BTR-7, No. 2, July, 1961

IRE Professional Group on Broadcast and Television Receivers (p. 1)
Program for PGBTR Radio Fall Meeting (p. 2)
1961 Chicago Spring Conference Highlights (p. 3)
PGBTR Administrative Committee (p. 4)

Some Considerations in the Application of Mechanical and Piezoelectric Filters—H. J. Benzuly (p. 5)

The operation of and design approaches to mechanical and piezoelectric electric wave filters are discussed. The literature is reviewed and typical values for resonator and filter characteristics are presented.

Comments on impedance levels, insertion loss, spurious responses and stability are included.

Component tests are discussed and the application of ceramic elements to the IF circuit of a transistorized broadcast receiver is described.

A Second Progress Report on TV-Receiver Reliability—E. H. Boden (p. 11)

The Midwest Program on Airborne Television Instruction—An Experiment in Progress—J. S. Miles (p. 14)

This paper is intended to describe an experiment now in progress. Considerable work has been and is being done. A great deal has been learned, but tentative conclusions currently arrived at are based almost wholly on subjective evidence.

Satellite Broadcasting?—S. G. Lutz (p. 17)

Now that the first demonstrations of satellite-relayed transoceanic television may occur within two years, what is the probable future of satellite broadcasting? This study examines problems of broadcasting via satellites directly to home television receivers, compared with those of relaying to earth-terminals and rebroadcasting locally. The former eventually may be possible, but would require high-power, highly engineered satellites and would involve other problems, which are discussed here. Direct FM audio broadcasting may be less difficult but also less spectacular and rewarding.

A Complete Specification of the Gain Control Characteristics of RF and IF Transistors—L. A. Weldon (p. 23)

This paper describes a unique method for specifying the gain control characteristics of high-frequency transistors over their entire AGC range. The forward gain control characteristics of transistors can be measured by means of a curve tracer to permit the specification, within published limits, of the high frequency power gain versus collector to emitter voltage curve. While this report describes the specification of forward gain control characteristics the system can also be used for reverse gain control specifications.

Operation of the curve tracer system is discussed and a description of the AGC specification is given as well as a method for its use in accurately predicting the gain and the AGC range spread for equipment in production.

Equations are given for calculating the base control voltage characteristics and the value of

collector bias resistor required for optimum operation.

A New Compact TV Tuner—T. F. Gossard, W. G. Delp, and J. F. Stolte (p. 29)

A brief review of the performance requirements and other factors influencing the design of VHF television tuners is presented, including some of the unforeseen problems encountered during development of a new design. The basic electrical similarity between tuners of different manufacturers is pointed out, which suggests that significant design improvement might best be obtained by concentrating attention on mechanical rather than electrical factors. Development of a new compact tuner was begun with maximum use of molded plastic parts, reduction of the number of mechanical parts, and suitability for automatic production techniques as the main design objectives. A final design was completed and the tuner is now in production. A description of the novel features of this tuner indicates how the design objectives were reached and greater product uniformity and lower costs realized.

An Efficient Noise Immune Sync and AGC Circuit for Television Receivers—R. N. Rhodes and W. F. Dietz (p. 35)

A Precision-Tuned Receiver Employing Solid-State Tuning Elements—E. M. Aupperle and T. W. Butler, Jr. (p. 39)

The capability of rapid frequency selection coupled with crystal controlled tuning accuracy are the salient features of this solid-state receiver. The heart of the system is a discrete local oscillator. It consists of an electronically tuned oscillator which is phase-locked to a selected harmonic of a master crystal. Since there are no mechanical adjustments necessary, the receiver can be built in a small, light-weight package.

An experimental AM-FM receiver covering the range 80–102 Mc in 100-kc steps was built. This paper presents a discussion of the design principles, the applications of such a receiver, and the techniques required in constructing the receiver.

Dynamic Polar Display of Transfer Characteristics of Television Receivers—P. H. Van Anrooy (p. 47)

A polar plot displays amplitude, as well as phase response versus frequency, in one single figure. This is interesting for evaluation of the influence of pole zero (circuit parameter) adjustments of transfer networks immediately, without time consuming transforms (from electrolytic—P. Z. "domain"—or other "analogs").

A Solid State Oscilloscope Display—S. Talesnick and S. Yando (p. 54)

A new solid-state display device utilizing certain unique properties of piezoelectric and electroluminescent materials is described and the principles of operation are reviewed. The device requires only four properly timed electrical inputs to produce a spot of light at any selected point on the display panel. The timing relationships are derived and a system capable of producting the required drive signals is described. Oscilloscope patterns are generated on the panel by a point-by-point plot of suitably processed X- and Y-input signals.

Factors Affecting Overall Performance of FM Stereophonic Receivers—A. Csicsatka and R. M. Linz (p. 59)

A flat phase linear IF pass band should be designed into a high fidelity stereo tuner.

A vector analysis of a tuner exhibiting an equivalent 5-μsec deemphasis in its output voltage vs frequency characteristics shows that the major cause of poor stereo performance is related to the level differences of the $L+R$ and $L-R$ channels. A simple adjustment of the $L+R$ level control in the synchronous oscillator stereophonic adapter circuit described can correct this difference.

Curves relating channel gain and phase difference indicate that 30-db separation can be maintained if the channel gain difference is less than $\pm\frac{1}{2}$ db and the channel phase difference is 3° or less. By observing the discriminator output of a receiver it is possible to judge separation capability of a transmission system using a specially developed visual analysis.

The synchronized oscillator circuit discussed in this paper uses the 19 kc/s pilot as a synchronizing signal for the 38 kc/s regenerated subcarrier and a simple matrix to recover the L and R channels. It is found that the phase of the reinserted subcarrier can shift up to $\pm 35°$ from correct insertion before stereo separation is reduced to 20 db.

Design of Stereophonic Receiver for a Stereo System in the FM Band Using an AM Subcarrier—A. J. DeVries (p. 67)

From the FM discriminator in the receiver we derive the composite signal containing a low frequency audio signal, a modulated subcarrier and a pilot signal related to the subcarrier. The stereophonic signal demodulator can operate on the composite signal in such fashion as to produce directly a left and right stereophonic signal.

Analytically it is shown that this can be accomplished by multiplying the composite signal by the appropriate function. Carrier regeneration can be accomplished in several ways.

It is also possible to construct a multiplex receiver by operating independently on the low frequencies and the modulated subcarrier information.

Stereophonic FM Broadcasting—C. G. Eilers (p. 73)

In arriving at a suitable choice of transmission parameters for stereophonic FM broadcasting, consideration must be given to several factors, as follows:

1. The modulation choice should provide an aurally-balanced program for the monophonic listener.
2. A reasonable compromise should be made between the stereophonic signal-to-noise ratio and the monophonic signal-to-noise ratio as compared to monophonic broadcasting.
3. Receivers designed for the system should be capable of reliable operation yet should be reasonably inexpensive.
4. If possible, the system should provide an additional channel for other services without degrading the desired service.

The transmission parameters should be selected with the present state of the electronic art in mind; however, it should be recognized that advances in the art will always take place. Thus, one must also keep the future in mind when selecting these parameters.

An Ultra-Low-Distortion Transistorized Power Amplifier—H. M. Kleinman and C. F. Wheatley (p. 81)

The development of a new type of power transistor has made possible the construction of ultra-high-performance audio-frequency amplifiers which can equal the performance of the finest vacuum-tube amplifiers available. The design, construction, and performance characteristics of such an amplifier, using RCA drift-field power transistors, is discussed. The amplifier is capable of providing a power output of 50 watts at less than one-half per cent distortion from 20 cycles to 20,000 cycles. Also discussed are a five-watt class A amplifier and a 15-watt-per-channel stereo amplifier which combine high performance with economy.

The Nuvistor Triode in Video IF-Amplifier Circuits—K. W. Angel and J. Gote (p. 88)

This paper discusses the use of the Nuvistor triode in two- and three-stage IF amplifiers and places particular emphasis on neutralization. Theoretical stable-gain limits are also discussed and the results of practical designs are presented.

Component Parts

Vol. CP-8, No. 3, September, 1961

In formation for Authors (p. 97)

Who's Who in PGCP: Kathryn M. Schwartz (p. 98)

Realization of a Filter with Helical Components—A. I. Zverev and H. J. Blinchikoff (p. 99)

In the VHF range, high-quality narrowband filters with reasonable physical dimensions are extremely difficult to realize. Excessive passband insertion loss accompanies filters employing lumped constant elements, and unreasonable size is a natural consequence of coaxial-resonator filters. Harmonic crystal filters are inadequate because of the unpredictable amount of spurious modes above the harmonic frequency; and hence they can only be used for very low percentage bandwidths. A solution to the above problems is provided by the use of helical resonators for high-quality filters.

This paper describes the helical resonator, measurement of its Q, and coupling to the resonator. A procedure for the design and construction of a filter using helical circuits is then presented. Finally an example is given illustrating the design method, and several photographs of helical-resonator filters are shown.

The Split-Feedback Push-Pull Magnetic Amplifier—I. M. Horowitz (p. 110)

This paper describes a high-gain phase-sensitive magnetic amplifier which simultaneously possesses the high-gain property of the self-saturating (100 per cent positive feedback) amplifiers and the limited circulating current property of the low-gain zero feedback amplifiers. These features are obtained by using feedback windings to obtain the self-saturating large-gain property. However, the feedback windings are arranged so that the feedback is positive only when load current flows and is zero when circulating currents flow. The circuit is analyzed and its various modes of operation are described. The theory is verified with numerous experimental results.

Radio-Frequency Autotransformers with Coaxial-Transmission-Line Windings—J. F. Cline (p. 119)

Impedance transformations are derived for radiofrequency autotransformers wound with sections of coaxial-transmission line. The outer conductors of the transmission-line sections all are connected in parallel to form a single-turn secondary winding, while the primary winding consists of this single turn plus all of the inner conductors connected in series. The circuit also can be used in single-port applications as a loop antenna, coupling link, or magnetic probe, the impedance being increased because of the transformer effect. A general method of analysis is described for an N-turn primary winding and explicit expressions are given for $N=2$ and $N=3$. From the standpoint of frequency response, the principal difference between this circuit and an ordinary autotransformer is that the ordinary leakage-inductance effect is replaced by a transmission-line effect that leads to alternate bands of usefulness and nonusefulness as the frequency is increased above the normal cutoff range.

Transient Effects of Pulsed Nuclear Radiation on Electronic Parts and Materials—H. J. Degenhart and W. Schlosser (p. 123)

Nuclear radiation induced transient changes in the electrical characteristics of electronic parts and materials obtained in recent experiments at the GODIVA II pulse reactor are described and discussed. The electronic parts investigated and monitored during exposure in-

clude: coaxial cables; resistors of various types and manufacture, ranging in value from 100 ohms to 1 megohm; sensistors; capacitors, ceramic and tantalum; rectifiers, silicon and selenium; and magnetic cores, ferrite. Most of the parts during exposure show transient parameter changes which exceed the tolerance values and then recover generally to the nominal value within two to five msec. This behavior is of serious concern in data and information processing equipment and in high-frequency and high-accuracy instrumentation which are exposed to such a nuclear environment, yet which must maintain their operational tolerance even for short periods of time.

Contributors (p. 129)

Electronic Computers

Vol. EC-10, No. 3, September, 1961

Logic and Switching Theory

Editorial—N. R. Scott (p. 345)

An Algorithm for Path Connections and Its Applications—C. Y. Lee (p. 346)

The algorithm described in this paper is the outcome of an endeavor to answer the following question: Is it possible to find procedures which would enable a computer to solve efficiently path-connection problems inherent in logical drawing, wiring diagramming, and optimal route finding? The results are highly encouraging. Within our framework, we are able to solve the following types of problems:

1) To find a path between two points so that it crosses the least number of existing paths.
2) To find a path between two points so that it avoids as much as possible preset obstacles such as edges.
3) To find a path between two points so that the path is optimal with respect to several properties; for example, a path which is not only one of those which cross the fewest number of existing paths, but, among these, is also one of the shortest.

The minimal-distance solution has been programmed on an IBM 704 computer, and a number of illustrations are presented. The class of problems solvable by our algorithm is given in a theorem in Section III. A byproduct of this algorithm is a somewhat remote, but unexpected, relation to physical optics. This is discussed in Section VI.

Cascaded Finite-State Machines—A. Gill (p. 366)

In this paper, *networks* of finite-state machines, rather than individual machines, are discussed. The investigation centers around *cascade* networks, where the output of one machine serves as an input to another. It is shown how, by means of connection matrices, the characteristics of such a network can be obtained from those of the component machines, and how a specified machine can be decomposed into a number of cascaded components. The advantages of such a decomposition, as well as some of the problems that remain to be solved in this area, are discussed.

The Realization of Symmetric Switching Functions with Linear-Input Logical Elements—W. H. Kautz (p. 371)

The problem of synthesizing switching networks out of linear-input (threshold) elements is studied for the class of symmetric switching functions. Tight bounds are derived for the number of elements required in a minimal realization, and a method of synthesis is presented which yields economical networks. Minimal networks result for all symmetric functions of no more than about twelve variables, and for several other cases. In particular, it is shown how the parity function of any number n of variables can be realized with about $\log_2(n)$ elements.

Orthogonal Functions for the Logical Design of Switching Circuits—R. P. Coleman (p. 379)

A new approach to the mathematical represenation of switching functions is presented. It was developed in connection with a theoretical study of magnetic-core logic, but the results are considered to be more basic and general than the core-logic problem. The ampere-turns (MMF) expression for core switching is shown to be part of a special type of Fourier series expansion of a switching function, in which the turns are directly related to the spectrum of the function. Fourier's transform methods, used for analysis of X-ray diffraction, have been adapted to the representation of switching functions. The method leads not to Boolean algebra, but to ordinary algebra in terms of the orthogonal functions

$$(-1)^{k_1x_1+k_2x_2+\cdots+k_nx_n}$$

where

$$x_1, x_2, \ldots, x_n = 0, 1,$$

and

$$k_1, k_2, \ldots, k_n = 0, 1.$$

Methods of application are described for magnetic-core logic and for character recognition.

Autocorrelations for Boolean Functions of Noiselike Periodic Sequences—B. M. Eisenstadt and B. Gold (p. 383)

One method of generating a waveform whose correlation function resembles that of noise is by means of combinations of periodic binary sequences. In this paper the properties of the correlation function for arbitrary functions of n periodic binary sequences are investigated. An especially simple formulation is obtained when each binary variable in all the sequences has equal probability of being 0 or 1. For this case, it is shown that there are only two functions which result in a correlation function like true purely random noise. One of these two functions corresponds to addition modulo 2. Also the correlation for the case of a random function of n sequences is derived. Finally, expressions are obtained for the number of degenerate Boolean functions.

Computer Systems and Circuits

Signed-Digit Number Representations for Fast Parallel Arithmetic—A. Avizienis (p. 389)

This paper describes a class of number representations which are called *signed-digit* representations. Signed-digit representations limit carry-propagation to one position to the left during the operations of addition and subtraction in digital computers. Carry-propagation chains are eliminated by the use of redundant representations for the operands. Redundancy in the number representation allows a method of fast addition and subtraction in which each sum (or difference) digit is the function only of the digits in two adjacent digital positions of the operands. The addition time for signed-digit numbers of any length is equal to the addition time for two digits. The paper discusses the properties of signed-digit representations and arithmetic operations with signed-digit numbers: addition, subtraction, multiplication, division and roundoff. A brief discussion of logical design problems for a signed-digit adder concludes the presentation.

Computing Machine Aids to a Development Project—C. W. Rosenthal (p. 400)

A system of integrated computer programs which provide useful machine assistance to the development of a digital system will be described. The individual programs are capable of such separate engineering tasks as verifying design data, optimally locating electronic logic packages on a chassis, routing interconnecting wires and preparing documents like wiring diagrams and wire running lists.

The engineer using the system need not be a computer programmer because the machine aids programs are called into operation with a simple mnemonic language keyed to the engineer's traditional tasks. This aspect of the work as well as the accomplishment of the individual engineering tasks are emphasized in this paper.

Improvement of Electronic-Computer Reliability through the Use of Redundancy—W. G. Brown, J. Tierney and R. Wasserman (p. 407)

Physical elements used for switching logic have finite probability of failure. The application of redundancy to logic circuits is presented for improving computer reliability. This paper shows various redundant configurations considered and the conclusion drawn.

From all of the considerations, the majority gate provides a practical method for increasing the reliability. It shows that for operating periods which are short compared to the mean time to failure of the elements, a substantial increase in system reliability is obtained with majority-gate redundancy.

Some Thoughts on Digital Components and Circuit Techniques—A. W. Lo (p. 416)

Signal standardization and control directivity are emphasized as the basic physical requirements in considering components and circuit techniques for the handling of digital information. The significance and the ways and means of meeting these requirements are most revealing when illustrated by the operations of the parametric phase-locked oscillator and the tunnel diode. A categorical listing of digital-gain elements, accompanied by illustrative comments, is presented to offer a unified viewpoint on digital components and circuit techniques in connection with present-day practice and prospective future development.

UNIVAC-LARC High-Speed Circuitry: Case History in Circuit Optimization—N. S. Prywes, H. Lukoff, and J. Schwartz (p. 426)

In recent years, the design of computer circuits has become a thorough and complex job. Factors such as logical design, behavior of components, manufacturing techniques, and life tests are playing an even more important role in the design of an efficient circuit.

This paper will discuss how circuit optimization techniques and use of the UNIVAC® I computing system aided in reducing cost and avoiding many of the pitfalls in the design and production of efficient high-speed circuitry for UNIVAC-LARC.

Digital Storage

Coincident-Current Superconductive Memory—L. L. Burns, Jr., G. A. Alphonse, and G. W. Leck (p. 438)

In a continuous superconductive film memory, elements are obtained through discrete regions of circulation of persistent currents near the intersection of *x-y* conductors deposited on the film. Analysis and confirming experiments show that these regions are stable. The elimination of edges of discrete film dots removes the main cause of variation of critical currents. Reproducibilities better than one quarter per cent were obtained. Simplicity of construction permits high bit densities. Memory planes of one-hundred cells were made. Advisable speed of operation depends mainly on addressing and sensing circuits. Write-in in 3 nsec was obtained in single elements with only 60 milliamperes drive.

Semipermanent Storage by Capacitive Coupling—D. H. MacPherson and R. K. York (p. 446)

The need arises for reliable, economical high-speed, semipermanent stores for electronic-telephone switching systems, as well as for modern digital computers. A semipermanent or fixed store is one in which the stored information may not be changed by the machine that is able to consult it. These stores provide data security for such information as operational programs and test routines.

A random-access store system where the memory elements consist of a matrix of printed capacitors has been developed. The store has a cycle time of 3 μsec and contains 1024 words each 34 bits long.

The access circuits developed enable one to utilize a matrix arrangement of components where a need exists for stores of thousands of words. These circuits consist of diodes and biased square-loop ferrite cores in the input, and magnetic gates, utilizing three transformers in a novel arrangement, in the output.

A Card-Changeable Permanent-Magnet-Twistor Memory of Large Capacity—W. A. Barrett, F. B. Humphrey, J. A. Ruff, and H. L. Stadler (p. 451)

The card-changeable permament-magnet-twistor memory is a large capacity (ca 10^5 bits) storage media for information that is infrequently changed. The information is stored in the form of small bar magnets bonded to a removable plastic card. The magnets, when magnetized, inhibit the switching of a section of twistor wire at a twistor-wire-solenoid crosspoint. For maximum information density the magnet shape and strength must be optimized with respect to the magnet's action on the inhibited crosspoint and the fringing action on neighboring crosspoints. The objective is a magnet with a small dipole moment, but with adequate inhibition of the twistor switching over a reasonable range of misposition. Suitable magnet shapes and a general discussion of the stray fields in a large array of magnets are given. For maximum capacity, the transmission characteristics of the twistor wire and the character of the access switch must be considered. Two novel structures of this memory permit increased information density and capacity. The feasibility of a random-access high-density memory submodule containing 360,000 bits in 0.7 foot with a cycle time of 5 μsec has been demonstrated.

Correction to "Reducing Computing Time for Synchronous Binary Division"—R. G. Saltman (p. 461)

Symbol Manipulation, Artificial Intelligence

The Simulation of Cognitive Processes: An Annotated Bibliography—P. L. Simmons and R. F. Simmons (p. 462)

A Note on the System Requirements of a Digital Computer for the Manipulation of List Structures—H. Gelernter (p. 484)

The technique of programming within the framework of the so-called Newell-Shaw-Simon (NSS) associative list memory is currently the subject of much interest among workers in the area of advanced programming research. Unfortunately, committing a given program to list memory generally entails accepting a significant loss of speed and efficiency in information processing, so that the advantages accruing from the use of list memory must be carefully balanced against its weaknesses. This paper is concerned with the system requirements of a digital computer for which the use of list techniques is to be competitive with standard programming, so that the particular memory organization for a given problem may be chosen on the basis of suitability and ease of programming alone. A description of a list-processing 7090-type computer is appended in order to make our discussion concrete, although engineering and economic feasibility is not implied.

Simulation of Three Machines Reading Arabic Numbers—L. A. Kamentsky (p. 489)

Three machines have been simulated using an optical scanner and the IBM 704 computer. Each of these simulated machines has read documents containing *rows* of handwritten Arabic numbers. Sample numbers were produced by at least 20 people for each simulation study. The three machines simulated differ in the control required of the writer during document preparation and in the complexity of the machines. Writing controls were required for the preparation of the first two types of documents. A section of this paper concerns experiments with and a mathematical model of controlled writing. The third simulated machine was applied both to numbers written within preprinted boxes and to numbers written without any guide marks. About one per cent of 2180 of these numbers were misread as the wrong character. This error rate is based on a sequential experiment in which the recognition logic is constructed from all characters not recognized and thus rejected prior to each input character. Numbers, when rejected, cause the program to identify them from a table. Their structure is then entered into the recognition logic. The rejection rate decreased throughout the experiment. The last rejection rate was about 10 per cent.

An Analog Method for Character Recognition—W. H. Highleyman (p. 502)

A method for character recognition which is capable of an analog implementation has been studied by simulation on a digital computer. In essence, this method involves maximizing the cross-correlation value between the unknown character and a set of average characters, there being one average character for each allowed character class. An average character is represented by a two-dimensional function. The value of this function at a point is the probability of occurrence of a mark at that point for the character class represented by the average character. Negative weights are given to areas of low probability in each average character to improve discriminability.

The simulation results indicate that this method is applicable to the recognition of machine printing, and perhaps to the recognition of constrained hand printing. The method can be implemented in an economical manner using electro-optical techniques.

Analog Computers

The Hall-Effect Analog Multiplier—G. Kovatch and W. E. Meserve (p. 512)

The application of the Hall effect to a general-purpose four-quadrant multiplier is discussed. Circuit diagrams for the transistor amplifiers are given. An evaluation of the experimental results is given for a breadboard model of the multiplier. Static accuracies on the order of 1 per cent to 3 per cent are obtained for the Hall channel and the magnetic channel, respectively. Bandwidths of 25 kc and 1.3 kc are achieved for the Hall channel and the magnetic channel, respectively.

Copper-Mandrel Potentiometer Dynamic Error and Compensation—C. H. Single and J. A. Brussolo (p. 516)

A simple potentiometer equivalent circuit is presented that is valid for single or multiturn, copper-mandrel, wire-wound precision potentiometers. Developed to obtain a practical approximation of potentiometer ac characteristics, it is particularly useful in error analyses where small phase errors are critical.

Capacitive compensation techniques are also given that can achieve considerable reduction in potentiometer dynamic error. Even for heavy capacitive loading it is possible virtually to eliminate potentiometer phase error (important in most analog computer circuits). Correspondingly, high-frequency square waves can be attenuated reasonably by such capacitively-compensated potentiometers.

Design of the ESIAC Algebraic Computer—M. L. Morgan and J. C. Looney (p. 524)

The concept of a pair of potential-plane "factor analogs," in which voltage measurements at the zeros and poles of a function are used for the calculation, is employed in the design of a general-purpose computer for algebraic functions of a complex variable. The logarithmic complex plane is used in order to represent a wide range of zeros and poles with uniform accuracy. Plotting facilities provide direct graphical output for applications such as frequency response plots and root-locus plots.

Correspondence (p. 530)

Reviews of Books and Papers in the Computer Field (p. 541)

Abstracts of Current Computer Literature (p. 555)

PGEC News (p. 575)

Notices (p. 579)

Human Factors in Electronics

Vol. HFE-2, No. 2, September, 1961

The Diagnostic Process in Men and Automata—E. M. Bennett and J. W. Degan (p. 68)

Diagnostic skill involves recognizing symptoms of unusual or atypical functioning or structure, understanding the meaning of these symptoms, and evolving the ways in which such knowledge can be applied in the discovery of other existing symptoms and in the isolation of existing defects. The talents involved in diagnosis and the characteristics of the search for symptoms and defects are outlined.

An Overview of Human Factors in Electronic Maintenance—B. H. Manheimer and J. R. Kelley (p. 73)

Electronic equipment is becoming increasingly complex, and proper performance and high availability are becoming more crucial. A recent emphasis on improving maintenance planning and implementation is one method being used to assure meeting availability requirements. Human-factors contributions are essential to electronic-maintenance planning and implementation in all phases of equipment design and support. Much effort has been devoted to preparing guides for designing more maintainable equipment, but results have been little used. In the areas of equipment support, maintenance methods and procedures (both in general and for specific equipments) are being improved, but they still reflect too little knowledge of the maintenance man in the maintenance environment. Human-factors skills are being applied, with varying degrees of effectiveness, to the formulation of maintenance-manpower data, planning of support environment, installation, publications, and training. Trends, particularly those noted in manned space-travel programs, indicate that human-factors efforts in the area of electronic maintenance will improve and form a very valuable contribution to the over-all efforts to improve maintenance.

The Influence of Teaching Machine Technology on Electronic Systems Maintenance Training—L. C. Silvern (p. 78)

The evolution of electronic systems maintenance philosophy is explored in terms of performance requirements, studies of behavioral patterns, technical training requirements, engineering design, and management competences. The probable degree of success in utilizing the teaching machine for employee and customer technical training involving the maintenance of complex electronic systems is considered.

Analysis of Fault-Location Behavior in Electronic Equipment—J. W. Rigney, D. H. Schuster, T. L. Runyan, and I. J. Budnoff (p. 84)

Two analyses of maintenance technicians' intermediate behavior in trouble-shooting electronic equipment are reported. In the first, 422 records of this behavior were analyzed to describe the characteristics of the process. It was found that technicians frequently accumulated sufficient symptom information from test points to isolate a malfunctioning stage or to identify a faulty component, before they recognized this fact. Typically, either they continued to make redundant or irrelevant checks before

entering the correct stage or replacing the correct part, or they never did use the information and thus failed to solve the problem. Also, 71 per cent of the first replacements of components were incorrect. Evidently, searching for symptom information and interpretation of that information occur on two different behavioral levels, which are not necessarily closely coordinated.

The second analysis revealed the differential effects of practice in applying a trouble-shooting strategy for two subsamples of technicians, one experienced and the other inexperienced in the circuitry involved. Subsequent to the practice, the experienced group made a higher proportion of most efficient moves, whereas the inexperienced group made a lower proportion, per problem, of completely irrelevant moves. It was concluded that the former improved primarily in terms of their trouble-shooting techniques and that the latter gained chiefly in their understanding of gross circuit relationships.

Why Design for Maintainability?—J. G. Wohl (p. 87)

The relationships among down time (a system-maintainability measure), time between failures (a system-reliability measure), equipment availability, number of equipments, number of on-call technicians, and system-readiness reliability are developed under the assumption of constant failure and repair rates. Design trade-off between reliability and maintainability is shown to be feasible with resulting reduction in both design and operating costs. A technique for specifying combined reliability, maintainability, and availability constraints to manufacturers is reported which allows the latter a great deal of design flexibility in meeting operational requirements at least cost. Finally, the need for research to establish the quantitative effects of maintainability-design practice upon down time is explored.

Designing Maintainable Circuits—J. M. McKendry, J. F. Corso, and G. Grant (p. 93)

A study was conducted to answer certain questions basic to the design of more maintainable circuits. The subjects were 210 engineers, all of whom had considerable experience in electronics. Questionnaires, designed to elicit information on the primary factors affecting fault-location time, were devised for 13 representative circuits varying over a wide frequency range. A statistical analysis of the subjects' responses was conducted to determine whether any general conclusions could be drawn from the replies taken as a group. Results indicated that certain parameters yield more trouble-shooting information on all circuits and that these parameters remain approximately the same for the whole frequency range studied. In addition, it was found that oscilloscopes were considered to be the most efficient test device available. This result points out a problem, since a number of studies have shown that technicians have difficulty in using oscilloscopes and, as a result, prefer meters. Suggestions are made for circumventing this problem. A number of other analyses pointed out areas in which no generalities could be drawn, *e.g.*, regarding the most efficient test-point locations. An attempt was made to reconcile these problems temporarily until more data are available.

Quantification of Expert Judgment in Maintenance Design Decisions—M. R. Munger, M. P. Willis, and J. W. Altman (p. 97)

Generalized findings, based on work carried out in the development of the Index of Electronic Maintainability for the U. S. Army Signal Corps, are reported on the quantification of expert judgment in the area of maintenance and maintainability. Results of this study indicated that judgments of maintenance consequences can be reliably obtained from field-maintenance personnel if proper precautions are observed in the development and utilization of the rating instruments. Further, these results revealed considerable consistency of ratings across various types of equipment, thus implying that this generality may be extended to new equipments. This generality also eases the problem of obtaining adequate numbers of raters, since the type of experience that the rater bases his judgments on does not appear to be highly specific. No evidence was presented concerning the amount or degree of experience required for competent raters. Finally, three suggested applications of the techniques described are presented, and some of the benefits to be derived from these applications are briefly discussed.

Evaluation of Trouble-Shooting Overlay Designs—W. L. Wasserman (p. 102)

An experiment was conducted to compare two parameters of trouble-shooting overlay design: type of point-to-point connection and type of coding. Eighteen subjects were used in the experiment. They were asked to trace four tests on each of four different designs encompassing the two parameters. The results indicated that the optimum design is straight-line point-to-point connection with color coding.

Human-Initiated Failures and Malfunction Reporting—J. Cooper (p. 104)

Two studies were conducted to determine the extent and nature of human-initiated failures in missile systems. The first study compared malfunction data obtained from written reports with data gathered from interviews with line and supervisory personnel. The study revealed large discrepancies in emphasis and extent of data between the reporting methods. Written reports generally were concerned only with failed equipment; interview data with operational, near, or possible malfunctions. The results indicated that personnel tend to report human-initiated malfunctions as equipment malfunctions, thus avoiding incrimination of themselves or their fellow workers. The second study attempted to establish the extent of unreported human-initiated malfunctions. Examination indicated that in individual missile systems, human-initiated malfunctions comprised from 20 to 53 per cent of all system malfunctions. It was also revealed that in two missile systems, human-initiated holds accounted for 16 and 23 per cent of total holds, respectively. Human-initiated malfunction data were further classified into the kinds of operations in which these malfunctions occurred. The percentages in these classifications are indicated in this report. Malfunction-reporting practices were reviewed to establish their effectiveness in revealing these data and to indicate the way in which the reporting schemes serve, or fail to serve, the problem of indicating human-initiated malfunction in order that corrective action may be taken.

Communications (p. 110)
Contributors (p. 114)
Reviews of Current Literature (p. 118)

Industrial Electronics

Vol. IE-8, No. 2, August, 1961

Transistorizing the Industrial Image Orthicon Camera—R. W. Cook (p. 1)

This paper describes the design of a fully transistorized image orthicon camera. Through the use of detailed circuit descriptions in areas such as the preamplifier, shading circuits and focus current regulator, the advantages transistors offer are pointed out. These advantages show themselves in the form of substantial reduction in weight, size, cost and operating power. Charts and photographs are used to describe in detail the sensitivity, capabilities and applications of such a camera. Schematics are used in describing pertinent circuit advantages.

Computers for Industrial Control—R. W. Sonnenfeldt (p. 10)

General Purpose Digital Computers are now making their appearance in industrial plants. For the most part, they do not merely mechanize tasks previously handled by humans but make possible an entirely new era in control of complicated processes. Industrial Control Computers are now being designed for such applications. This paper discusses in basic terms the characteristics and performance features of industrial Computers, and how they can increase process profitability.

Computer Speed, Memory Capacity, Kind of Memory, Mechanical Design, Programming Features, Reliability and other specifications are related to requirements of Industrial Control. A typical application analysis is explained through use of a high-speed tin plate line as an illustrative example. Several suggestions are offered as an aid in the writing of better purchase specifications.

Currently about three years are needed to go from first conception to an operating Industrial Computer installation. A discussion is given of the many tasks to be completed by user and supplier in this process.

The Infrared Radiometric Method and its Application to Remote Temperature Measurement—H. L. Berman (p. 18)

The principles of infrared thermometry are reviewed. Basic properties of infrared optical materials and detectors are presented with reference to design and performance of the radiation thermometer. Application of the radiometric method to a broad class of common industrial materials forms the substance of this paper. Recent extensions of the method to temperature measurement of flames, glass and plastics are described. Applications of special interest to the Radio Engineer are included.

A Phase-Shift Data-Transmission System for Analog to Digital or Digital to Analog Conversion—H. Kilroy (p. 31)

A block diagram of the basic building blocks of phase-shift data-transmission systems is outlined in Figure 1. These basic blocks establish a reference time base in one or more synchro receivers to which phase signals may be compared.

A pulse source generates a train of pulses which provide this time base for the system. This chain of pulses is divided down in the reference counter and provides two 400-cycle (chosen for convenience) square-wave signals which are 90° out of phase. These signals are filtered and amplified in the synchro exciter and appear as outputs of the exciter in the form of two sinusoidal, 400-cycle signals 90° out of phase. The two sinusoids are used to excite the two stator windings of one or more synchro resolvers. The voltage induced in the rotor of each synchro resolver is a constant-amplitude, 400-cycle sinusoid whose phase angle with respect to the reference is equal to the mechanical angle of the rotor.

Radio Frequency Interference

Vol. RFI-3, No. 1, May, 1961

Scanning the Issue—A. R. Kall (p. 1)

Response of Ideal Radio Noise to Continuous Sine Wave, Recurrent Impulses, and Random Noise—D. B. Geselowitz (p. 2)

The responses of an ideal radio noise meter to continuous sine wave, recurrent impulses, and random noise are evaluated and tabulated. The ideal meter consists of a narrow-band linear low noise superheterodyne network followed by a detector which responds to the envelope of the intermediate frequency and a dc voltmeter which indicates the detector output. Four detector circuits—peak, quasi-peak, average, and rms—are considered. Their "ideal" characteristics are defined in the text.

Signal Acceptability Criteria—R. F. Schwartz (p. 11)

The detailed study of interference of unwanted radio signals having arbitrary modulation, with a specified co-channel signal carrying the desired intelligence, forms the basis for this paper. Detailed information about the modulation characteristics, as well as the transfer function of the receiver from antenna to output channel, are needed in order to predict acceptance ratios, or what this author has called TSI ratios. In some cases, masking of one intelligence by another needs to be taken into account, in others, beat note interference is the prime culprit, while in still others, the mechanism is far more complex. Representative TSI ratios are deduced and presented for a large number of systems, but the set of figures is by no means complete.

Interference Computations for a Complex Signal Environment—L. Katz (p. 18)

A digital computer has been programmed to evaluate the interference existing at each receiver in a large-scale army deployment involving about 20,000 receivers and transmitters. In order to reduce data handling problems, spurious responses are considered to be due to separate receivers and transmitters. Propagation path losses are statistically tailored to the terrain. The model is suitable for a parametric analysis of path loss, selectivity, spurious emissions, sensitivity, etc.

Radio Interference Reduction and Spectrum Utilization of VHF FM Net Equipment in a Mobile Environment—F. E. Rock (p. 27)

Spectrum conservation and interference reduction are not mutually complementary in a field area complex. Spectrum economy implies minimum utilization of RF channels, whereas interference-free operation requires an extensive number of channels. A certain minimum level of interference is tolerable in practice. Therefore, it follows that a system designer achieves realistic spectrum economies by designing the frequency assignment plan for a "calculated risk" level of interference.

Frequency assigners have, in fact, been doing just this sort of thing on a "rule of thumb" basis. An evaluation is made of what the use of such a practical rule means in terms of the probability of interference. The analyses is based on a statistical propagation model called "Universal Terrain." A procedure is established for conserving spectrum when unlike combinations of equipment are employed. Curves of propagation loss and interference statistics are presented.

Measurement and Suppression of VHF Radio Interference Caused by Motorcycles and Motor Cars—C. Egidi and M. Nano (p. 30)

The problem of ignition interference and its reduction has been emphasized in Europe, due to the simultaneous growth in both the number of motor vehicles, and in the number of FM and TV receivers. The paper reports the results of a large number of interference measurements made on automobiles and motorcycles. The data include the effects of various suppression schemes. As a result of these measurements, and taking into account existing European standards, a draft of an international standard was prepared for submittal to CISPR. This proposed standard covers both methods of measurement and limits.

Correspondence (p. 39)

Abstracts of Books on Topics of Interest (p. 46)

Reliability and Quality Control

Vol. RQC-10, No. 2, August, 1961

Reliability in Missile and Space Operation —Maj. Gen. L. I. Davis (p. 1)

Reliability—Whose Responsibility?—H. L. Hoffman (p. 4)

Do Present Government Procurement Practices Promote Delivery of UNRELIABLE Equipment?—Panel Discussion (p. 9)

This round table discussion was established in the belief that much of the problem of unreliability stems from inadequate communication of concepts and understanding between the top people in military and industry. Open discussion of the common problems should be beneficial to the common cause.

This compilation is a follow-up action to record for further study and discussion the major points brought out at the meeting. Comments from the reader and suggestions on how to make progress in the problem areas described will be appreciated.

Reliability Planning for Space Systems—N. E. Golovin (p. 20)

The Space Environment and Its Effects on Materials and Component Parts—S. N. Lehr and V. J. Tronolone (p. 24)

The best available preliminary information has been gathered on what materials can be used successfully and how these materials react in various space environments. Such information is necessary as a guide to space vehicle design engineers.

In addition to the factors presented here, such items must be considered as: the exact nature of the missile of a space vehicle, the type of orbit, the length of time the vehicle is expected to function, the reliability objective, and similar goals, although regardless of the mission certain general effects of the space environment present problems which must be met in the design itself. Data have been gathered on these general effects, which include high vacuum, magnetic fields, gravitational fields, micrometeorites, cosmic rays, neutrons, trapped charged particles, and electromagnetic radiation, including ultraviolet light, X rays, and gamma rays. This information is summarized in Table I.

Small Subcontractors in Reliability Programs—D. C. Berman (p. 38)

Today's military systems contracts invariably have numerical and organizational reliability requirements. With systems of any size, it is advantageous for the prime contractor to subcontract out many equipments and units. Small firms often provide superior specialized technical competence, more favorable prices, faster delivery, and a more conscientious effort; however, the small firm's lack of continuing and repetitive contractual requirements for reliability usually results in organizational weakness in this area. These firms are unable to support the cost of permanent reliability, standards, and quality control functions of the type required by these contracts.

A standard comprehensive quality or reliability survey would eliminate these organizations from competition, and a superficial survey leading to their acceptance would result in the acquisition of an ineffective subcontractor. As a substitute, a specially designed analytical survey is performed which investigates the quality, reliability, standards, and design functions of the prospective subcontractor, and indicates not only the deficiencies, but also the remedial action required.

If, on the basis of price, delivery and technical competence, a firm in this category is awarded a subcontract, procedures are instituted which invariably result in a reliability achievement at least equal to that of some large organizations which, at times, have inflexible and incompatible procedures.

This paper describes, in brief, the survey techniques and the remedial procedures instituted.

The Economics and Reliability of Multifunction Devices—J. A. Davies and C. D. McCool (p. 42)

The widely prevalent assumption that device failure rates are multiplied when two or more functions are incorporated in a single enclosure is examined with respect to actual experience on single-element vs multiple-element electron tubes. The feasibility and economics of multi-element structures are considered in the light of the recent trend toward greater and greater complexity of device combinations. The natural limits to this trend are predicted by extrapolating known factors related to spread of characteristics, random catastrophic failures, and life. Some of the most recent examples of this philosophy are described and discussed in comparison to earlier versions providing similar functional performance.

Military System Reliability: Some Department of the Air Force Contributions—J. Spiegel and E. M. Bennett (p. 53)

This report discusses the evolution, since the formation of the Department of the Air Force in 1947, of the Air Force's administrative policy concerning the reliability of complex military electronic equipment and systems. It describes developments in defining and regulating the contractor reliability effort and the monitoring and advisory activity of the Air Force procuring agencies. By reference to numerous policy statements made by the Air Force, the report demonstrates that, within only a few years after its first stated concern regarding reliability, the Air Force has succeeded in developing a reliability program which is sufficiently detailed and integrated to provide substantial assurance of reliable equipment.

Letters to the Editor (p. 64)

Biographies (p. 67)

Space Electronics and Telemetry

Vol. SET-7, No. 3, September, 1961

Availability of Moon for Global Communications—P. M. Hahn and N. C. Randall (p. 57)

This paper describes a method for quickly and quite accurately estimating the time that the moon is in common view of two stations on earth during the lunar day. A mathematical derivation and a detailed description of the method are given, together with a nomogram which simplifies the calculation. A sample problem is solved and a short table of time availability for several links of interest is included.

Thresholds and Tracking Ranges in Phase-Locked Loops—C. S. Weaver (p. 60)

This paper presents a general discussion of phase-locked-loop thresholds and tracking ranges. A typical phase-locked loop and its linear equivalent are introduced, and there is a brief discussion of application of the root locus method and the Bode amplitude plot to this circuit. Calculation of the maximum allowable deviation is considered for both phase and frequency modulation (sinusoidal).

The SNR threshold is a function of tracking and modulation, and may vary considerably. Threshold behavior—with and without limiting—is discussed, and methods are presented for estimating the threshold in each case. Calculating the tracking range and variation of the tracking range with threshold variation are also discussed. Since an increase in tracking range and a decrease in threshold are obvious design objectives, procedures are given for achieving these goals.

After a description of the effects of interference on tracking and the threshold, there is a brief report of a phase-locked-loop intelligibility study conducted by Philco Western Development Laboratories.

Appendixes I–IV consider: 1) a phase-locked loop containing an IF amplifier, 2) designing a loop to track Doppler shift only, and 3) improving the SNR by increasing deviation.

The Effect of Antenna Characteristics on Antenna Noise Temperature and System SNR—M. L. Livingston (p. 71)

With the development of low-noise amplifiers, the noise contribution of the antenna has become a limiting factor on system performance in many applications. This paper discusses the calculation of the equivalent noise temperature contribution of parabolic reflector antennas using their radiation characteristics and environment. As an example, the equivalent noise temperature of an 85-foot reflector at 2 kMc is estimated as a function of orientation for two different primary illuminations. The relative contributions of the mainlobe, sidelobes and backlobes to the total antenna noise temperature is determined in each case to show the effect of antenna radiation characteristics on noise temperature. A functional relationship between the primary illumination of a parabolic reflector antenna and the system SNR is then derived from which the edge illumination producing the maximum SNR can be specified for a given family of primary illuminations.

Fundamental Accuracy Limitations in a Two-Way Coherent Doppler Measurement System—J. A. Develet, Jr. (p. 80)

This paper derives relationships which express the contributions of ground-receiver noise and round-trip transit time to the errors in two-way radio Doppler measurements.

Only one method of Doppler measurement is considered. This is the method of counting the number of cycles in a given time interval. From this measurement the signal frequency may then be determined. In usual tracking systems this frequency measurement is further utilized to determine the range-rate of the vehicle with respect to the tracking station.

The power-spectral densities of additive-receiver noise and oscillator-frequency noise are assumed white. This situation prevails when the random disturbances are thermal in origin. This is a tractable assumption when one seeks *fundamental* accuracy limitations for Doppler measurement.

The results of this paper should be useful to those concerned with radio tracking and, in particular, tracking of space probes.

Contributors (p. 86)

Vehicular Communications

Vol. VC-10, No. 2, August, 1961

World Wide Communications Using Satellite Repeaters—R. D. Campbell (p. 2)

Mobotry: The New Art of Remote Handling—J. W. Clark (p. 12)

Equipment to perform a great variety of tasks within hostile environments has been designed and built utilizing well-proven electronic techniques. Such systems perform most of the operations which would be performed manually were it possible for a man to enter the hazardous area. Examples of hostile environments include space, the ocean, nuclear laboratories, and numerous others.

A simple trinary coding command system has proved quite practical and is capable of commanding mobile remote systems having 50 or more degrees of freedom. Conventional closed-circuit television systems may be used for driving and steering remotely-controlled vehicles and for accomplishing manipulative tasks. Two or more such cameras are highly desirable for obtaining good spatial perception.

Examples of remotely-controlled systems for hostile environments include the Hughes Mark II Mobot system for nuclear hot laboratories, the RUM (Remote Underwater Manipulator) built by Scripps Institute of Oceanography for scientific and military operation in the depths of the ocean, and a variety of outdoor remotely-controlled vehicles designed and operated by Engineer Research and Development Labaratory at Fort Belvoir, Virginia, and by Air Force Special Weapons Center in Albuquerque, New Mexico.

Air Lines Radio Communications—G. Kidd (p. 25)

Thin Route Tropo—A New Approach to Long Range Communications—H. H. Davids (p. 28)

This new system of communications makes use of tropospheric scatter for the transmission of digital information over long distances more reliably than high frequency radio; more economically than wire; less vulnerably than microwave or VHF and cheaper than conventional tropospheric scatter systems. Using only a narrow-band width, it can be used for transmission of data (teletype, telemetry, canned messages, facsimile, etc.) over distances of upwards to 500 miles, using relatively low power transmitters and simple antenna systems. It will provide a useful link in the radio communication systems for many government agencies, both military and non-defense. While limited to these under the present regulations, it has potential for use for commercial applications in the future.

A New Helical Ground Plane Antenna—L. H. Hansen (p. 36)

A unity gain ground plane antenna of greatly reduced size is presented. The ground plane consists of four evenly spaced sloping helices. The fed element is constructed of double helical windings. All the helices are enclosed in Fiberglass tubes.

Wide-Band Channels for Emergency Communication—H. Magnuski (p. 40)

A single wideband channel could be assigned to all short range *emergency* communication systems, resulting in better service and better spectrum utilization. Many independent VHF or UHF mobile users or military nets could use this one channel at random without any form of centralized control or synchronization, and each could transmit different simultaneous emergency messages without significant mutual interference.

In reviewing wideband modulation and addressing (coding) techniques, it is shown that Delta modulation and discrete frequency coding is best suitable for this application.

Tone Signaling Increases Mobile Radio Efficiency—T. G. Humphreys, Jr. (p. 45)

A New Approach to Transistorization of Mobile Radio Telephone Equipment—I. Teose (p. 49)

An equipment design is described in which transistors are employed in both receiver and transmitter to reduce power drain and increase reliability. The following design objectives are believed successfully met:

Low power drain in receive condition.

Tuning adjustments minimized by use of lumped ferrite filters for both first and second I.F. selectivity of receiver.

All components easily and quickly accessible for maintenance.

Up to eleven r.f. channels available within a one Mc/s band for both receiver and transmitter. Thus particularly adaptable to Maritime VHF.

Manufacturing cost of same order as vacuum tube designs of similar r.f. power output.

A detailed description is given of a compact unit suitable for either underdash or trunk mounting in vehicular installation.

A 150-Mc Personal Radio Signaling System—D. Mitchell and K. G. Van Wynen (p. 57)

An experimental 150-Mc personal signaling system has been set up in New York City to evaluate over-all technical performance and explore subscriber reactions to the system. The system includes pocket receivers equipped with tuned reeds and central office arrangements adapted for direct customer dialing. The paper describes the system in over-all terms, and tells how it was engineered. It also compares this system with present 35 Mc-systems and discusses traffic and radio transmission problems.

Splitting the 450-Mc Channels—C. J. Schultz (p. 71)

A recently released FCC Notice of Proposed Rule Making, Docket No. 13847, contains a proposal to subdivide the existing 50-kc channels in the 450–470-Mc private land mobile band into twice as many 25-kc channels.

Field and laboratory tests conducted to date indicate that the proposed technical standards can be successfully implemented in *closely controlled* test systems. Some significant problems may arise in actual "user" systems, however, if transmitters and receivers are not properly netted and held to a close RF channel tolerance. Considerable attention must be given to the various factors which determine the amount of receiver performance degradation experienced, if successful implementation of "same area" adjacent channel operation is to be achieved.

Existing 450-Mc equipment of recent manufacture should provide adequate performance in most systems until the 25-kc split channels are assigned to new users in the same area.

Abstracts and References

Compiled by the Radio Research Organization of the Department of Scientific and Industrial Research, London, England, and Published by Arrangement with that Department and *Electronic Technology*, Dorset House, Stamford St., London, S.E. 1, England

NOTE: The Institute of Radio Engineers does not have available copies of the publications mentioned in these pages, nor does it have reprints of the articles abstracted. Correspondence regarding these articles and requests for their procurement should be addressed to the individual publications, not to the IRE.

Acoustics and Audio Frequencies	1726
Antennas and Transmission Lines	1727
Automatic Computers	1728
Circuits and Circuit Elements	1728
General Physics	1730
Geophysical and Extraterrestrial Phenomena	1731
Location and Aids to Navigation	1734
Materials and Subsidiary Techniques	1734
Mathematics	1736
Measurements and Test Gear	1736
Other Applications of Radio and Electronics	1737
Propagation of Waves	1737
Reception	1738
Stations and Communication Systems	1738
Subsidiary Apparatus	1738
Television and Phototelegraphy	1738
Tubes and Electronics	1739
Miscellaneous	1740

The number in heavy type at the upper left of each Abstract is its Universal Decimal Classification number. The number in heavy type at the top right is the serial number of the Abstract. DC numbers marked with a dagger (†) must be regarded as provisional.

UDC NUMBERS

Certain changes and extensions in UDC numbers, as published in PE Notes up to and including PE 666, will be introduced in this and subsequent issues. The main changes are:

Artificial satellites:	551.507.362.2	(PE 657)
Semiconductor devices:	621.382	(PE 657)
Velocity-control tubes, klystrons, etc.:	621.385.6	(PE 634)
Quality of received signal, propagation conditions, etc.:	621.391.8	(PE 651)
Color television:	621.397.132	(PE 650)

The "Extensions and Corrections to the UDC," Ser. 3, No. 6, August, 1959, contains details of PE Notes 598 658. This and other UDC publications, including individual PE Notes, are obtainable from The International Federation for Documentation, Willem Witsenplein 6, The Hague, Netherlands, or from The British Standards Institution, 2 Park Street, London, W.1., England.

ACOUSTICS AND AUDIO FREQUENCIES

534.121.1–8 3213

Experimental Confirmation of Lamb Waves at Megacycle Frequencies—D. C. Worlton. (*J. Appl. Phys.*, vol. 32, pp. 967–971; June, 1961.) Confirmation of a theory formulated in 1916 by Horace Lamb predicting that plates may vibrate in an infinite number of modes.

A list of organizations which have available English translations of Russian journals in the electronics and allied fields appears each June and December at the end of the Abstracts and References section.

534.2+538.566 3214

Wave Propagation in an Inhomogeneous Waveguide—Brekhovskikh and Eliseevnin. (See 3339.)

534.2 3215

Nonlinear Effects in some Acoustic Problems—M. A. Isakovich. (*Akust. Z.*, vol. 6, no. 3, pp. 321–325; 1960.) In contrast to the case of propagation in an unbounded space, the secular terms are missing in the solution for waveguide propagation, with the exception of degenerate cases. The absence of secular terms is dependent on dispersion.

534.2–8 3216

Finite-Amplitude Ultrasonic Wave Propagation in Relaxing Media—A. L. Polyakova. (*Akust. Z.*, vol. 6, no. 3, pp. 356–359; 1960.) If the sound amplitude is less than the value characterizing the dispersion and relaxation absorption, the second-harmonic content is determined basically by the absorption.

534.232 3217

Maximum-Power Criterion for the Vibrating Free-Edge Disk—R. N. House, Jr. (*J. Acoust. Soc. Am.*, vol. 33, pp. 561–565; May, 1961.) A method of determining safe power levels for piezoelectrically driven flexural-mode transducers has been developed.

534.232 3218

On Correlating the Loss Factors of Cylindrical and Spherical Resonators—P. D. Edmonds. (*J. Acoust. Soc. Am.*, vol. 33, pp. 615–622; May, 1961.)

534.232:538.652 3219

Magnetostrictive Ferrites as Materials for Electroacoustic Transducers—I. P. Golyamina. (*Akust. Z.*, vol. 6, no. 3, pp. 311–320; 1960.) Investigation of Ni, Ni-Zn and Ni-Co ferrites shows that their magnetostrictive properties are comparable in magnitude with the corresponding parameters of more generally used metals.

534.232–8 3220

Coupling of Ultrasonic Resonators to Self-Excited Single-Stage High-Frequency Generators—W. Steglich. (*NachrTech.*, vol. 10, pp. 446–449; October, 1960.) The coupling of piezoelectric and magnetostrictive resonators to an oscillator circuit is discussed, with examples.

534.26–14 3221

Experimental Study of the Scattering of Acoustic Energy from Solid Metal Spheres in Water—L. D. Hampton and C. M. McKinney. (*J. Acoust. Soc. Am.*, vol. 33, pp. 664–673; May, 1961.) The spheres cannot be counted as rigid bodies as appreciable energy penetrates the surface, which causes a complicated echo pattern to be returned. The acoustic energy distribution for spheres of diameter 5 in and 7 in is illustrated.

534.417 3222

Factors that Determine the Equivalent Noise Pressure, Free-Field Voltage Response, and Efficiency of a Transducer at Low Frequencies—P. M. Kendig. (*J. Acoust. Soc. Am.*, vol. 33, pp. 674–676; May, 1961.) A well-designed hydrophone should have an equivalent noise pressure well below zero sea-state ambient. The equivalent noise pressure or efficiency of a transducer gives an essential indication of ability to measure low-level signals but the free-field voltage response does not.

534.75:534.32 3223

What do we Sense as Uniform Noise?—L. Schreiber. (*Frequenz.*, vol. 14, pp. 399–403; December, 1960.) Theoretical consideration of Dirac-type noise and the minimum pulse frequency at which a succession of pulses is heard as uniform noise. The results of subjective tests are given and discussed, in which the effect of varying the parameters of an inserted low-pass filter is also investigated.

534.78 3224

Liveness Effects on the Intelligibility of Noise-Masked Speech—P. O. Thompson, J. C. Webster, and R. S. Gales. (*J. Acoust. Soc. Am.*, vol. 33, pp. 604–605; May, 1961.) Speech is more intelligible against a noise background when the reverberant components associated with "liveness" are not present.

534.78:621.391 3225

Bandwidth Compression of Speech—J. Das. (*Electronic Tech.*, vol. 38, pp. 298–300; August, 1961.) A method of reducing the bandwidth of time-varying signals by sampling in the frequency domain alone is discussed. Intelligible signals can be obtained even with large bandwidth compression.

534.793 3226

The Development of a Level-Distribution Meter for the Assessment of Audibility in Rooms—H. Niese. (*NachrTech.*, vol. 10, pp. 487–494; November, 1960.) The equipment de-

The Index to the Abstracts and References published in the PROC. IRE from February, 1960, through January, 1961, is published by the PROC. IRE, May, 1961, Part II. It is also published by *Electronic Technology* and appears in the March, 1961, issue of that journal. Included with the Index is a selected list of journals scanned for abstracting with publishers' addresses.

scribed uses a source of periodic pulses and a stereophonic microphone; the sound level distribution in a lecture hall has been measured and results are illustrated.

534.8–8:539.32.08 3227
Notes and References for the Measurement of Elastic Moduli by Means of Ultrasonic Waves—H. J. McSkimin. (*J. Acoust. Soc. Am.*, vol. 33, pp. 606–615; May, 1961.) Aspects of wave propagation applicable to the measurement of elastic moduli of solids are reviewed. Experimental techniques and factors affecting accuracy are discussed. 111 references.

534.83 3228
The Effect of Open Acoustic Screens in Interior Rooms—H. Börner. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 221–225; December, 1960.) The effectiveness of noise-reducing screens is calculated; experimental results are also given.

534.846 3229
Recent Applications of Acoustical Engineering Principles in Studios and Review Rooms—W. B. Snow. (*J. Soc. Mot. Pic. Telev. Engrs.*, vol. 70, pp. 33–38; January, 1961.)

534.861 3230
Statistical Properties of a Radio Broadcast Signal—A. V. Rimskil-Korsakov. (*Akust. Z.*, vol. 6, no. 3, pp. 360–369; 1960.) Analysis of experimental results obtained by various authors relating to the distribution of instantaneous values and of the dynamic levels of broadcast music and speech.

534.88 3231
Measuring the Transverse Correlation Coefficient of a Continuous Acoustic Signal in the Sea—S. G. Gershman and Yu. I. Tuzhilkin. (*Akust. Z.*, vol. 6, no. 3, pp. 292–298; 1960.) Investigation showed that at a frequency of 7.5 ± 0.2 kc, for distances between the wave front and the source of up to 12 km, and for a spacing of receivers along the wave front of up to 3 km, the correlation coefficient had a value close to unity.

534.88 3232
Effect of an Internal Wave on Sound in the Ocean—O. S. Lee. (*J. Acoust. Soc. Am.*, vol. 33, pp. 677–681; May, 1961.) A comparison of computed sound fields with and without an oscillation of the thermoclines for an ideal ocean medium with three distinct layers. Intensity changes of as much as 22 db may occur over one internal wavelength.

621.395.61 3233
The Insensitivity to Noise of Gradient Microphones of First and Higher Order—K. Feik and G. Kaszynski. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 201–211; December, 1960.) Theoretical and experimental investigation is made of first- and second-order gradient microphones.

621.395.61:681.84 3234
Guidance on the Microphone Distance in Sound Recordings—E. Briner-Aimo. (*Tech. Mitt. PTT*, vol. 39, pp. 5–20; January, 1961.) Aspects of sound field distribution and reverberation effects which are important to the sound recording engineer are summarized.

621.395.623.7 3235
Electrodynamic Loudspeaker has Totally Active Surface—S. R. Rich. (*Electronics*, vol. 34, pp. 49–51; June 16, 1961.) A system giving excellent response over the whole AF range is described. It consists of a nonresonant, pneumatically loaded bass unit and a current-carrying sheet within a magnetic field as a treble unit. High-frequency performance is improved by a thin corrugated Al diaphragm as a secondary radiator, mounted near the driver coil of the treble unit.

621.395.625.3:538.221 3236
Magnetic Recording—Sebestyen and Takacs. (See 3493.)

ANTENNAS AND TRANSMISSION LINES

621.315.212 3237
A Liquid-Helium-Cooled Coaxial Termination—C. T. Stelzried. (Proc. IRE, vol. 49, p. 1224; July, 1961.) This unit is useful for low-noise calibrations.

621.372.823 3238
The Effect of Guide Irregularities on the Transmission of TE_{01} Waves—M. Jouguet. (*Câbles & Trans. (Paris)*, vol. 15, pp. 3–26; January, 1961.) An examination of the parasitic waves generated in waveguides including estimates of their amplitude and power. Numerical results are given for a circular waveguide of diameter 50 mm operated at 35 Gc. See also 2080 of August.

621.372.824 3239
The Suppression of Parasitic Gap Resonances on Noncontacting Short-Circuiting Plungers for Coaxial Resonant Circuits—W. Spindler. (*Arch. elekt. Übertragung*, vol. 14, pp. 554–560; December, 1960.) An exact equivalent circuit is derived for the plunger gap with slots [see 644 of 1948 (Huggins)]. New types of pattern are described which provide greater mechanical stability and a wider useful band for the coaxial resonator.

621.372.824:621.316.8 3240
A Precision Coaxial Termination Resistor—C. Stäger. (*Tech. Mitt. PTT*, vol. 39, pp. 25–28; January, 1961.) The design of a 50-Ω reflectionless termination for use in the frequency range 1–9 Gc is described.

621.372.829 3241
TM Modes in Parallelogrammic Waveguides—R. J. Doviak, D. J. Lewis, and P. P. Lombardini. (Proc. IRE, vol. 49, p. 1222; July, 1961.) TM modes can exist in parallelogrammic waveguides and an approximate formula for f_c is given.

621.372.832.4 3242
A Variable Microwave Power Divider—D. Milanovic. (*Onde élect.*, vol. 41, pp. 180–183; February, 1961.) A practical form of power divider is described using directional coupling between two waveguides and the Faraday effect in a ferrite rod.

621.372.832.43 3243
The Use of Asymmetric Coupling for Waveguide Directional Couplers with Frequency-Independent Coupling Factor—W. Nowak. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 179–188; October, 1960.) The asymmetric $H_Z - H_Z$ multiaperture coupler described has a flat frequency response and is suitable for coupling factors of the order of 3–20 db.

621.372.832.43 3244
The Oblique-Slot Coupler, a New Waveguide Directional Coupler for Frequency-Independent Loose Couplings—W. Nowak. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 193–201; December, 1960.) The coupler described is suitable for coupling factors of about 10–60 db. An arrangement for closer coupling is described in 3243 above.

621.372.837:621.382.23 3245
Semiconductor-Diode Waveguide Switch—T. H. B. Baker. (*Electronic Tech.*, vol. 38, pp. 300–304; August, 1961.) The relation of the switching ratio, bandwidth and power-handling capabilities to diode and transmission-line parameters is given.

621.372.852.2 3246
Reciprocal and Nonreciprocal Phase Shifters in Rectangular Waveguide—E. Pivit. (*Frequenz*, vol. 14, pp. 369–378; November, 1960.) Theoretical and experimental investigation of the dielectrically loaded waveguide as reciprocal phase shifter. Experimental results of measurements on ferrite-loaded nonreciprocal phase shifters are discussed, with particular reference to the temperature compensation of phase shift.

621.372.852.323:538.632 3247
Microwave Isolator combines Hall Effect and Tunnel Diodes—C. H. Hubbard, L. A. LoSasso, and E. Rousso. (*Electronics*, vol. 34, pp. 56–57; June 16, 1961.) A simple circuit is described giving useful isolation up to about 30 Mc, and performance parameters are discussed. The InSb Hall-effect plate is provided with a thermoelectric cooler to provide additional circuit adjustment. Tunnel-diode lead inductance limits its performance.

621.396.67 3248
Some Problems regarding Medium-Wave Broadcast Aerials with Cross-Section Gradually Increasing towards the Centre (Fish-Belly Aerials)—N. Stanulov. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 161–170; October, 1960.) Determination of the current distribution along this type of antenna and of its vertical radiation characteristics. Methods of improving the antifading properties are suggested.

621.396.67:621.318.134 3249
A Nondirectional Ferrite Rod Antenna Arrangement Suitable for AM Radios—O. K. Nilssen. (Proc. IRE, vol. 49, pp. 1222–1223; July, 1961.) Signals from orthogonal ferrite rod antennas are added in quadrature.

621.396.67:621.396.669 3250
The Suppression of Corona- and Precipitation-Interference in V.H.F. Reception—Page. (See 3531.)

621.396.67.012.12 3251
A Method for the Synthesis of Radiation Patterns at Finite Distances—L. Caprioli, L. Rónchi, A. Scheggi, and G. Toraldo di Francia. (*Alta Frequenza*, vol. 29, pp. 653–666; December, 1960.) A semi-empirical procedure is described for an approximate synthesis using a finite number of spherical waves.

621.396.673 3252
The Behaviour of Linear Short and Thin Aerials with a Variation in Current Distribution—G. D'Auria and F. Todero. (*Alta Frequenza*, vol. 30, pp. 28–42; January, 1961.) The effect of top loading on antenna performance is is investigated. Expressions are derived for input impedance and radiation efficiency as a function of current distribution.

621.396.677.85 3253
Dielectric Lenses and Reflectors made from Homogenous Spherical Layers—P. M. Prache. (*Ann. Télécommun.*, vol. 16, pp. 85–95; March/April, 1961.) A method which is given for calculating the ray paths in manufactured lenses and reflectors is also used to determine the equivalent surface of a reflector as a function of the angle between the incident and reflected rays. Theoretical results are in good agreement with results of measurements on a reflector of diameter 175 mm.

621.396.679 3254
The Achievement of Optimum Vertical Field Strength at the Ground by means of Wire

Grids—K. Baur. (*Elektrotech. Z., Edn. A.*, vol. 82, pp. 13–18; January 2, 1961.) The effect of SW reflection at the foot of receiving antennas is considered, and details are given of the design of wire grids for producing a maximum of the interference field strength at ground level.

AUTOMATIC COMPUTERS

681.142 3255
Design and Application of a Digital Differential Analyser—D. Lamb. (*Proc. IRE (Australia)*, vol. 22, pp. 243–249; April, 1961.) The principles of operation and limitations of a digital incremental computer are given and fields of research in which its accuracy and speed would be useful are suggested.

681.142 3256
Full Binary Adder with One Tunnel Diode—B. Rabinovici and C. A. Renton. (PROC. IRE, vol. 49, pp. 1213–1214; July, 1961.) Three resistors and one tunnel diode in a Wheatstone bridge network give both "sum" and "carry" outputs.

681.142:512.3 3257
A Program for finding the Zeros of a Polynomial by Analogue Computer—A. Lepschy. (*Alta Frequenza.*, vol. 30, pp. 21–27; January, 1961.)

681.142:621.318.134 3258
A Magnetic Associative Memory—J. R. Kiseda, H. E. Petersen, W. C. Seelbach, and M. Teig. (*IBM J. Res. Dev.*, vol. 5, pp. 106–121; April, 1961.) A computer storage system is described in which data flow in and out on the basis of content rather than location. A small experimental model of the system using ferrite cores is also described.

681.142:621.319 3259
A Probability Distribution Analyser utilizing Electrostatic Storage—I. K. Harvey. (*Electronic Engrg.*, vol. 33, pp. 432–436; July, 1961.) The instrument has a linearity within ±0.25 per cent and analyzes input waveforms of frequency of 0–20 kc.

681.142:621.372.54:621.391 3260
A Universal Nonlinear Filter, Predictor and Simulator which Optimizes itself by a Learning Process—D. Gabor, W. P. L. Wilby and R Woodcock. (*Proc. IEE*, pt. B, vol. 108, pp. 422–435; July, 1961. Discussion, pp. 436–438.) After a discussion of some cybernetic principles a machine is described which, by a process of successive runs on an input function, ultimately produces a target function with least error. The machine incorporates a 20-track tape recorder, and 80-analog multipliers of a novel piezomagnetic type which perform 1000 multiplications per second with errors not exceeding 0.5 per cent.

681.142:621.385.832 3261
A Cathode-Ray-Tube Output for a Digital Computer—R. L. Grimsdale and N. Barraclough. (*J. Brit. IRE*, vol. 21, pp. 497–501; June, 1961.) A variety of displays can be programmed and are photographed by a camera controlled by the computer.

681.142:621.385.832 3262
Radar-Computer Display traces Alphanumeric Characters—K. E. Perry and E. J. Aho. (*Electronics*, vol. 34, pp. 75–79; June 30, 1961.) The 64 available characters are displayed by the spot deflection method at a rate of 13,500/sec. A full description of the system with block and circuit diagrams is given.

681.142:621.398 3263
Logarithmic Compression of Binary Numbers—D. H. Schaeffer. (PROC. IRE, vol. 49, p. 1219; July, 1961.) This 19-to-8 bit converter uses 4 bits for the most significant figures and 4 bits to indicate the position of the binary point. Accuracy is within ± 3 per cent.

CIRCUITS AND CIRCUIT ELEMENTS

621.3.049.7:539.23 3264
Step-by-Step Design Techniques for Multilayer Thin-Film Networks—W. N. Carroll and F. F. Jenny. (*Electronics*, vol. 34, pp. 90–93; May 10, 1961.) Performances of various circuits incorporating thin-film passive networks and those with conventional components are compared.

621.318.43:621.396.962.33 3265
Magnetics in Doppler Signal Data Extraction—R. J. Metz and J. G. Fay. (*Commun. and Electronics*, no. 53, pp. 33–43; March, 1961.) Doppler radar data extraction problems such as detection, integration and interrogation using devices with magnetic cores are discussed.

621.318.57 3266
A Magnetic Device for High-Speed Sensing of Small Currents—J. A. Baldwin, Jr. (*Commun. and Electronics*, no. 53, pp. 1–3; March, 1961.) The structure and operation of the "ferrod" device are described. It comprises a bar of low-coercive-force square-loop ferrite with two holes transverse to the long axis. The material around the holes acts as a pair of toroidal cores whose switchable flux may be controlled by a solenoid current.

621.319.4:621.317.72 3267
The Vibrating Capacitor, Theory and Application—Riegler. (See 3510.)

621.372.44 3268
The Energy Properties of Nonlinear Reactance Circuits—J. Neirynck. (*Rev. HF, Brussels*, vol. 5, no. 1, pp. 13–17; 1961.) There will be a conversion of power at one frequency to power at another frequency if one frequency is a rational fraction of the other or if at least one intermodulation frequency exists.

621.372.5 3269
A Network Theorem—J. B. Rudd. (*AWA Tech. Rev.*, vol. 11, pp. 107–128; December, 1960.) The problem of determining the transfer impedance between a generator EMF at one end of a resistance-terminated ladder network and the load current at the other end is simplified by splitting the circuit into two sections.

621.372.5 3270
On Scattering Matrices Normalized to Complex Port Numbers—D. C. Youla. (PROC. IRE, vol. 49, p. 1221; July, 1961.) A $2n$-terminal network with generators having complex impedances is considered.

621.372.5:517.94 3271
A Review of Methods of Linear Network Analysis in the Steady State: Parts 1 and 2—P. W. Seymour. (*Proc. IRE (Australia)*, vol. 22, pp. 77–96 and 253–270; February and April, 1961. Correction, *ibid.*, p. 249.) The establishment of an independent set of network variables permits various methods of network solution. The four-terminal network and the use of reference parameters are also considered.

621.372.51 3272
Wide-Band Impedance Transformers—J. B. Rudd. (*AWA Tech. Rev.*, vol. 11, pp. 179–194; December, 1960.) An analysis of networks consisting of cascades of lumped-circuit $\lambda/4$ sections of graded impedance level.

621.372.54 3273
A Property of Passive Lossless Quadripoles and its Application in the Design of Ladder Filters—Y. Peltier. (*Câbles & Trans. (Paris)*, vol. 15, pp. 27–50; January, 1961.) The validity of formulas giving the values of elements of various filter structures is established by expressing the insertion loss as a function of the iterative parameters of a fictitious network.

621.372.54:517.7 3274
Using Jacobians for Frequency-Selective Networks—T. R. Nisbet and W. W. Happ. (*Electronic Ind.*, vol. 20, pp. 86–89; January, 1961.) The advantages of the use of Jacobians for synthesis of networks to give a specific frequency response is demonstrated with a simple network.

621.372.54:534.143 3275
Computation of Mechanical Filters—M. Börner. (*Elektron. Rundschau*, vol. 15, pp. 11–14; January, 1961.) Filter-design procedure and data are summarized.

621.372.54:621.372.57 3276
Active Low-Pass RC Filters—D. P. Franklin. (*Electronic Tech.*, vol. 38, pp. 278–282; August, 1961.) A method is described of synthesizing the over-all response of active cascaded low-pass filters using simple RC ladders and buffer amplification.

621.372.632:621.382.23 3277
Tunnel-Diode Down-Converters—D. G. Peterson. (PROC. IRE, vol. 49, pp. 1225–1226; July, 1961.) Different circuit analyses are compared.

621.373:621.372.44 3278
The Dynamics of a Subharmonic Oscillator with Linear Dissipation—G. J. Lasher. (*IBM J. Res. Dev.*, vol. 5, pp. 157–161; April, 1961.) A mathematical analysis is made of the dynamic behavior of subharmonic oscillators (parametrons) assuming a nonlinear reactance but a linear dissipation or resistance.

621.373+621.375].029.65 3279
Present State of Millimetre-Wave Generation and Amplification—W. Veith. (*Nachrtech. Z.*, vol. 13, pp. 592–597; December, 1960.) A review of techniques, particularly those based on the use of conventional microwave valves.

621.373.42.072.7 3280
Pull-In Frequency of the Phase-Controlled Oscillator—A. J. Goldstein and C. J. Byrne. (PROC. IRE, vol. 49, p. 1209; July, 1961.) The pull-in frequency derived by Goldstein and confirmed experimentally by Byrne is lower than that recently derived by Rey (81 of February).

621.373.422 3281
Additional Negative-Resistance Oscillation Modes—W. N. Carr and T. C. Matty. (PROC. IRE, vol. 49, p. 1225; July, 1961.) Several "class-C" modes are considered.

621.373.43 3282
Voltage-Variable Capacitors make a Relaxation Oscillator—J. Lopez and J. Brown. (*Electronics*, vol. 34, pp. 96–98; May 19, 1961.) The controllable frequency range is 15 cps–1.5 kc.

621.374 3283
Random-Pulse Generator tests Circuits, encodes Messages—B. K. Ericksen and J. D. Schmidt. (*Electronics*, vol. 34, pp. 56–59; June 23, 1961.) The shift-register generator uses high-speed logic circuits in producing complicated pulse sequences up to 4×10^9 bits in length.

621.374:621.3.018.782 3284
Testing the Linear Distortion of Transmis-

sion Systems by means of Rectangular Pulses and Application of this Method for Explaining the Differential Equalization used in Magnetic-Tape Equipment—H. Kumpfert. (*Frequenz*, vol. 14, pp. 416–421; December, 1960. Correction. *ibid.*, vol. 15, p. 31; January, 1961.)

621.374:621.382.23 3285
Generation of Nanosecond Carrier Pulses at *X* Band with Tunnel Diodes—L. U. Kibler. (Proc. IRE, vol. 49, p. 1204; July, 1961.)

621.374.32:621.382.23 3286
100-Mc Tunnel-Diode Ring Counter—F. P. Heiman. (Proc. IRE, vol. 49, p. 1215; July, 1961.)

621.374.32:621.398 3287
Multiaperture-Core Counters give Nondestructive Storage Read-Out—W. R. Johnston. (*Electronics*, vol. 34, pp. 62–64; June 16, 1961.) Description of a counter circuit and its use in a missile guidance control system.

621.374.33 3288
R.F. Gate with 10^9 Carrier Suppression—R. J. Blume. (*Rev. Sci. Instr.*, vol. 32, pp. 554–556; May, 1961.) A 10.7-Mc RF gate is described with a carrier supression ratio >180 db. The ungated CW signal is continuously available. Circuitry, leakage measurements, and screening techniques are described.

621.374.4 3289
Frequency Multiplication by Large Factors by means of the Oscillation-Build-Up Method—G. Becker. (*Frequenz*, vol. 14, pp. 412–416; December, 1960.) Frequency multiplication by factors of several thousands can be achieved with the oscillator described, which is pulse-controlled at the fundamental frequency and produces a harmonic spectrum of few components during the build-up of oscillations.

621.374.4:529.786 3290
Methods of Pulse Selection to Produce Accurate Timing Marks from Standard Frequencies—G. Becker. (*Arch. elekt. Übertragung*, vol. 14, pp. 539–542; December, 1960.) Counter circuits are given which are suitable for the production of low-frequency timing pulses independent of phase fluctuations in the frequency dividers of crystal clocks.

621.375:512.83 3291
A Matrix Representation of Linear Amplifiers—K. G. Nichols. (*J. Brit. IRE*, vol. 21, pp. 517–533; June, 1961.) Expressions are developed for the transfer matrices of combinations of bilateral and unilateral networks, and of some passive and active networks including feedback amplifiers.

621.375.049.7:621.317.7 3292
Designing for Low-Level Inputs—D. B. Schneider. (*Electronic Ind.*, vol. 20, pp. 81–85; January, 1961.) Difficulties arising in low-level input instrumentation, and methods of checking and evaluating the performance of such equipment are given.

621.375.121.1 3293
Interstage Design for Stagger-Loaded Amplifiers—L. A. Beattie. (*Electronics*, vol. 34, pp. 60–63; May 26, 1961.) A family of low-pass Butterworth amplifiers, each stage having a different load impedance, is described. The resulting stagger-loaded amplifier has high gain and large bandwidth; an example shows half-power points at 2.7 Mc and 25 Mc and a mid-band gain of 95.

621.375.132 3294
The Theory of Negative-Feedback Voltage Amplifiers—C. H. Vincent. (*Electronic Engrg.* vol. 33, pp. 442–444; July, 1961.) A modification of the standard method of analysis taking account of the fact that the attenuated feedback voltage cannot always be subtracted directly from the input voltage in practice.

621.375.2.024 3295
D.C. Amplifier with Particularly High Zero-Level Stability—H. L. König. (*Arch. elekt. Übertragung*, vol. 14, pp. 543–553; December, 1960.) A push-pull circuit for drift compensation in dc amplifiers is described and details are given of its practical application and performance.

621.375.221 3296
Contribution on the Dynamic Plate-Load Amplifier—K. Emden. (*Arch. elekt. Übertragung*, vol. 14, pp. 487–490; November, 1960.) A method is described for improving frequency and phase response of the type of amplifier considered in 2163 of 1959 (Brown).

621.375.3:621.3.087.6 3297
Single-Ended Self-Balancing Magnetic Amplifiers for Changing the Effective Impedance of Ink Recorders—W. A. Geyger. (*Commun. and Electronics*, no. 53, pp. 8–13; March, 1961.)

621.375.4 3298
Common-Emitter Amplifier—R. Leek. (*Electronic Tech.*, vol. 38, pp. 285–297; August, 1961.) The medium-frequency performance of common-emitter amplifiers is examined in terms of the simple equivalent circuit for a transistor. Formulas enabling the best type of transistor to be selected are derived.

621.375.4 3299
Transistor Cascode Circuit Improves Automatic Gain Control in Amplifiers—J. F. Perkins, Jr. (*Electronics*, vol. 34, pp. 49–51; June 2, 1961.) An improved method, with circuit details, for applying AGC to transistor IF tuned amplifiers is described. The effects of changes in the transistor parameters, with change of operating point, on the *Q*-factor and the center frequency of the tuned circuit are minimized.

621.375.4:621.391.822 3300
A Theoretical Comparison of Average- and Spot-Noise Figure in Transistor Amplifiers—J. A. Ekiss and J. W. Halligan. (Proc. IRE, vol. 49, pp. 1216–1217; July, 1961.)

621.375.9:538.569.4 3301
Investigation of the Performance of Coupled-Cavity Maser-Type Amplifiers: Part 2—G. Broussaud and L. Malnar. (*Onde élect.*, vol. 41, pp. 184–199; February, 1961.) A general formula is developed to determine the equivalent noise temperature and gain stability of several elementary structures. By comparing these results, interesting features of multicavity masers are demonstrated. Part 1: *ibid.*, vol. 40, pp. 555–572; September, 1960.

621.375.9:538.569.4 3302
Traveling-Wave Maser with Instantaneous Bandwidths in Excess of 100 Mc—S. Okwit and J. G. Smith. (Proc. IRE, vol. 49, p. 1210; July, 1961.) Broad bandwidths, more than twice the intrinsic linewidth of ruby, were obtained by stagger-tuning the applied external magnetic field.

621.375.9:621.372.44 3303
Parametric Circuits with Nonlinear Reactances and Resistances—K. H. Steiner. (*Arch. elekt. Übertragung*, vol. 14, pp. 482–486; November, 1960.) Equivalent circuits of nonlinear reactances and resistances are derived for calculations on parametric amplifiers. Expressions giving the circuit voltages are tabulated for parametric amplifiers, up-converters and down-converters of the dynatron type and the nonlinear-capacitance type.

621.375.9:621.372.44 3304
Sensitivity of the Degenerate Parametric Amplifier—J. T. de Jager and B. J. Robinson. (Proc. IRE, vol. 49, pp. 1205–1206; July, 1961.) Although the noise temperature of a degenerate parametric amplifier is half that for a nondegenerate amplifier, the minimum detectable signal is only $\sqrt{2}$ better because the post-detector noise fluctuation increases by a $\sqrt{2}$ factor.

621.375.9:621.372.44 3305
Noise Measure of Distributed Negative-Conductance Amplifiers—A. van der Ziel. (Proc. IRE, vol. 49, pp. 1212–1213; July, 1961.) The modification required to the noise measure *M* for circuits in which the characteristic impedance has a reactive part is given.

621.375.9:621.372.44 3306
The Noise Temperature of Cascade-Connected Amplifiers—W. Dahlke and H. Rieck. (*Telefunken-Röhre*, no. 38, pp. 37–60; December, 1960.) A formula is derived for the noise temperature of a cascade-connected amplifier with negative conductances as active elements. This permits a simple graphical representation of noise characteristics; examples are given of parametric-amplifier stages, and the influence of isolators and circulators on noise temperature and bandwidth is discussed.

621.375.9:621.372.44 3307
Parametric Amplification with a Low-Frequency Pump—G. F. Montgomery. (Proc. IRE, vol. 49, pp. 1214–1215; July, 1961.) The degenerate form of a three-frequency parametric amplifier is considered.

621.375.9:621.372.44 3308
An *L*-Band Traveling-Wave Parametric Amplifier—S. J. Tetenbaum, F. A. Olson, and A. Savarin. (Proc. IRE, vol. 49, pp. 1230–1231; July, 1961.) A gain of 10 db over a 10 per cent band around 1.35 Gc has been achieved.

621.375.9:621.372.44:621.382.23 3309
Reactance Diodes and their Application in Wide-Bend Waveguide Amplifiers—Bobisch and Sondhauss. (See 3571.)

621.375.9:621.372.44:621.385.63 3310
Noise in Beam-Type Parametric Amplifiers—Gordon. (See 3592.)

621.375.9:621.372.44:621.385.63 3311
Parametric Coupling between the Transverse Waves on O- and M-Type Beams—Klüver. (See 3593.)

621.375.9:621.372.44:621.385.63 3312
Transduction of Noise Theory of a Generalized Travelling-Wave Coupler—Pease. (See 3594.)

621.375.9:621.382.23 3313
Selective High-Frequency Amplification with Tunnel Diodes—K. H. Müller. (*Elektronik*, vol. 10, pp. 39–43; February, 1961.) The design of a VHF FM tuner using tunnel diodes is detailed.

621.375.9:621.382.23 3314
Minimum Noise Figure of the Negative-Resistance Amplifier using Esaki Diodes—M. Müller. (*Arch. elekt. Übertragung*, vol. 14, pp. 499–502; November, 1960.) The minimum noise figure is determined for a nonreciprocal single-stage amplifier, and the result is extended to cover multistage amplifiers. A noise figure of about 5 db can be achieved for high-gain single-stage or multistage amplifiers.

621.375.9:621.382.23 3315
Semiconductor Diode Circuit Provides Gain—S. Ritterman. (*Electronics*, vol. 34, pp. 60–62; June 2, 1961.) The forward-reverse characteristics of a diode can be used to provide amplification (see 987 of 1955). The characteristics of a circuit operating with power-supply frequency considerably higher than the signal frequency are noted.

621.375.9:621.382.23 3316
Noise Measure of Lossy Tunnel-Diode Amplifier Stages—A. van der Ziel. (PROC. IRE, vol. 49, pp. 1211–1212; July, 1961.) The influence of circuit losses and the diode series resistance on the noise figure of tunnel-diode amplifiers is considered. The calculation is repeated for a stable parallel circuit.

621.376.2:621.318.435 3317
A Saturable-Core Modulation Integrator—R. C. Barker and A. J. Gruodis. (*Commun. and Electronics*, no. 53, pp. 13–17; March, 1961.) A circuit is discussed which illustrates the use of saturable-core reactors for operating directly on a modulation carrier. Use is made of the ability of a saturable reactor to convert a voltage integral to a magnetic flux and store it until required.

621.376.223 3318
Constant-Resistance Modulators—D. G. Tucker. (*J. Brit. IRE*, vol. 21, pp. 491–496; June, 1961.) Zobel's constant-resistance networks are interpreted in terms of constancy with time, when the elements of the network are time-variable, and simultaneously in the same network the original conception of constancy with frequency, when the elements are frequency-variable, may be realized. The application to rectifier modulators is examined.

621.376.23 3319
Requirements regarding Electrical Squaring Circuits and Practical Possibilities for the Realization of Square-Law Cahracteristics—E. Sonntag. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 211–216; December, 1960.) The design of square-law detector circuits for use in the measurement of rms values is discussed and the characteristics of various types of circuit using diodes or amplifier valves are examined.

621.376.23 3320
Squaring Circuits with Staggered Diodes—E. Sonntag. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 217–221; December, 1960.) With the circuit described a square-law characteristic can be synthesized over a range of about 30 db. Ge diodes give better results than those obtained with thermionic valves. See also 3319 above.

621.376.233.029.65 3321
Crystal Biasing Improves Millimeter-Wave Detector—K. Ishii and A. L. Brault. (*Electronics*, vol. 34, p. 65; June 16, 1961.) At 73 Gc a 14-db improvement in noise figure could be obtained by suitable biasing.

GENERAL PHYSICS

537.311.1 3322
Variational Method for Transport Parameters in Electron Conductors—R. Klein. (*Z. Naturforsch.*, vol. 16a, pp. 116–121; January, 1961.) The method described results in a simplification and clarification of calculation procedure.

537.311.1 3323
Derivation of the Boltzmann Transport Equation for Inelastic Collisions—P. N. Argyres. (*J. Phys. Chem. Solids*, vol. 19, pp. 66–72; April, 1961.) A quantum-mechanical treatment similar to that developed by Kohn and Luttinger for elastic collisions (1105 of 1958). For Fermi-Dirac particles the scattering in the collision term of the transport equation is restricted to unoccupied states only.

537.311.33 3324
Negative Resistance and Hot Electrons—I. Adawi. (*J. Appl. Phys.*, vol. 32, pp. 1101–1111; June, 1961.) *I/V* characteristics of hot electrons are analyzed for negative-resistance regions. Electrons in a homogeneous semiconductor are assumed to interact only with acoustic phonons and charged centers of heavy mass which could be ionized impurities or heavy holes.

537.52:537.533.8 3325
Electron Bunching in the Multipacting Mechanism of High-Frequency Discharge—A. J. Hatch. (*J. Appl. Phys.*, vol. 32, pp. 1086–1092; June, 1961.) Electron bunching is analyzed by an extension of simple multipacting theory.

537.525 3326
Electronic and Ionic Current at the Cathode of a Hollow-Cathode Discharge—V. K. Rohatgi. (*J. Appl. Phys.*, vol. 32, pp. 1173–1174; June, 1961.) The fractions of electronic and ionic current densities in the discharge are estimated. The possibilities of other electron-emission mechanisms are discussed.

537.56 3327
Instability of a Plasma with an Anisotropic Distribution of Ion and Electron Velocities—A. V. Kitsenko and K. N. Stepanov. (*Zh. Eksp. Teor. Fiz.*, vol. 38, pp. 1840–1846; June, 1960.) Investigation of the propagation of magneto-hydrodynamic waves in an infinite rarefied plasma. A kinetic treatment leads to an increase of the instability region compared to that obtained in the quasi-hydrodynamic approximation.

537.56 3328
Fluctuations in a Multicomponent Plasma—C. Buneman. (*J. Geophys. Res.*, vol. 66, pp. 1978–1979; June, 1961.) A theory of fluctuations in a plasma consisting of electrons and one kind of ion (3391 below) is generalized to apply to several species of ions.

537.56:534.1 3329
Electrostatic Sound Wave Modes in a Plasma—F. W. Crawford. (*Phys. Rev. Lett.*, vol. 6, pp. 663–665; June 15, 1961.) The ratios between the frequencies of the peaks observed in the anode voltage fluctuations in Hg discharge tubes agree with those calculated using a simple theory of radial modes.

537.56:538.56 3330
Coupling Mechanisms between Longitudinal and Transverse Waves in a Plasma—G. Burkhardt, C. Fahl, and R. W. Larenz. (*Z. Phys.*, vol. 161, pp. 380–387; January 27, 1961.) The possible coupling mechanisms are deduced on the basis of fundamental plasma equations. The existence of a nonlinear "internal coupling" effect is proved which can cause electromotive radiation.

537.56:538.56 3331
Enhanced Diffusion and Oscillations in Weakly Ionized Plasmas—J. F. Bonnal, G. Briffod and C. Manus. (*Phys. Rev. Lett.*, vol. 6, pp. 665–667; June 15, 1961.)

538.3 3332
Average Forces in Electromagnetic Systems—W. E. Smith. (*Aust. J. Phys.*, vol. 14, pp. 152–159; March, 1961.) For a linear and loss-free system, it is shown that the time-average force can be expressed in directly measurable circuit-theory parameters.

538.56 3333
A Supplement to a Study of Electromagnetic Point Sources—M. Bouix. (*Ann. Télécommun.*, vol. 16, pp. 105–107; March/April, 1961.) A supplement to a previously published paper (*ibid.*, vol. 14, pp. 143–150; May/June, 1959) establishing that there are only two fundamental fields which can effectively be replaced by a point source, corresponding to a distribution concentric about its origin.

538.561:537.122 3334
Cherenkov Radiation for a Dipole Moment in a Medium with Spatial Dispersion—G. A. Begiashvili and É. V. Gedalin. (*Zh. Eksp. Teor Fiz.*, vol. 38, pp. 1738–1739; June, 1960.) Treatment of electric and magnetic dipoles in an isotropic nongyrotropic medium. Radiation from a ring-current in such a medium is also considered.

538.561:537.56 3335
Radiation by Charged Particles passing through an Electron Plasma in an External Magnetic Field—S. K. Majumdar. (*Proc. Phys. Soc. (London)*, vol. 77, pp. 1109–1120; June 1, 1961.) Coupling between the longitudinal plasma wave and the transverse electromotive wave modifies the nature of the radiation. At particle velocities greater than that required for the excitation of plasma waves, a non-Cherenkov type of radiation will occur.

538.561:537.56 3336
Incoherent Microwave Radiation from a Plasma in a Magnetic Field—J. L. Hirshfield and S. C. Brown. (*Phys. Rev.*, vol. 122, pp. 719–725; May 1, 1961.) "The microwave emission from a plasma in a magnetic field is calculated theoretically using Kirchhoff's radiation law for cases when characteristic waves do not couple within the plasma. Experimental observations of radiation temperatures and cyclotron radiation line breadth and shape are cited to illustrate applications of the theory to experiment."

538.561:539.12 3337
Classical Electrodynamic Equations of Motion with Radiative Reaction—G. N. Plass. (*Rev. Mod. Phys.*, vol. 33, pp. 37–62; January, 1961.) The classical theory is reviewed: previous objections to it are shown to be largely invalid.

538.561:539.12 3338
Radiation from Fast Particles Moving through Magnetic Materials—T. B. Day. (*Phys. Rev.*, vol. 122, pp. 1028–1036; May 15, 1961.) Under certain conditions of frequency and angle of observation "ringing" of the spin system occurs. Differences from the normal Cherenkov effect are discussed, also the possibility of using the effect as a neutral-magnetic-moment detector or as a probe of magnetic materials.

538.566+534.2 3339
Wave Propagation in an Inhomogeneous Waveguide—M. M. Brekhovskikh and V. A. Eliseevnin. (*Akust. Z.*, vol. 6, pp. 284–291; 1960.) Analysis of the propagation of acoustic waves in a waveguide whose properties vary along its length. The theory developed is applied to the propagation of acoustic and electromotive waves in natural waveguides which may extend to distances of 1000 km and more.

538.566 3340
Study of the Electromagnetic Field produced by a Magnetic Doublet in the Presence of Two Media Separated by a Plane Surface—L. Robin. (*Ann. Télécommun.*, vol. 16, pp. 96–

104; March/April, 1961.) A rigorous treatment for the general case of a doublet with its axis at any angle to the surface between the media. The effects of special media are also considered.

538.566:[535.312+535.34 3341
The Reflection of Electromagnetic Waves at a Plane Metal Surface Covered with an Absorbing Layer—B. Unbehauen and H. J. Hoffman. (*Arch. elekt. Übertragung*, vol. 14, pp. 521–530; December, 1960.) The reflection coefficient is calculated as a function of λ for an electromotive wave incident perpendicularly on a thin absorption layer. Numerical and graphical methods are given for the evaluation of layer parameters which make the reflection coefficient as small as possible over a wide range of λ.

538.566:535.42]+534.26 3342
A Note on the Back-Scattering of a Circular Disk—S. R. Seshadri. (*Proc. Nat. Inst. Sci. India*, pt. A, vol. 26, pp. 609–616; November 26, 1960.) Asymptotic series are obtained for the back-scattering cross sections of an acoustically hard disc, an acoustically soft disc and a perfectly conducting disc.

538.566:535.42 3343
The Diffraction of Electromagnetic Waves at Rectangular Apertures in Plane Meta Screens—H. Severin and K. Körper. (*Z. angew. Phys.*, vol. 13, pp. 41–47; January, 1961.) An approximation method of calculating the diffraction field [see, *e.g.*, 2694 of 1951 (Severin)] is applied to the case of rectangular apertures; results are compared with those obtained experimentally.

538.566:535.42 3344
Diffraction by an Elliptic Cone—L. Kraus and L. M. Levine. (*Commun. Pure Appl. Math.*, vol. 14, pp. 49–68; February, 1961.) Two Green's functions are derived for the reduced wave equation in the exterior or interior of an elliptic cone.

538.566:535.43 3345
A Note on the Back-Scattering by an Infinite Strip—S. R. Seshadri. (*Proc. Nat. Inst. Sci. India*, pt. A, vol. 26, pp. 603–608; November 26, 1960.) The first few terms in the asymptotic series of the back-scattering cross section of an infinite strip lying in a plane perpendicular to the direction of propagation of an electromotive wave are calculated for all angles of incidence.

538.566:535.43 3346
Scattering of a Surface Wave by a Discontinuity in the Surface Reactance on a Right-Angled Wedge—F. C. Karal, Jr., S. N. Karp, T. S. Chu, and R. G. Kouyoumjian. (*Commun. Pure Appl. Math.*, vol. 14, pp. 35–48; February, 1961.) An examination of the electromotive field produced when a surface wave travels along the front face of a right-angled wedge and is scattered by the tip.

538.566:535.43 3347
An Experimental Study of Bistatic Scattering from some Small, Absorber-Coated, Metal Shapes—R. J. Garbacz and D. L. Moffatt. (PROC. IRE, vol. 49, pp. 1184–1192; July, 1961.) The absorber coating reduces energy scattering in the back hemisphere but increases the energy scattered in the forward hemisphere.

538.569.4:538.22 3348
Mechanisms of Double Resonance in Solids—J. Lambe, N. Laurance, E. C. McIrvine, and R. W. Terhune. (*Phys. Rev.*, vol. 122, pp. 1161–1170; May 15, 1961.)

538.569.4:538.221 3349
Ferromagnetic Relaxation: Part 1—Theory of the Relaxation of the Uniform Precession and the Degenerate Spectrum in Insulators at Low Temperatures—M. Sparks, R. London, and C. Kittel. (*Phys. Rev.*, vol. 122, pp. 791–803; May 1, 1961.) Scattering by surface polishing imperfections, equalization of degenerate-mode populations, and Raman scattering are considered theoretically and compared with experiment.

538.569.4:538.221 3350
Theory of Magnetostatic Modes in Long, Axially Magnetized Cylinders—R. I. Joseph and E. Schlömann. (*J. Appl. Phys.*, vol. 32, pp. 1001–1005; June, 1961.) The characteristic equation determining the eigen frequencies of the magnetostatic modes is derived from the equations of motion and the boundary conditions.

538.569.4:538.221 3351
Instability of Spin Waves and Magnetostatic Modes in a Microwave Magnetic Field Applied Parallel to the D.C. Field—E. Schlömann and R. I. Joseph. (*J. Appl. Phys.*, vol. 32, pp. 1006–1014; June, 1961.) Two methods of calculating the instability threshold are described, a plane-wave analysis strictly applicable only in an infinite medium and a more rigorous theory in which the boundary conditions at the surface of the sample are taken into account.

538.569.4:538.222 3352
The Role of Phonons in Paramagnetic Relaxation—B. W. Faughnan and M. W. P. Strandberg. (*J. Phys. Chem. Solids*, vol. 19, pp. 155–166; April, 1961.) Theory is given for the coupled spin-lattice-bath system, with nonequilibrium phonons. Experiments fail to indicate the presence of such phonons.

538.569.4:621.375.9:535.61–2 3353
Observation of Forbidden Resonances in Optically Driven Spin Systems—W. E. Bell and A. L. Bloom. (*Phys. Rev. Lett.*, vol. 6, pp. 623–624; June 1, 1961.)

538.569.4:375.9:535.61–2 3354
Thermal Tuning of Ruby Optical Maser—I. D. Abella and H. Z. Cummins. (*J. Appl. Phys.*, vol. 32, pp. 1177–1178; June, 1961.)

GEOPHYSICAL AND EXTRATERRESTRIAL PHENOMENA

523+55]:621.396 3355
Radio Techniques and Space Research—(*Wireless World*, vol. 67, pp. 394–395; August, 1961.) A brief review of the papers on radio topics presented at the British IRE Convention, 1961.

523.15 3356
The Stability of Force-Free Magnetic Fields—B. B. Chakraborty and P. L. Bhatnagar.—(*Proc. Nat. Inst. Sci. India*, pt. A, vol. 26, pp. 592–597; November 26, 1960.) The condition is derived for a force-free magnetic field to exercise a stabilizing influence on an equilibrium configuration; several cases are given for which the condition is satisfied. See also 784 of 1959 (Woltjer).

523.164 3357
The Technique of Radio Astronomy—F. Tank. (*Bull. schweiz. elektrotech. Ver.*, vol. 52, pp. 69–75; February 11, 1961.) Review of applications of radio techniques in modern astronomy, including radio telescopes, interferometers and echo equipment.

523.164 3358
Results of Radio Astronomy—M. Waldmeier. (*Bull. schweiz. elektrotech. Ver.*, vol. 52, pp. 75–80; February 11, 1961.) Review of the field of radio-astronomy measurements, particularly with regard to solar observations.

523.164:621.317 3359
Radio Astronomy—P. G. Mezger. (*Nachrtech. Z.*, vol. 13, pp. 579–591; December, 1960.) Various measurement techniques in the three main fields of research are described and their limitations discussed.

523.164:621.396.677.833.2 3360
The Radio Telescope Interferometer at the Royal Radar Establishment—J. S. Hey. (*Nature*, vol. 190, pp. 1150–1152; June 24, 1961.) Two mobile and steerable radio telescopes, with parabolic reflectors 25 m in diameter, are used either separately or in conjunction as an interferometer. The system is designed to operate in a wide frequency range down to 10 cm λ.

523.164.3 3361
A New Source of Centimetre Radio-Waves—Yu. N. Parilskiĭ. (*Dokl. Akad. Nauk SSSR*, vol. 137, pp. 307–309; March 11, 1961.) During observations carried out at Pulkov Observatory on March, 1959, on 9.4 cm. λ, a new RF source, of energy $>3\cdot 50^{50}$ erg, was detected in the galactic plane, the coordinates being $\alpha_{1950}=18^h\ 53^m\ 38^s$ and $\delta_{1950}=1°.15'$.

523.164.3:523.3 3362
Lunar Occultation of a Radio Source—C. Hazard. (*Nature*, vol. 191, p. 58; July 1, 1961.) By observation of the times of disappearance and reappearance of a radio star behind the moon, the position of the source can be obtained with great accuracy. Taking into account all sources of error, the estimated position is probably correct to within 5″ of arc.

523.164.32 3363
Solar Radio Astronomy in Italy—G. Righini. (*Ricerca Sci.*, pt. 1, vol. 1, pp. 25–37; January, 1961.) The development of radio astronomy outside and inside Italy is traced, and details are given of installations at the Astrophysical Observatory at Arcetri. Some results of observations made there are illustrated and discussed.

523.164.32 3364
Observations of 26.3-Mc/s Solar Radio Noise during August 1959—W. C. Erickson. (*J. Geophys. Res.*, vol. 66, pp. 1773–1780; June, 1961.) Solar RF noise during the noise storm in August, 1959, showed that the intense amplitude scintillation does not appear to extend down to frequencies as low as 26 Mc, and that the 26-Mc storm both began and ended before the m-λ storm did so.

523.164.32 3365
Very-Low-Frequency Modulation of Discrete-Frequency Solar Noise Bursts—J. Aarons, S. Basu, W. Kidd and R. Allen. (*Nature*, vol. 191, pp. 56–57; July 1, 1961.) Measurements of Type II and Type IV bursts at 220, 400 and 3000 Mc show envelope fluctuations which were examined over the range 5–550 cps. The observed narrow-band structure is illustrated.

523.164.32:523.75 3366
A Relation between Solar Radio Emission and Low-Energy Solar Cosmic Rays—K. Sakurai and H. Maeda. (*J. Geophys. Res.*, vol. 66, pp. 1966–1969; June, 1961.)

523.164.4 3367
Characteristics of the NGC 4486 Radio Emission—Yu. N. Parilskiĭ. (*Dokl. Akad. Nauk SSSR*, vol. 137, pp. 49–50; March 1, 1961.) Observations carried out with the Pulkov radiotelescope of Virgo-A showed that the angular extensions of the RF source on 9.4

cm are smaller than those determined by Mills on 3.5 m. Brightness distribution depended essentially on wavelength.

523.165 3368
Radiation Measurements to 1500 Kilometres Altitude at Equatorial Latitudes—F. E. Holly, L. Allen, Jr, and R. G. Johnson. (*J. Geophys. Res.*, vol. 66, pp. 1627–1639; June, 1961.) The relative fluxes, energy spectra, and angular distributions of electrons and protons determined during three flights are reported. The electron spectrum appears to be softer than that expected from a neutron beta-decay origin.

523.165 3369
Effect of Hydromagnetic Waves on the Lifetime of Van Allan Radiation Protons—A. J. Dragt. (*J. Geophys. Res.*, vol. 66, pp. 1641–1649; June, 1961.) Hydromagnetic waves with frequency less than 5 cps and amplitude 3 γ at two or three earth radii are capable of removing all high-energy outer-belt protons (maximum energy $\approx$10 Mev) in about $\frac{1}{2}$ day. If an albedo neutron source is assumed for the inner-belt protons the calculated proton flux, as a function of radial distance from the earth, agrees well with Pioneer III results.

523.165:523.75 3370
Cosmic-Ray Phenomena durlng the November 1960 Solar Disturbances—J. G. Roederer, J. R. Manzano, O. R. Santochi, N. Nerurkar, O. Troncoso, R. A. R. Palmeira, and G. Schwachheim. (*J. Geophys. Res.*, vol. 66, pp. 1603–1610; June, 1961.) Cosmic-ray data for high- and middle-latitude stations are examined to investigate the interaction of a solar-flare increase and Forbush decrease.

523.165:523.75 3371
The Spectrum and Propagation of Relativistic Solar Flare Particles during July 17–18, 1959—H. S. Ghielmetti. (*J. Geophys. Res.*, vol. 66, pp. 1611–1625; June, 1961.) An examination of cosmic-ray data reveals two increases of solar protons for which the time variations are quite different. This difference is attributed to a change in the interplanetary field.

523.3+523.4]:621.396.96 3372
A Theory of Radar Reflection from the Moon and Planets—F. B. Daniels. (*J. Geophys. Res.*, vol. 66, pp. 1781–1788; June, 1961.) Relations between the surface statistics of an irregular radar target and the angular power spectrum and autocorrelation function of the reflected signal are derived. The spatial correlation function is also computed. The theory is used to investigate the small-scale structure of the moon's surface.

523.53 3373
Meteorites and Meteors—N. Carrara. (*Ricerca Sci.*, pt. 1, vol. 1, pp. 14–24; January, 1961.) A general outline of the field of meteor studies with a few details of meteor tracking equipment at the Microwave Centre in Florence and results obtained there.

523.53 3374
The Distribution of Meteor Masses for Sporadic Meteors and Three Showers—A. A. Weiss. (*Aust. J. Phys.*, vol. 14, pp. 102–119; March, 1961.) Distributions of maximum line densities in meteor trails are derived from radio echo data for sporadic and shower meteors.

523.53:621.396.96 3375
Attachment Processes in Meteor Trails—J. S. Greenhow and J. E. Hall. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 261–271; July, 1961.) The effects of electron attachment to neutral particles on the characteristics of long-duration meteor echoes are considered. Two-body and three-body attachment processes produce differing effects and these are compared with observations. See also 2339 of 1960 (Davis *et al.*).

523.53:621.396.96 3376
The Characteristics of Persistent Sporadic Meteor Echoes—J. W. Smith. (*Aust. J. Phys.*, vol. 14, pp. 89–101; March, 1961.) For sporadic meteors whose trails have an electron line density greater than 10^{13} electrons/cm, the observed distribution of meteor echo duration cannot be explained by power-law distributions. There is no significant seasonal or diurnal variation in the mass distribution of the meteors examined.

523.53:621.396.96 3377
A Possible Explanation of the Long-Duration Radar Echoes of Ionized Trails in the Upper Atmosphere—C. L. Tang. (*J. Geophys. Res.*, vol. 66, pp. 1974–1975; June, 1961.) In ionospheric regions where the plasma frequency is near the frequency of the incident wave, the local wavelength of the latter is very long and the destructive interference of the fields scattered from the dispersed trail is less effective.

523.53:621.396.96 3378
Volume Density of Radio Echoes from Meteor Trails in Radar-Type Reception—N. Carrara, P. F. Checcacci, A. Consortini, and L. Ronchi. (*Alta Frequenza*, vol. 29, pp. 615–638; December, 1960.) The echo density is evaluated taking into account trail orientation, the meteor evaporation process and the characteristics of the transmitter/receiver system used for back-scatter reception.

523.53:621.396.96 3379
Volume Density of Reflection Points of Meteor Trails in Radio Links—N. Carrara, P. F. Checcacci, L. Ronchi, and G. Tassinario. (*Alta Frequenza*, vol. 29, pp. 639–652; December, 1960.) The procedure developed for back-scatter systems (3378 above) is applied to the case of forward-scatter links.

550.385.35:523.75 3380
Geomagnetic Crochet of 15 November 1960—M. Yasuhara and H. Maeda. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 289–293; July, 1961.) Discussion of the geomagnetic and ionospheric effects of a large solar flare.

550.385.4 3381
A Possible Explanation of *sc Observed at High Geomagnetic Latitudes**—T. Ondoh. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 284–286; July, 1961.) An explanation of *sc** is given in terms of hydromagnetic waves propagating along the geomagnetic field lines.

551.507.362.2 3382
The Scientific Uses of Earth Satellites—J. H. Blythe. (*Marconi Rev.*, vol. 24, pp. 84–97; 2nd Quarter, 1961.) A survey is given of the effect of the use of artificial satellites on measurements relating to the gravitational field, the atmosphere, the upper ionosphere, magnetic fields near to the earth and interplanetary space, and the zones of trapped radiation.

551.507.362.2 3383
On Simulation Studies of Motion of Bodies in Ionized Atmosphere—K. P. Chopra. (*Z. Phys.*, vol. 161, pp. 445–453; January 27, 1961. In English.) The problems involved in laboratory model studies on satellite motion in an ionized atmosphere are analyzed. Scaling relations obtained satisfy the conditions for aerodynamic, magnetohydrodynamic and electrodynamic similitude. Flight conditions corresponding to the earth's upper atmosphere can be simulated by suitable scaling of the test model.

551.507.362.2 3384
On the Long-Period Lunisolar Effect in the Motion of the Artificial Satellite—P. Musen. (*J. Geophys. Res.*, vol. 66, pp. 1659–1665; June, 1961.) Formulas for the determination of long-period effects caused by the sun and the moon on the motion of satellites and the stability of their orbits are developed.

551.507.362.2 3385
Rapid Variations of the Rotation Period of the Second Soviet Artificial Earth Satellite with respect to the Transverse Axis—V. M. Grigorevskiĭ. (*Dokl. Akad. Nauk SSSR*, vol. 137, pp. 572–575; March 21, 1961.) A table is given of data on the rotation period during March/April, 1958.

551.507.362.2 3386
Determination of the Vertical Distribution of Ozone by Satellite Photometry—S. V. Venkateswaran, J. G. Moore, and A. J. Krueger. (*J. Geophys. Res.*, vol. 66, pp. 1751–1771; June, 1961.)

551.507.362.2 3387
Density of the Upper Atmosphere Determined from Satellite Orbits, and its Variation during 1957–61—D. G. King-Hele and D. M. C. Walker. (*Nature*, vol. 191, pp. 114–118; July 8, 1961.) Calculations from the orbits of 29 satellites in the height range 180–700 km show a decrease in density as the sunspot activity declined between 1957 and 1961. The influence of latitude on density and the large day-to-night variation above 400 km are also considered.

551.507.362.2:551.510.535:621.3.087.4 3388
Satellite Sounder and Telemeter Chart Ionosphere Electron Density—S. Horowitz and L. Humphrey. (*Electronics*, vol. 34, pp. 50–53; June 23, 1961.) A satellite-borne ionosonde is described which is to be launched (into a 2000 km orbit) by the U.S.A. Measurements will be made on six log-spaced frequencies between 3 and 15 Mc, by transmitting 20 pulses of each frequency in turn: crossed dipole receiving antennas are connected in phase quadrature, and the receiver is arranged to receive 10 echo pulses of one polarization and then 10 pulses of opposite polarization. A transistorized transmitter gives a peak power of 150 w with pulse length 500 μsec. Data will be recorded by the satellite and transmitted on command to ground stations.

551.510.535/.536 3389
The Atmospheric Density in the Earth's Ionosphere and Exosphere—H. K. Paetzold. (*Naturwiss.*, vol. 48, pp. 39–40; January, 1961.) The atmospheric density distribution in the exosphere and the *F* layer, as determined from satellite observations, is plotted, and causes of density fluctuations with height are briefly discussed.

551.510.535 3390
Rate of Ion-Atom Interchange—D. R. Bates and M. Nicolet. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 286–287; July, 1961.) Conclusions about the rate of conversion of atomic ions into molecular ions in the ionosphere (*J. Atmos. Terr. Phys.*, vol. 18, pp. 65–70; April, 1960) are reiterated, and an alternative suggestion [1838 of June (Hertzberg)] is discounted.

551.510.535 3391
Density Fluctuations in a Plasma in a Magnetic Field, with Applications to the Ionosphere—T. Hagfors. (*J. Geophys. Res.*, vol. 66, pp. 1699–1712; June, 1961.) General expressions are derived for the fluctuation in density of electrons, ions and net charge in a plasma in thermal equilibrium in an external magnetic field. Coulomb interaction and two-body col-

lisions are taken into account. The total scattered power and Doppler spectrum are calculated for incoherent scatter from the ionosphere at 300–2000 km with a radar at 50–3000 Mc. The total power is unaffected by the magnetic field, but resonance peaks at multiples of the ion gyro-frequency appear in the spectrum when the radar beam is within 5° of orthogonality with the field lines.

551.510.535 3392

Extensions of the 'Chapman' Theory of Layer Formation—C. H. Cummack. (*J. Geophys. Res.*, vol. 66, pp. 1685–1697; June, 1961.) "An attempt has been made to establish some of the theorems necessary for the extension of the "Chapman" theory of layer formation to the case where a spectrum of ionizing radiation acts on an atmosphere with any temperature profile. Some invariant properties of the electron production function have been established, and they have proved useful in estimating the temperature and temperature variations in the ionosphere."

551.510.535 3393

Theory of Electrostatic Fields in the Ionosphere at Polar and Middle Geomagnetic Latitudes—J. R. Spreiter and B. R. Briggs. (*J. Geophys. Res.*, vol. 66, pp. 1731–1744; June, 1961.) Analysis of the elongated electrostatic fields which provide the coupling in the dynamo-motor concept of the *E* and *F* regions. The electrostatic field is taken to be of arbitrary horizontal scale, and numerical solutions are determined for the attenuation of the field with height. Fields with a horizontal scale as small as 3 or 4 km can extend from 130 to 400 km height with a reduction of only about 25 per cent, but the coupling efficiency is critically dependent on ionospheric conditions.

551.510.535 3394

Photoionization Heating in the F Region of the Atmosphere—D. C. Hunt and T. E. Van Zandt. (*J. Geophys. Res.*, vol. 66, pp. 1673–1682; June, 1961.) An estimate of the total *F* region heating due to photoionization is made, based on a comparison of theoretical and observed models of several atmospheric parameters. The heat flux due to photoionization is estimated to be approximately 1.0 erg/cm^2/sec which would be a major, if not predominant, source of heat in this region.

551.510.535 3395

Observations on the Ionospheric *F* layer at Night: Part 1—Height of Maximum Ionization, Critical Frequency and 'Semi-thickness' of F layer at Night—C.S.G.K. Setty. (*J. Inst. Telecommun. Engrs., India*, vol. 7, pp. 21–26; January 1961.) Measurements taken at Cambridge, England, agree with those for other stations. The scale height determined from the "semi-thickness" of the layer is too small when compared with rocket and satellite observations.

551.510.535 3396

Group and Phase Velocities of a Travelling Disturbance in the *F* Region of the Ionosphere—L. H. Heisler and J. D. Whitehead. (*Nature*, vol. 191, p. 157; July 8, 1961.) The disturbances cause gross distortions of ionogram records, and have a velocity of about 10 km/min. They are associated with sporadic-*E* patches having a velocity of about 5 km/min which is the phase velocity of the disturbances.

551.510.535 3397

On Vertical Drift Velocities of the F_2 Layer—H. Unz. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 237–242; July, 1961.) Vertical drift velocities in the F_2 layer are deduced by evaluating the equation of continuity of electron density, and compared with observed movements. Some correlation is found.

551.510.535:523.164 3398

A Statistical Study of Ionospheric Drifts Measured by the Radio Star Scintillation Technique—H. J. A. Chivers. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 221–224; July, 1961.) The method gives the E-W component of the drift velocity throughout the day. This component is commonly found to reverse suddenly near 2300 L.T. but the complementary reversal occurs at a less definite time during the following day.

551.510.535:551.507.362.1 3399

Rocket Measurements of *F*-Layer Electron Density and their Interpretation—S. A. Bowhill. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 272–283; July, 1961.) Theoretical considerations about the shape of the electron density profile near the F_2 peak are compared with data obtained from rockets [882 of April (Nisbet and Bowhill)]. The results are consistent with day and night temperatures of about 1500°K and 1200°K respectively. Numerical values of the loss coefficient and other parameters are given.

551.510.535:551.507.362.1 3400

An Ion-Trap Measurement of the Ion Concentration Profile above the F_2 Peak—W. B. Hanson and D. D. McKibbin. (*J. Geophys. Res.*, vol. 66, pp. 1667–1671; June, 1961.) The results of a winter evening rocket flight give the ion concentration from 240 to 750 km, and indicate a constant scale height (152 km) above 350 km.

551.510.535:551.507.362.2 3401

An Annual Variation of the Density of the Upper Atmosphere of the Earth—H. K. Paetzold. (*Z. Naturforsch.*, vol. 16a, pp. 50–56; January, 1961.) The various causes of the fluctuations of upper air densities (see *e.g.* 1839 of July) which result in observed changes of satellite orbits are discussed. The possible influence of interplanetary matter and of an interstellar wind is mentioned.

551.510.535:621.3.087.4 3402

Active High-Frequency Spectrometers for Ionospheric Sounding: Part 4—Numerical Recording of Delay Times—E. Harnischmacher and H. Porsche. (*Arch. elekt. Übertragung*, vol. 14, pp. 503–507; November, 1960.) Equipment for the automatic determination and printing of echo heights in numerical form is described. Part 3: 2973 of September (Paul).

551.510.535:621.3.087.4 3403

Active High-Frequency Spectrometers for Ionospheric Sounding: Part 5—Methods of Automatic Determination of True Height—A. K. Paul, H. Porsche, and K. Rawer. (*Arch. elekt. Übertragung*, vol. 14, pp. 561–569; December, 1960.) The direct evaluation of $N(h)$ profiles from the echo delays measured at the output of an ionosonde is proposed. Three digital and three analog methods are discussed and block diagrams given. Part 4: 3402 above.

551.510.536 3404

Density in a Planetary Exosphere—J. Herring and L. Kyle. (*J. Geophys. Res.*, vol. 66, pp. 1980–1982; June, 1961.)

551.510.536:621.396.96 3405

Evidence on the Laminar Nature of the Exosphere Obtained by means of Guided High-Frequency Wave Propagation—R. M. Gallet and W. F. Utlaut. (*Phys. Rev. Lett.*, vol. 6, pp. 591–594; June 1, 1961.) Radar pulses at 14 Mc were transmitted in the direction of the earth's magnetic field from Washington, D. C. Delayed echoes were found on many occasions from distances between 20,000 and 30,000 km. Each echo remained at a constant range. A possible explanation is given.

551.594.5 3406

Orientation of Polar Auroras—J. V. Denholm and F. R. Bond. (*Aust. J. Phys.*, vol. 14, pp. 193–195; March, 1961.) Observations of "homogeneous arc" auroras at three antarctic stations are presented and show a diurnal variation of orientation, thus supporting the observations of Weill (*C.R. Acad. Sci. (Paris)*, vol. 246, pp. 2925–2927; May 19, 1958.

551.594.5 3407

The East-West Drift of Auroral Forms determined from All-Sky Camera Films—W. Stoffregen. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 257–260; July, 1961.)

551.594.5 3408

Thickness of an Active Auroral Curtain—S. I. Akasofu. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 287–288; July, 1961.)

551.594.5:621.396.96 3409

Models of Auroral Ionization: Part 1—Auroral Ionization Models and their Radio-Reflection Characteristics—D. R. Moorcroft. (*Canad. J. Phys.*, vol. 39, pp. 677–694; May, 1961.) Several general models of auroral ionization are developed. By considering the ionization as an assembly of scattering centers, it is possible to include a unified treatment of weak scattering and critical reflection.

551.594.5:621.396.96 3410

Models of Auroral Ionization: Part 2—Applications to Radio Observations of Aurora—D. R. Moorcroft. (*Canad. J. Phys.*, vol. 39, pp. 695–715; May, 1961.) The radio reflection characteristics are examined in the light of the theory developed in 3409 above. Critical reflection at 30–50 Mc implies electron densities up to 3×10^{10} electrons/cm^3. The observations are consistent with the existence of clouds of electrons elongated in the ratio of 5 or 10:1 parallel to the field lines and a few meters in diameter perpendicular to the field.

551.594.6 3411

Atmospheric Noise Levels from 0.6 to 10 Kilocycles per Second—L. H. Ginsberg and D. J. Blattner. (*J. Geophys. Res.*, vol. 66, pp. 1745–1749; June, 1961.) A comprehensive series of observations on atmospheric noise in California and Florida for frequencies below 10 kc is described and analyzed. The diurnal variation for N-S loop orientation is a minimum in the interval 0400–1200 L.T. at both sites, and minimum noise levels are found to occur between 3 and 5 kc. The latter result is in agreement with the theory of Wait (2886 of 1957).

551.594.6 3412

A Study of Whistling Atmospherics: Part 1—Occurrence—J. Crouchley. (*Aust. J. Phys.*, vol. 14, pp. 22–39; March, 1961.) Results of I.G.Y. whistler observations at Brisbane, Adelaide, Hobart and Macquarie Island are presented, and the seasonal, diurnal and latitude variations of incidence of occurrence are discussed.

551.594.6 3413

A Study of Whistling Atmospherics: Part 2—Diffuseness—J. Crouchley and R. J. Finn. (*Aust. J. Phys.*, vol. 14, pp. 40–56; March, 1961.) Diffuseness, defined as the average time duration of whistler energy on a fixed frequency, is found to be twice as large for long as for short whistlers, to be independent of season and time of day, and to be linearly related to geomagnetic latitude and whistler dispersion. Part 1: 3412 above.

551.594.6:550.385.37 3414
Observations of Hydromagnetic Emissions—L. R. Tepley. (*J. Geophys. Res.*, vol. 66, pp. 1651–1658; June, 1961.) A frequency/time analysis of geomagnetic pulsations was made in the range 0.5–5 cps for the period November 18–21, 1960. The oscillations were observed simultaneously in California and Nevada and were probably influenced by solar flares which occurred before and during the dates mentioned.

551.594.6:621.391.812.63 3415
Two-Hop 18.6-kc/s Whistler-Mode Echoes Received at Seattle—Willard. (See 3528.)

LOCATION AND AIDS TO NAVIGATION

621.396.933 3416
Servo Filter and Gain Control Improve Automatic Direction Finder—P. V. Sparks. (*Electronics*, vol. 34, pp. 110–113; June 9, 1961.) The principles and circuit details of a light-weight low-power airborne DF system are given. The goniometer is driven by a servo system to keep it at the point of minimum gain. Ambiguity of the bearing is resolved by switching in a vertical sense antenna.

621.396.933:621.376.56 3417
Pulse-Duration Coding as a Means of Increasing the Number of Channels in the Australian 200-Mc/s D.M.E. System—B. R. Johnson. (*AWA Tech. Rev.*, vol. 11, pp. 129–142; December, 1960.) The number of channels is increased from 12 to 48 by the use of pulse-duration as well as the present pulse-separation coding. Interference from other beacons is reduced.

621.396.962.33:621.318.43 3418
Magnetics in Doppler Signal Data Extraction—Metz and Fay. (See 3265.)

621.396.969.18 3419
Principles of Three-Dimensional Radar Location (3-D Radar)—K. Röhrich. (*Nachrtech. Z.*, vol. 13, pp. 571–570; December, 1960.) Review of existing techniques. 32 references.

MATERIALS AND SUBSIDIARY TECHNIQUES

533.5:621.38 3420
The Interplay of Electronics and Vacuum Technology—J. M. Lafferty and T. A. Vanderslice. (Proc. IRE, vol. 49, pp. 1136–1154; July, 1961.) A review of modern ultra-high-vacuum systems and the electronic components used in them. 53 references.

535.215:539.23 3421
Light Interference and Internal Photoeffect in Thin Photoconductive Films—D. Kossel and W. Schmidt. (*Naturwiss.*, vol. 48, pp. 67–68; February, 1961.) Investigations were carried out on Sb_2S_3 films at $\lambda = 550$ mμ; absorption and photocurrent were measured as a function of film thickness to determine the effect of interference phenomena.

535.215:546.47'221 3422
Infrared Enhancement and Quenching of Photoconduction in Single Crystals of ZnS:Cu—F. G. Ullman and J. J. Dropkin. (*J. Electrochem. Soc.*, vol. 108, pp. 154–159; February, 1961.) Photoelectric currents produced by infrared radiation may either enhance or quench the currents resulting from ultraviolet irradiation of the crystals.

535.215:546.48'221 3423
Low-Field Breakdown, Non-ohmic Conductivity, and Photoconductivity of CdS at Low Temperatures—H. Shenker. (*J. Phys. Chem. Solids*, vol. 19, pp. 1–7; April, 1961.)

535.37:539.12.04 3424
Luminescence Damage of Inorganic Phosphors by Ions—R. Grasser and A. Scharmann. (*Z. Naturforsch.*, vol. 16a, pp. 10–12; January, 1961.) The effect on luminescence of ion bombardment is investigated as a function of ion mass and energy. See also 1440 of 1958 (Martin).

535.37:546.47'221:539.12.04 3425
Effects of α Radiation on Zinc Sulphide Phosphors—N. Riehl, R. Sizmann, and O. J. Stadler. (*Z. Naturforsch.*, vol. 16a, pp. 13–20; January, 1961.) Investigation of changes in glow curves and the luminescence spectrum of ZnS and ZnO phosphors following irradiation by α particles. No new glow curves were found.

537.226:539.23 3426
Anomalous Capacitance of Thin Dielectric Structures—C. A. Mead. (*Phys. Rev. Lett.*, vol. 6, pp. 545–546; May 15, 1961.) Measurements are made of the capacitance across thin Ta oxide films on Ta using Au or Bi upper electrodes. This shows that the inverse of the capacitance varies linearly with film thickness, extrapolating to give an apparently noninfinite capacitance at zero thickness. This anomaly is explained by a density-dependent penetration of the oxide into the metal of the electrodes.

537.227 3427
Ferroelectricity in $Bi_4Ti_3O_{12}$ and its Solid Solutions—E. C. Subbarao. (*Phys. Rev.*, vol. 122, pp. 804–807; May 1, 1961.)

537.227 3428
Effect of Two-Dimensional Mechanical Stress on the Dielectric Properties of Poled Ceramic Barium Titanate and Lead Zirconate Titanate—R. F. Brown. (*Canad. J. Phys.*, vol. 39, pp. 741–753; May, 1961.) The dielectric constant decreases and the dielectric loss increases with increasing stress; part of the change is irreversible and part reversible. The dielectric constant appears not to change instantaneously on application of stress but decreases linearly with the logarithm of time.

537.228.1:548.0].001.4(083.7) 3429
IRE Standards on Piezoelectric Crystals: Measurements of Piezoelectric Ceramics, 1961—(Proc. IRE, vol. 49, pp. 1161–1169; July, 1961.) Standard 61 IRE 14.S1.

537.228.4 3430
Microwave Modulation of the Electro-optic Effect in KH_2PO_4—I. P. Kaminow. (*Phys. Rev. Lett.*, vol. 6, pp. 528–530; May 15, 1961.) Light of wavelength about 8000 Å is modulated at 9.25 Gc by a cavity-resonance method using the linear electro-optic effect of KDP crystals. The presence of the modulation is confirmed by two methods. Future developments and applications are suggested.

537.311.33 3431
Scattering of Electrons by Phonons and Impurities in Semiconductors—H. Reiss and A. I. Anderman. (*Phys. Rev.*, vol. 122, pp. 1135–1140; May 15, 1961.) A formula is developed for the carrier mobility in the presence of both types of scattering in *n*-type semiconductors for small relaxation times.

537.311.33 3432
A Group of Ternary Semiconducting Compounds—L. S. Polatnik, Yu F. Komnik, V. M. Koshkin, and E. K. Belova. (*Dokl. Akad. Nauk SSSR*, vol. 137, pp. 68–71; March 1, 1961.) The lattice parameters of six ternary semiconductors such as Cu_2GeS_3, Cu_2SnS_3 and Cu_2GeTe_3 are given.

537.311.33:538.63 3433
Some Theoretical Considerations on the Longitudinal-Magnetic-Field-Induced Oscillations in Semiconductors (the Oscillistor) and a Tentative Explanation—A. C. Prior. (*Proc. Phys. Soc.*, vol. 77, pp. 1121–1124; June 1, 1961.) Conditions under which oscillations have been observed are such that a system of circulating currents could arise. These currents could tend to increase the carrier concentration at one surface and oscillations of a relaxation type could result.

537.311.33:538.63 3434
Esaki Tunnelling in the Presence of Magnetic Fields—R. R. Haering and E. N. Adams. (*J. Phys. Chem. Solids*, vol. 19, pp. 8–17; April, 1961.) The theory for Esaki tunnelling in the presence of a magnetic field is given for both transverse and longitudinal magnetic fields; it is shown that there are important qualitative differences between the two cases.

537.311.33:539.23 3435
Use of Monomolecular Layers in Evaporated-Film Tunnelling Devices J. L. Miles and H. O. McMahon. (*J. Appl. Phys.*, vol. 32, pp. 1176–1177; June, 1961.) Samples have been made to measure tunnelling currents between Sn-Pb and Sn-In evaporated-film pairs by using a monolayer of Ba stearate as a barrier.

537.311.33:546.23 3436
Space-Charge-Limited Current Flow and Deep Trapping in Selenium—H. P. D. Lanyon and W. E. Spear. (*Proc. Phys. Soc.* (*London*), vol. 77, pp. 1157–1165; June 1, 1961.) I/V characteristics show an ohmic part at low applied voltages and, with increasing hole injection, a V^2 region which precedes the trap-filled limit predicted by theory.

537.311.33:546.24:539.23 3437
Variation of Field-Effect Mobility and Hall-Effect Mobility with the Thickness of the Deposited Films of Tellurium—S. K. Ghosh. (*J. Phys. Chem. Solids*, vol. 19, pp. 61–65; April, 1961.) Experimental measurements of the mobilities and the conductivity of Te films are reported. A tentative explanation is given for the low values found for Hall mobility.

537.311.33:[546.28+546.289 3438
Field Emission from Silicon and Germanium; Field Desorption and Surface Migration—F. G. Allen. (*J. Phys. Chem. Solids*, vol. 19, pp. 87–99; April, 1961.) Desorption has been used to produce clean Ge patterns on a field-emission microscope.

537.311.33:[546.28+546.289 3439
Oxygen Adsorption on Silicon and Germanium—H. D. Hagstrum. (*J. Appl. Phys.*, vol. 32, pp. 1020–1022; June, 1961.)

537.311.33:[546.28+546.289]:538.569.4 3440
Cyclotron Resonance in Germanium and Silicon and the Effect of Negative Effective Masses—Yu. Kagan. (*Zh. Eksp. Teor Fiz.*, vol. 38, pp. 1854–1865; June, 1960.) The frequency (effective-mass) spectra of degenerate semiconductors are determined for the case of a magnetic field parallel to the [001] axis. The existence of negative-frequency branches is demonstrated and the problem of negative absorption is considered.

537.311.33:546.28 3441
Preparation of Uniform-Resistivity *n*-Type Silicon by Nuclear Transmutation—M. Tanenbaum and A. D. Mills. (*J. Electrochem. Soc.*, vol. 108, pp. 171–176; February, 1961.) The technique has been used to produce *n*-type Si with resistivity between 0.1 and 20 $\Omega \cdot$cm, uniform to within ± 5 per cent.

537.311.33:546.28 3442
The Manufacture of Silicon Single Crystals

by the Czochralski Method—G. Greger. (*Z. Angew. Phys.*, vol. 13, pp. 47–51; January, 1961.) Problems involved in obtaining crystals of highest purity and a homogeneous distribution of resistivity are discussed.

537.311.33:546.28 **3443**
Investigations on the Diffusion of Minority Carriers from a Point on Silicon—C. H. Champness. (*Canad. J. Phys.*, vol. 39, pp. 754–767; May, 1961.) The field-free diffusion of minority carriers injected at a point has been studied and the time from injection to the maximum of the collector signal due to the arriving carriers has been measured for various emitter-collector distances. For different samples, the time to maximum varied as the distance raised to powers 1.2 and 1.6. The decay times following the maximum decreased with distance. The results may be explained by assuming that the effective lifetime is dependent on the excess carrier density and decreases as the emitter point is approached.

537.311.33:546.28 **3444**
Theory of Microplasma Instability in Silicon—R. J. McIntyre. (*J. Appl. Phys.*, vol. 32, pp. 983–995; June, 1961.) A statistical theory is presented to explain microplasma instability at the onset of avalanche in reverse-biased Si. The agreement between theory and experiment for the turn-off proabaility is sufficiently good to suggest that the turn-off mechanism is the correct one. This implies that microplasmas turn off because the number of carrier pairs happens to fluctuate to zero.

537.311.33:546.28 **3445**
Study of Li-O Interaction in Si by Ion Drift—E. M. Pell. (*J. Appl. Phys.*, vol. 32, pp. 1048–1051; June, 1961.) Ion drift in a reverse-biased *p-n* junction has been used to measure the effective drift mobilities of Li^+ between 20° and 125°C in Si samples with oxygen concentration up to 1.3×10^{18} atoms/cm^3.

537.311.33:546.28 **3446**
Recombination Kinetics for Thermally Dissociated Li-B Ion Pairs in Si—E. M. Pell and F. S. Ham. (*J. Appl. Phys.*, vol. 32, pp. 1052–1063; June, 1961.)

537.311.33:546.28 **3447**
Surface Potential of Silicon—C. T. Raymo, C. W. Brands, and B. Schwartz. (*J. Appl. Phys.*, vol. 32, pp. 1165–1166; June, 1961.) A simple experimental method using the dc field effect is described.

537.311.33:546.28 **3448**
Valence Spin-Orbit Splitting and Conduction *g* Tensor in Si—L. Liu. (*Phys. Rev. Lett.*, vol. 6, pp. 683–685; June 15, 1961.) An orthogonalized-plane-wave method is used for calculating the *g* factor of electrons in Si. The two-band approximation used by Roth (4288 of 1960) is shown to be inadequate.

537.311.33:546.28:621.317.3 **3449**
Radio-Frequency Carrier and Capacitive Coupling Procedures for Resistivity and Lifetime Measurements on Silicon—I. R. Weingarten and M. Rothberg. (*J. Electrochem. Soc.*, vol. 108, pp. 167–171; February, 1961.) By using an RF bridge capacitive-coupling technique, ohmic contacts are avoided when measuring lifetime by photoconductivity decay.

537.311.33:546.281'26 **3450**
Measurement of Minority-Carrier Lifetime in SiC by a Novel Electroluminescent Method—G. G. Harman and R. L. Raybold. (*J. Appl. Phys.*, vol. 32, pp. 1168–1169; June, 1961.) The method is applicable to large-energy-gap semiconductors.

537.311.33:546.289 **3451**
Acoustic-Mode Scattering of Holes—M. Tiersten. (*IBM J. Res. Dev.*, vol. 5, pp. 122–131; April, 1961.) Matrix elements are calculated for acoustic-mode scattering of holes in the valence-band structure typified by Ge and a general expression for the electron-phonon interaction matrix element is obtained.

537.311.33:546.289 **3452**
Optical Constants of Germanium in the Region 0–27 eV—O. P. Rustgi, J. S. Nodvik, and G. L. Weissler. (*Phys. Rev.*, vol. 122, pp. 1131–1134; May 15, 1961.)

537.311.33:546.289 **3453**
Low-Temperature Thermal Resistance of *n*-Type Germanium—R. W. Keyes (*Phys. Rev.*, vol. 122, pp. 1171–1176; May 15, 1961.)

537.311.33:546.289 **3454**
Imaginary Part of X-Ray Scattering Factor for Germanium. Comparison of Theory and Experiment—B. W. Batterman. (*J. Appl. Phys.*, vol. 32, pp. 998–1001; June, 1961.)

537.311.33:546.289 **3455**
Kinetics of Donor Reactions in Oxygen-Doped Germanium—C. S. Fuller. (*J. Phys. Chem. Solids*, vol. 19, pp. 18–28; April, 1961.)

537.311.33:546.289:539.12.04 **3456**
Effect of Fission-Spectrum Neutrons on *n*-Type Germanium—D. Binder. (*Phys. Rev.*, vol. 122, pp. 1147–1148; May 15, 1961.) The electron removal rate per neutron is roughly constant.

537.311.33:546.289:539.12.04 **3457**
Effects of Monolayer Adsorption and Bombardment Damage on Auger Electron Ejection from Germanium—H. D. Hagstrum. (*J. Appl. Phys.*, vol. 32, pp. 1015–1019; June, 1961.) See also 233 of January.

537.311.33:546.289:539.23 **3458**
Hall Effect and Conductivity of Vapour-Deposited Germanium Films—F. Eckart and G. Jungk. (*Ann. Phys. (Lpz.)*, vol. 7, pp. 210–215; January 30, 1961.) The films investigated exhibited *p*-type conductivity irrespective of the type of material used. The Hall coefficient was found to increase with magnetic field strength.

537.311.33:546.289:539.23 **3459**
Germanium Films on Germanium Obtained by Thermal Evaporation in Vacuum—O. Weinreich, G. Dermit, and C. Tufts. (*J. Appl. Phys.*, vol. 32, pp. 1170–1171; June, 1961.) The method of preparation and results of measurements are described.

537.311.33:546.681'19 **3460**
Determination of the Effective Ionic Charge of Gallium Arsenide from Direct Measurements of the Dielectric Constant—K. G. Hambleton, G. Hilsum, and B. R. Holeman. (*Proc. Phys. Soc. (London)*, vol. 77, pp. 1147–1148; June 1, 1961.)

537.311.33:546.681'86 **3461**
Diffusion of Tin in Gallium Arsenide—B. Goldstein and H. Keller. (*J. Appl. Phys.*, vol. 32, pp. 1180–1181; June, 1961.)

537.311.33:546.682'19'241 **3462**
Electrical and Optical Properties of InAs-In_2Te_3 Alloys—J. C. Woolley, B. R. Pamplin, and J. A. Evans. (*J. Phys. Chem. Solids*, vol. 19, pp. 147–154; April, 1961.)

537.311.33:546.682'241 **3463**
Solid Solutions of In_2Te_3 in Sb_2Te_3 and Bi_2Te_3—A. J. Rosenberg and A. J. Strauss. (*J. Phys. Chem. Solids*, vol. 19, pp. 105–116; April, 1961.)

537.311.33:546.682'86 **3464**
Thermal Conductivity, Electrical Conductivity, Hall Effect and Thermo-E.M.F. of InSb—G. Busch and E. Steigmeier. (*Helv. Phys. Acta*, vol. 34, pp. 1–28; February 15, 1961. In German.) Measurements were made on single-crystal material in the temperature range 195°–715° K. 49 references.

537.311.33:546.682'86 **3465**
Antimony Edge Dislocations in InSb—H. C. Gatos, M. C. Finn and M. C. Lavine. (*J. Appl. Phys.*, vol. 32, pp. 1174–1175; June, 1961.)

537.311.33:546.817'241:538.63 **3466**
Observations of de Haas-van Alphen Oscillations in *p*-Type PbTe—P. J. Stiles, E. Burstein, and D. N. Langenberg. (*Phys. Rev. Lett.*, vol. 6, pp. 667–669; June 15, 1961.) Magnetic susceptibility oscillations, examined by pulsed-magnetic-field techniques, are reported.

537.311.33:546.824–31 **3467**
Electric Strength of Rutile Single Crystals—D. A. Powers and I. J. T. Johansen. (*J. Appl. Phys.*, vol. 32, pp. 1083–1085; June, 1961.)

537.311.33:546.863'873'241'231 **3468**
Relations between the Electronic Properties and the Chemical Bonding of $Sb_xBi_{2-x}Te_{3-y}Se_y$ System—I. Teramoto and S. Takayanagi. (*J. Phys. Chem. Solids*, vol. 19, pp. 124–129; April, 1961.)

537.311.33:546.873'241 **3469**
***n*- and *p*-Type Single-Crystal Bismuth Telluride**—A. C. Yang and F. D. Shepherd. (*J. Electrochem. Soc.*, vol. 108, pp. 197–198; February, 1961.) Both crystal types have been grown using the Czochralski method for pulling rates between 0.2 cm/h and 20 cm/h.

537.312.62 **3470**
Some New Superconducting Compounds—B. T. Matthias, V. B. Compton, and E. Corenzwit. (*J. Phys. Chem. Solids*, vol. 19, pp. 130–133; April, 1961.) Superconductivity and crystal structure data are tabulated. The new compounds: $ThRu_2$, $ThOs_3$ and $ThIr_3$ have transition temperatures of 3.56, 1.51 and 1.52°K respectively.

537.312.62 **3471**
Study of Superconductors by Electron Tunnelling—I. Giaever and K. Megerle. (*Phys. Rev.*, vol. 122, pp. 1101–1111; May 15, 1961.) The energy-gap width variation with temperature agrees with the Bardeen-Cooper-Schrieffer theory of superconductivity. The energy gap in thin films decreases with increasing applied magnetic field.

537.312.62 **3472**
Superconductivity at High Magnetic Fields and Current Densities in some Nb-Zr Alloys—T. G. Berlincourt, R. R. Hake, and D. H. Leslie. (*Phys. Rev. Lett.*, vol. 6, pp. 671–674; June 15, 1961.)

537.312.62 **3473**
Variation of the Elastic Moduli at the Superconducting Transition—G. A. Alers and D. L. Waldorf. (*Phys. Rev. Lett.*, vol. 6, pp. 677–679; June 15, 1961.)

537.312.62 **3474**
First- and Second-Order Stress Effects on Superconducting Transitions in Ta and Sn—D. P. Seraphim and P. M. Marcus. (*Phys. Rev. Lett.*, vol. 6, pp. 680–682; June 15, 1961.)

537.312.62 3475
Superconductivity in the Neighbourhood of Metallic Contacts—L. N. Cooper. (*Phys. Rev. Lett.*, vol. 6, pp. 689–690; June 15, 1961.) Theoretical discussion of the effect described by Smith *et al.* (3476 below).

537.312.62:539.23 3476
Superconducting Characteristics of Superimposed Metal Films—P. H. Smith, S. Shapiro, J. L. Miles and J. Nicol. (*Phys. Rev. Lett.*, vol. 6, pp. 686–688; June 15, 1961.) A report of experiments showing that a normal conductor film in contact with a superconducting film acts as a superconductor.

537.533 3477
Temperature Dependence of the Work Function of Metals (Mo, Ni)—G. Comşa, A. Gelberg, and B. Iosifescu. (*Phys. Rev.*, vol. 122, pp. 1092–1100; May 15, 1961.) Detailed report of measurements made using the electron-beam method.

537.583 3478
On the Thermionic Properties of ZrC, UC, and a ZrC.UC Mixture—W. E. Danforth and A. J. Williams, III. (*J. Appl. Phys.*, vol. 32, pp. 1181–1182; June, 1961.)

538.221 3479
Ferromagnetism in Dilute Solutions of Cobalt in Palladium—R. M. Bozorth, P. A. Wolff, D. D. Davies, V. B. Compton, and J. H. Wernick. (*Phys. Rev.*, vol. 122, pp. 1157–1160; May 15, 1961.)

538.221:534.283–8 3480
The Influence of Bloch-Wall Displacements on the Attenuation of Ultrasonic Waves in Ferromagnetic Metals—G. Simon. (*Ann. Phys. (Lpz.)*, vol. 7, pp. 140–148; January 30, 1961.) The investigation of the dynamic behavior of the Bloch walls is based on Kersten's model (1825 of 1957).

538.221:538.632 3481
Wall Effect and Resistance in the Iron-Cobalt Series—W. Jellinghaus and M. P. de Andrés. (*Ann. Phys. (Lpz.)*, vol. 7, pp. 149–158; January 30, 1961.) For results of measurements on Fe-Ni alloys see *ibid.*, vol. 5, pp. 187–199; January 15, 1960.

538.221:538.632 3482
Influence of Neighbour Elements of Iron on the Hall Effect of Mixed Crystals with High Iron Content—W. Jellinghaus and M. P. de Andrés. (*Ann. Phys. (Lpz.)*, vol. 7, pp. 189–200; January 30, 1961.)

538.221:539.23 3483
Polarity of the Domain Boundaries in Thin Ferromagnetic Films—L. V. Kirenskiĭ and V. A. Buravikhin. (*Dokl. Akad. Nauk SSSR*, vol. 136, pp. 575–576; January 21, 1961.) Results of experimental investigations show that in thin films Bloch walls are of alternating polarity and that the polarity in Néel boundaries is not sharply defined. With the application of a magnetic field perpendicular to the surface of the film this polarity becomes more distinct.

538.221:621.318.134 3484
A Neutron Diffraction Study of the Temperature Variation of the Spontaneous Sublattice Magnetization of Ferrites and the Néel Theory of Ferrimagnetism T. Riste and L. Tenzer. (*J. Phys. Chem. Solids*, vol. 19, pp. 117–123; April, 1961.)

538.221:621.318.134 3485
The Ideal Magnetization Curve of Ferrites with Differing Hysteresis Loops—M. Kornetzki and E. Röss. (*Z. angew. Phys.*, vol. 13, pp. 28–31; January, 1961.) The ideal magnetization curve is derived from Preisach diagrams obtained experimentally for various ferrites. A finite gradient at zero field strength, the ideal initial permeability, was found in all cases.

538.221:621.318.134 3486
Measurements of Long-Term Magnetic After-Effects of Remanence in Ferrites—F. Pliquett. (*Ann. Phys. (Lpz.)*, vol. 7, pp. 216–219; January 30, 1961.) Magnetometer equipment is described and test results obtained with Ni-Zn ferrites are given.

538.221:621.318.134 3487
Square-Loop Ferrites with Temperature-Independent Properties and Improved Disturb Ratio—R. S. Weisz. (*J. Appl. Phys.*, vol. 32, pp. 1152–1153; June, 1961.) Magnetic annealing of Mn-ferrous ferrites and Ni-ferrous ferrites has produced storage-type cores with improved properties. Preparation of the cores, their switching properties and an explanation of their behavior are given.

538.221:621.318.134 3488
Manganese-Zinc Ferrites with Different Types of Hysteresis Loop—M. Kornetzki, E. Moser, and E. Ross. (*Z. angew. Phys.*, vol. 13, pp. 31–36; January, 1961.) Normal, square, isoperm and perminvar types of hysteresis loop can be obtained by varying the Fe_2O_3 content of the ferrites investigated.

583.221:621.318.134 3489
Elastic Constants of Single-Crystal YIG—A. E. Clark and R. E. Strakna. (*J. Appl. Phys.*, vol. 32, pp. 1172–1173; June, 1961.)

538.221:621.318.134:534.13–8 3490
Extremely Low-Loss Acoustic Resonance in Single-Crystal Garnet Spheres—R. C. LeCraw, E. G. Spencer, and E. I. Gordon. (*Phys. Rev. Lett.*, vol. 6, pp. 620–622; June 1, 1961.) An acoustic resonance has been observed at 9.2 Mc in spheres of Y-Fe garnet at room temperature with losses an order of magnitude less than for other materials in similar conditions.

538.221:621.318.134:538.569.4 3491
Magnetic Resonance in Canted Ferrimagnets—P. A. Miles. (*Phys. Rev.*, vol. 122, pp. 1143–1146; May 15, 1961.) It should be possible to detect and analyze the structure of canted ferrimagnets as their magnetic resonance spectra differ characteristically from ferrimagnets with collinear sublattices.

538.221:621.318.134:548.5 3492
Growth Orientation in Ferrite Single Crystals—G. Elbinger and U. Rösler. (*Ann. Phys. (Lpz.)*, vol. 7 pp. 111–112; January 12, 1961.) Note on results obtained using a very low pulling speed. See also 2725 of September (Rösler and Elbinger).

538.221:621.395.625.3 3493
Magnetic Recording—L. G. Sebestyen and J. Takacs. (*Electronic Tech.*, vol. 38, pp. 274–278; August, 1961.) A new theory of the magnetization of tape and the role played by ac bias is described. The theory accounts for several previously unexplained phenomena.

538.222:534.283–8:621.375.9 3494
Amplification of 9.3-kMc/s Ultrasonic Pulses by Maser Action in Ruby—E. B. Tucker. (*Phys. Rev. Lett.*, vol. 6, pp. 547–548; May 15, 1961.) Experimental evidence is produced for amplification of 9.3-Gc ultrasonic pulse by spin-phonon interaction in a pumped Linde pink crystal. The system was similar to that used previously to observe attenuation of these pulses (1952 of July) but with the spin population inverted. Experimental details are given and the conditions for realizing a phonon maser are briefly considered.

538.222:537.228.5 3495
Splitting of the Emission Lines of Ruby by an External Electric Field—W. Kaiser, S. Sugano, and D. L. Wood. (*Phys. Rev. Lett.*, vol. 6, pp. 605–607; June 1, 1961.) An additional splitting of the doublet comprising each emission line is shown to take place in an external electric field. This effect should allow frequency modulation of the output of a ruby optical maser.

538.222:538.569.4 3496
Paramagnetic Resonance of Gd^{3+} in Al_2O_3—S. Geschwind and J. P. Remeika. (*Phys. Rev.*, vol. 122, pp. 757–761; May 1, 1961.) The substitution of Gd^{3+} impurities for Al^{3+} has been examined using the paramagnetic resonance spectrum at 24 Gc.

538.222:538.569.4 3497
Paramagnetic Resonance of Cr^{3+} in Yttrium Oxide—J. W. Carson, D. P. Devor, and R. H. Hoskins. (*Phys. Rev.*, vol. 122, pp. 1141–1143; May 15, 1961.)

538.652 3498
Investigations on Magnetostrictive Circular Rings and Rods for the Determination of the Dynamic Magnetostrictive Coefficient as a Function of External Field Strength—J. Narrog. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 225–229; December, 1960.)

MATHEMATICS

517.918 3499
Concerning the Partition Theory and Associated Transform Methods—E. V. Bohn. (Proc. IRE, vol. 49, pp. 1215–1216; July, 1961.) Critical comment on earlier papers [*e.g.* 2854 of 1960 (Ku and Wolf)].

517.94:621.372.5 3500
A Review of Methods of Linear Network Analysis in the Steady State: Parts 1 and 2—Seymour. (See 3271.)

MEASUREMENTS AND TEST GEAR

621.317.3:621.391.822 3501
A Voltage Comparator for Low-Frequency Noise Measurements—F. A. Spelman. (*Elect. Engrg.*, vol. 80, pp. 200–201; March, 1961.) A circuit is given which was designed to measure low-frequency noise in transistors but is suitable for the study of any noise in the range of 50–5000 cps.

621.317.3.029.6:621.391.822 3502
Techniques of Microwave Noise Measurement—B. G. Bosch and W. A. Gambling. (*J. Brit. IRE*, vol. 21, pp. 503–515; June, 1961.) Some aspects of microwave oscillator noise are discussed and measurement techniques applicable to oscillators and to modulation noise in amplifiers are described. These techniques include AM and FM direct-detection methods, the superheterodyne method, and systems for the measurement of correlation.

621.317.3.029.63:621.391.822 3503
New Microwave Noise Generator for the 200-Mc/s Band—G. Almássy and I. Frigyes. (*Period. Polyt., Bp., Elect. Engrg.*, vol. 4, no. 4, pp. 293–303; 1960.) Description of a small and easily operated microwave noise generator comprising a gas-discharge tube built into the inner conductor of a coaxial line. The output power depends exclusively on the noise temperature of the plasma.

621.317.337.029.6 3504
Measurement of Resonance Coefficients of the Order of a Million in the Microwave Field

—F. Parisi. (*Alta Frequenza*, vol. 30, pp. 14–20; January, 1961.) Equipment is described which is designed for Q-factor measurement in mm-λ H_{01}-mode circular waveguide systems; experimental results are given as examples.

621.317.35 3505

A Direct Digital Method of Power Spectrum Estimation—P. D. Welch. (*IBM J. Res. Dev.*, vol. 5, pp. 141–156; April, 1961.) A method is discussed for the estimation of a digital power spectrum which involves the direct combination of the sample time function with sines and cosines; practical design details are given.

621.317.36:621.376.3 3506

Measurement of Frequency Deviation in F.M.—J. Marique. (*Rev. HF, Brussels*, vol. 5, no. 1, pp. 1–12; 1961.) Two methods are described: one suitable only for symmetrically modulated waves, using a spectrum analyzer, the other based on reconstructing the modulator signal and measuring its peak-to-peak value.

621.317.44 3507

Field Measurements by the Method of Harmonics: Angle Probes—J. Greiner. (*Nachrtech.*, vol. 10, pp. 495–498; November, 1960.) Description of various types of probe for magnetometer measurements using the method of perpendicularly superposed magnetic fields. See also 1608 of June and back references.

621.317.44 3508

Induction Probe with Microscope for the Measurement of Field-Strength Distribution in Magnetic Fields—F. Graul. (*Nachrtech.*, vol. 10, pp. 499–501; November, 1960.) The principle of operation is electrodynamic, indication being provided by the deflection of a current-carrying wire in the unknown magnetic field.

621.317.7:621.382.3.001.4 3509

Pulse-Sampling Voltmeter and its Application to Transitor Testing—L. J. Herbst and J. R. W. Smith. (*J. Sci. Instr.*, vol. 38, pp. 242–245; June, 1961.) A 100-cps signal is applied to the transistor under test and also to the voltmeter which generates a 20-μsec sampling pulse at the same frequency. The transistor output waveform can be examined at any phase in the cycle for voltages between 100 mv and 75 v. The sampled voltage is rectified and measured to an accuracy within 1 per cent.

621.317.72:621.319.4 3510

The Vibrating Capacitor, Theory and Application—H. Riegler. (*Nachrtech.*, vol. 10, pp. 501–505; November, 1960.) The design of vibrating capacitors for use in electrometer amplifiers is discussed.

621.317.755:621.3.012.11 3511

A Circle-Diagram Recorder for Frequencies between 10 kc/s and 200 Mc/s—P. Thilo. (*Frequenz*, vol. 14, pp. 403–412; December, 1960.) Description of equipment for the display of locus curves and diagrams of the Smith-chart type on a CR tube screen.

621.317.755:621.372.2.001.4 3512

Testing Microwave Transmission Lines using the Sampling Oscilloscope—H. Halverson. (*Electronics*, vol. 34, pp. 86–88; June 30, 1961.) By using pulse reflection techniques and a CRO with a fast rise time direct readings of characteristic impedance can be made. Discontinuities along the line can also be identified.

621.317.789.029.65 3513

100–200-kMc/s Water Calorimeter—J. B. Thaxter and J. McGowan, III. (*Rev. Sci. Instr.*, vol. 32, pp. 605–606; May, 1961.) The minimum detectable signal is 5×10^{-5} w with response time of 20 sec, and sensitivity about 10 μv/mw. An important feature of the calorimeter is that heat losses from the water are nearly the same for the microwave and dc calibrating power sources.

621.317.79:538.569.4:535.33 3514

Sensitive Triple Modulation Method for Measuring Widths of Microwave Spectral Lines—E. A. Rinehart and C. C. Lin. (*Rev. Sci. Instr.*, vol. 32, pp. 563–563; May, 1961.) The method eliminates from the CRO display the power fluctuations due to the klystron. The technique may be useful for resolving closely spaced lines.

621.317.79.029.64:551.510.62 3515

The Construction and Performance of an Airborne Microwave Refractometer—J. A. Lane, D. S. Froome and G. J. McConnell. (*Proc. IEE*, pt. B, vol. 108, pp. 398–402; July, 1961.) "The paper describes the construction of a Birnbaum-type microwave refractometer and its application in studies of refractive-index variations at heights up to 20,000 ft. Practical problems encountered in airborne measurements are discussed in detail. Some typical results are given which illustrate the performance obtained in measurements of refractive-index profiles and discontinuities."

OTHER APPLICATIONS OF RADIO AND ELECTRONICS

621.362+621.56 3516

New Concepts in Thermoelectric Device Design—W. H. Clingman. (Proc. IRE, vol. 49, pp. 1155–1160; July, 1961.) Examples are given in which an analysis based on irreversible thermodynamics can be useful.

621.384.611.2 3517

The CERN 600-MeV Synchrocyclotron at Geneva—(*Philips Tech. Rev.*, vol. 22, pp. 141–180; March 6, 1961.)

Part 1—Object and Design. W. Gentner (pp. 142–149).
Part 2—The Radio-Frequency System. K. H. Schmitter and S. Kortleven (pp. 149–161).
Part 3—The Tuning-Fork Modulator. B. Bollée and F. Krienen (pp. 162–180).

621.56:537.322.1 3518

Peltier-Effect Cooling Blocks—M. Fournet. (*Onde élect.*, vol. 41, pp. 140–141; February, 1961.) A note on the construction and characteristics of semiconductor thermoelements.

681.61 3519

Neon Diode/Resistor Matrix controls Electronic Typewriter—M. Ruderfer. (*Electronics*, vol. 34, pp. 108–109; June 9, 1961.) An improved printing mechanism is described using a printing type which is controlled by the matrix. This system allows faster operation, easy change of printing wheels and type faces and is of small and light construction.

PROPAGATION OF WAVES

621.371 3520

An Iteration-Variation Method for Wave Propagation Problems—W. J. Byatt and G. P. DeVault. (*J. Geophys. Res.*, vol. 66, pp. 1793–1797; June, 1961.) An inhomogeneous wave equation in which refractive index is a function of one space coordinate and time is reduced to an ordinary differential equation by transform methods. An equivalent integral equation is formed with a symmetric kernel so that an iterative expansion has radius of convergence given by the numerical value of the smallest eigenvalue. A variational solution similar to the Rayleigh-Ritz method is given.

621.391.812.6.029.64/.65 3521

Microwave Absorption in the Earth's Atmosphere—S. N. Ghosh and V. Malaviya. (*J. Atmos. Terr. Phys.*, vol. 21, pp. 243–256; July, 1961.) The absorption for different atmospheric layers, and for the whole atmosphere, is calculated for frequencies between 10 and 100 Gc. The profiles and half-widths for principal absorption lines are given.

621.391.812.62 3522

Results and Evaluation of Measurements of Tropospheric Transhorizon Propagation over several Paths of Different Type in Central and South-East Europe—H. Carl. (*Nachrtech. Z.*, vol. 13, pp. 566–570; December, 1960.) Results are given of measurements of transhorizon loss made on radio links of length 230–400 km, some purely over land and others over sea, during periods of 4–6 weeks between February and May. The dependence of loss on elevation angle and dew point was in accordance with theory and some correlation with other meteorological conditions was found.

621.391.812.62.029.63 3523

Space-Diversity Measurements on a Radio-Link Path within Optical Range—U. Kühn. (*Nachrtech.*, vol. 10, pp. 430–435; October, 1960.) Measurements were made over a period of 21 months for transmissions at 1.3 Gc over an 82-km path with antennas vertically spaced by 250 λ. Long-term as well as short-term fluctuations are frequently reduced by the system. See also 1753 of 1960.

621.391.812.624:621.396.677 3524

Tropospheric Scatter Observations at 3480 Mc/s with Aerials of Variable Spacing—R. W. Meadows. (*Proc. IEE*, pt. B, vol. 108, pp. 349–360; July, 1961.) Measurements are described of signal amplitude, fading characteristics, correlation distances, and height gain at ranges of 130, 258 and 398 km in southern England, the 130-km path being largely over sea. Cross-correlation measurements showed definite evidence of the steady drifting of scattering centers.

621.391.812.63 3525

Scattering of Radio Waves by an Ionized Gas in Thermal Equilibrium in the Presence of a Uniform Magnetic Field—J. A. Fejer. (*Canad. J. Phys.*, vol. 39, pp. 716–740; May, 1961.) The earlier theory (1290 of May) was restricted to cases where the "characteristic scale" was much greater or less than the Debye length, and where only one type of singly charged ion was present. Ion and electron temperatures were assumed equal and the external magnetic field was ignored. These restrictions have now been removed. The total power is independent of the magnetic field and an expression for the frequency spectrum of the power in the presence of the field is given. The field may be ignored in interpreting the results of Bowles (*Phys. Rev. Lett.*, vol. 1, pp. 454–455, December 15, 1958) and Pineo *et al.* (188 of January) but it could be important at great heights.

621.391.812.63 3526

Long-Distance One-Hop F_1 Propagation through the Auroral Zone—L. H. Tveten. (*J. Geophys. Res.*, vol. 66, pp. 1683–1684; June, 1961.) "The existence of one-hop F_1 propagation through the auroral zone over a 4495-km path is described, and an example of a sweep-frequency record illustrating this F_1 mode is shown."

621.391.812.63:551.507.362.2:621.396.43 3527

The Propagation of Wide-Band Signals through the Ionosphere—Staras. (See 3537).

621.391.812.63:551.594.6 3528
Two-Hop 18.6-kc/s Whistler-Mode Echoes Received at Seattle—H. R. Willard. (*J. Geophys. Res.*, vol. 66, pp. 1976–1977; June, 1961.) The observation of delay times ranging from 0.7 to 1.7 sec suggests the existence of whistler propagation paths at quite different latitudes.

621.391.812.63.029.51 3529
A Diffraction Theory for L.F. Sky-Wave Propagation—J. R. Wait. (*J. Geophys. Res.*, vol. 66, pp. 1713–1724; June, 1961.) The propagation of radio waves via discrete ionospheric reflections is treated theoretically with the earth and the ionosphere represented by two concentric spherical surfaces of known reflection characteristics. The *m*th-hop sky wave may generally be represented by a complex integral, and geometrical-optics formulas are developed for special cases and their limitations discussed. Techniques for evaluating the complex integral for sky waves near and beyond the caustics are discussed. For an additional note reporting some numerical results see *ibid.*, pp. 1725–1729 (Wait and Conda).

RECEPTION

621.391.814.2.029.53 3530
Temporal Variation of Medium-Frequency Ground-Wave Field Strength—J. M. Dixon. (*Proc. IRE, Aust.*, vol. 22, pp. 250–252; April, 1961.) The results of field-strength measurements are analyzed to show the variation to be expected under Australian conditions, with particular reference to path conductivity.

621.396.669:621.396.67 3531
The Suppression of Corona- and Precipitation-Interference in V.H.F. Reception—H. Page. (*Proc. IEE*, pt. B, vol. 108, pp. 469–470; July, 1961.) A note describing the results of preliminary tests on systems designed to screen television receiving antennas from such effects.

STATIONS AND COMMUNICATION SYSTEMS

621.376.5 3532
The Elimination of Intersymbol Interference by Input Signal Shaping—I. Gerst and J. Diamond. (Proc. IRE, vol. 49, pp. 1195–1203; July, 1961.) The problem is treated mathematically by considering the effect of the input wave shape on the output tail.

621.391 3533
Signal Detection and Establishment of the Mean Value in Periodic Signal Sequences with Superimposed Fluctuations—C. Moeller. (*Hochfrequenz. und Elektroak.*, vol. 69, pp. 189–192; October, 1960.)

621.391:534.78 3534
Bandwidth Compression of Speech—M. Das. (See 3225.)

621.396:[523+55 3535
Radio Techniques and Space Research—(See 3355.)

621.396.43:551.507.362.2 3536
Economic Potential of Communication Satellites—W. Meckling. (*Science*, vol. 133, pp. 1885–1892; June 16, 1961.) Communication satellites may reduce costs if high rates of utilization can be achieved.

621.396.43:551.507.362.2:621.391.812.63 3537
The Propagation of Wide-Band Signals through the Ionosphere—H. Staras. (Proc. IRE, vol. 49, p. 1211; July, 1961.) Differential group delay across the frequency band can cause distortion of television signals relayed by satellites. This distortion is strongly dependent on frequency and it may be necessary to use carriers in excess of 1 Gc.

621.396.65:621.396.43 3538
Results and Experience Gained from a Transhorizon Link in the Long-Distance Communications Network of the German Federal Post Office—E. Dietrich. (*Nachtech. Z.*, vol. 13, pp. 563–565; December, 1960.) Report dealing with the Berlin-West Germany radio link operating at 2 Gc. See also 1635 of June (Hoffmann).

621.396.933 3539
Automatic Techniques in Civil Air Line Communication Systems—W. E. Brunt. (*J. Brit. IRE*, vol. 21, pp. 549–553; June, 1961. Discussion, pp. 554–555.) Methods of modulation and coding are considered.

621.396.97:534.76 3540
The H.M.D. System—a Method for the Transmission of Stereophonic Broadcasts—E. Frank and J. Ratsch. (*Elektron. Rundschau*, vol. 14, pp. 463–466; November, 1960.) Description of a single-carrier time-multiplex system using half-wave modulation with signal-difference control.

621.396.97:621.391.812.63 3541
An Investigation of the Usefulness of Back-Scatter Sounding in the Operation of H.F. Broadcast Services—E. D. R. Shearman. (*Proc. IRE*, pt. B, vol. 108, pp. 361–372; July, 1961. Discussion, pp. 372–374.) Echo patterns measured at 15 and 21 Mc agreed well with those calculated from parabolic ionospheric-layer theory. Further tests, including listeners' reports, at night showed that propagation modes to 5000 km were correctly evaluated when predict ons, corrected by local vertical-incidence soundings, gave erroneous results.

SUBSIDIARY APPARATUS

621–52 3542
Complex-Plane Charts for Obtaining Closed-Loop Frequency Responses in Linear Control Systems—F. Csáki. (*Period. Polyt., Bp., Elec. Engrg.*, vol. 4, no. 4, pp. 361–378; 1960.) Summary of graphical methods for plotting complex-plane charts.

621.3.087.4:621.395.625.3 3543
Outside-Coil Magnetic Head Improves High-Frequency Recording—N. Camras and R. Sears. (*Electronics*, vol. 34, pp. 89–91; June 30, 1961.) High resolution is obtained as a result of smaller air gaps and on improved field configuration.

621.314.58 3544
Replacing Sine-Wave Sources with Solid-State Inverters—D. Levy. (*Electronics*, vol. 34, pp. 80–83; June 30, 1961.) A series magnetic amplifier or a saturable reactor is used following a solid state inverter to give a modified square-wave output such that the heater and direct voltages available are the same as would be obtained from a sinusoidal ac supply.

621.314.58:621.382.23 3545
Converter Efficiency and Power Output of a Tunnel-Diode Relaxation Oscillator—S. Wang. (Proc. IRE, vol. 49, pp. 1219–1220; July, 1961.) A simple dc/ac converter is discussed.

621.314.58:621.382.3 3546
Control of Frequency and Phase Displacement in Transistor Converter Circuits by means of RC Networks—F. V. Kadri. (*Commun. and Electronics*, no. 53, pp. 43–48; March, 1961.) A new type of adjustable-frequency transistor converter is described in which the operating frequency is controlled by an RC network and is independent of the direct voltages. Power regulation by means of RC phase control of a pair of transistor converters is discussed.

621.314.63:621.374 3547
Controlled Rectifier Produces Quarter-Megawatt Pulse Power—H. G. Heard. (*Electronics*, pp. 54–55; June 23, 1961.) Circuit details are given of pulse generator equipment using solid-state devices as active elements. A *p-n-p-n* Si controlled rectifier acts as the switch, and two-layer and four-layer diodes are used in the trigger generator.

621.314.634 3548
Recent Developments in Selenium Rectifiers—C. Loeffler. (*Onde élect.*, vol. 41, pp. 123–131; February, 1961.) An account of phenomena occurring during the construction and operation of different types of Se rectifier.

621.316.72:621.382.3 3549
A Note on Transistorized Ripple Filters—B. W. Moore and J. P. O'Neil. (*AWA Tech. Rev.*, vol. 11, pp. 169–177; December, 1960.) A smoothing circuit providing optimum efficiency over a wide range of load currents is described.

TELEVISION AND PHOTOTELEGRAPHY

621.397.12:621.396.4:523.5 3550
Transmitting Facsimile Messages over Meteor-Burst Paths—B. F. Gedaminski and W. F. Griffin, Jr. (*Electronics*, vol. 34, pp. 85–89; May 19, 1961.) Average information rate for ½-hr periods was 2 300 bits/sec, in a 220 kc bandwidth.

621.397.13 3551
B.B.C. Television 1939–60—E. L. E. Pawley (*Proc. IEE*, pt. B, vol. 108, pp. 375–397; July, 1961.) A comprehensive technical review of progress in planning and equipment.

621.397.13(083.7) 3552
IRE Standards on Video Techniques: Definition of Terms relating to Television, 1961—(Proc. IRE, vol. 49, pp. 1193–1195; July, 1961). Standard 61 IRE 23. S1.

621.397.132 3553
Land's System of Two-Colour Projection—M. H. Wilson and R. W. Brocklebank. (*J. Brit. IRE*, vol. 21, pp. 535–536; June, 1961. Discussion, pp. 546–548.) A brief discussion of the physical principles involved.

621.397.132 3554
The Range of Colours Excited by a Two-Colour Reproduction System—W. N. Sproson. (*J. Brit. IRE*, vol. 21, pp. 537–544, June, 1961. Discussion, pp. 546–548.) An assessment of the accuracy with which colors can be reproduced relative to those of a three-color system. The two-color process is considered to be insufficient for a good approximation to true color.

621.397.331.222 3555
Modifying Vidicon Camera Chain for Slow-Scan Television Systems—F. F. Martin and C. T. Shelton. (*Electronics*, vol. 34, pp. 101–103; June 9, 1961.) In order to reduce bandwidth and transmitter power the use of low scan rates is discussed; further advantages are increased resolution, and more time available to interpret the scene. Disadvantages are microphonic signals due to vibration and critical beam setting.

621.397.6.001.4 3556
A Television Imagery Simulator—J. P. Smith and J. F. Baumunk. (*J. Soc. Mot. Pic. Telev. Engrs.*, vol. 70, pp. 27–32; January, 1961.) A high-quality television chain suitable for testing television systems and providing means for comparing them.

621.397.61/.62].029.63 3557
U.H.F. Television Techniques—C. Reuber. (*Elektrotech. Z., Edn B*, vol. 13, pp. 135–141; March 20, 1961.) Review of problems concerning transmitter-network planning, transmitter design, receiving antennas and antenna cables, and the design of UHF tuners.

621.397.621 3558
Reflected Images on Curved and Plane Television-Tube Front Plates—R. Suhrmann. (*Elektron. Rundschau*, vol. 14, pp. 467–468; November, 1960.) The use of a flat, instead of a curved, safety-glass plate in front of television tubes minimizes interference by reflections particularly if the plate is inclined slightly downwards.

621.397.621 3559
Electronic Brightness Contouring—R. L. Hallows. (*J. Soc. Mot. Pic. Telev. Engrs.*, vol. 70, pp. 23–27; January, 1961.) A circuit technique is described for producing an "equal-brightness contour" which may be superimposed on a television picture and set to any level of brightness.

TUBES AND ELECTRONICS

621.382.004.6 3560
Life Characteristics of some Typical Semiconductor Devices—R. Brewer and D. J. E. Richards. (*J. Brit. IRE*, vol. 21, pp. 485–489; June, 1961.) Changes in characteristics after many thousands of hours in service, and the incidence of inoperative failures are discussed. Results from field reports and laboratory measurements are compared.

621.382.22 3561
Influence of Surface Currents on the Characteristics of Formed Point-Contact Rectifiers—R. Ebhardt, E. Hofmeister, and E. Groschwitz. (*Z. angew. Phys.*, vol. 13, pp. 16–28; January, 1961.) Results of measurements on point-contact semiconductor diodes are given and analyzed with reference to previous theoretical work [3180 of October (Groschwitz *et al.*) and back references].

621.382.22:621.372.44 3562
High-Frequency Silicon Varactor Diodes—C. A. Burrus. (*J. Appl. Phys.*, vol. 32, pp. 1166–1167; June, 1961.) By adopting point-contact diode geometry, Si varactor diodes with zero-bias junction capacitances at least an order of magnitude below the minimum value associated with the Si mesa diode have been made.

621.382.22:621.372.622 3563
Excess Noise in Microwave Mixer Crystals—B. G. Bosch, W. A. Gambling, and T. H. Wilmshurst. (Proc. IRE, vol. 49, pp. 1226–1227; July, 1961.) Noise-temperature measurements have been made over a frequency range 25 cps–80 Mc.

621.382.23 3564
Tunnel-Effect Diodes—R. Deschamps. (*Onde élect.*, vol. 41, pp. 132–139; February, 1961.) A description of the mechanism and characteristics of the tunnel diode. Optimum operating conditions are considered and possible applications are noted.

621.382.23 3565
The Technology of Tunnel Diodes—J. Hartmann and M. Michelitsch. (*Elektrotech. Z., Edn A*, vol. 82, pp. 114–116; February 13, 1961.) Types of construction and manufacturing techniques are discussed.

621.382.23 3566
Stability Criteria for Tunnel Diodes—L. I. Smilen and D. C. Youla. (Proc. IRE, vol. 49, pp. 1206–1207; July, 1961.) Various conditions for stability are stated and discussed.

621.382.23 3567
Electrical Characteristics of Diffused InAs *p-n* Junctions—G. Lucovsky. (*Brit. J. Appl. Phys.*, vol. 12, pp. 311–312; June, 1961.) Rectification properties are examined at 300°K, 196°K and 77°K. At 196°K, the I/V characteristic was in good agreement with conventional diode theory [*e.g.* 2906 of 1958 (Moll)]. Deviations noted at the other temperatures are accounted for.

621.382.23 3568
Gallium Arsenide Esaki Diodes for High-Frequency Applications—A. C. Burrus. (*J. Appl. Phys.*, vol. 32, pp. 1031–1036; June, 1961.) "Esaki diodes which show promise of usefulness into the millimeter-wave region have been made from both *p*- and *n*-type GaAs. Both diodes were alloyed junctions having point-contract geometry and dimensions. The fabrication of these diodes is briefly described, and their initial performance as oscillators in mechanically simple circuits is discussed. Fundamental oscillations to 103 kMc have been obtained." See also 3184 of October.

621.382.23:621.372.44 3569
Circuit Control of Tunnel-Diode Negative-Resistance Characteristics—W. N. Carr and A. G. Milnes. (*Proc. IRE*, vol. 49, pp. 1204–1205; July, 1961.) Typical control circuits and characteristics are given.

621.382.23:621.374 3570
Application of Tunnel Diodes in Pulse Techniques—U. L. Rohde and H. J. Thaler. (*Elektronik*, vol. 10, pp. 33–37; February, 1961.) Design procedures for multivibrator circuits are described.

621.382.23:621.375.9:621.372.44 3571
Reactance Diodes and their Application in Wide-Band Waveguide Amplifiers—P. Bobisch and C. Sondhauss. (*Telefunken-Röhre*, no. 38, pp. 115–124; December, 1960.) Semiconductor reactance diodes with disc electrodes housed in a cartridge of greatly reduced size are used in the construction of a two-stage traveling-wave parametric amplifier for the frequency range 2.7–2.9 Gc. The construction and performance of a frequency multiplier for use up to 6 Gc are also described.

621.382.233 3572
The *p-n-p-n* Diode—M. Chappey. (*Onde élect.*, vol. 41, pp. 99–113; February, 1961.) The characteristics of the diode applicable to heavy-current uses, calculating machines or switching circuitry are discussed. An elementary theory of its operation and details of its production by double diffusion, simple diffusion, or alloying are given.

621.382.233:621.373.44 3573
Silicon Four-Layer Devices as High-Power Pulse Generators—R. P. F. Lauder. (*Electronic Engrg.*, vol. 33, pp. 426–431; July, 1961.) "Several circuits are presented showing that *p-n-p-n* devices in the two- or three-terminal configuration may be used as pulse generators delivering accurately rectanglular power pulses for a variety of purposes including transmitters in the 20-kw peak input power region."

621.382.3 3574
Thermal Problems in Transistors—H. J. Thuy. (*Elektron. Rundschau*, vol. 15, pp. 15–18 and 61–65; January and February, 1961.) The problems reviewed include the dependence of transistor life on junction temperature, the calculation and measurement of internal thermal resistances, the measurement of heat interchange of cooling surfaces and the runaway effect and related stability criteria. 38 references.

621.382.3.001.4:621.317.7 3575
Pulse-Sampling Voltmeter and its Application to Transistor Testing—Herbst and Smith. (See 3509.)

621.382.333.33 3576
The Calculation of Cut-Off Frequencies of Minority-Carrier Transport Factors in Drift Transistors when the Mobilities are not Constant—T. Sugano and F. Koshiga. (Proc. IRE, vol. 49, p. 1218; July, 1961.

621.382.333.4 3577
The Field-Effect Tetrode—H. A. Stone, Jr., and R. M. Warner, Jr. (Proc. IRE, vol. 49, pp. 1170–1183; July, 1961.) The field-effect tetrode is described and its applications are discussed. The equations for its behavior as a gyrator, an isolator, a negative resistance and an electronically variable resistor are developed.

621.382.333.4 3578
Examination of a New Tetrode Field-Effect Device: the Alcatron—J. Grosvalet. (*Onde élect.*, vol. 41, pp. 114–122; February, 1961.) A transistor field-effect device of annular construction is described. It contains a small control grid and a second larger grid which removes the dissipation power and modifies the equivalent circuit at high frequencies. It gives values beyond the limits suggested by Dacey and Ross (1240 of 1956). See also 1670 of June (Martin).

621.383.032.217.2 3579
Bismuth-Silver-Oxygen-Cesium Photocathode—A. H. Sommer and W. E. Spicer. (*J. Appl. Phys.*, vol. 32, pp. 1036–1042; June, 1961.) Chemical and physical studies on the Bi-Ag-O-Cs photocathode to gain an understanding of the chemical nature and the energy band model of the material are reported.

621.383.032.217.2 3580
Measurement of the Partial Pressure of Cesium over Cesium Antimonides—K. Miyake. (*J. Appl. Phys.*, vol. 32, pp. 1132–1136; June, 1961.)

621.385.032.269.1 3581
Electron Gun for the Generation of a Hollow Beam—R. Johne and W. Henne. (*Telefunken-Röhre*, no. 38, pp. 99–114; December, 1960.) Design calculations for the electrodes of the gun are based on the assumption that the hollow beam can be regarded as a strip-beam system. Results obtained with an experimental gun confirm the validity of the assumption when the ratio of beam thickness to beam diameter is small.

621.385.3/.4].029.63 3582
New Ceramic Power Triodes and Tetrodes Operating at Very High Frequencies—P. Gerlach. (*Onde élect.*, vol. 41, pp. 167–171; February, 1961.) Negative-grid valves are described which, when giving 10 kw CW power at 1 Gc, have an envelope temperature of several hundred °C.

621.385.4:621.397.61 3583
Electron-Transit-Time Effects in Transmitter Tetrodes for Television Bands IV/V—W. Seiffarth. (*Arch. elekt. Übertragung*, vol. 14, pp. 491–498; November, 1960.) The method used by Hülster (3449 of 1955) for triodes is applied to high-power transmitter tetrodes for operation at 800 Mc. Problems of valve design are considered with reference to these calculations.

621.385.6 3584
An Approximation Method for the Determination of the Quadripole Characteristics of Electron Beams with the Aid of Elementary Functions—K. B. Niclas. (*Telefunken-Röhre*, no. 38, pp. 61–70; December, 1960.) The solution obtained for the quadripole parameters are given in graphical form. The method is applied to the study of the transformation region in a low-noise traveling-wave tube.

621.385.6:621.396.65 3585
Microwave Valves for Radio-Link Systems—W. Klein. (*Telefunken-Röhre*, no. 38, pp. 5–36; December, 1960.) The operation of the principal types of microwave tube is described and their performance in the local oscillator, microwave modulator and power amplifier stages is discussed.

621.385.62 3586
On the Possibility of Drift-Tunnel Oscillations in High-Power Klystrons—K. Tomiyasu. (PROC. IRE, vol. 49, pp. 1207 1208; July, 1961.) Spurious oscillations observed in high-power klystrons are discussed. The evidence which suggests they may be drift-tunnel oscillations is examined.

621.385.623.5 3587
Theory of Reflex Klystron with Inhomogeneous Retarding Field—K. H. Kupferschmidt. (*Arch. elekt. Übertragung*, vol. 14, pp. 477–481; November, 1960.) The influence of the inhomogeneity on the build-up of oscillations and on the efficiency of the klystron is investigated. Measurements on a reflex klystron provide confirmation of the theoretical considerations.

621.385.623.5 3588
The Influence of Mechanical Vibrations on Reflex Klystrons—P. Hain, H. Lind, and W. Henne. (*Telefunken-Röhre*, no. 38, pp. 135–150; December, 1960.) Methods are described for measuring the influence of sound and mechanical shock on the frequency stability of reflex klystrons. Results obtained on various klystrons are given and discussed.

621.385.623.5 3589
Electrically Tuned Klystron—R. Musson-Genon and J. Faralier. (*Onde élect.*, vol. 41, pp. 155–158; February, 1961.) An X-band reflex klystron has been developed which is tuned electronically over a range of 300 Mc the range being covered in approximately 200 μsec.

621.385.63 3590
Tubes with Crossed Electric and Magnetic Fields—P. Guénard and O. Doehler. (*Onde élect.*, vol. 41, pp. 142–154; February, 1961.) Various types of crossed-field tubes are classified according to beam geometry and interaction mechanism. A description is given of results obtained with backward-wave oscillators and forward-wave amplifiers.

621.385.63:621.375.9:621.372.44 3591
Energy Interchange between Cyclotron and Synchronous Waves in Quadrupolar Pump Fields—E. I. Gordon and A. Ashkin. (*J. Appl. Phys.*, vol. 32, pp. 1137–1144; June, 1961.) "The various coupling interactions which occur in quadrupolar pump fields have been described using a coupled-mode formalism and from knowledge of the beam orbits. Experiments have been described which verify the basic interactions. Further experimental work is required in order to assess the usefulness of these interactions in low-noise microwave amplification."

621.385.63:621.375.9:621.372.44 3592
Noise in Beam-Type Parametric Amplifiers—E. I. Gordon. (PROC. IRE, vol. 49, p. 1208; July, 1961.) Some additional noise which arises from the finite electron temperature and the size of the beam is discussed.

621.385.63:621.375.9:621.372.44 3593
Parametric Coupling between the Transverse Waves on *O*- and *M*-Type Beams—J. W. Klüver. (*J. Appl. Phys.*, vol. 32, pp. 1111–1114; June, 1961.) To couple only two waves the pump field should be two-dimensional. For HF pumping only waves of the same polarization can couple while for LF pumping only two waves of opposite polarization can couple. Except for cyclotron-cyclotron wave coupling the pump wave will always be in synchronism with a beam wave and thus interact actively or passively with the beam.

621.385.63:621.375.9:621.372.44 3594
Transduction of Noise Theory of a Generalized Travelling-Wave Coupler—M. C. Pease. (*J. Appl. Phys.*, vol. 32, pp. 1145–1151; June, 1961.) A study is made of the response to noise of systems described as "generalized lossless networks" which may include, for example, electron beams and parametrically pumped components. The theory is applied to a generalized coupler.

621.385.632.1 3595
The Uniformity of Active Lines for Microwaves—W. Klein. (*Telefunken-Röhre*, no. 38, pp. 71–84; December, 1960.) Various influences affecting the uniformity of helix or delay-line structures in traveling-wave tubes are investigated.

621.385.633 3596
The Resonant-Type Backward-Wave Oscillator: a Generator of Microwaves—H. Heynisch. (*Arch. elekt. Übertragung*, vol. 14, pp. 531–538; December, 1960.) The oscillator described differs from the normal type of backward-wave tube in that it uses the resonance effect produced by short-circuiting the delay line at both ends. The expressions giving the parameters of the normal backward-wave oscillator are modified by the introduction of the Q factor of the short-circuited delay line to become applicable to the resonant type of oscillator. Experimental results are given for a resonant backward-wave tube operating in the range 3.5–4.7 Gc.

621.385.633.14 3597
O-Type Carcinotron Tubes and their Applications in V.H.F. Measurements—R. Olivier and D. Reverdin. (*Elektrotech. Z., Edn. A.*, vol. 82, pp. 41–46; January 16, 1961.) Applications described include an UHF wobbulator and a wide-band spectrum analyzer.

621.385.65 3598
Design Aspects regarding Travelling-Wave Tubes with Tubular-Magnet Focusing for Radio-Link Applications—W. Klein, J. Bretting, and E. Mayerhofer. (*Telefunken-Röhre*, no. 38, pp. 85–98; December, 1960.) The use of a straight-field focusing by means of barrel-shaped permanent magnets [see *e.g.*, 3697 of 1957 (Glass)] is shown to be advantageous in respect to stray magnetic fields and of power-supply equipment.

621.387 3599
Relaxation Oscillations in a Plasma Diode—J. M. Rocard and G. W. Paxton. (*J. Appl. Phys.*, vol. 32, pp. 1171–1172; June, 1961.) The dependence of the oscillation frequency on the various diode parameters is investigated.

621.387.132.223:621.376.5 3600
Measurement of Energy Losses in a Hydrogen-Filled Thyratron in Modulator Duty—H. de B. Knight and J. Lord. (*Proc. IEE*, pt. B, vol. 108, pp. 455–464; July, 1961.) Values of dissipation at the leading and trailing edges of a current pulse and during the steady state are separated by a pulse-chopping process.

MISCELLANEOUS

061.4:621.38.002.3 3601
Radio Components Show—(*Wireless World*, vol. 67, pp. 361–367; July, 1961.) Review of new equipment and developments exhibited at the Radio and Electronic Components Show, London, May 30–June 2, 1961.

061.4:621.39 3602
Soviet Exhibition in London—(*Wireless World*, vol. 67, pp. 398–399; August, 1961.) Specifications are given of some of the industrial and domestic equipment which was displayed at Earls Court, London.

Within the next few years a powerful astronomical observatory will be placed in orbit outside the distortion of the earth's atmosphere. The space observatory will look at interstellar matter, map the sky's ultraviolet light and perform other experiments to help scientists understand how stars and nebulae are born.

IBM is developing an advanced memory system to go aloft in this satellite and store its observations. The system will receive instructions from the ground, help aim the satellite's instruments and hold collected data for periodic radio transmission back to earth.

The new space memory, being developed by IBM for Grumman Aircraft Engineering Corporation and the Goddard Space Flight Center of the National Aeronautics and Space Administration, called for some unusual solutions from IBM engineers. For example, they were able to reduce power demands considerably by designing the memory to read out information over and over without writing it back into memory each time. Another significant accomplishment is the remarkable design reliability of the new system, achieved through new techniques of redundant circuitry.

Solving problems like these in systems development requires imagination that can travel easily back and forth across technical disciplines. At IBM, people with this kind of imagination are making important advances in such areas as semiconductors, microwaves, magnetics and superconductivity. If any of these fields interests you —and you have a degree and experience in engineering, mathematics or one of the sciences—we'd like to hear from you.

All qualified applicants will receive consideration without regard to race, creed, color or national origin. Please write:

Manager of Technical Employment
IBM Corporation, Department 645L
590 Madison Avenue
New York 22, New York

IBM®

SATELLITE MEMORY SYSTEM: Control Center For An Orbiting Observatory



weather conditioned microwave

ANDREW RADOME EQUIPPED ANTENNAS DEFY ICE...SNOW...WIND

Andrew radomes provide excellent 2-way year-round protection for Andrew microwave antenna systems. First, they protect feed and reflecting surface against the attenuating effects of snow, ice and debris accumulation. Secondly, for tower mounted antennas they reduce the effects of wind thrust by 35%.

All Andrew radomes are lightweight and easy to install—clip directly to the dish rim of existing antennas. Unheated radomes are suitable for all but exceptional cases. In areas where freezing rain occurs, heated radomes can be provided.

SPECIFICATIONS

STANDARD RADOMES

Dia. Feet	Type No.	Attenuation @ 6 kmc. db	VSWR Contribution @ 6 kmc	Thrust at* 30 psf (Flats), lbs.
10	R10	0.4	0.02	1,990
8	R8	0.4	0.02	1,270
6	R6	0.4	0.02	714
4	R4	0.4	0.02	320
2	R2	0.4	0.02	75

*Including antenna

HEATED RADOMES

Dia. Feet	Type No.	Attenuation @ 6 kmc. db	VSWR Contribution @ 6 kmc.	Thrust at* 30 psf. (Flats), lbs.	Power** Reqmts.
10	HR10	0.7	0.02	1,990	3,400 watts
8	HR8	0.7	0.02	1,270	2,400 watts
6	HR6	0.7	0.02	714	1,200 watts
4	HR4	0.7	0.02	320	550 watts
2	HR2	0.7	0.02	75	150 watts

*Including antenna

**Power requirements for HR10 and HR8 are 3 wire single phase 60 cycle 220 volts.

Power requirements for HR6, HR4 and HR2 are single phase 60 cycle 115 v.

For further details on ANDREW Microwave Antennas, Radomes, Wave Guides write for new Andrew Catalog M.

ANTENNAS
ANTENNA SYSTEMS
TRANSMISSION LINES

ANDREW Andrew CORPORATION

P. O. Box 807, Chicago 42, Illinois

Boston • New York • Washington • Los Angeles • Toronto



"We have paid particular attention to antennas during high wind conditions of gusts up to 40-60 m.p.h. It is very obvious that these radomes quite materially reduce the wind loading on the parabolas–due to their shape factor." *Washington State Patrol, Kennewick, Washington*

"We have had up to four inches of ice on the radome with practically no reduction of antenna effectiveness." *KLIX-AM-TV, The KLIX Corporation, Twin Falls, Idaho*

"Our field forces report that the radomes produce a signal loss of less than 1 db per antenna. Several radomes were removed and antennas inspected following a heavy snow storm and no snow or ice was found in the antennas." *Natural Gas Pipeline Company of America*

IRE People

(Continued from page 82A)

Sava I. Sheer (A'57), Manager of Government Operations for International Resistance Co., has been appointed Chairman of the Military Test Equipment and Instrumentation Committee of the Electronic Industries Association.

Committee members come both from industry and from the three armed services. Function of the group is the development of a coordinated industry position on military problems as pertaining to environmental test facilities, environmental test procedures and test instrumentation for the measurement of products and test facilities.

Mr. Sheer, who is also a member of the Armed Forces Communications and Electronics Association, has been affiliated with IRC since 1956.

❖

The Hazeltine Corporation, Little Neck, N. Y. has announced the appointment of **W. S. Sturgeon** (M'48–SM'57) as Assistant Manager of its Greenlawn Engineering Laboratory.

W. S. STURGEON

Mr. Sturgeon has been with Hazeltine since 1946. His diversified engineering career encompasses design, development and installation responsibilities for undersea, shipboard, ground and air and missile-borne systems. An Associate Member of the AIEE (American Institute of Electrical Engineers), he is a graduate of New York University and is a member of the Advisory Commission on Electrical Technology of the New York City Community College.

❖

Walter F. Tackett (SM'58) will direct design and production for the newly formed company, Electroplex, Inc., Los Angeles, Calif. He was formerly in charge of product design at Electronic Engineering Company, Santa Ana, Calif. He also has held positions with the same firm as engineer, project engineer and group engineer in charge of design and instrumentation of special electronic equipment in the timing, data handling and digital recording fields. He is an electrical engineering graduate of University of California at Los Angeles.

Equipment was designed and installed under Tackett's direction for use at Point Mugu, Cape Canaveral, Pacific Missile Range, Edwards Air Force Base, China Lake, Port Huachucha, Eglin Gulf Test Range and the Canadian Cold Lake Range, as well as at missile tracking stations around the world. He is well known for his work on timing and automatic firing devices and digital data transmission equipment.

❖

(Continued on page 88A)

Low-noise TWTs . . . wide dynamic range



Huggins low-noise traveling wave tubes provide 10 DBM minimum saturation P_{out} over major portions of octave bandwidths—coincident with low-noise performance. An example is the HA-89 characteristics shown above. The low noise figure plus high P_{out} results in the maximum degree of linear operation consistent with the present state of the TWT manufacturing art.

S-band low-noise tubes perform at extremely low noise levels, shown typically below, in solenoids requiring 150 watts maximum power and weighing 25 pounds.



Huggins low-noise tubes carry a 1500 hour warranty.

Contact Huggins for further TWT information, including modification of standard tubes to your system specifications.

HUGGINS manufacture development engineering design research LABORATORIES

HUGGINS LABORATORIES INC.

999 East Arques Avenue • Sunnyvale, California
Regent 6-9330 • TWX SUNV 908

from MOTOROLA

VALUABLE HANDBOOKS for CIRCUIT ENGINEERS



Complete your reference bookshelf with these liberally-illustrated technical handbooks

POWER TRANSISTOR HANDBOOK

A 200 page manual with 9 chapters covering: Semiconductor electronics, transistor characteristics, power amplifiers, switching applications, ignition systems, special circuits, power supplies, testing and specifications. Written by Motorola's Applications Engineering Department. Price $2.00.

ZENER/RECTIFIER HANDBOOK

A new 185 page guide to basic theory, design characteristics and applications of zener diodes and rectifiers. The second edition of the popular zener handbook first published in 1959. Price $2.00.

ORDER TODAY — You can obtain these handbooks from your local Motorola Semiconductor distributor or by sending $2 (check or money order) for each book to Motorola Semiconductor Products Inc., 5005 East McDowell Road, Phoenix 10, Arizona. Please specify handbook desired. No purchase orders, please.

MOTOROLA
Semiconductor Products Inc.
A SUBSIDIARY OF MOTOROLA, INC.

IRE People

(Continued from page 87A)

B. Rodman Tuttle (S'58–M'61) has been appointed district manager of the recently opened Boston office of Non-Linear Systems, Inc. He was formerly sales manager for Electro Scientific Industries. He is a graduate of Lafayette College, Easton, Pa., with a degree in electrical engineering. He is a member of the American Institute of Electrical Engineers.

❖

Hazeltine Corporation, Little Neck, N. Y., has announced the appointment of **E. M. Tyler** (A'47–M'55) as Manager of its Greenlawn Engineering Laboratory.

E. M. TYLER

Mr. Tyler, who is an assistant vice president of Hazeltine Electronics Division, joined Hazeltine in 1959 after serving as general manager of the Military Products Division of the Gorham Manufacturing Co. In his capacity as head of the engineering laboratory, he is assigned complete administrative and operational responsibility. A graduate of the University of Wisconsin, he was previously head of Hazeltine's Test Engineering Department.

❖

The appointment of **Joseph P. Vang** (A'61) as product manager for ground support equipment in General Dynamics/Electronics' Marketing Division has been announced.



J. P. VANG

Mr. Vang has been with General Dyananics since 1957 and has held several marketing positions with the company. Immediately prior to his new assignment, he was assistant manager of field sales. He was previously with the Sperry Gyroscope Company, Long Island, for nearly eight years. He served as a radio technician in the U. S. Navy, from 1943 through 1947.

He is a graduate of Yale University, where he received an electrical engineering degree in 1950. He is a member of the Armed Forces Communications and Electronics Association, Association of the U. S. Army, Navy League, and the American Society of Chemical Engineers.

❖

The appointment of **Frederick Walzer** (M'57) as Quality and Reliability Manager of the Allen B. Du Mont Laboratories, Division of Fairchild Camera and Instrument Corp., was recently announced. In his new capacity, he will have overall quality and reliability responsibility for products of the Electronic Tube Division as well as Du Mont's Industrial Electronics Division. Tube products include industrial and military cathode-ray tubes for oscilloscopes, radar and other displays; direct-view storage tubes; multiplier photo tubes; microwave tubes; fiber optics cathode-ray tubes; scan convertors; image dissectors; and image intensifiers. He will also have quality responsibility for the company's 2-way radio systems and apparatus; industrial and closed-circuit television; oscilloscopes, oscilloscope cameras, and other scientific instruments; and electronic automotive test equipment.

F. WALZER

He has been associated with Du Mont Laboratories since 1949, and has served in a number of Quality Control supervisory posts since joining the organization. Most recently he was quality control manager of the Electronic Tube Division. Before joining Du Mont, he was a quality control engineer with National Union Radio Corporation.

He received his electrical engineering education at the College of the City of New

(Continued on page 90A)

NEW For Single Sideband Two-Tone Testing

DUAL SIGNAL GENERATOR



Model **210A**
10 cps — 1 mc

$480.00
F.O.B. Factory

Either signal available separately or at combined balanced output terminals. Total harmonic distortion under 0.1% — intermodulation products 60 db down. Separate calibrated 1 to 110 db step attenuators for each oscillator.

Write for Complete Specifications

RON ELECTRONICS CORP.
150 Pine St., Montclair, N. J.
PIlgrim 4-8330

New Bourns Precision Potentiometer Resolves the Quality-Price Dilemma!

Here is military reliability in a competitively-priced industrial potentiometer. Bourns wirewound 10-turn Model 3500 measures just ¾" in diameter by 1" long—shorter by ½" than units available elsewhere—yet has a resistance element 20% longer than that of comparable potentiometers.

Fully meeting military requirements for steady-state humidity, Model 3500 can also be provided at a 10% premium to meet the cycling humidity specs of MIL-STD-202, Method 106. It's the only ¾" 10-turn potentiometer guaranteed to meet this spec. Its published characteristics incorporate wide safety margins.

Reliability insurance is provided by the exclusive Bourns Silver-weld® bond between terminal and resistance wire. Virtually indestructible under thermal or mechanical stress, this termination eliminates a chief cause of potentiometer failure. In addition, a special close-tolerance rotor almost completely does away with backlash.

Model 3500 is also subjected to the rigorous double-check of Bourns' exclusive Reliability Assurance Program. In short, every possible step is taken to ensure that the performance you specify is the performance you get. Write for complete data.

Resistances	500Ω to 125K, ± 3%, std. (to 250K spl.)
Linearity	± 0.25% std.
Power rating	2w at 70°C
Operating temp.	−65° to +125°C
Mech. life	2,000,000 shaft revolutions

Manufacturer: Trimpot® potentiometers; transducers for position, pressure, acceleration. Plants: Riverside, California; Ames, Iowa; and Toronto, Canada

FXR's
STANDARD STEP ATTENUATORS

5*



Series 176

- OPERATION: Full waveguide bandwidth
- FREQUENCY RANGE:
  7.05 KMc to 10 KMc
  8.2 KMc to 12.4 KMc
- STEP LOSS: 40 db
- CALIBRATION & FREQUENCY SENSITIVITY: ±0.4 db max
- VSWR: 1:1 max
- INSERTION LOSS: 0.5 db max

*

No. 5 of a series of FXR's new precision microwave components designed to meet the ever-growing needs of the microwave industry.

FXR's Standard Step Attenuator differs uniquely from other standard step attenuators in that the attenuation in a waveguide line can be changed without removing any component in the line. This convenient feature adds significantly to measurement accuracy. The attenuation is determined by the size of coupling holes and not by the resistivity of a loss-producing element. The attenuation value is, therefore, independent of time and ambient conditions and is relatively constant with frequency.

MODEL NO.	FREQUENCY RANGE KMc	WAVEGUIDE TYPE RG-( )/U	PRICE
W176A	7.05-10.0	51	$185.00
X176A	8.2-12.4	52	165.00

Write for Catalog Sheet No. 176

FXR a division of Amphenol-Borg Electronics Corp.
25-26 50th Street / RA. 1-9000
Woodside, N. Y. / TWX: NY 43745

IRE People

(Continued from page 88A)

York and Randolph-Macon College in Georgia. Mr. Walzer served with the U. S. Signal Corps during World War II.

❖

The appointment of **Dr. Bernard Wambsganss** (S'46–A'49–M'55–SM'58) as assistant to President Fred W. Krause of Alfred Electronics Corporation has been announced by the Palo Alto, California, firm. Alfred manufactures broad-band microwave instrumentation.

B. Wambsganss

Before joining Alfred, Dr. Wambsganss was Chief Scientist of the Office of Naval Research Branch Office, San Francisco, Calif. His previous experience also includes 5 years at Sylvania Electronics Defense Laboratories in Mountain View, Calif., where he was Systems Engineering Laboratory Manager from 1958–60.

Dr. Wambsganss received his PhD. in electrical engineering from Stanford University in 1955. He is a member of the Research Society of America and of Sigma Xi.

❖

The election of **William J. Weisz** (S'48–A'49–M'53–SM'59) as Vice President, Communications Products, for the Communications Division of Motorola, Inc. was recently announced. Mr. Weisz, a 1948 graduate in electrical engineering of Massachusetts Institute of Technology, Cambridge, Mass., joined the company in that year and was appointed Manager of Subminiature Equipment Engineering Section in 1952.



W. J. Weisz

He became Product Manager for Portable Communications products in 1954, Chief Engineer for two-way mobile and portable products in 1956, and Manager of that department in 1958. He is a past Chairman of the Chicago Chapter of the IRE. He is a member of the American Institute of Electrical Engineers and has represented Motorola on various committees of the Electronics Industry Association. His military service was as instructor in Naval Radar and Radio Material School.

❖

(Continued on page 92A)

PTE-3
AN/GRM-33A

SINGLE SIDEBAND ANALYZER



The TMC Model PTE-3 (AN/GRM-33A) is a multipurpose test instrument used at communication facilities, in laboratories, and in electronic production facilities for visual analysis of RF signals within the frequency range of 1.5 to 64.5 megacycles. The PTE-3 may be used for tuning and aligning transmitters, sideband exciters, RF filters, and for band occupancy studies. Detailed analysis of any portion of the selected spectrum for intermodulation distortion, harmonic distortion, sideband suppression, carrier suppression, spurious signals, hum, noise, and adjacent channel interference is made possible by a manual sweep control.

The PTE-3 contains a variable frequency oscillator with long term stability, a two tone RF generator for unit test and calibration, and a two tone audio generator for distortion analysis.

THE TEST EQUIPMENT DIVISION OF
THE TECHNICAL MATERIEL CORPORATION
World Wide Suppliers of Electronic Communications Equipment
and Subsidiaries
OTTAWA, ONTARIO • GARLAND, TEXAS • ALEXANDRIA, VIRGINIA
MAMARONECK, NEW YORK

Submarine Cables for Communications, Control & Power

Since 1954 alone, more than 15,000 miles of submarine cable have been delivered from Simplex Wire & Cable Company's Submarine Cable Division at Portsmouth, N. H., the only modern U. S. plant specifically designed for submarine cable production.

SCD offers *complete* capabilities for both commercial and military underwater cable technology...cable and fitting design and manufacture ...laying techniques and supervision for laying... splicing instruction and equipment...planning, manufacture, and emplacement of complete submarine cable systems.

SCD has wharfside facilities for loading two ocean cable ships simultaneously from tanks capable of storing more than 3000 miles of finished cable.

Simplex
WIRE & CABLE CO.
SUBMARINE CABLE DIVISION
Portsmouth, New Hampshire
EXECUTIVE OFFICES: CAMBRIDGE, MASS.

Write today for your free copy of the new SCD Brochure, detailing facilities and capabilities.

AT LAST—The IDEAL BARRIER TERMINAL STRIP



JONES 500 SERIES
LONGER—STURDIER

Wider and higher barriers for increased creepage distances. Closed bottoms for complete insulation. Material between barriers at the base adds to the strength and maintains the same creepage distance between contact to contact and contact to ground. Can be imprinted here. No insulating or marker strip required. Three series—540, 541 and 542 having the same terminal spacing as our 140, 141 and 142 series.

Complete listing in the new Jones No. 22 catalog. Write for your copy today.

Jones
HOWARD B. JONES DIVISION
CINCH MANUFACTURING COMPANY
CHICAGO 24, ILLINOIS
DIVISION OF UNITED-CARR FASTENER CORP.



TRYLON
BROADBAND VERTICAL RADIATORS

for frequency ranges from 2 to 6 mc. 4.5 to 13.5 mc.–11 to 33 mc.–or similar ranges

A multi-frequency service radiator requiring no matching equipment

ADVANTAGES

- Extremely constant input impedance over a wide frequency range.
- Power handling capacity to 150 kw. or more.
- Radiation performance equal to, or better than a conventional radiator without the need of impedance matching equipment.

WIND TURBINE COMPANY
WEST CHESTER, PA.
Phone: OWen 6-3110

TRYLON TOWER AND ANTENNA SYSTEMS
• RESEARCH • MANUFACTURE
• DEVELOPMENT • INSTALLATION

Write, wire or phone for information or application to your requirements.

IRE People

(Continued from page 90A)

Arthur B. Williams (M'59) is President of a new company, Electroplex, Inc., Los Angeles, Calif., formed to design, develop and produce equipment for the digital field. He will also direct sales for the firm. He was formerly Vice President for Sales at Engineered Electronics Company, Santa Ana, Calif., a manufacturer of digital plug-in circuit modules. Before joining Engineered Electronics, he was with Baker Brothers, Toledo, Ohio; Booz, Allen and Hamilton, New York and Los Angeles; and Wright Engineering Company, Pasadena, Calif.

He holds a B.S.E.E. degree from Yale University and the M.B.A. degree from Harvard University.

❖

Membership

The following transfers and admissions have been approved and are now effective:

Transfer to Senior Member

Affel, R. G., Knoxville, Tenn.
Bean, O. E., Cochituate, Mass.
Boyle, H. G., Dayton, Ohio
Brewster, P. J., Palmyra, N. J.
Brown, R. L., San Francisco, Calif.
Fleckenstein, W. O., Whippany, N. J.
Hamer, W. A., Lyndhurst, N. J.
Johnston, E. F., Jr., Dayton, Ohio
Kaufman, B. A., Los Angeles, Calif.
Lamb, J. F., Columbia, Mo.
Mayer, A., Sunnyvale, Calif.
Mohsen, A., Newark, N. J.
Overdeer, R. H., Jenkintown, Pa.
Raynes, H. D., Baltimore, Md.
Ross, A., Bayside, N. Y.
Sabto-Agami, J. C., Murray Hill, N. J.
St. John, J. D., Milwaukee, Wis.
Stranix, R. G., Philadelphia, Pa.
White, G. T., Johnsville, Pa.
Zippler, W. N., New York, N. Y.

Admission to Senior Member

Alexander, E. E., Pleasanton, Calif.
Anderson, A. G., San Jose, Calif.
Biggs, J. K., Jr., Dallas, Tex.
Bledsoe, W. W., Palo Alto, Calif.
Boyd, H., Cuyahoga Falls, Ohio
Bronzo, J. A., Whippany, N. J.
Brown, M. S., Temple City, Calif.
Conrad, V. A., Palo Alto, Calif.
Crawford, F. W., Stanford, Calif
Denning, L. S., Fairfax, Va.
Dotson, E. J., Redstone Arsenal, Ala.
Franck, A., Minneapolis, Minn.
Harris, R. B., McLean, Va.
Heywood, J., Caterham, Surrey, England
Jacoby, G. V., Camden, N. J.
Johnson, W. E., Merchantville, N. J.
Katz, I., Ithaca, N. Y.
Knowlton, O. H., Jr., Van Nuys, Calif.
Kollanyi, M., Pleasant Hill, Calif.
Levine, J., North Bellmore, N. Y.
Murphy, E. M., Northport, N. Y.
Podoski, J. J., Washington, D. C.

(Continued on page 95A)



CODI

EPOXY ENCAPSULATED SILICON RECTIFIERS

New Small Size / Double Sealed
All Welded Construction
Low Leakage / High Current
Polarized for Automatic Insertion

Specifications for CODI Rectifier Types CODI 531 to 538

Electrical Characteristics	CODI 531	CODI 532	CODI 533	CODI 534	CODI 535	CODI 536	CODI 537	CODI 538	UNITS
Max. forward voltage drop @ 500 mA	1.1	1.1	1.1	1.1	1.1	1.1	1.1	1.1	volts
Max. reverse leakage @ rated voltage	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	μA
Max. reverse leakage under load (Note 1)	50	50	50	50	50	50	50	50	μA
Max. forward voltage drop under load (Note 1)	0.6	0.6	0.6	0.6	0.6	0.6	0.6	0.6	volts
Maximum Ratings									
Peak Inverse Voltage	100	200	300	400	500	600	700	800	volts
Applied R M S Voltage	70	140	210	280	350	420	490	560	volts
Surge Current for one cycle	35	35	35	35	35	35	35	35	Amps
Average rectified current @ 25°C	750	750	750	750	750	750	750	750	mA
Average rectified current @ 100°C	500	500	500	500	500	500	500	500	mA

Operating and Storage Temperature Range −65°C to +150°C
All specifications at 25°C unless otherwise stated.

Note 1: Average over one cycle for full wave choke or resistive circuit with rectifier operating at rated current.

Computer Diode manufactures

General Purpose Diodes
250 mW Zener Diodes
400 mW Zener Diodes
Special Circuit Packages
Non-Metallic Epoxy Rectifiers

COMPUTER DIODE
CORPORATION

250 GARIBALDI AVENUE • LODI, NEW JERSEY • PRESCOTT 3-2511

How to show the sky in stereo

Up till now, radar has literally been blind in one eye. It lacked one of the prime dimensions—depth perception. Conventional radar could only show objects in two dimensions. Either direction and distance *or* height and distance.

This limitation often makes radar lag behind the pace of modern aircraft—forcing planes to slow down in the busy intersections over airport areas.

But now the other eye has been opened. Hughes' new 3-dimensional—or stereoscopic—radar presents a scaled-down "cylinder of sky." Watching this radar, you could see the earth, the air space above and aircraft represented with a definition never before possible. The result: planes could move through busy intersections with new speed and safety.

This new radar display console—called Stereoscan—has two Hughes Tonotron* picture tubes which are combined to make this startling 3-dimensional view possible. Because they remember images—they produce a radar picture where the "blips" leave contrails like a jet. It is these patterns that clearly show the direction *and* altitude *and* distance which separates the planes.

This improved radar display is also more accurate, easier to view and can be used under normal room lighting.

Hughes is hiring. Immediate needs now exist for engineers and scientists for assignment to: Radar Displays, Underseas Warfare, Field Engineering, Circuit Design, Space Controls and Infrared. For further information write: Mr. S. L. Gillespie, Hughes Aircraft Company, Building 21, M.S. 2320-N, Culver City, California.

Creating a new world with electronics

HUGHES





Hughes 3-D radar display console can give a continuous view of sky activity. Integrated with a complete control system, it would tell air traffic controllers if planes were on a collision course. They could make swift decisions and direct air traffic in a fraction of the time it takes today.

**Trademark Hughes Aircraft Company*

Membership

(Continued from page 92A)

Ritow, I., Melville, N. Y.
Schmid, H., Amityville, L. I., N. Y.
Sherman, K. I., Affton, Mo.
Talbot, S. A., Baltimore, Md.
Thun, R. E., West Hurley, N. Y.
Totman, V. S., Utica, N. Y.
Tuppen, A. R., Wayne, N. J.
Von Struve, H. C., III, Arlington, Tex.
Williams, F. B., Golf, Ill.
Wilson, C. R., Indialantic, Fla.

Transfer to Member

Allsopp, W. C., Jr., Little Rock, Ark.
Aristogenis, G. S., Athens, Greece
Bocchieri, A. J., Highland Park, N. J.
Burns, B. E., Inglewood, Calif.
Cole, L. M., Winston-Salem, N. C.
Common, C. A., Flint, Mich.
Conant, T. W., Rutherford, N. J.
Cropley, B. M., Santa Clara, Calif.
Gazzigli, J. J., White Plains, N. Y.
George, J. A., Newmarket, N. H.
Lancaster, W. W., Mulvane, Kans.
Mullick, S. K., Kharagpur, India
Myers, W. B., Lombard, Ill.
Novak, B. R., Arlington Heights, Ill.
Olmo, W. J., Jr., San Bruno, Calif.
Peterson, C. H., Silver Spring, Md.
Reinschmidt, A. L., Biloxi, Miss.
Reyda, D. C., West Vancouver, B. C., Canada
Snyder, J. D., Omaha, Neb.
Temple, T. W., Dayton, Ohio
Washburn, L. A., Fort Worth, Tex.

Admission to Member

Antipov, I., Pleasant Valley, N. Y.
Appley, W. A., Anaheim, Calif.
Barrow, E. A., Harlow, Essex, England
Bates, W. L., Montrose, Calif.
Belyea, A. E., New Hyde Park, L. I., N. Y.
Black, R. L., Bay Shore, L. I., N. Y.
Bomboy, R. L., Harrisburg, Pa.
Bottenfield, C. L., Baltimore, Md.
Boulanger, J. L., Winchester, Mass.
Brinker, H., Baltimore, Md.
Brock, G. B., Arlington, Va.
Brosha, W. C., Falls Church, Va.
Brustad, J. T., Claremont, Calif.
Buehrle, W. B., Scottsdale, Ariz.
Bush, G. S., Syracuse, N. Y.
Bylock, N., Port Washington, L. I., N. Y.
Carlowe, J. F., Satellite Beach, Fla.
Carson, R. T., Islington, Ont., Canada
Chisholm, A. N., Alamogordo, N. M.
Cohen, L., Brooklyn, N. Y.
Cole, P. H., Oatley, N. S. W., Australia
Conner, A. D., Phoenix, Ariz.
Crabtree, T. M., Tewksbury, Mass.
Crole-Rees, D. G., Lausanne/Pully, Switzerland
Denham, R. C., Westerly, R. I.
Diamond, H. W., Jr., Sunnyvale, Calif.
Dimmick, H. M., Butler, Pa.
Dorr, W. B., Long Beach, Calif.
Dunn, G. E., Jr., Roslyn, N. Y.
Elmgren, J. F., Las Vegas, Nev.
Feinberg, J. E., New Rochelle, N. Y.
Fichthorn, R. J., Levittown, N. J.
Flannery, J. V., Los Angeles, Calif.
Foster, J. P., Bethpage, L. I., N. Y.
Fulford, A. J., Jr., North Charleston, S. C.
Gantt, L., Jr., Baltimore, Md.
Gentry, D. E., Atlanta, Ga.
Glynn, D. C., Sunnyvale, Calif.
Gordon, J. D., Wayland, Mass.
Gotelipe, J. R., Palo Alto, Calif.
Grimwood, C., Philadelphia, Pa.
Grinspoon, L. N., Gulfport, Miss.
Gumaer, H., Carlisle, Mass.
Hagerling, S. W., Vienna, Va.
Harding, L. P., Mt. View, Calif.
Hart, R. T., Richardson, Tex.
Hemann, R. G., Garden Grove, Calif.
Herbert, W. R., III, Atlanta, Ga.
Hlavac, F. W., Kingsville, Md.
Hornyak, S. J., Baltimore, Md.
Hubbard, A. C., Blauvelt, N. Y.
Hughes, W. C., Scotia, N. Y.
Hume, D. R., Torrance, Calif.
Hunter, J. E., Jr., Sudbury, Mass.
Hurd, W. A., Atlanta, Ga.
Jackson, T. A., Lombard, Ill.
Jennings, J. B., Columbia, Mo.
Johnson, E. A., Charleston, S. C.
Jones, W. N., Allentown, Pa.
Kallfelz, C. P., Lansdale, Pa.
Katz, A. I., Somerset, N. J.
Kaufman, R. A., Schenectady, N. Y.
Kennedy, D. T., Ottawa, Ont., Canada
Kernin, W. F., Niagara Falls, N. Y.
Ketel, C. G., Cedar Rapids, Iowa
Kiefer, J. E., Canoga Park, Calif.
Kilgore, R. A., Kansas City, Mo.
Kiser, D. O., Palo Alto, Calif.
Kluetz, J. H., Panama City, Fla.
Koch, D. V., San Diego, Calif.
Kozlowski, L. J., Jr., Jersey City, N. J.
Laing, R. L., Fort Worth, Tex.
Liepmann, W. H., Stamford, Conn.
Lincoln, B. R., Woburn, Mass.
Little, N. K., Jr., Pleasant Hill, Calif.
Lorenz, R., San Antonio, Tex.
Loutensock, W. R., Northridge, Calif.
Madson, M. M., Milwaukee, Wis.
Mangru, S. J., Diego Martin, Trinidad, B. W. I.
Mann, C. C., Washington, D. C.
Martin, R. E., Beverly Hills, Calif.
Mayer, W. H., Mountain Lakes, N. J.
McClelland, A. J., Altadena, Calif.
Mereckis, Z. A., Chicago, Ill.
Miller, J. C., Oklahoma City, Okla.
Minkoff, R. T., Columbus, Ohio
Murphy, G. F., Arlington, Tex.
Murray, J. J., Endwell, N. Y.
Neal, E. H., Watertown, Mass.
Nell, D. E., Philadelphia, Pa.
O'Bryant, D. L., Whitesboro, N. Y.
Odagawa, K., Kawasaki, Kanagawa, Japan
Oslund, R. R., Los Angeles, Calif.
Pabalan, J. A., Jr., Corning, N. Y.
Paul, J. F., Palo Alto, Calif.
Pike, D. B., Earlwood, N. S. W., Australia
Pollak, P. I., Rahway, N. J.
Rademaker, J. R., Ann Arbor, Mich.
Redman, S. J., Sydney, Australia
Rudolph, L. D., Ithaca, N. Y.
Scarling, N., Jr., Somerdale, N. J.
Schell, M. V., Livermore, Calif.
Scott, G. W., Little Waltham, Nr. Chelmsford, Essex, England
Shacklett, F., Mountain View, Calif.
Sherrell, F. G., Manchester, Tenn.
Shurtleff, D. R., Potsdam, N. Y.
Sink, J. R., Arlington, Va.
Skovholt, J., Stanford, Calif.
Smay, T. A., Ames, Iowa
Smith, C. L., Santa Monica, Calif.
Snell, N. M., Mercury, Nev.
Snyder, T. D., Fairfax, Va.
Stidham, J. R., Albuquerque, N. M.
Streleckis, A. C., Plymouth Meeting, Pa.
Swatton, J. F., Rhinebeck, N. Y.
Thaler, S. S., Stamford, Conn.
Thorson, G. O., Los Angeles, Calif.
Thurman, G. O., Tucson, Ariz.
Totten, R. W., Flint, Mich.
Vann, H. R., Baltimore, Md.
Wachholz, J. J., South Milwaukee, Wis.
Waite, T. R., Canoga Park, Calif.
Widney, E. F., Ventura, Calif.
Wilewski, H. M., Mountainside, N. J.
Winter, M., New York, N. Y.
Witte, A. H., Jr., Redwood City, Calif.
Womack, C. P., Marion, Iowa
Worth, L. R., Chicago, Ill.
Yaggy, L. S., North Carlsbad, Calif.
Yamada, R., Hamamatsu-City, Japan

(Continued on page 96A)

Designed for
M
Application

CATHODE RAY TUBE BEZELS

Illustrated are a few of the stock molded phenolic and/or cast aluminum Bezels and support cushions available for most popular Cathode Ray Tubes. Not illustrated but also available, camera-mount and illuminated types.

JAMES MILLEN MFG. CO., INC.
MALDEN
MASSACHUSETTS

Membership

(Continued from page 95A)

Zanin, S. R., San Diego, Calif.
Zimmerman, M. L., Wappingers Falls, N. Y.

Admission to Associate

Alexander, G. F., Montreal, Que., Canada
Asa, M., Oakland, Calif.
Avis, C. E., Tulsa, Okla.
Bailey, J. H., Downey, Calif.
Bellizzi, J. A., La Habra, Calif.
Bennett, C. P., Somerville, N. J.
Bensinger, G. I., Great Lakes, Ill.
Blom, R. E., Palo Alto, Calif.
Bonanno, V. R., Elmont, L. I., N. Y.
Bourke, K. P., Ontarioville, Ill.
Bradrick, W. L., San Bruno, Calif.
Breedon, N. C., Victoria, B. S., Canada
Brice, S. H., Spenard, Alaska
Camburn, M. L., Tecumseh, Mich.
Collins, E. A., Jr., Pittsburgh, Pa.
Cowhig, W. W., Waltham, Mass.
Crewson, M. E., Belleville, Ont., Canada
Cupp, J. D., El Monte, Calif.
Eisenhut, D. F., Fort Wayne, Ind.
Elias, K. J., Memphis, Tenn.
Eymann, E. F., Springfield, Ill.
Gale, W A., Victoria, B. C., Canada
Goodwin, L. E., Macon, Ga.
Goss, J. W., Montreal, Que., Canada
Hagenbuch, E. A., Levittown, Pa.
Hall, H. J., Mineola, L. I., N. Y.
Holshouser, E. L., San Jose, Calif.
Holtzman, D. E., Arleta, Calif.
Hutchinson, R. A., Jamaica, N. Y.
Jerril, R. J., New York, N. Y.
Kelly, J. J., Alden, N. Y.
Kramer, E. L., New York, N. Y.
Lamb, B., Nashville, Tenn.
Larsen, L. A., Stamford, Conn.
Laubscher, F. H., San Rafael, Calif.
Leal, A. J. B. de C. M., Rio de Janeiro, Brazil
Miyasaka, E., Shinagawaku, Tokyo, Japan
Ogata, H. K., Los Angeles, Calif.
Pereira, M. C. R., Rio de Janeiro, Brazil
Perrin, E. S., Riviera Beach, Fla.
Place, D. R., Berryville, Va.
Rocha, J. E. V., Rio de Janeiro, Brazil
Rungaitis, W. G., Jr., La Mirada, Calif.
Schaefer, A., Massapequa, N. Y.
Shepherd, J. J., Ottawa, Ont., Canada
Stachew, E. K., Pittsburgh, Pa.
Stubbs, E. A., Glen Cove, N. Y.
Stultz, D. C., Tampa, Fla.
Tateishi, M., Amagasaki, Hyogo Prefecture, Japan
Turner, G. E., Westford, Mass.
Tracy, P. J., Winston-Salem, N. C.
Zwiebel, J. J., Burlington, Wis.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

Impulse Counter

A new 4-digit Sodeco predetermining electric impulse counter is available from **Landis & Gyr, Inc.**, 45 W. 45th St., New York 36, N. Y.

Designated Type 2TCeF4PE, the new counter provides a visual in-line count, and a control function, in a single compact unit.



The counter is readily preset by means of knurled wheels behind the flat near the top of the unit to any number from 1 to 9999. After the preselected number of counts has been registered, a single-pole double-throw contact reverses, permitting a control function. Counters are available with either push button manual or remote electric instantaneous reset.

Although an incorporated rectifier permits direct operation from a 110 or 220 volt ac source, counter coils are dc. Rated speed is 1500 counts/minute.

This panel mounting instrument measures 2″×4″×5″, and utilizes engraved white on black figures. The mechanism is protected by an aluminum housing. It may be used with any pulse generator capable of creating a pulse of the required specifications.

Complete technical data, including wiring diagrams, is available.

(Continued on page 112A)



ONE METER TO FOUR MILLIMETERS

New Litton Electron Tubes for Advanced Applications

A. L-3403 KLYSTRON TUBE: One of our super power pulse klystrons for use in long range space radar detection and tracking.

B. L-3270 BROADBAND KLYSTRON: A 2 megawatt L-band klystron offering long life, high peak power, 8 percent bandwidth. Other broadband klystrons, using the exclusive Litton Skirtron techniques, are available with higher power in the L through S-band region with .002-.004 duty cycles.

C. L-3455 HIGH POWER MAGNETRON: A new magnetron delivering a minimum of 2 megawatts peak power at 406-450 mc. with a .002 duty cycle.

D. L-3458 HIGH TEMPERATURE PULSE MAGNETRON: Provides long life operation at ambient temperatures in excess of 662°F. Many hours of 900°F. operation have been achieved in X-band tests.

E. L-3629 FLOATING DRIFT TUBE KLYSTRON: High power, water-cooled klystron oscillator fixed tuned at 33,000-37,000 mc. Power output: 15 watts CW minimum. Other tubes available for immediate delivery from 12-4 mm. wavelength.

F. L-3472 TWT: PPM focused traveling wave tube offers higher CW power — 10 watts minimum — and wider bandwidth in a compact 3-lb. size. Operates in the range of 7,000-11,000 mc. One of a line of TWT's including a 1000-watt X-band pulse tube.

G. MICROTRON: The L-3189, one-kilowatt CW magnetron, is accompanied in package form by an electromagnet and filter assembly, high voltage and filament and isolation transformers. Only 6-second warm-up. Two year warranty for domestic microwave cooking.

H. L-3430 CUBE MINIATURE MAGNETRON: A one-kilowatt miniature magnetron, fixed tuned at 9300 ± 30 mc, weighing less than 9 ounces and no bigger than a normal X-band waveguide flange. Developments at other power levels and frequencies are planned.

I. L-3408 SWITCH TUBE: Provides switching at relatively low control voltage levels with an efficiency of 95 percent. Features high voltage holdoff, high current handling. Collector ratings: 150 Kv; 20 Amps; 10 KW dissipation.



For information on our tube line, exclusive of classified types, send for the 1961 Electron Tube Condensed Catalog. Write to: Marketing Dept., Electron Tube Division, 960 Industrial Road, San Carlos, California

LITTON INDUSTRIES
Electron Tube Division
MICROWAVE TUBES AND DISPLAY DEVICES



Opportunities for

circuit designers

Requirements of new and continuing projects, such as Surveyor and supersonic interceptor fire control systems have created new openings for circuit designers. The engineers selected for these position will be assigned to the following design tasks:

1 the development of high power airborne radar transmitters, the design of which involves use of the most advanced components,

2 the design of low noise radar receivers using parametric amplifiers, solid state masers and other advanced microwave components,

3 radar data processing circuit design, including range and speed trackers, crystal filter circuitry and a variety of display circuits,

4 high efficiency power supplies for airborne and space electronic systems,

5 telemetering and command circuits for space vehicles such as Surveyor and the Hughes Communication Satellite,

6 timing, control and display circuits for the Hughes COLIDAR* (Coherent Light Detection and Ranging).

In addition, openings exist for several experienced systems engineers capable of analysis and synthesis of systems involving the type of circuits and components described above.

If you are interested and believe that you can contribute, please airmail your resume to: **Mr. Robert A. Martin,** Supervisor, Scientific Employment, Hughes Aerospace Engineering Division, Culver City 45, California.

*Trademark H.A.C.

We promise you a reply within one week.

Creating a new world with electronics

HUGHES

HUGHES AIRCRAFT COMPANY
AEROSPACE DIVISIONS

Positions Open

The following positions of interest to IRE members have been reported as open. Apply in writing, addressing reply to company mentioned or to Box No. ....

The Institute reserves the right to refuse any announcement without giving a reason for the refusal.

Proceedings of the IRE
1 East 79th St., New York 21, N.Y.

DATA PROCESSING ENGINEER

An attractive position is open for an engineer or mathematician with one to four years experience (or the equivalent in graduate education) who would like to attack challenging problems such as the analysis of automatic control, data processing, and tracking systems. Education and/or experience in disciplines such as control systems, statistical communications theory, digital systems, and network analysis desirable. Opportunity to work with an energetic group of talented engineers in a conducive research atmosphere. Contact Mr. A. P. Rentschler, Employment Mgr., Cornell Aeronautical Lab., 4455 Genesee St., Buffalo 21, New York.

ENGINEERS

Two Electrical Engineering positions open with Application Engineering Dept. charged with the responsibility of assisting the technical groups of customers and prospective customers in the application of products manufactured by the company, with especial emphasis on the application of capacitors to equipment and systems. This group supplements the work of the sales personnel in the field, works closely with the Design and Product Depts. One Engineer desired with strong background in electronic circuitry and filter design; second Engineer, with experience with electronic computers and computer circuits. Location: East coast. Write including personal resume and curriculum vitae. Box 2059.

PROFESSORS

The Air Force Institute of Technology, Wright Patterson Air Force Base, Ohio, has a vacancy in the Department of Mathematics. Most of the work is at advanced undergraduate and graduate level. One quarter out of four free of teaching duties for research or other academic pursuits, plus vacation. Working conditions comparable to those in leading universities. Employment will be effected in accordance with Civil Service regulations. Rank and salary will depend upon qualifications of applicant and may be anywhere between assistant professor, GS-11, $7,560.00 and full professor, GS-14, $12,210.00. Applications should be made on Standard Form 57, available at any Post Office or by letter to Head of the Department of Mathematics, Institute of Technology, Wright Patterson AF Base, Ohio.

GRADUATE ASSISTANTSHIPS

Research and Graduate Assistantships in Instrumental Sciences leading to a M.S. degree in Instrumental Sciences. Engineering and Physics majors with strong background in instrumentation. Course work in fundamental principles and theory of basic instrumentation and process control. Research work in many fields such as high vacuum, electron and ion generation, mass spectrometry and gas chromatography, and process instrumentation. Stipend $2100 to $2400 for twelve months. Send transcript and vitae to: Head, Electronics and Instrumentation, University of Arkansas, Graduate Institute of Technology, P.O. Box 3017, Little Rock, Arkansas.

(Continued on page 100A)

The scientists and engineers at Amherst Laboratories are currently engaged in communications projects which are making vital contributions to our nation's defense efforts. The basic objective of this facility is the advancement of the state-of-the-art of communications and instrumentation systems, with emphasis on the role that microwave and millimeter wave technology will play in that advancement. Coupled with these on-going specific projects, is a freedom of investigation that allows no past premise to go unchallenged, allows no new avenues of inquiry to go unexplored. Together, they form what we like to call "Project Tomorrow"... a total dedication to the advancement of the science of communications.

MANAGEMENT AND STAFF OPPORTUNITIES exist for dedicated scientists and engineers with advanced degrees and creative desire. Physicists, Mathematicians and Electronic Engineers are invited to direct inquiries in complete confidence to Mr. H. L. Ackerman, Professional Employment,

AMHERST LABORATORIES • 1181 WEHRLE DRIVE • WILLIAMSVILLE, NEW YORK
AN EQUAL OPPORTUNITY EMPLOYER

SYLVANIA ELECTRONIC SYSTEMS
Government Systems Management
for GENERAL TELEPHONE & ELECTRONICS

Shrinking the Universe . . . through Communications

RADAR - ECM ENGINEERS

Several staff positions are open for qualified engineers to participate in research projects involving ECM and ECCM techniques.

Work centers around system and subsystem analysis for susceptibility to countermeasures, the creation of special jamming techniques, and the investigation of special ECCM concepts.

Electronic Engineers with appropriate experience in microwave and radar systems are invited to reply to:
C. P. Rentschler

CORNELL AERONAUTICAL LABORATORY, INC.
of Cornell University
BUFFALO 21, NEW YORK

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

MAN IS HIS WORK

And next to spiritual progress, advancement in his work is his highest form of expression.

When a man is blocked in his work, he dies a little. For some, a vacation or a slight change in responsibilities suffices to put him back on the track. For others, a complete change of positions is necessary.

The scientist of job satisfaction in electronics is Davies-Shea, Inc., of Chicago, combining over 50 years experience in helping professional men plan and attain their career objectives.

For our free bulletin listing America's best electronics jobs each month, send your name and home address to:

DAVIES - SHEA, Inc. WEbster 9-3833
332 South Michigan Chicago 4, Ill.
Electronics Personnel Consultants

ENGINEERS MATHEMATICIANS PHYSICISTS

Engineering-Physics Co. has recently embarked upon new fields of research and development. Singular opportunities exist for engineers and scientists who have the resourcefulness, imagination and technical background to assume a responsible role. All qualified applicants will be considered for employment regardless of race, creed, color or national origin.

Projects include studies and developmental work on:

INSTRUMENTATION
MAGNETOHYDRODYNAMICS
ELECTROMECHANICAL DEVICES
SYSTEMS CONCEPT & DEVELOPMENT

Address inquiries to Dr. Vincent Cushing

EPCO ENGINEERING PHYSICS COMPANY
5515 Randolph Road
Rockville, Maryland

Positions Open

(Continued from page 99A)

SOLID STATE RESEARCH

Opening for Ph.D. in physical chemistry, physics or metallurgy. We are producers of highest quality silicon and one of our chief research interests in this field is vapor-deposited single-crystal layers. We are interested in having as accurate and comprehensive information as possible on such structures and on their possible application to devices. We are already engaged in electrical and optical studies and are most desirous of deepening and broadening these studies. A sufficiently qualified applicant would have ample opportunity for choosing and exploiting directions as well as specific problems of interest. Other fields of research in semiconductors are gallium arsenide, germanium and thermoelectric materials. Reply in confidence to Box 2060.

SENIOR MATHEMATICIAN—STATISTICIAN

Supervisory position for a Senior Mathematician experienced in the use of Gaussian, Exponential, Gamma and Weibull Distributions for reliability predictions in electronic circuitry. Apply to Melpar, Inc., 3013 Arlington Blvd., Falls Church, Va.

MEDICAL ELECTRONICS

A rapidly expanding medical school requires an engineer to head an electronics development service. A graduate degree with an interest in the bio-medical field or a B.S. degree with considerable applicable experience is required. Contact Dr. John Schuder, University of Missouri, Medical Center, Columbia, Missouri.

COGNITIVE SYSTEMS SCIENTIST

A staff opening exists in the Computer Research Department of the Cornell Aeronautical Laboratory which will permit a resourceful, imaginative scientist to participate in research programs on cognitive, self-organizing and adaptive systems.

The several active and expanding programs now underway were developed from—but are not limited in scope by—the earlier conception and development of perceptrons at this not-for-profit research organization. Current analytical and experimental work includes pattern recognition problems such as those encountered in photo interpretation, target classification, and speech recognition.

In the past we have found that electrical engineers, mathematicians, and psychologists with training and/or experience in such areas as information theory, statistics, adaptive control systems, advanced programming, automata theory, brain models and learning mechanisms—frequently possess suitable capabilities and interests. We invite your application. Salaries are competitive with offerings of private industry, working conditions are excellent, and outstanding talent is appropriately rewarded. Contact A. P. Rentschler, Cornell Aeronautical Laboratory, Inc., 4455 Genesee Street, Buffalo 21, N.Y.

CREATIVE ENGINEER

Nation's leading manufacturer of high speed solid state counting, timing and frequency measuring instrumentation seeks imaginative young engineer to design and develop digital and pulse instruments and systems. Outstanding opportunity for technical growth and advancement.

One to two years' experience in transistor application of digital and pulse techniques plus BSEE or equivalent are required. Send resume to: Personnel Manager, Computer Measurements Company, 12970 Bradley Avenue, San Fernando, California.

(Continued on page 104A)





THE EDGE OF SPACE IS IN ST. LOUIS

Years before McDonnell space vehicles reach the testing centers at Canaveral, designs are subjected to the severe environment existing at the edge of space. At McDonnell's Hypervelocity Impulse Tunnel in St. Louis the combined electrical impulse power of the Grand Coulee and Hoover Dams breaks loose into the confines of a cannon-like funnel and subjects space vehicle models to simulated altitudes up to 60 miles, 14,000° temperatures and speeds up to Mach 27.

From McDonnell's unduplicated aerospace facilities such as this come innovations; innovations that have characterized McDonnell products through the Company's 22-year history; innovations from forward thinking engineers who seek to shape air and space vehicles to their unique environmental requirements, rather than stretch existing designs to achieve marginal success. In the development of these advanced air and space systems, opportunities exist for advanced degree physicists, scientists and electronic management engineers anxious to take broad strides across the "State of the Art" barrier. Your inquiry is invited.

Write R. F. Kaletta, Engineering Employment
McDonnell Aircraft, St. Louis, Mo.

MCDONNELL

Phantom II and F-101 Fighter and Attack Aircraft • Project Mercury and Aeroballistic Spacecraft • Talos Airframes and Propulsion Systems • Quail Decoy Missiles • Rotorcraft • Electronics Systems • Automation

MCDONNELL AIRCRAFT • ST. LOUIS

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

ADVANCED SOLID STATE RESEARCH & DEVELOPMENT

Senior scientists and engineers are needed to fill new positions in our rapidly expanding research and development laboratories near San Francisco. Our broadening interests have created challenging positions for individuals with significant backgrounds in the following fields:

SURFACE PHYSICS AND CHEMISTRY
ELECTROCHEMISTRY
ELECTRON MICROSCOPY
MAGNETIC THIN FILMS
EVAPORATED CIRCUITRY
SEMICONDUCTOR MATERIALS
ELECTRO-OPTICS
ADVANCED CIRCUIT DEVELOPMENT
MICROWAVE PHYSICS

A Ph.D. Degree or commensurate experience is especially desirable.

Applicants are invited to send detailed resumes, including salary history and requirements, to Mr. Donald Palmer. Palo Alto interviews for qualified applicants will be arranged from anywhere in the United States. All inquiries strictly confidential and acknowledged promptly. All qualified applicants will be considered regardless of race, creed, color or national origin.

FAIRCHILD
SEMICONDUCTOR
844 CHARLESTON ROAD • PALO ALTO, CALIFORNIA

DIRECTOR—DEVICE DEVELOPMENT LABORATORY

This is a new position and will involve the establishment of a group concerned with device development in the electronic component area. Integrated circuit development, molecular electronic circuitry, and new product development will be included in the scope of this laboratory. Applicants should have experience in directing technical personnel in development work. Advanced degree in physics or electrical engineering with circuit and solid state physics background required.

Experience and qualification summaries should be sent to: Dr. D. G. Wilson, Vice President Research and Engineering.

P. R. MALLORY & CO., INC.
3029 E. Washington Street
Indianapolis, Indiana
Equal opportunity employer

NCR

National

MILITARY ELECTRONICS

AERO/SPACE PROJECTS

ADVANCED DEVELOPMENT PLANNING

Continued growth in the Research and Development program of The National Cash Register Company has created senior level openings in our Military Development Planning Group. Particular areas of interest are:

NAVIGATION AND GUIDANCE SYSTEMS ■ HUMAN ENGINEERING OF CONTROLS AND DISPLAYS ■ DIGITAL COMPUTER DEVELOPMENT ■ MICROWAVE EQUIPMENT DEVELOPMENT ■ ELECTRO-OPTICAL DEVICE DEVELOPMENT

All positions require a minimum of six years' experience in military research and development activity and an M.S. or Ph.D. degree in Electrical Engineering or Physics.

All qualified applicants will be considered regardless of race, creed, color, or national origin. Replies to this ad should be addressed to:

T. F. Wade. Technical Placement, The National Cash Register Company, Main and K Streets, Dayton 9, Ohio.



Creative minds

thrive best

where the climate

is best

Lockheed-California Company proves this every day. For nowhere do Scientists and Engineers find a more creative, more stimulating, more academic climate.

In this environment Scientists and Engineers are encouraged to try the untried; to express new ideas; to experiment and explore. And in so doing, win recognition and reward.

Small wonder Lockheed's future in *Spacecraft and Aircraft* is brighter than ever before!

Scientists and Engineers of initiative and talent will find it worthwhile to examine immediate openings in: Aerodynamics; thermodynamics; dynamics; electronic research, servosystems; electronic systems; physics (theoretical, infrared, plasma, high energy, solid state, optics); electrical and electronic designers; structural design (wing, empennage, fuselage).

Write today to Mr. E. W. Des Lauriers, Manager Professional Placement Staff, Dept. 1811, 2402 N. Hollywood Way, Burbank, California. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin. U.S. citizenship or existing Department of Defense industrial security clearance required.

LOCKHEED·CALIFORNIA CO.

A DIVISION OF LOCKHEED AIRCRAFT CORPORATION

at MOTOROLA in PHOENIX:

Beyond a shadow of a doubt

Are *you* beginning to have doubts about achieving the professional goals you set for yourself? Fretting over the lack of opportunity for growth in your present job? If you are, this will interest you: Our philosophy at Motorola is to select engineers and scientists with extreme care. Then we assign them to a Project Group – composed of men whose combined experience and talents cover a broad spectrum. To the group we give challenging state of the art assignments – and the technological tools to solve the problems. By thus affording our professional personnel maximum opportunities for individual growth and achievement, we are convinced – beyond a shadow of a doubt – that we strengthen our *own* ability to maintain leadership in the field of military electronics.

Immediate Opportunities

- Systems Test Equipment Design
- Communications and Navigation
- Systems Analysis and Preliminary Design
- Missile and Space Guidance and Control
- Digital Circuitry Design
- Microwave and Radar
- Reliability and Components
- Solid State Devices

All qualified applicants will receive consideration for employment without regard for race, creed, color, or national origin.

Write Phil Nienstedt (Dept. 1101)

MOTOROLA

MILITARY ELECTRONICS DIVISION, WESTERN CENTER

P. O. Box 1417, Scottsdale, Arizona

Motorola also offers opportunities at
Chicago, Illinois, and at Culver City and Riverside, California

Positions Open

(Continued from page 100A)

PRODUCTION MANAGER—ELECTRONIC EQUIPMENT

Require a man with at least 10 years experience in direct management of male and female assemblers, wiremen and testers, working on both military and commercial electronic equipment.

Must be familiar with military specifications for workmanship and know cost cutting techniques. Should be experienced in estimating labor hours and maintaining budgeted hours via strict production control.

This man will run the entire wiring and assembly operation (up to 100 people) and will be a part of the top management team. Salary open. Contact George W. Fellendorf, President, Planetronics, Inc., Easton, Pennsylvania.

TECHNICAL WRITER

Technical Writer to work with scientific, engineering and public relations personnel. BS in engineering or physics. Nuclear experience desirable. Send resume to Mgr. of Employment, General Atomic Div., General Dynamics Corp., P.O. Box 608, San Diego 12, Calif.

ASSISTANT PROFESSOR

Ph.D.s required with interests in circuits, electromagnetic theory or controls, in expanding Graduate and Undergraduate School. Applications from abroad invited. Apply to Chairman, Department of Electrical Engineering, Villanova University, Villanova, Pa., U. S. A.

(Continued on page 106A)

STANFORD RESEARCH INSTITUTE

is seeking Senior PHYSICISTS or ENGINEERS experienced in WEAPONS SYSTEMS EVALUATION to:

—Analyze operational capability of proposed weapons systems to provide technical support to R&D planners.

—Examine technological and environmental implications upon over-all systems capability.

A degree in Physics or Engineering is required with preference given to those having advanced degrees. In addition, a minimum of 3-5 years of systems experience is desired. Emphasis is placed on a willingness to become familiar with a wide range of technological areas to evaluate their implications upon systems performance.

Please send resume to: R. E. Ditmore
Stanford Research Institute
Menlo Park, California

(An equal opportunity employer)

ENGINEERS & SCIENTISTS:

One way to measure the challenge of a long-term assignment: Examine the program's mission.

MORE THAN 27 MILLION CUBIC MILES OF AIRSPACE MANAGEMENT!*

If you have been seeking professional challenge of this magnitude, and your experience is in any of the areas listed, we urge you to get in touch with us.

COMMUNICATION SYSTEMS
OPERATIONS ANALYSIS
SYSTEM EQUIPMENT ANALYSIS
WEAPONS INTEGRATION
APPLIED MATHEMATICS
TELECOMMUNICATIONS SYSTEMS DESIGN
PROGRAMMING ANALYSIS
ENGINEERING WRITING
ANTENNA & MICROWAVE COMPONENTS
EQUIPMENT EVALUATION
INFORMATION PROCESSING & DISPLAY SYSTEMS

*Using the hypothetical example of a 412-L system covering Australia alone, a rough approximation of the airspace to be managed may be arrived at by multiplying the continent's area (roughly, 2.97 million miles) by the 9.4 miles of altitude within easy reach of today's aircraft.

In concept, 412-L is an electronic air weapons control system providing *universal* air space management – outside the continental United States.

It will consist of a closely coordinated network of data acquisition stations, data processing and display centers and weapon bases. It provides the tools for effective and flexible airspace management – continent-wide or in single-point defense. Vital detection and tracking information is supplied automatically to human decision-makers within seconds. Effective direction of both manned and unmanned weapons, including return of manned aircraft to base, is a system function.

Managing the over-all 412-L program is the task of General Electric's weapon system management team, under the direction of the U.S. Air Force's Electronic Supporting System Project Office. The Air Force and G.E. direct the 412-L program from system concept and development, through the buying, producing, installation and checkout of complete operating equipments.

Write in strict confidence to Mr. P. W. Christos, Div. 53-MK, DEFENSE SYSTEMS DEPARTMENT, General Electric Company, Northern Lights Office Building – Syracuse, New York

DSD DEFENSE SYSTEMS DEPARTMENT
A Department of the Defense Electronics Division

An Equal Opportunity Employer

GENERAL ELECTRIC

ENGINEERS

NOW—CHOOSE YOUR ASSIGNMENT
AND LOCATION THROUGH OUR
NATION-WIDE PLACEMENT SERVICE
SALARIES $9,000 to $20,000

We can offer you a large selection of diversified positions with America's foremost electronic organizations WITH NO COST TO YOU.

SOME POSITIONS FOR RESIDENT NON-CITIZENS AND CANADIANS

WHAT WE DO FOR YOU—

Take all the work from you—no need for you to write to five or six companies, fill out applications for each one, only to find there is no job that interests you. We do all that for you, find the job that you want—in the location you want—we work with over 250 companies—all over the country.

ALL WE ASK YOU TO DO—

Send us 3 complete resumes, telling us your present and desired salary; the kind of work you want and where you would like to live. That is all you have to do!

THEN YOU—

Wait to hear from us or our clients. There is no need to write directly to any companies, as we do all that for you and at absolutely NO COST TO YOU!

Engineering managers, systems, projects, and design and development engineers:

INDICATE YOUR AREAS OF INTEREST

- ☐ Transmitters
- ☐ Servos
- ☐ Displays
- ☐ Satellite Tracking
- ☐ Weapon Systems Analysis
- ☐ Antennas
- ☐ Receivers
- ☐ Analog and Digital Devices
- ☐ Radar Techniques
- ☐ Logic Design
- ☐ IF Devices
- ☐ Reliability
- ☐ Microwave
- ☐ Engineering Reports
- ☐ Structures
- ☐ Precision Mechanisms

A National Electronic Placement Service Established in 1937. You are assured of prompt and completely confidential service by forwarding three resumes to HARRY L. BRISK (Member IRE)

APS Accredited Personnel Service

Employment Counselors Since 1937

Department A

12 South 12th St., Philadelphia 7, Penna. WAlnut 2-4460

Positions Open

(Continued from page 104A)

ASSISTANT or ASSOCIATE PROFESSOR

Assistant or Associate Professor with Ph.D. in Electrical Engineering or Physics. Interest in Electronics, Microwaves, Solid State, Circuit Theory, or Computers. Active research and graduate program with opportunities for outside consulting. May start February 1 or September 1, 1962. Send resume to W. P. Smith, Chairman Electrical Engineering Department, University of Kansas, Lawrence, Kansas.

CRITICAL VACANCIES AT GRIFFISS AIR FORCE BASE, ROME, N. Y.

Electronic Engineer	GS-7	$6345 pa.
Industrial Engineer	GS-9	$6435 pa.
Electrical Engineer	GS-9	$6435 pa.
Librarian	GS-9	$6435 pa.
Supply Comm. Mgt. Officer	GS-11	$7560 pa.
Supply Requirements Officer	GS-11	$7560 pa.
Supply Distr. Officer	GS-11	$7560 pa.
Supv. Electrical Eng.	GS-11	$7560 pa.
Industrial Engineer	GS-11	$7560 pa.
Supv. Tech. Manuals Writer (Electronics)	GS-12	$8955 pa.

Critical vacancy in the position of Electronics Engineer, GS-11, $7560 per annum. Contact Industrial Relations Department, U. S. Naval Air Station, Quonset Point, R. I.

Positions Wanted

By Armed Forces Veterans

In order to give a reasonably equal opportunity to all applicants and to avoid overcrowding of the corresponding column, the following rules have been adopted:

The IRE publishes free of charge notices of positions wanted by IRE members who are now in the Service or have received an honorable discharge. Such notices should not have more than five lines. They may be inserted only after a lapse of one month or more following a previous insertion and the maximum number of insertions is three per year. The IRE necessarily reserves the right to decline any announcement without assignment of reason.

Address replies to box number indicated, c/o IRE, 1 East 79th St., New York 21, N.Y.

ENGINEER

Communications oriented. Age 33. 15 years experience in communications and allied fields, with some broadcast experience. Desires challenging position in this field in either development or application. Feeling of accomplishment more important than salary or location. Box 3952 W.

SALES ENGINEER

Graduate engineer experienced in promotion and sale of test equipment and power supplies to OEM and Government Agencies, set up and supervision of reps. Locate anywhere for challenging position. Box 3953 W.

(Continued on page 108A)

does

$$X^n + Y^n = Z^n$$

?

Pierre de Fermat's last theorem states that the above equation has no solutions in which x, y, and z are positive whole numbers if "n" is a whole number greater than two. Mathematicians have yet to prove him wrong.

But their attempts to prove the theorem (or conjecture, since it *hasn't* been proved) have produced some of the most revolutionary concepts in modern algebra and number theory!

Questions are what answers are made of. Questions about our universe, for example. What is the Moon made of? Is there life on other planets? The answers are coming from Cal Tech's Jet Propulsion Laboratory for the National Aeronautics and Space Administration.

JPL scientists and engineers are supervising the design of spacecraft and their instruments to be sent to the Moon and planets. Ranger, Surveyor, Mariner. Some day, they'll be remembered as our first steps into space.

Today, they're a job to do. And a fascinating job at that. If you'd like to put your experience to work on this kind of a job, maybe JPL is your kind of place. Write to us and find out. It never hurts to ask questions.

JET PROPULSION LABORATORY
4804 OAK GROVE DRIVE, PASADENA, CALIFORNIA
Operated by California Institute of Technology for the National Aeronautics & Space Administration

All qualified applicants will receive consideration for employment without regard to race, creed or national origin/U.S. citizenship or current security clearance required.

How Sanders

meets rising need for design simplification of sophisticated electronic equipments

New Beam-Forming Matrix for Electronic Scanning at Microwave Frequencies

This new Sanders development drastically reduces the astronomical number of components required by conventionally designed antennas. For instance, a 64 x 64 array requiring almost half a million 3-port dividers needs less than 25,000 hybrids with Sanders' new techniques. Accompanying diagrams illustrate radiation pattern and eight-element, eight beam matrix, formed by TRI-PLATE® components, a Sanders' first dating back to 1952.



Equally Challenging Assignments
Open to Engineers
at **Sanders** in Diverse Fields Such as:

Phased Array Radar
Pulse Doppler Radar Systems
Space and Communications Systems

Specific background required in
SYSTEMS DESIGN • TRANSISTOR CIRCUIT DESIGN
RECEIVER DESIGN • TRANSMITTER DESIGN

This phenomenal growth company—up from 11 men to over 2000 in 10 years—today has a backlog of over $90 million in diversified R&D and production contracts. Concentration on bold technical innovations rather than marginal improvements is the dynamic force behind this growth. If you believe your career will flourish in a creative atmosphere that favors the individual contributor, send a resume now to R. W. McCarthy.

All qualified applicants will be considered without regard to race, creed, color or national origin

® reg. U. S. trademark

SANDERS ASSOCIATES, INC.

(in the New Hampshire hills about an hour from downtown Boston) **NASHUA, NEW HAMPSHIRE**

RESEARCH ENGINEERS AND PHYSICISTS

UNUSUAL OPPORTUNITIES FOR PROFESSIONAL CAREERS.
CHALLENGING THEORETICAL PROBLEMS IN:

- **Theory of Communications**
- **Self-Adaptive Systems**
- **Satellite Systems Studies**
- **Nuclear Weapons Effects**
- **Space Physics**
- **Operations Research**

- Owned and Managed by Employee-Scientists
- Southwest Climate • Low Population Density
- Wide Range of Benefits Including Profit Sharing
- Emphasis Placed on Theoretical Concepts
- No Hardware Development • Advanced Degree Desirable

ADDRESS INQUIRIES TO:

THE Dikewood CORPORATION

4805 Menaul Blvd. N.E. **Albuquerque, N.M.**

Positions Wanted

By Armed Forces Veterans

(Continued from page 106A)

PROFESSOR

Professor of Electrical Engineering. Age 38; Ph.D. 15 years teaching and industrial experience, research, publications. Desires challenging position in education or industry. Box 3954 W.

BUSINESS TRAINEE

B.E.E., very high score on the admission test for graduate study in business. Would like Business Trainee position. Desires general business experience and training program or an area in which I can obtain Master's degree in business. Box 3955 W.

ELECTRONICS TECHNICIAN

Electronics Technician desires position in Western Europe. Single, 35. 11 years experience communications, navigation, avionics (military-commercial). 2 years field engineer, radar, College graduate RCA Institutes. Resume upon request. Box 3956 W.

SALES REPRESENTATIVE

Competent Electronics Engineer with extensive sales experience seeks to represent good component lines and equipments; thoroughly experienced in microwaves as well as all lower frequencies down to DC. Prefer Metropolitan New York area including Long Island and New Jersey, and/or export franchise, Master's Degree, age 37, married. Excellent financial backing. I offer rapid growth in sales by providing engineering consultation services and fast liaison as your man on

(Continued on page 110A)

ELECTROMAGNETIC COMPATIBILITY ANALYSIS

Here is your opportunity for professional growth in a challenging and extremely interesting field, as a member of an outstanding and stimulating scientific team. Armour Research Foundation, specialist in electronic interference evaluation, is now expanding its facilities and staff requirements in the area of Electromagnetic Compatibility Analysis. We are looking for qualified electronic engineers at all levels (B.S. through Ph.D.) for research and applied studies concerned with system analysis and performance prediction. Immediate openings are available at either our Chicago laboratories or at ARF's Electromagnetic Compatibility Analysis Center in Annapolis, Maryland for individuals with experience in one or more of the following fields . . .

RADAR AND COMMUNICATION SYSTEM ANALYSIS

RADAR MEASUREMENT TECHNIQUES

PROPAGATION ANALYSIS

Staff members receive attractive salaries, up to four weeks vacation, generous insurance and retirement benefits and tuition free graduate study. All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin. Please reply in confidence to Mr. S. M. Ream.

ARMOUR RESEARCH FOUNDATION

Electromagnetic Compatibility Analysis Center, NEES Annapolis, Maryland

An Invitation to • • •

PHYSICISTS
MATHEMATICIANS
AND ENGINEERS

from **= M.I.T.**

The Laboratory's staff of over 1000 under the direction of Dr. C. Stark Draper is engaged in the conception and perfection of completely automatic control systems for the flight and guidance of missiles and space vehicles. Its achievements include the Navy Mark 14 Gunsight, the Air Force A-1 Gunsight, Hermetic Integrating Gyros (HIG), and the Ship Inertial Navigation System (SINS). The Laboratory developed basic theory, components and systems for the Air Force THOR and, later, the TITAN missile. Other accomplishments include the Navy's POLARIS Guidance System.

Recently, the Instrumentation Laboratory was selected by NASA to develop the guidance navigation system for the moon space craft project, APOLLO.

Research and Development opportunities exist in:

- ANALYSIS OF SYSTEMS AND COMPONENTS
- HIGH PERFORMANCE SERVOMECHANISMS
- POWER SUPPLIES AND MAGNETIC AMPLIFIERS
- DIGITAL AND ANALOG COMPUTERS
- ELECTRO-MECHANICAL COMPONENTS
- TRANSISTOR CIRCUITRY AND PULSE CIRCUITRY
- RESEARCH, DESIGN AND EVALUATION OF GYROSCOPE INSTRUMENTS
- COMPUTER PROGRAMMING AND SIMULATOR STUDIES
- OPTICS, ASTRONAUTICS AND MANY OTHER AREAS

CALL OR WRITE HOWARD P. MILLER, PERSONNEL OFFICER

INSTRUMENTATION LABORATORY
MASSACHUSETTS INSTITUTE OF TECHNOLOGY
68 ALBANY STREET Bldg. 11-P ● CAMBRIDGE 39, MASS.
UNIVERSITY 4-6900, EXT. 3544

• Graduate courses may be taken while earning full pay.

"An equal opportunity employer"

JOIN ACF ELECTRONICS

. . . a company on the move!

NEW CAREER POSITIONS CREATED IN SUBURBAN WASHINGTON, D.C. & NEW YORK

Challenging developments are taking place at ACF Electronics!

We are expanding our efforts along the entire electronics front . . . in equipments and systems . . . underseas, on ground, in the air, and in space . . . in research, design and development.

It pays to join a company on the move. We offer talented Engineers on all levels an opportunity to grow with us; promotions are based strictly on individual merit and you are given increased responsibilities as soon as you are ready to assume them. The assignments are challenging and require from the practitioner state-of-the-art level contributions.

Career appointments are available immediately in these fields:

DIGITAL TECHNIQUES
SIMULATOR SYSTEMS
IONOSPHERIC PROPAGATION
HF COMMUNICATIONS
MICROWAVE COMPONENTS & SYSTEMS
INFRARED DEVICES
ASW SYSTEMS
RADAR BEACONS & DISPLAYS
FIELD ENGINEERING

Our modern facilities are located in residential suburbs of Washington, D. C. and New York City, affording you a choice of city, suburban or country living. Houses and apartments in all price ranges are readily available. Advanced study under tuition refund may be conducted at several nearby universities.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

For details, contact:
A.C. Sugalski
Mgr., Professional Staffing, Dept. A-1
(at our Riverdale facility)

ACF ELECTRONICS
DIVISION

ACF INDUSTRIES

Riverdale, Md. • Hyattsvile, Md. • Paramus, N.J.

Positions Wanted

By Armed Forces Veterans

(Continued from page 108A)

the scene, in contrast to the nontechnical "salesman" who always answers with the "I don't know" and takes up your time with needless questions. Why take less when you can get the best! If your domestic markets are already covered, let me handle your exports and take your sales way up; I am that type of Engineer that knows the business side as well as the technical side, my financial assets prove it. Box 3957 W.

FIELD SERVICE ENGINEER

Age 32; 10 years field service experience with airborne radio and radar systems, fire control, analog computers and test equipments, FCC First Phone. Member IRE, CREI Grad. Desires Field Service position with progressive company. Box 3958 W.

ACADEMIC POSITION

B.S. and M.S. in E.E.; present position Assistant Professor; 7 years teaching experience and 1 year training in Guided Missiles. Desires teaching position in Fall of 1962 with opportunity for graduate study. Box 3961 W.

MARKETING MANAGER

Outstanding record in sales, sales management and training, sales promotion and merchandising. Engineering background. Capable of taking on responsibility for the introduction of new products or the growth of present products. Primary interest and experience in communications and closed circuit TV. Age 39. Resume available. Box 3966 W.

(Continued on page 112A)

ARIZONA
Phoenix

"Opportunity & Ideal Living"

GOODYEAR AIRCRAFT CORPORATION
Arizona Division

ELECTRONIC CIRCUITRY

Radar Circuitry, Data Processing, Analog Computer Circuitry, Control Systems.

THEORETICAL PHYSICIST

Background in Electromagnetic Theory and Plasma Physics, Ph.D. Preferred.

EXPERIMENTAL PHYSICIST

Background in Physical Optics, Classical Mechanics, Microwaves, and Information Theory or Quantum Mechanics and Statistical Mechanics, Ph.D. Preferred.

ELECTRONIC PACKAGING

"All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin."

Request Application or Send Resume to:

B. A. Watts, Engineering Personnel
Goodyear Aircraft Corp.
Litchfield Park, Arizona

Similar Positions at Goodyear Aircraft Corporation, Akron, Ohio



THE *EXCEPTIONAL* **MAN**

when the position you wish to fill is vital to your organization . . .

when the man you seek requires all the attributes of leadership . . . plus the ability to make significant technical contributions to the work for which he will be responsible . . .

when you need a man who can command the respect of his associates and subordinates because of his intimate knowledge of and first-hand experience in their fields . . .

when you need a man who is well educated and trained in the specialized fields of knowledge you require . . .

you need The Exceptional Man.

Let us locate him for you.

Charles A. Binswanger **ASSOCIATES**
INCORPORATED

EXECUTIVE SEARCH SPECIALISTS
44 FRANKLIN BUILDING • BALTIMORE 2, MD. • PLAZA 2-5013

Philco WDL has immediate and challenging engineering positions open in Discoverer, Midas and Advent programs in these categories:

Data systems engineering

Technical Staff — communications and data systems

Systems test planning

Systems reliability analysis

Design Engineering — surface and vehicle electronics

Human factors and operations analysis

Field tracking station activation

Tracking and control systems design

Logistics and station support

And others

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin; U. S. citizenship or current transferable Department of Defense clearance required.

if your future is for growing...

People at Philco's Western Development Laboratories are proud of their achievements, secure in the steady growth of their company, enthusiastic about their future.

In just four years, Philco WDL has expanded from a staff of 18 to more than 2,000. At the end of this year WDL will open a new 250,000-square-foot facility which will accommodate a continually expanding complement of engineers, scientists and supporting staff members.

Philco WDL, the space organization which designed and built the Courier satellite, conducts an ever-growing development program in tracking, satellite instrumentation, communications, data processing and command—moving hand in hand with the federal government in space exploration and space age defense.

Your growth with a growing company, ideal living on the Northern California Peninsula, professional and monetary advancement commensurate with your own ability—these are some of the advantages and satisfactions of working at Philco Western Development Laboratories.

If yours is one of the fields listed at the left, write today to Mr. W. E. Daly, in confidence, of course, Department R-11.

This new 250,000-square-foot addition to Philco Western Development Labs will open by the end of the year.



PHILCO®
Famous for Quality the World Over

WESTERN DEVELOPMENT LABORATORIES
3875 Fabian Way, Palo Alto, California

PRODUCT AND PROPOSAL ENGINEERS

- Computer Control
- PCM Telemetry
- Automatic Checkout & Monitoring
- Analog to Digital Conversion
- Electro-medical Instrumentation

EXCELLENT SALARIES . . . . . STOCK OPTIONS

Applicants must have design or proposal experience in data acquisition systems, computers, linkages or telemetry.

Join our dynamic staff of 600 employees by writing:

IVAN P. SAMUELS

Epsco incorporated

275 Massachusetts Avenue
Cambridge, Massachusetts

"An equal opportunities employer"

SCIENTISTS ENGINEERS

CALIFORNIA

offers you and your family

- A world center of the electronic industry for CAREER ADVANCEMENT
- The High Sierra and the Pacific Ocean for RECREATION
- Some of the nation's finest public schools for your CHILDREN
- World Famous Universities for ADVANCED STUDY
- MAJOR CULTURAL CENTERS

while living in such places as

Exciting San Francisco
Fabulous Southern California
Cultural Palo Alto

companies pay interview, relocation and agency expenses

submit resume in confidence to:

PROFESSIONAL & TECHNICAL RECRUITING ASSOCIATES
(a division of the
Permanent Employment Agency)
825 San Antonio Rd.
Palo Alto, Calif.

Positions Wanted

By Armed Forces Veterans

(Continued from page 110A)

ELECTRICAL ENGINEER

Professional E.E. degree (MIT). Four years experience in digital control system development, circuit design, logic design and programming. Speaks 4 foreign languages. U.S. Citizen. Seeks challenging position in U.S. or Europe. Box 3967 W.

HAWAII

Communications Systems Engineer. Data transmission, HF, VHF, UHF, microwave, common carrier; SSB, MUX, tropo and iono scatter, mobile, CCTV; Systems planning, design, procurement, installation, operation. Recent experience in high speed data transmission. Desires position in or leading to assignment in Hawaii. Available about first of 1962. Box 3968 W.

ELECTRONICS TECHNICIAN

November Graduate RCA Institute V7 course, age 29, married. Four years USAF ground radio maintenance. Experience repairing and maintaining of VHF, HF, UHF, DF, carrier bay equipment, field telephones, and remote lines. Have first-class radio telephone license, also 80 credits toward EE degree. Prefer New York area. Box 3969 W.

V.P. or GENERAL MANAGER

Age 42, BSEE, 24 years "extremely" diversified engineering, manufacturing and management experience with 5 major U.S. companies, in telecommunications, test ranges, aerial navigation and intelligence equipments and systems. Presently management consultant but will consider major responsibilities with smaller company or strictly autonomous division of larger one. East Coast (suburban area) preferred. Box 3970 W.

LIBRARIAN

MS (Library) 9 years general, aeronautical, and electronic library experience. Familiar Government documents. Favor southern LI or midtown NY City. Box 3971 W.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 96A)

Pre-Programming Patchboard



Vector Electronic Co., 1100 Flower St., Glendale 1, Calif., announces the availability of their new Pre-Programming

(Continued on page 114A)

ENGINEERS

Enjoy Maximum Responsibility

PROBE NEW AREAS

in telemetry and data processing

Planned growth and diversification at Electro-Mechanical Research, Inc. (e.m.r) enable men with imagination to exercise the full scope of their professional skills. Opportunity to probe new areas is insured by initiating within the company the major portion of all research. Current projects include development of the test instrumentation subsystem for Dyna-Soar space glider.

ELECTRONIC SYSTEM DESIGN ENGINEERS
Must have experience, state-of-the-art knowledge and a keen interest in the whole systems field, from initial concept through detail design and prototype development. Includes such areas as magnetics and solid state circuitry, RF transmitters and semiconductor applications, DC through UHF.

Please direct inquiries in confidence to
ROLAND E. HOOD, JR.
Personnel Manager,
Systems Division

e·m·r

electro-mechanical research, inc.

P. O. Box 3041-T, Sarasota, Florida

exploration . . .
manufacture/reliability

Qualified applicants considered without regard to race, creed, color or national origin.



15 SECONDS
ON THE SURFACE OF THE SUN

Cornell Aeronautical Laboratory has devised a new facility, the Wave Superheater*, which simulates, for approximately full-scale models, the extreme conditions of hypersonic flight. Temperatures of roughly 9000°R, suitable for research on many hypersonic problems, can be generated if the test gas is air, and approximately 17,000°R if the test gas is argon. Test times of 15 seconds at speeds up to Mach 15 can be obtained in this continuously operating shock tube device. The large, 40-square-foot test section permits simultaneous testing over a much greater range of test conditions than can be accommodated in any existing facility. Such composite testing gives the engineer a means of checking aerophysical and aerostructural interactions.

For this and other advanced research programs we need capable engineers. Attractive compensation, freedom to select the type of research suited to your interests and background, and a climate conducive to rapid professional advancement are among the many advantages available to you here. Mail the coupon for details.

*Now being developed under ARPA sponsorship

CORNELL AERONAUTICAL LABORATORY, INC.
OF CORNELL UNIVERSITY

J. P. RENTSCHLER
CORNELL AERONAUTICAL LABORATORY, INC.
Buffalo 21, New York

Please send me your brochure, "A Community of Science."

Name _____

Street _____

City _____ Zone _____ State _____

☐ Please include employment information.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

APL OFFERS

UNUSUAL OPPORTUNITIES

IN

MICROELECTRONICS

A new group of scientists and engineers at the Applied Physics Laboratory of The Johns Hopkins University are performing highly advanced research and development work in solid state microelectronics. The objective: to explore new techniques and methods to produce reliable microelectronic functions for wide application in missiles, satellites, radar, adaptive computers, etc.

SEMI-CONDUCTOR DEVICES, PROTOTYPE PRODUCTION *An opening with exciting possibilities. You will establish a semi-conductor laboratory and work freely within broad policy directives. Funds have been allocated for the laboratory. Duties include making integrated semiconductor electronic circuits on a laboratory basis. B.S. plus three years of experience in this field desirable.*

CIRCUIT-SYSTEMS ANALYSIS *Position involves microelectronic system and circuit analysis and design, as well as maintaining close working relationship with prototype fabricator and user groups. Applicant must have a B.S. in electronics or physics and approximately three years of experience in system and/or circuit analysis.*

SOLID STATE THEORY *The position requires a Ph.D. with two or more years of experience in solid state theory. You will apply the principles of dielectrics, conducting materials, and semi-conductors to the theory of the electrical properties of solids. This is a new area of activity with unusual opportunities for rapid personal advancement.*

For details about these positions, direct your inquiry to:

Professional Staff Appointments

The Applied Physics Laboratory
The Johns Hopkins University

8603 Georgia Avenue, Silver Spring, Maryland
(Suburb of Washington, D. C.)

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 112A)

Patchboards. The equipment has wide application in any situation where flexible program control is required, such as in digital and analog computers, data processing equipment, test and control equipment, and automation systems. A wide range of sizes is now available including 200, 300, 450, and 600 contacts, and multiples of 600 contacts. Special sizes can also be made to order in moderate quantities. The boards are designed so that a simple engaging lever which is operated with one hand engages the pre-programmed panel with the rear frame assembly. To permit more flexible system design, the patchboards may be mounted either vertically or horizontally.

A full complement of single and multiple conductor self-contacting type patchcords is available. Special connectors can also be provided. For more details and prices write to the factory at the above address.

Variable Frequency Power Source

A 50-watt, low-distortion variable frequency power source, with better than

(Continued on page 116A)

ELECTRONICS ENGINEERS
WITH
RADAR EXPERIENCE
Silver Springs, Maryland

Armour Research Foundation, a leading independent research organization, offers exceptional long term opportunities for experienced electronics engineers who wish to work in Silver Springs, Maryland (convenient to both Washington and Baltimore areas). The Foundation is now forming a highly competent technical group to aid in the development of an advanced radar-missile system. Present assignments involve primarily circuit design and experimental system work. Applicants must have at least a B.S. degree in Electrical Engineering with an above average academic record and several years of radar experience.

Work on this program offers exceptional opportunities for professional and personal growth. Staff members receive attractive salaries, up to four weeks vacation, generous insurance and retirement benefits, and tuition paid graduate study. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin. Please reply in confidence to Mr. S. M. Ream.

ARMOUR RESEARCH FOUNDATION
ELECTROMAGNETIC COMPATIBILITY ANALYSIS CENTER
N.E.E.S. ANNAPOLIS, MARYLAND

ROOM TO THINK...

Working at MITRE gives you the opportunity to investigate new scientific areas, and, at the same time, to become identified with projects of the utmost national urgency. The effort involves a wide range of computer-based command and control systems. You will face important and challenging problems . . . and be free to pursue them on your own. Your colleagues will be men of considerable professional stature who work in an atmosphere of intellectual freedom. This is a job for the highly talented scientist or engineer — the man with imagination, common sense, and a feel for systems. If you qualify, and if you are prepared to accept the challenge of command and control systems, MITRE needs you now. Write, in confidence, to Vice President — Technical Operations. The MITRE Corporation. Post Office Box 208, Dept. MY4, Bedford, Massachusetts.

Appointments are now being made in the following areas:

- Operations Research
- System Analysis
- Communications
- Econometrics
- Economics
- Computer Technology
- Human Factors
- Advanced System Design
- Mathematics
- Radar Systems and Techniques
- Air Traffic Control System Development
- Antenna Design — Microwave Components

Formed under the sponsorship of the Massachusetts Institute of Technology and now serving as Technical Advisor to the United States Air Force Electronic Systems Division.

An equal opportunity employer

THE MITRE CORPORATION

Ranking members of MITRE's technical staff will be conducting interviews during Nov. and Dec. in the following cities:
SAN FRANCISCO — Nov. 9, 10, 11 • SEATTLE — Nov. 13, 14, 15 • EULESS, TEXAS — Nov. 16, 17, 18 • WASHINGTON, D.C. — Dec. 4, 5, 6, 7.

Current Openings with

GENERAL DYNAMICS | ELECTRONICS

SINGLE SIDEBAND COMMUNICATIONS

Requires 6 to 10 years experience, with emphasis on high power vacuum tube amplifier design. Also desirable is a background in single sideband linear amplifier techniques.

LOGIC DESIGN

To participate in system design of all-electronic communication switching systems. Will be responsible for solving circuit problems from concept and interpretation of laboratory test results to final approved drawings. Requires BSEE with 5 to 10 years experience in telecommunications or other switching field.

RELIABILITY

1/ To set up a reliability group in military electronics. Requires BSEE with 10 years experience in electronics engineering, including design, and a minimum of 3 years in reliability.

2/ To make reliability analyses of circuits and components for commercial electronic telecommunications. Requires BSEE with 5 years experience in engineering design and 3 years in reliability.

ANTI-SUBMARINE WARFARE

To supervise receiver section of ASW Laboratory. Requires BSEE with over 5 years experience including RF and audio circuit design, ASW communications problems and signal processing.

ELECTRONIC SWITCHING

For development work in electronic telephone switching and other areas of digital logic, storage and control. Requires BS in EE or Physics with several years experience and a sound knowledge of solid state.

Please address resumes to M. J. Downey.

GENERAL DYNAMICS

GENERAL DYNAMICS | ELECTRONICS

1476 N. Goodman St., Rochester 3, New York

All qualified applicants will be considered for employment without regard to race, creed, color or national origin.

MANAGEMENT

Continued expansion by the Automatic Equipment Division has created two outstanding openings. This division is located in Northwest Chicago and is a major new industrial machinery division. These positions offer an extreme challenge to those who are resourceful and who can implement their creative ideas into action.

MANAGER—ENGINEERING

Graduate Electrical or Mechanical Engineer, preferably with graduate or multiple degrees, to be responsible for all engineering activity including development design and application engineering for a newly organized product department. Must have at least 10 years management experience with overall project level responsibility for the design and development of highly engineered systems. Should have a strong background in several of the following areas: logic circuitry, servo networks, hydraulic servo controls, tape recorders. Must also be experienced in the design of practical hardware for such systems, and should have demonstrated leadership and managerial capabilities.

CHIEF SYSTEMS ENGINEERING

Graduate Electrical Engineer to assume responsibility for highly engineered systems comprising logic circuitry, servo networks, hydraulic servo actuators, tape recorders and similar sub-systems. Will work in liaison capacity with development engineers, manufacturing, customers and field service groups. MS in electrical engineering desired but most important is demonstrated ability to analyze and trouble-shoot hydraulic servo controlled-electro mechanical systems.

AMF, a leader in the manufacture of automated machinery, offers an exceptional opportunity for personal and professional growth.

These positions offer many excellent employee benefits and a salary commensurate with experience. Please reply in confidence to:

Mr. R. B. Martin
Personnel Manager

AMERICAN MACHINE & FOUNDRY COMPANY
Automatic Equipment Division
2100 East Lunt Avenue
Elk Grove Village, Illinois

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 114A)

0.01% amplitude stability and 0.1% harmonic distortion produced by **Krohn-Hite Corp.,** 580 Massachusetts Ave., Cambridge 39, Mass., enables users of ac voltmeters and ammeters to calibrate their own instruments.



Designated Model LDS-1500, the unit delivers continuously variable voltage from zero to 1500 volts and current from zero to 15 amperes, at any frequency between 20 and 20,000 cps.

The instrument offers nearly complete freedom from "hum bounce" or line frequency beat, less than 0.05%, when operating near line frequency or its harmonics. Amplitude change with line voltage is

(Continued on page 118A)

INFORMATION PROCESSING RESEARCH

APPLIED RESEARCH LABORATORY

Pictured above is the Applied Research Laboratory's new building which was recently occupied. The Laboratory is the central research facility for Sylvania Electronic Systems.

The Applied Research Laboratory is located in Waltham, Massachusetts, a suburb of Boston, convenient to Harvard, M.I.T., Boston University, Brandeis, Northeastern, and several other colleges and universities offering outstanding programs for advanced study and professional growth.

We should like to add to our staff qualified personnel with advanced training and creative experience in the Information Processing Research area. In particular, experience in advanced computer and data processing technology, applied mathematics and mathematical physics, statistics, statistical decision theory, speech or pattern recognition, perception and learning theory, applied linguistics and information theory is desirable. Three areas are presently of utmost importance.

(1) CHARACTER RECOGNITION – instrumentation of page and form readers, design of recognition logics for statistically distorted printing.

(2) SPEECH RECOGNITION – computer simulation and intelligibility testing of analyses of speech via expansions of series of orthonormal functions for machine recognition and bandwidth compression.

(3) PERCEPTION AND LEARNING THEORY – analysis of models of automata and human perception in learning, their experimental evaluation and ultimate instrumentation (bionics) and their applications.

Efforts are equally divided between instrumentation, experiment, and theoretical analyses.

Additional information may be obtained
by writing Dr. Donald B. Brick
Applied Research Laboratory

SYLVANIA ELECTRONIC SYSTEMS
Government Systems Management
for GENERAL TELEPHONE & ELECTRONICS

GENERAL SYSTEM

40 Sylvan Road—Room H-11—Waltham 54, Mass.

An Equal Opportunity Employer

Why don't you Talk with Westinghouse about MOLECULAR ELECTRONICS



Significant electronic break-throughs have been accomplished at Westinghouse in making complex systems with multi-function "blocks" of microscopic solids. The biggest developments are still to come and—if *you* talk to Westinghouse—you may be a part of them.

Westinghouse-Baltimore has many career opportunities in major projects in airborne, landbased and shipboard electronics.

Current opportunities include:

Electronic Countermeasures
Electronic Systems Analysis
Microwave Techniques
Infrared Detection
Pulse Circuitry
Semiconductor Circuitry
Research Design & Development
Liaison & Field Engineering

Send resume to: Mr. J. F. Caldwell, Dept. 439

Westinghouse
BALTIMORE
P. O. Box 746 Baltimore 3, Maryland
AIR ARM • ELECTRONICS • ORDNANCE

An Equal Opportunity Employer

Systems Synthesis and Management Openings with General Electric

■ The General Electric Company has new openings for Engineers whose experience and interests are systems oriented, and whose technical competence qualifies them for systems synthesis and management work. These openings are with the Heavy Military Electronics Department, focal point within the Company for the design, development, and production of some of the Nation's most advanced surface-based, ship-borne, and undersea defense systems.

■ Each job position involves the systems synthesis and management functions as applied to active and passive defense systems. Exact responsibilities will be determined individually, based on experience and technical competence. All are immediate openings.

■ **SENIOR SYSTEMS ANALYST:** Requires a BSEE, preferably with advanced degree, who is aerospace oriented. Missile airframe, undersea systems, and/or associated electronics experience would be ideal. Work involves determination of future problems, establishment of advanced systems specifications, as well as determination of optimum configurations based on utility, performance, cost, delivery.

■ **SENIOR SYSTEMS ANALYST:** Requires a BSEE, preferably with advanced degree, who is familiar with mathematical probability, system simulation, operational analysis, generalized harmonic analysis. Must be able to state systems problems mathematically, determine workable and realistic solutions.

■ **SYSTEMS SYNTHESIS:** Requires a BSEE, preferably with advanced degree, and strong analytical inclinations. Will work to solve specific systems problems through application of alternate methods, new techniques, revised concepts.

■ **DATA SYSTEMS DESIGN ENGINEER:** Requires a BSEE, preferably with advanced degree, who can design computation and data handling systems to meet specific, over-all system specifications. Must be capable of utilizing a variety of engineering resources within the Company and be of project management potential.

These are all permanent, career opportunities with unusual potential. Qualified applicants will be invited to visit Syracuse at Company expense. Relocation assistance will be provided.

■ For detailed information, write in confidence to:

Mr. Dana S. Brown, Systems Operation T-15, Heavy Military Electronics Department, General Electric Company, Court Street, Syracuse, N. Y.

Please include enough information to justify further consideration for positions of these competence and salary levels. 177-55

An Equal Opportunity Employer

GENERAL ELECTRIC

ENGINEERS

You are invited to investigate the excellent opportunities at MOLECULAR RESEARCH, INC.—W. PALM BEACH, FLA. Openings at management, staff, senior engineer and engineer level for *Industrial* and *Military* programs including:

ASW Systems	Reconnaissance System	Automation
Oceanography	Detection System	Industrial Control
Instrumentation	Radar & ECM	Microwave

Excellent ground floor opportunities with a Company with excellent financial backing and in one of the most ideal climates and locations in the country. Please write:

MOLECULAR RESEARCH, INC.
P. O. Box 1326 West Palm Beach, Florida

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 116A)

0.005%. Short-term amplitude stability is 0.01%.

A second amplifier and a phase shifting circuit, that extends the instrument's function to include calibration of wattmeters, varmeters, and power factor meters, is available.

The cabinet measures 40″ high, 22″ wide, and 19″ deep. Detailed electrical and mechanical specifications are available on request.

Narrow-Band Crystal Filters



Now available from **Midland Manufacturing Co., Division, Pacific Industries, Inc.,** 3155 Fiberglas Rd., Kansas City 15,

(Continued on page 120A)

IMPERFECT MARRIAGE?

We are not marriage counsellors, but we can give you some sound advice on how to correct an imperfect marriage. The marriage we speak of is the wedding of your talents and interests to the most compatible work available. In this we are experts with over 37 years of experience in the technical placement field. In that time, we have established a close rapport with some of the foremost organizations in science and engineering. Therefore, our prescription for an imperfect marriage of man and job is Abbott's Employment Specialists.

Positions available with salary ranges from $10,000 to $30,000. All negotiations conducted in strict confidence. All service charges paid by our client organizations.

Please direct your inquiry to:

MR. LOUIS A. KAY

ABBOTT'S

EMPLOYMENT SPECIALISTS

150 Tremont Street, Boston 11, Massachusetts
HAncock 6-8400

Do you share his reluctance to accept the accepted?

Doubt is his dogma. He questions everything, takes nothing for granted — not even his own answers.

Do you share his stubborn skepticism? Then come to Northrop, where the breadth and variety of projects give ample scope to the most determined questioner. Northrop's divisional organization makes it possible to support a broad range of programs from countermeasures systems and airborne computer design to techniques for aero-space deceleration and re-entry, and the maintenance of a total human environment in space.

Top priority, just now, goes to senior aerodynamicists and computer circuit designers. But whatever your specialization, if you're the kind of man Northrop needs, there'll always be an opening for you. Why not get in touch with us today and find out more? Just write to Northrop Corporation, Post Office Box No. 1525, Beverly Hills, California.

NORTHROP

AN EQUAL OPPORTUNITY EMPLOYER

Increased technical responsibilities in the field of range measurements have required the creation of new positions at the Lincoln Laboratory. We invite inquiries from senior members of the scientific community interested in participating with us in solving problems of the greatest urgency in the defense of the nation.

RADIO PHYSICS and ASTRONOMY

RE-ENTRY PHYSICS

PENETRATION AIDS DEVELOPMENT

TARGET IDENTIFICATION RESEARCH

SYSTEMS:
Space Surveillance
Strategic Communications
Integrated Data Networks

NEW RADAR TECHNIQUES

SYSTEM ANALYSIS

COMMUNICATIONS:
Techniques
Psychology
Theory

INFORMATION PROCESSING

SOLID STATE
Physics, Chemistry, and Metallurgy

• *A more complete description of the Laboratory's work will be sent to you upon request.*

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Research and Development
LINCOLN LABORATORY
Massachusetts Institute of Technology
BOX 16
LEXINGTON 73, MASSACHUSETTS

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 118A)

Kans., for new design is a Type FB series of six hermetically sealed, 8-crystal, narrow-band filters that provide bandwidths in the range of 2 to 30 kc @ 6 db, with a center frequency of 10.7 Mc. Each filter in the FB series is less than 2.5 cubic inches in size. They are designed to operate between −55° and +90°C, with an insertion loss of 4 db maximum and an inband ripple of 0.8 db maximum. Their specified ultimate rejection is 105 db minimum. Write for Engineering Bulletin NBS-102 detailing these stock filters.

Single Turn Trimmer Catalog Sheet

CTS Corporation, Elkhart, Ind., has just released Data Sheet 184 containing 4 dimensional drawings, comparative photo, and mechanical and electrical specifications of its new 7/16″×1/2″ economically priced single turn commercial composition trimmer potentiometer for small space printed circuit applications, CTS Series 220.

(Continued on page 122A)

to a man

in search of a dream . . .

Your future is waiting for you—and it's limitless as your imagination. Let GUILFORD—with a thousand eyes searching every opportunity — set your imagination free. All opportunities fee paid. Send your resume today.

Engrng. Mgr. $23,000
Subsystems Mktg. Mgr., E.E. $25,000

Guilford
Personnel Service
management consultants
Seven Saint Paul Street
Baltimore 2, Md.
MUlberry 5-4340

I want a "Whatcha-ma-call-it?"
It's a "thinga-ma-jig that . . . . . "

How often have you struggled to remember the name of a component or electronic item. . . . Just could not think quickly what it is called?

YOU CAN FIND IT IN THE IRE DIRECTORY!
because

(1) The IRE Directory classifies products by purpose and use.
(2) Its listings are fundamental—the way an engineer thinks.
(3) "Terminology" is cross indexed in the pink pages—condensed, simple, not mixed in with firm names.
(4) Ads face listings thus helping to identify products by actual pictures.
(5) Product code numbers reduce complex and duplicate listings, saving you "searching" time and effort.

Study it . . . save it . . . work it.

THE INSTITUTE OF RADIO ENGINEERS
1 East 79th Street, New York 21, N.Y.

Computer people will admit that when a general purpose machine is operating in an interpretive mode it may spend most of its time doing non-productive work loosely called "housekeeping" functions. There's nothing wrong with this, as long as a user is willing to sacrifice efficiency for convenience. However, there are users and users, and many of them resent having to accept penalties of any kind—for any reason. Others need to have a computer that will perform as efficiently in many different modes as it does in the characteristic mode for which it was designed. Ordinary interpretive systems simply can't do this.

■ The basic trouble stems from the fact that computers and people (not counting programmers) don't speak the same language. The user often has to "command" his machine in codes archly called pseudo-instructions. The computer can't work from pseudo-instructions, but has to translate them into logic steps that will open gates, start counters, trigger flip-flops, and otherwise cause the machine to react to the problem.

■ It is this roundabout way of doing things that gives interpretive systems their bad reputation. (Small wonder, when a routine may take an ordinary computer ten to fifteen times as long to run interpretively as it would if the computer were lucky enough to be working from instructions originally wired into its back panel!)

■ It would be nice if all instructions could be wired into the computer in exactly the form that every present and future user would possibly desire. Of course, that's just dreaming. There are always new users and new problems.

■ A practical approach is to wire in only the basic (or generic) elements of all instructions, in order to get machine efficiency—and store in the computer's memory the logic for putting together the endless varieties of instructions and routines that users inevitably think up once they get their hands on a new computer.

■ This is the approach used by Ramo-Wooldridge in the design of its "stored logic" computer. The first model in R-W's stored logic line is the AN/UYK-1, an inexpensive machine being built for the Navy for general shipboard use. To illustrate its efficiency: the AN/UYK-1 can do a 15-bit basic add in 12 microseconds; a 30-bit arithmetic sine instruction, composed from some 30 generic commands, will take about six milliseconds. With 54 types of basic command elements, most of which have 32 options, the AN/UYK-1 offers its users more than 1100 generic portions (called logands, from LOGic commANDS) from which to compose instructions. These tailor-made instructions can be used directly by the programmer to solve his problems.

■ Recent contract awards for stored logic computers have created opportunities for adventurous programmers, systems analysts and circuit design engineers interested in helping to exploit the inherent advantages of the Stored Logic concept.

■ All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Contact Mr. R. L. Eddy at

RAMO-WOOLDRIDGE

A DIVISION OF

Thompson Ramo Wooldridge Inc.

8433 FALLBROOK AVENUE, CANOGA PARK, CALIFORNIA

Planning a Strategic Move?

Many unusual opportunities are available to qualified engineers and scientists capable of assuming responsible positions with HRB-Singer. One of the country's leading R & D organizations, HRB continues to expand its research and development activities at a rate far surpassing most electronics industries. Top scientific personnel continue to make state-of-the-art advancements in the development of complete electronic systems but a constant supply of new talent is essential to the continued growth of any organization.

HRB-Singer, the acknowledged leader in the development of airborne infrared reconnaissance systems, provides extensive R & D facilities in an atmosphere conducive to professional development.

In addition to the many technical challenges, HRB provides an exceptional employee benefit package which includes Company financed graduate study at the Penn State University, free hospitalization and life insurance along with an extremely liberal vacation program.

If you are interested in learning more about career opportunities at HRB-Singer, write George H. Rimbach, Supervisor of Personnel, Dept. R-4.

HRB

HRB-SINGER, INC.

A SUBSIDIARY OF THE SINGER MANUFACTURING COMPANY

Science Park, P.O. Box 60, State College, Pa.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 120A)

Delay Filters

SEG Electronics Co., Inc., 12 Hinsdale St., Brooklyn 7, N. Y., announces the PPC series of delay-distortionless filters. They are available in low, high and band-pass versions with rather wide bandwidth and sharp roll-offs. Each PPC type of filter is designed to the particular requirements of pass band, frequency range and nature of transmitted signal.

The application of this filter series covers the entire range of data transmission and processing as well as any other application where a complex signal or group of signals must be passed without distortion due to delay of attenuation while rejecting undesirable components.

(Continued on page 124A)

DESIGNED to
FIND the creative
ENGINEER and
SCIENTIST

IN THE $10-$55,000 RANGE

Dir. Solid State Res.
Dir. Systems Res.
Character Recog.
Pulse & Digital Circ.
Computer Products Mgr.
Telemetry Dir.
HF Comm'cations
Airborne Radar Dir.
Tracking Systems
Inertial Guidance
Comm'cation Systems
Publication Engr.
Infra-Red Device
Computer Components
Vice-Pres. R & D

CROSS COUNTRY
CONSULTANTS
Personnel Search Specialists
225 E. Redwood St., Baltimore 2, Md.
LExington 9-6604

Said Svante Arrhenius: *"The change of the logarithm of a chemical reaction rate constant with respect to temperature, is inversely proportional to the square of the absolute temperature."*

The aerospace industry is searching constantly for strong, light-weight, heat-resistant materials. Finely-spun glass fiber, bonded with a plastic binder, is beginning to exhibit superior properties. Until recently the glass fiber has been far more heat-resistant than any binder.

Scientists at Lockheed Missiles & Space Company, however, have developed a compatible binder. This now makes it necessary for the glass-producing industry to evolve a glass to match its superior heat-resistance.

Comparable successes are being achieved in dozens of disciplines in which Lockheed is engaged. As Systems Manager for the DISCOVERER, MIDAS, and other satellites, and the POLARIS FBM, Lockheed probes all areas of aerospace endeavor.

Lockheed Missiles & Space Company is located on the beautiful San Francisco Peninsula, in Sunnyvale and Palo Alto, California. Why not investigate future possibilities at Lockheed? Write Research and Development Staff, Dept. M-30C, 962 West El Camino Real, Sunnyvale, California. U.S. citizenship or existing Department of Defense industrial security clearance required. An Equal Opportunity Employer.

LOCKHEED MISSILES & SPACE COMPANY

A GROUP DIVISION OF LOCKHEED AIRCRAFT CORPORATION

Systems Manager for the Navy POLARIS FBM and the Air Force AGENA Satellite in the DISCOVERER and MIDAS programs. Other current programs include SAINT, ADVENT and such NASA projects as OGO, OAO, ECHO, and NIMBUS.

SUNNYVALE, PALO ALTO, VAN NUYS, SANTA CRUZ, SANTA MARIA, CALIFORNIA • CAPE CANAVERAL, FLORIDA • HAWAII

BOSTON AREA SITE OF NEW LABORATORY FOR PHYSICAL SCIENCE

A modern and well-equipped research facility established by P. R. Mallory & Co. Inc. offers the following staff openings for scientists in *Solid State Physics, Thin Films, Materials, Metallurgy* and *Electrochemistry.*

Group Managers and *Research Scientists*—for fundamental experimented and theoretical investigations of:

Thin Films—Dielectric, magnetic, resistive and semiconductor.

Materials—Thermoelectric, semiconductors (including organics), metallurgical studies.

Electrochemistry—Fuel cells, general electrochemical phenomena.

Expressions of interest may be submitted in confidence to Dr. S. P. Wolsky, Director, Laboratory for Physical Science.

P. R. MALLORY & CO. INC.
Laboratory for Physical Science
Northwest Industrial Park
Burlington, Massachusetts

Equal Opportunity Employer

Kollsman

Continued Expansion in AEROSPACE SYSTEMS

Creates New Opportunities in Research, Development and Engineering

STAFF ENGINEERS

For creative staff engineering in air data systems, pressure sensors and transducers, optical electronic systems, digital computers and sensors, solid state physics, logical design, systems analysis and synthesis, infrared and visual scanning techniques, information theory, systems development for navigation and guidance of aircraft, missiles and space vehicles, and heat transfer analyses.

DEVELOPMENT ENGINEERS

For project engineering assignments on automatic navigation, air data and flight control systems and devices. Also assignments in ground support equipment in the above areas, as well as in our new ordnance equipment group. Experience in electromechanical/optical systems desirable.

An Equal Opportunity Employer

Please forward resume, in confidence, to Mr. Donald Svenson.

Kollsman Instrument Corporation

A Subsidiary of Standard Kollsman Industries Inc. 80-08 45th AVE., ELMHURST 73, QUEENS, NEW YORK

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 122A)

Johnson Named VP by Dunn

Leonard B. Johnson, a director and operations manager of **Dunn Engineering Corp.,** 225 O'Brien Highway, Cambridge, Mass., has been elected a vice president of the company. He has been with Dunn since it was founded in 1951 to design and manufacture advanced electronics systems and inertial guidance and other missile program test equipment.

Joseph M. Dunn, president, said Johnson would continue to have over-all responsibility for technical operations, directing the activities of four departments: systems and test facilities engineering, inertial products, manufacturing and quality assurance.

Johnson was a member of the Massachusetts Institute of Technology Research Laboratory's engineering staff from 1947 to 1954. He received a B.A. degree from Bowdoin College in 1947, concurrently with a B.S. in electrical engineering from MIT. In the Army Signal Corps during World War II, he helped install high-power point-to-point radio communication facilities in the China-Burma-India Theater.

Low Power Rectifiers

A new series of low power silicon rectifiers (1N536) is available from the **Westinghouse Electric Corp., Semiconductor Dept.,** Youngwood, Pa. The new units are available in ratings to 750 ma maximum forward current and range in peak reverse voltages from 50 to 1000 volts. Applications include magnetic amplifiers, precision metering, ring modulators, high Q circuits and test equipment.



The units are made by a new fused double-diffused process, which produces the silicon junctions having low forward voltage drops and low reverse currents.

(Continued on page 126A)

ELECTRONIC ENGINEERS

Research and Development

Armour Research Foundation, one of the largest independent research organizations, offers exceptional opportunities in Chicago for qualified Electronics research engineers to work on a variety of industrial and military research projects in the fields of

- RADAR
- ANTENNAS
- CIRCUIT DEVELOPMENT
- MICROWAVES
- GUIDANCE & CONTROL
- PROPAGATION
- COMMUNICATION
- SIGNAL PROCESSING
- SEMICONDUCTOR DEVICES
- MEASUREMENT TECHNIQUES

Minimum requirements include a B.S. degree in Electrical Engineering with above average academic grades. Research experience in one of the above fields is highly desirable, though not absolutely necessary.

Our environment combines the better features of academic and industrial research and offers you the opportunity to work on advanced research programs.

Staff members receive attractive salaries, up to 4 weeks vacation, generous insurance and retirement benefits, and tuition paid graduate study. Our Chicago location offers excellent cultural and recreational advantages. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin. Please reply in confidence to Mr. S. M. Ream.

ARMOUR RESEARCH FOUNDATION
OF ILLINOIS INSTITUTE OF TECHNOLOGY
TECHNOLOGY CENTER, CHICAGO 16, ILL.



IONOSPHERIC PROPAGATION and HF COMMUNICATIONS

If you have the background, the imagination and the desire to contribute to important programs in these fields, you are invited to join a carefully selected team of outstanding scientists and engineers now contributing significantly to current knowledge through advanced research.

These programs are being conducted at our ELECTRO-PHYSICS LABORATORIES in the SUBURBAN WASHINGTON, D. C. area, ideally located from the viewpoint of advanced study which may be conducted at one of several nearby universities; for readily available housing in pleasant residential neighborhoods; and for the general amenities of living offered by this important Metropolitan center.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

OUR PRESENT NEEDS ARE FOR:

SENIOR IONOSPHERIC PHYSICISTS Ph.D. preferred, with several years' experience in the study of Ionospheric phenomena. Should be familiar with present knowledge of upper atmosphere physics and possess an understanding of current programs using rockets and satellites for studies in F-region and beyond. Qualified individuals with supervisory abilities will have an exceptional opportunity to assume project leadership duties on HF projects already under way involving F-layer propagation studies backed by a substantial experimental program.

SENIOR DEVELOPMENT PHYSICISTS Advanced degree in Physics or E.E. preferred. Must be familiar with latest techniques in the design of advanced HF receivers and transmitters and possess working knowledge of modern HF networks employing ferrites and metallic tape cores. Strong theoretical background in modern linear circuit theory desired. Will carry out laboratory development and implementation of new HF communications systems.

SENIOR ELECTRONIC ENGINEERS Advanced degree in E.E. preferred. Must be familiar with conventional pulse circuit designs and applications. Technical background should include substantial experience in data process and data recovery systems using both analog and digital techniques. Knowledge of principles and application of modern information theory including correlation techniques helpful. Will be responsible for the design of sub-systems.

JUNIOR ELECTRONIC ENGINEERS To assist Senior Engineers and Scientists in the development of HF communications and data process equipment. Should have formal electronics schooling and 2 years' experience in circuit design checkout or analysis of HF communications, Radar Pulse, Analog/Digital or Data Recovery equipment. Construction of prototypes of new and interesting equipment and design of individual components of communications and data processing systems will comprise the major efforts of selected applicants.

FIELD STATION ENGINEERS B.S.E.E. or equivalent, consisting of combined civilian or military technical school, with work experience. Presently employed as a field engineer or project engineer with a valid 1st or 2nd Class FCC license and a good command of some of the following: Radar, preferably high power; HF long-distance communications systems; Tropospheric or Ionospheric scatter systems. Must be willing to accept assignments in areas where dependents are not permitted for periods of up to one year. Differential paid for overseas assignments.

For a prompt reply to your inquiry, please forward resume in confidence to:
W. T. WHELAN, Director of Research & Development

ACF ELECTRONICS
DIVISION

ACF INDUSTRIES

DEPT. A-2, HYATTSVILLE, MARYLAND

Westinghouse

announces

immediate openings for

TUBE ENGINEERS

The expansion of our Electronic Tube Division to meet the growing demands of the commercial, industrial and military markets has created several outstanding opportunities for experienced ENGINEERS. Salaries are open, depending on experience and qualifications. The plant is located in Elmira, N.Y. . . . a delightful community for work and recreation in the Finger Lakes region of upstate New York.

Experience in any of the following areas is desirable:

- **MICROWAVE TUBES & DEVICES**

  Senior Engineers with experience in design or manufacture of MAGNETRONS, KLYSTRONS, TRAVELING WAVE TUBES and other microwave tubes and devices.

- **IMAGE TUBES**

  Design or manufacture of STORAGE TUBES, CAMERA TUBES and other imaging devices.

- **CATHODE RAY TUBES**

  Design or manufacture of black and white PICTURE TUBES, and INDUSTRIAL and MILITARY TUBES.

Write or send resume to:

William Kacala,
Technical Recruiting,
P.O. Box 284, Elmira, N.Y.
or phone collect
Elmira, REgent 9-3611

An Equal Opportunity Employer

Westinghouse
ELECTRONIC TUBE DIVISION ELMIRA, NEW YORK

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 124A)

The rectifiers are suitable for operation in ambient temperatures from minus 65 to 165°C without the use of external heat sinks.

These cells can be supplied, upon request, to meet military specifications. Each cell is in a hermetically sealed case designed for rugged construction and long life, and may be mounted in any position. The axial leads are flexible and tinned for easy soldering.

For higher voltage applications, the units may be connected in series; however, each diode should be shunted by a resistor to force equal division of reverse voltage. In such high voltage applications, the use of shunting capacitors may also be indicated.

For more information write to the firm.

Digital Transducers

The Electronics Div., DeJur-Amsco Corp., 45-01 Northern Blvd., Long Island City 1, N. Y., offers a group of digital transducers and subminiature pressure instruments in self-contained solid-state packages.



The transducers are designed to measure various parameters such as pressure, temperature, flow and acceleration, and supply a digital output without the use of auxiliary equipment. They are constructed and produce signals compatible with digital computers and electronic counters found in all military and industrial installations.

A set of six technical bulletins including features, characteristics and outline drawings is available free on request. Write to the firm.

New Headquarters For Arco

The new headquarters plant of **Arco Electronics, Inc.,** in the Lake Success Business and Professional Park, Community Dr., Great Neck, N. Y., was dedicated June 6 as a symbol of the increasing importance of marketing to the electronics industry. Arco is an exclusive sales and marketing agency for manufacturers of electronic products, and is itself a manufacturer of complementary components.

(Continued on page 128A)

ELECTRONICS DIVISION

of Space Technology Laboratories, Inc.

Offers Immediate Assignments in Southern California

The continuing growth and diversification of Space Technology Laboratories, Inc. creates immediate career openings in the Communication, Electromechanical, Guidance, and Space Physics Laboratories of STL's Electronics Division.

In supporting STL's expanding contributions to the Advent, OGO, Atlas, Titan, and Minuteman programs, this division's responsibilities include analysis, design, and development of advanced guidance, control, and communications systems—at every phase from applied research through electronic product and ground support equipment design.

Immediate career opportunities exist here for outstanding engineers and scientists in the fields of:

- Digital computers
- Logical design
- Communication systems analysis
- Parts application
- Electronic packaging
- Electromechanical systems development
- Ground support circuit design
- Systems design and integration
- Equipment systems—checkout and evaluation
- Support equipment systems design
- Control systems analysis
- Electromechanical design
- Space communications systems
- Telemetry systems design
- Antenna systems
- R-F transistor equipment design
- Transistor circuit design
- Guidance systems analysis
- Materials and processes
- Reliability
- Aerospace ground equipment design

All qualified applicants, regardless of race, creed, color or national origin, are invited to communicate with Dr. R. C. Potter, Manager of Professional Placement and Development.

SPACE TECHNOLOGY LABORATORIES, INC.
a subsidiary of Thompson Ramo Wooldridge Inc.
P. O. Box 95005-I, Los Angeles 45, California

A MESSAGE FROM KEARFOTT TO EMINENT MEN

who have received their doctorates, are specialists in Radiation Theory and Techniques and have spent 8-10 years in industrial, academic or government research

ANNOUNCING A NEW RESEARCH CENTER FOR THE AEROSPACE SCIENCES

Your interest is enlisted in a new scientific community entirely concerned with scientific and technical investigations; totally divorced from administrative or development duties.

Studies will be related as closely as possible to urgent needs of government agencies, determined through personal consultation with their representatives. Particular (but not exclusive) emphasis will be placed on problems bearing on navigation, guidance and control of upper atmosphere, space and undersea vehicles, areas where Kearfott has long held a leadership position in the development of systems and components.

A PRINCIPAL STAFF SCIENTIST IS SOUGHT *who will initiate and guide his own research and whose experience is sufficiently broad to provide technical direction to other men in a plurality of the following areas:*

- INFRARED TECHNIQUES, SOURCES & THEORY
- ATMOSPHERIC TRANSMISSION (Intensities, Attenuation Studies)
- SCANNING TECHNIQUES (Space Applications)
- ENERGY CONVERSION (Thermo Cooling, Power Generation)
- WAVE PROPAGATION (In Various Media)
- KINETIC THEORY OF IONIZED GASES (Including Multiple Fluid Models of Plasmas, Magneto Hydrodynamic Flow)

If you are interested in being one of the outstanding scientists from many fields of science who will form the nucleus of the new Research Center, write in confidence to Dr. R. C. Langford, Director of Research.

An Equal Opportunity Employer

KEARFOTT DIVISION
GENERAL PRECISION, INC.

Dept. 2B / 1150 McBride Avenue
Little Falls, New Jersey

expansion at **VITRO** *creates new career positions in*

ADVANCED DEVELOPMENT
•
SYSTEMS
•
DESIGN

. . . and an unusual opportunity for pleasant and rewarding living

If you are a talented engineer or physicist, it will pay you to check one of the new and permanent career positions at Vitro Electronics.

The assignments are exciting and include state-of-the-art level work. You have to be creative, capable of developing original concepts, and you should have experience in one of the following areas: design of receivers, transmitters and associated equipment in the RF and microwave fields, particularly 30 - 3000 m.c. regions; solid state circuitry and printed circuit applications; parametric and other low noise preamplifiers; spectrum display equipment, signal generators, microwave components, wide band IF and Video amplifiers and TV circuitry, and phase measuring equipment.

Our facilities are located in Silver Spring, Maryland, a residential suburb of Washington, D. C., affording you a choice of country, suburban or city living. Public schools are excellent and five nearby universities offer graduate courses. The cultural pleasures of the Nation's Capital are just minutes away, and the countryside provides every opportunity for sports, from mountain climbing to boating and fishing on the Chesapeake Bay.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Address your inquiry to:
Mr. D. R. Statter, Director of Industrial Relations

Vitro ELECTRONICS
A Division of the Vitro Corporation of America

PRODUCERS OF NEMS-CLARKE EQUIPMENT

919 JESUP-BLAIR DRIVE, SILVER SPRING, MD.
(Suburb of Washington, D.C.)

Outstanding Missile and Space Openings for Electronic/Electrical Engineers

The Boeing Company, system contractor on the Dyna-Soar manned space glider and weapon system integrator on the solid-fuel Minuteman ICBM, has a number of immediate openings for graduate Electronic/Electrical engineers. These positions, available in areas described below, offer challenge and scope, and exceptional opportunities to advance to higher levels of responsibility and income.

RADIO FREQUENCY INTERFERENCE

Assignments in this area include performing electro-interference tests on military equipment; developing familiarization with RFI specification and compliance requirements; evaluating the physics of generation of electro-magnetic interference and methods of reducing susceptibility to both radiated and conducted interference. Requirements: BSEE degree plus minimum of two years of applicable experience.

ELECTRONICS PACKAGING DESIGN

Duties in this area include evaluation, selection, development and documentation of packaging techniques and systems; evaluation, selection, test and qualification of electronic parts and documenting pertinent engineering information; evaluation, development and application of hardware designs for all types of electronic circuits; design, evaluation and qualification of electronic packaging; selection, design and test of production processes; evaluation, selection, test and qualification of special materials.

Salaries are competitively commensurate with education and experience. Boeing provides travel and moving allowances. In Seattle you'll enjoy the advantages of the uncongested, evergreen Pacific Northwest area, famous for mild year-round climate, unexcelled recreational facilities, modern housing, fine schools and outdoor Western living for the whole family.

Send your resume, today, to: Mr. William B. Evans, The Boeing Company, P. O. Box 3707 - PRM, Seattle 24, Washington. The Boeing Company is an equal opportunity employer.



BOEING

. . . environment for dynamic career growth

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 126A)

Local government and civic leaders and representatives of the electronics industry participated with Albert I. Rothenstein and other officials of the company in the dedication ceremonies and inspected the new, 46,000 square foot plant, on Community Drive. Arco, which was formerly in New York City, has equipped the plant with the latest production, engineering and warehousing facilities.

The Great Neck plant, which Arco occupied several months ago, contains twice the floor space of its former quarters. Some 15,000 square feet are given over to the PFC Division, which produces a complete line of precision film capacitors and related components for military, industrial and space markets.

Last year, Arco was appointed exclusive sales and marketing agency to U. S. and Canadian distributors for the standard line of HST miniaturized transistor transformers and other types manufactured by

(Continued on page 130A)

THE UNITED STATES INFORMATION AGENCY SEEKS ELECTRONICS ENGINEERS with COMMUNICATIONS or BROADCASTING SYSTEMS Experience for its VOICE OF AMERICA

Washington, D.C. Vacancies: Positions require ability to plan communications or broadcasting systems, including transmitting plants, equipment layout, antenna systems, micro wave and VHF radio link systems, receiving stations employing diversity receiving systems, audio distribution, tape recording and playback systems.

Broadcasting and Communications systems cover frequency ranges in the medium and high frequency (standard and short wave) bands.

Domestic employees subject to travel and temporary duty within the United States and abroad.

Salaries: $8955 thru $15,030 annually with entrance rates of $8955, $10,635, $12,210, and $13,730 commensurate with background and experience. These are career positions under Federal Civil Service at the GS-12 thru 15 grade levels.

Overseas Vacancies are of a construction management type, which require Electronic Engineers to supervise the installation of equipment mentioned above. These positions are concerned with the construction of plants utilizing multiple transmitter installations ranging in power up to 1000 kilowatts.

Foreign Service salaries range from $10,785 to $12,025 plus overseas allowances. All appointments will be made at the entrance level of $10,785.

All applicants *must* be AMERICAN citizens

Relocation expenses paid in accordance with government regulations.

Applicants Should:

Send a background resume or preferably an application for Federal Employment (Standard Form 57) directly to:

Employment Branch
U. S. INFORMATION AGENCY
1776 Pennsylvania Avenue, N.W.
Washington 25, D C.

New Positions at

SYLVANIA

RESEARCH & DEVELOPMENT LABORATORIES

on the San Francisco Peninsula

The Reconnaisance Systems Laboratory and Electronics Defense Laboratories are expanding their R&D facilities and advancing the state of the art—as well as America's defense capabilities—at Sylvania Mountain View Operations. Here, in the heart of the San Francisco Peninsula, numerous new electronics research and development programs are under way. Challenging positions for electronic engineers exist at all levels. Positions include:

Origination of Advanced Systems and Equipment Concepts

Design of Unique Electronic Circuits

Development of Experimental Electronic Equipment

in the following areas:

ADVANCED TECHNIQUES
SYSTEMS ANALYSIS
OPERATIONS RESEARCH
PROPAGATION STUDIES
SIGNAL ANALYSIS
RECEIVER SYSTEMS
TRANSMITTERS
D. F. SYSTEMS
MECHANICAL DESIGN

B. S. or M. S. degree and U. S. citizenship required; Ph. D. required for some positions. For further information, please contact Mr. R. R. Keeffe at Box 188, Mountain View, Calif.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

SYLVANIA ELECTRONIC SYSTEMS
Government Systems Management
for GENERAL TELEPHONE & ELECTRONICS

GENERAL SYSTEM

MICROWAVE ENGINEERS

Experienced microwave engineers capable of assuming project responsibility are needed for advanced work with microwave instrumentation.

Programs include theoretical and experimental research in radar target signatures and propagation phenomena associated with ICBM defense.

Write to Mr. D. P. Rentschler.

CORNELL AERONAUTICAL LABORATORY, INC.
of Cornell University
BUFFALO 21, NEW YORK

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 128A)

Dresser Electronics, a division of Dresser Industries, Inc. For this assignment, Arco organized and maintains a network of 50 of the country's largest and best known distributors.

Similarly, the company stocks a complete line of Elmenco capacitors, produced by Electro Motive Manufacturing Co., for off-the-shelf, 24-hour delivery service.

Landing System for Unpowered Space Vehicles

General Electric's Defense Systems Department, Syracuse, N. Y., has announced that it has an automatic landing system under development for unpowered space vehicles and reusable booster vehicles returning for a normal landing.

The system, utilizing radio-tracking, computer and command techniques to solve problems of energy management after a vehicle re-enters the atmosphere, is designed to acquire a vehicle on radar at a 500-mile range, calculate a safe flight path to avoid over-heating or over-stressing the vehicle, and guide through approach, flare-out and rollout on a pre-designated runway.

According to J. K. Records, Manager of Instrumentation & Guidance products, "We have already simulated over 100 landings with various systems on an analog computer, and this system is now ready for implementation and application to a specific vehicle. The system is one of several studied which utilize techniques resulting from several years investigation into the problem of recovering and landing boosters and payloads of orbiting and interplanetary vehicles. The landing system will use equipment cur-

(Continued on page 132A)

RANDOM CRITERIA IN PATTERN RECOGNITION



Random mask used in studies of adaptive pattern recognition systems.

The use of statistically-independent random criteria has been recently shown by Philco scientists to be an unusually powerful tool in the general pattern recognition problem. Statistical independence permits combination of sub-decisions through simply-determined linear weighting and leads to extreme simplicity in experimental arrangements. Results demonstrate high accuracy in visual pattern recognition problems obscure to the human observer.

Pattern recognition is one aspect of Philco's well-balanced and substantial programs in artificial intelligence. Typical projects range from fundamental investigations in decision and learning theory to highly directed studies in automatic photo interpretation and time bandwidth conservation by means of pattern recognition.

Philco Research is seeking scientists with advanced degrees for research in the realm of artificial intelligence, as well as in solid state electronics, thin film technology, electron and ion optics, and electrodynamics. For further information, please write:

Mr. W. P. Diefenbach, Personnel Director
Philco Research Center, Blue Bell, Penna.

RESEARCH CENTER
PHILCO®
Famous for Quality the World Over

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin

ENGINEERS ARE CHARTING A NEW COURSE AT AC

AC's newest assignment is Systems Integrator for the modified B-52C&D Bombing Navigation System. AC's responsibility includes program and engineering integration, and coordination of associate contractors in the production phase. ■ Other programs at AC include a new, miniaturized inertial guidance system for the TITAN II missile. In addition, AC's Los Angeles Advanced Development Laboratory is currently developing an advanced STellar INertial Guidance System. ■ AC is seeking qualified men to work on these important projects. If you have a BS, MS or PhD in Electrical Engineering, Mechanical Engineering or Physics, please contact Mr. G. F. Raasch, Director of Scientific and Professional Employment, Dept. 5753, 7929 South Howell, Milwaukee 1, Wisconsin. An Equal Opportunity Employer. ■ Immediate positions available:

Milwaukee
Radar Systems Engineers
Radar Test Engineers
Radar Reliability Engineers
Design Review Engineers
Contact Engineers
Field Service Engineers

Los Angeles
(Advanced Inertial Guidance Systems—
Airborne Computers)
Transistor Circuit Design Engineers
Sr. Digital Computer Development
Engineers

■ AChiever Inertial Guidance Systems for TITAN II, THOR and MACE—Bombing Navigation Systems for the B-52C&D and B-47—AChieverfone mobile radiotelephones.

AC SPARK PLUG THE ELECTRONICS DIVISION OF GENERAL MOTORS

MILWAUKEE • LOS ANGELES • BOSTON

THIS NEW CATALOG DESCRIBING LINDBERG'S COMPREHENSIVE LINE OF EQUIPMENT FOR SEMICONDUCTOR PRODUCTION IS NOW AVAILABLE



This catalog gives complete information on more than 25 Lindberg units especially designed for the production of semiconductor, solid state and other electronic devices. Processes covered by this equipment include germanium reduction, crystal growing, zone refining, gaseous and solid diffusion, bonding and special processes with controlled atmospheres or vacuum. Send for your copy today!

LINDBERG
heat for industry

Lindberg Engineering Company
Semiconductor Equipment Division
2482 West Hubbard St., Chicago 12, Ill.

Please send copy of Semiconductor Equipment Catalog to:

Name_____

Firm_____

Address_____

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 130A)



rently in production by the General Electric Company and will be transportable by air or truck."

It was also indicated that the system would be tailored to the capability of each individual vehicle. The firm anticipates that the landing system will be able to acquire a vehicle at very long ranges and very high velocities within wide tolerance limits, and by furnishing commands from the ground, dissipate the vehicle's energy within the limits of overheating and overloading so that it can be precisely landed for reuse. Control of the flare and landing maneuver would be to a sinking speed accuracy of 1 to 2 feet per second in normal wind conditions with a landing speed of 100 f.p.s., he indicated.



The landing system incorporates the use of an AN/TPQ-10 radar (shown), a van with associated radar equipment and a General Electric 225 digital computer, and airborne equipment consisting of G.E.'s Mod 111G transistorized track beacon (pulse) and decoder. One of the virtues of this combination of equipment, the company indicates, is that the airborne package could be used during the guidance function of the booster vehicle at launch and then reused for the recovery operation by the landing system. Further, the beacon only weighs 12 lbs. and the decoder 11 lbs. Including a 5-lb. antenna, total airborne system weight would be about 28 lbs.

The landing system would be equally applicable to manned and unmanned vehicles in free flight. Following re-entry, the vehicle's velocity might still be as much as 15,000 f.p.s. At these tremendous speeds, even manned spacecraft would need some instrumentation assistance. The problem in landing the vehicle at a predesignated point is that this high kinetic energy must be dissipated without overheating the vehicle or subjecting it to destructive stress loads.

By working with the vehicle's performance characteristics, a series of safe flight paths are calculated and stored in the computer. The computer selects the precise flight path to suit the position and velocity conditions of the vehicle, and the TPQ-10 radar sends a pulsed command signal to the track transponder aboard the vehicle. The transponder in turn feeds the signal to the decoder which passes it along to the vehicle's autopilot or to a pilot display. For an unmanned vehicle, normally, an autopilot integral to the booster or spacecraft is used for the landing guidance function. However, if there is none, a lightweight autopilot could adequately tie-in to the landing system and perform the mechanical control functions.

(Continued on page 134A)



Another BUSS sub-miniature fuse and holder combination

EXTREME RELIABILITY UNDER HIGH SHOCK AND SEVERE ENVIRONMENTAL CONDITIONS.

Rigid construction of fuse and holder assures extraordinary reliability under high shock and vibration conditions. Fully insulated ceramic body isolates fusible element from effect of dust, corrosion, moisture and vapors.

DESIGNED FOR SPACE-TIGHT APPLICATIONS

Panel Mounted. Holder can be mounted on panel by hand. No special tool required to run down holding nut.

Prong type contacts on fuse make it easy to install or replace.

A knob for the holder may be used to make holder water proof from front of panel.

HOLDER CAN BE MOUNTED IN PRINTED CIRCUITS

Terminals of holder can be inserted into holes and soldered on printed circuit board without additional forming.

If desired, GMW fuse may be used without holder and mounted directly into printed circuit boards.

AVAILABLE RATINGS FOR GMW FUSES.

Fuses are made in sizes from 1/10 to 5 amperes for use on circuits of 125 volts or less where fault current does not exceed 50 amperes.

Transparent window in end of fuse body permits visual inspection of fusible element.

Before crystallizing your design using subminiature fuses be sure to get full data on the Buss GMW fuse and HWA holder combination.

Exploded view of GMW-HWA fuse & holder combination.

IN THE BUSS LINE, you'll find the type and size fuse to fit your every need . . . plus a companion line of clips, blocks and holders.

FUSETRON TRUSTWORTHY NAMES IN ELECTRICAL PROTECTION BUSS McGRAW EDISON

BUSSMANN MFG. DIVISION, *McGraw-Edison Co.,* **UNIVERSITY AT JEFFERSON, ST. LOUIS 7, MO.**

Give your products
MORE RELIABILITY and
BETTER PERFORMANCE with
FREED
QUALITY
IN STOCK FOR IMMEDIATE DELIVERY

CONSTANT VOLTAGE TRANSFORMERS.

Meets Military Specifications
No Tubes
No Moving Parts
Accurate Regulations
Fast Response
Fully Automatic

MIL Type


Commercial Type

Here at last is a hermetically sealed magnetic voltage regulator that will provide constant output voltage regardless of line and/or load changes.

SUPPLIED EITHER MIL. OR COMMERCIAL				
CAT. #	INPUT VOLT.	LINE FREQ.	OUTPUT VOLT.	OUTPUT VA.
MCV- 620L	95-130 v	60 cps.	115	20
MCV- 670L	95-130 v	60 cps.	115	70
MCV-6130L	95-130 v	60 cps.	115	130
MCV- 670F	95-130 v	60 cps.	6.4	70
MCV-6130F	95-130 v	60 cps.	6.4	130
MCV- 420F	95-130 v	400 cps.	6.4	20

MAGNETIC AMPLIFIERS

- Hermetically Sealed To MIL Specifications
- No Tubes
- Direct Operation from Line Voltage
- Fast Response
- Long Life Trouble Free Operation
- Phase Reversible Output

Power Gain 2 x 10^8


Transistor Preamp. MAT-1 Wt. 10 oz.

Mag. Amp. MAF-5 Wt. 18 oz.

Motor



PARTIAL LISTING ONLY
WRITE FOR FURTHER INFORMATION ON THESE UNITS OR SPECIAL DESIGNS.
Send for NEW 48 page transformer catalog. Also ask for complete laboratory test instrument catalog.

FREED TRANSFORMER CO., INC.
1720 Weirfield St., Brooklyn (Ridgewood) 27, N. Y.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation

(Continued from page 132A)

Palmer Appointed by Huggins

Dr. James L. Palmer has been appointed to the staff of the Research and Development Department at **Huggins Laboratories, Inc.,** Sunnyvale, Calif., as director of research. Previously, Dr. Palmer was employed as engineering manager for Traveling Wave Tubes at Litton Industries Electron Tube Div., San Carlos, Calif. Prior to that he was engaged in fundamental research on microwave tubes with the Electronics Research Laboratory of the University of California at Berkeley. He is the author of several papers on electron beam theory.

In his new position at Huggins Laboratories, Dr. Palmer will be in charge of planning, administration, and technical direction of all R&D activities, including projects dealing with lowering of noise figures, refinement of focusing methods, extension of frequency coverage and tube life, and increase of gain and power output. Immediate development work is scheduled for high power, high efficiency, light weight helix-type traveling wave tubes meeting the extreme environments of airborne, missile, and space applications.

Linear Actuators

Block Associates of 385 Putnam Ave., Cambridge, Mass., announces the development of the new BM-02 High Force Linear Actuator.



The new BM-02 is not a solenoid, but, rather, a special type of biased moving iron transducer where the moving element is displaced perpendicularly to the magnetic lines of forces. This permits a linear relation between force and both current and displacement. The main advantage of this type of unit is the push-pull actuation with a force about ten times larger than that of comparable solenoids and a response at least ten times faster.

In addition to replacing present solenoids, this product has new applications, such as: Linear motions formerly obtained with a motor and an eccentric (positive displacement pumps, electric saw, electric sanders, etc.) high speed printing, shaking tables, fatigue testing equipment, large displacement valves, and vibration sorting equipment.

Specifications are as follows: Force (push-pull), 3 pounds; Time constant, 5 ms; Stroke displacement, $\frac{5}{16}$ inch; Maximum rated (linear range) stroke displacement, $\frac{1}{4}$ inch; Power requirements, 30 watts (approximately).

Other models with from 1 to 15 lb. forces will be available soon. Special purpose high force linear actuators can be tailored to individual specifications. Further information may be obtained by writing directly to the company.

Gallay Director of Electronic Research

Harris Gallay has been named director of the newly formed **Microwave Div., Electronic Research Associates, Inc.,** 67 Factory Pl., Cedar Grove, N. J.

This new division is engaged in the development and marketing of a complete line of commercial microwave communications equipment for single-hop and relay applications.

Gallay has pioneered in microwave pulse communications at the the IT&T Laboratories where he was responsible for the research and development of microwave ground based relay systems, as well as air-to-air time division, pulse multiplex communications systems, in which fields he holds a number of patents.

Gallay comes to ERA from the Curtiss-Wright Electronics Div., where he was engaged in the development of light-weight, high resolution, airborne Ka band radar systems

Small "Y" Circulator

Hycon Mfg. Co., 700 Royal Oaks Dr., Monrovia, Calif., has perfected a 2-inch diameter Y-circulator for 2 kMc region. Even smaller units are available for higher frequencies.

(Continued on page 136A)

HOW TO GET THE POWER TRANSISTORS YOU NEED?

JUST ASK DELCO. For even though our catalog lists only a handful of germanium power transistors, there is only a handful out of all those ever catalogued that we don't make. And those only because nobody ever asked for them.

We've made, by the millions, both large and small power transistors. Both diamond and round base. Both industrial and military types. And each in a wide variety of parameters that have proved themselves reliable in nearly every conceivable application.

You get Delco transistors fast. You get Delco transistors in any quantity. And for all their high reliability, you get them reasonably priced. All you have to do is contact our nearest sales office—and ask for them.

Union, New Jersey
324 Chestnut Street
MUrdock 7-3770

Santa Monica, California
726 Santa Monica Blvd.
UPton 0-8807

Chicago, Illinois
5750 West 51st Street
POrtsmouth 7-3500

Detroit, Michigan
57 Harper Avenue
TRinty 3-6560

Syracuse, New York
1054 James Street
GRanite 2-2668

DELCO RADIO

Division of
General Motors
Kokomo, Indiana

PORTABLE REGULATED
DC POWER SUPPLY

Large Capacity Low-priced

model L3501
6" x 8" x 8"

only **$199.50**

- CONSTANT VOLTAGE 0-35v, 0-1A.
- CONSTANT CURRENT 0-30v, 0-1A.
- Fully transistorized — regulated 5 mv. N.L. to F.L. or 10% line change.
- Remote programming & current limiting.
- Ripple 250 microvolts rms.
- Several units may be paralleled.
- Transient response 50 microseconds.
- 150 other models available.

Universal Electronics
1720-22nd St. / Santa Monica, Calif.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 134A)

The new component can be magnetically tuned with either electromagnets or permanent magnets which become an integral part of the package. Standard configuration is with TNC connectors at 120° spacing.

A 6 per cent bandwidth is obtained across S band frequency range from 2 to 4 kMc. Insertion losses are less than 0.4 db with isolation of −20 db (−30 db at center frequency) and VSWR of 1.3 (1.1 at center frequency).

The new Hycon circulator can be converted into an isolator by terminating one arm, either internally or externally. Positions of the connectors can be varied for specified uses. The new Y-circulator is available as an off-the-shelf item.

Attenuators

A new line of small size L and T Pad attenuators is now available from **Centralab, The Electronics Div. of Globe-Union Inc.,** 900 E. Keefe Ave., Milwaukee 1, Wis. These units measure less than $1\frac{3}{16}$" deep from the mounting surface and are designed to fit into any standard junction or switch box. These units are rated at 20 watts audio, 5 watts dc.



Another feature of these attenuators is their anti-backlash construction. The two wiper contacts are attached to the shaft so that they will always move in unison. The "play" that is sometimes found in dual controls cannot occur, thus guaranteeing resettability to predetermined levels. All frequently used impedance ratings are available. They are individually packaged with a gold anodized dial plate and a black set screw knob.

The full line is now available from stock through Centralab distributors. Complete information can be obtained by writing for Bulletin 42-112.

Aluminum Coaxial Connectors

General RF Fittings, Inc., 702 Beacon St., Boston 15, Mass., announces the availability of special weight-saving aluminum connectors in both TNC and TM (miniaturized TNC) types.

By use of special aluminum, these two types feature high strength combined with lightness. For example, a mated plug and jack in aluminum weigh less than either one alone in standard brass construction. In some cases, a single connector in aluminum weighs 64% less than the same part in brass.

These aluminum connectors are the same size, mate with and are interchangeable with non-aluminum TNC and TM types; they also have good electrical and mechanical qualities.

Thread Couplings are TNC 7/16-28 UNEF-2, TM 5/16-32 NEF-2. The heat treated beryllium copper contacts have gold plate over silver plate on all contacts. All aluminum parts are specially treated, silver plated, and rhodium flashed. There is low VSWR and insertion loss. The mated aluminum connectors will not freeze together.

Pollacek Appointed By Radio Receptor

Appointment of Edgar Pollacek as supervisor of sales for industrial selenium rectifiers manufactured by the **Selenium**

(Continued on page 138A)

FINE WIRE

for
- Semiconductors
- Resistors
- Potentiometers
- Thermocouples
- Electronic Tubes
- Other Electronic Applications

in precious, base, exotic and special metals — bare or insulated

Custom Melting, Complete Redrawing, Strand and Vacuum Annealing Services for fine wire processing to customers' specifications.

WRITE for valuable brochure containing fine wire compositions, pertinent properties and applications.

CRM

CONSOLIDATED REACTIVE METALS, inc.
115 Hoyt Avenue — Mamaroneck, N.Y. — OWens 8-2300

All that's new in PLASMA research

read

December

Proceedings

for the facts!



No matter what your field in electronics, having a working knowledge of plasmas is greatly to your advantage. Why? Because plasmas are becoming increasingly important in electronics research and application.

Think of the major new developments in this field. Scientists are using gaseous plasmas to convert heat directly into electricity. Will this affect your work? Of course it will! Others are designing new vacuum pumps, again with gaseous plasmas helping to increase efficiency. Do you see the impact this will have on vacuum tubes, on a whole host of electronics products?

Much specialized research has been done on gaseous plasmas in the last few years. Much more is being planned. To catch up with it, you'd have to read a mass of technical papers, weed through conflicting theories, and often find at the end that the research is not pertinent to your work at all.

Realising this . . .

Proceedings of the IRE devotes its entire December issue to a survey of plasma research and findings to date . . . More than 15 technical papers, each one written by an authority, will spell out what plasmas are, how they behave, what they can do. Guest editor is Dr. E. W. Herold, Vice President, Research, Varian Associates.

Every special issue of *Proceedings* in the past has remained a definitive reference work for years. Many were sold out almost immediately. If you are not a member of the IRE, make sure of your copy of the December special issue on plasmas by sending in the coupon immediately.

more than 15 definitive papers covering the following areas of plasma research and application:

1. Fundamental plasma processes
2. Applications to communications
3. Electric power generation
4. Propulsion systems
5. Low density plasma explorations
6. Generation and amplification of oscillations in plasmas
7. Diagnostic procedures

Proceedings of the IRE

The Institute of Radio Engineers
1 East 79th Street, New York 21

The Institute of Radio Engineers
1 East 79th Street, New York 21

Please send me the December 1961 issue of **Proceedings of the IRE**, containing a survey of the research carried out on plasmas.

☐ Enclosed is $3.00 (for non-members only).*

☐ Enclosed is company purchase order.

*Extra copies to IRE members, $1.25 each (limit: 1 extra to a member).

NAME.....

COMPANY.....

ADDRESS.....

.....

Academic Press

NEW YORK and LONDON

Advances in Computers

Edited by FRANZ L. ALT

VOLUME 2, *November 1961, 434 pp., approx. $10.50*

A Survey of Numerical Methods for Parabolic Differential Equations, *by* JIM DOUGLAS, JR.

Advances in Orthonormalizing Computation, *by* PHILIP J. DAVIS *and* PHILIP RABINOWITZ

Microelectronics Using Electron-Beam-Activated Machining Techniques, *by* KENNETH R. SHOULDERS

Recent Developments in Linear Programming, *by* SAUL I. GASS

The Theory of Automata, A Survey, *by* ROBERT MCNAUGHTON

AUTHOR INDEX—SUBJECT INDEX.

Solid State Physics

Advances in Research and Applications

Edited by FREDERICK SEITZ *and* DAVID TURNBULL

VOLUME 12, *November 1961, about 450 pp., approx. $13.50*

Group Theory and Crystal Field Theory, *by* CHARLES M. HERZFELD *and* PAUL H. E. MEIJER

Electrical Conductivity of Organic Semiconductors, *by* HIROO INOKUCHI *and* HIDEO AKAMATU

Hydrothermal Crystal Growth, *by* R. A. LAUDISE *and* J. W. NIELSEN

The Thermal Conductivity of Metals at Low Temperatures, *by* K. MENDELSSOHN *and* H. M. ROSENBERG

Theory of Anharmonic Effects in Crystals, *by* G. LIEBFRIED *and* W. LUDWIG

APPENDIX—AUTHOR INDEX—SUBJECT INDEX.

Advances in Electronics and Electron Physics

Edited by L. MARTON

VOLUME 15, *November 1961, about 400 pp., approx. $11.50*

Atomic Beam Frequency Standards, *by* RICHARD C. MOCKLER

Masers and Other Quantum Mechanical Amplifiers, *by* J. R. SINGER

Relaxation in Diluted Paramagnetic Salts at Very Low Temperatures, *by* G. A. WOONTON

Millimeter Wave Techniques, *by* W. CULSHAW

The Distribution of Electrons in the Ionosphere, *by* S. A. BOWHILL *and* E. R. SCHMERLING

The Autodyne as Applied to Paramagnetic Resonance, *by* FRANS BRUIN

CUMULATIVE AUTHOR INDEX—CUMULATIVE SUBJECT INDEX.

Rarefied Gas Dynamics

Proceedings of the Second International Symposium held August 1960, at the University of California, Berkeley

Edited by L. TALBOT

Supplement 1 of

ADVANCES IN APPLIED MECHANICS

Edited by H. L. DRYDEN, T. VON KÁRMÁN, *and* G. KUERTI

October 1961, 748 pp., $22.00

111 Fifth Avenue, New York 3, New York

17 Old Queen Street, London, S. W. 1

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 136A)



Div., Radio Recepter Co., Andrews Rd., Hicksville, L. I., N. Y., subsidiary of General Instrument Corp., is announced by Arno Nash, vice president and general manager of the division.

In his new post, Pollacek will be responsible for all industrial selenium rectifier sales, including the company's line of ultra high voltage rectifier stacks.

Pollacek comes to Radio Receptor from Industrial Rectifier Devices, Inc., where he was vice president in charge of sales and engineering. Previously, he had been sales and advertising manager of Power Equipment Co., and before that he had been sales manager of both the Selenium and Rectifier Equipment Division of Federal Telephone and Radio Corp.

Rotary Solenoid



A new MIL-1-22075 rotary solenoid requiring less input current than a transistor has been developed by **John Oster Manufacturing Co., Avionic Div.,** Racine, Wis. Type 9931-04 has approximately 0.0033 amperes input current at room temperature and 0.005 amperes maximum at 29 vdc at −55°C. Torque at 95°C is 0.005 oz./in. minimum. Voltage range is from 25 to 29 vdc. Designed to operate flags in indicators to MIL-1-22075 and for other rotary motion military applications requiring low input and 35° total rotation. Price upon request. Delivery is 60 days after receipt of order.

Ferrimagnetic Materials

Several new magnetic materials recently developed in the **Solid State Materials Laboratory, Sperry Microwave Electronics Co.,** Clearwater, Fla., will find application in the microwave field and will facilitate the fabrication of more sophisticated microwave components, according to Dr. J. E. Pippin, who directs the materials research.

One family of materials reported by D. G. P. Rodrigue was developed under the partial sponsorship of RADC, (Contract No. AF 30(602)-2330, directed by Mr. P. D. Romanelli), and can be synthesized so as to control the effective internal anisotropy field over values that make the materials suitable for applications for X to V bands. In these oriented polycrystalline members of the barium ferrite family, the crystalline anisotropy field of material can be used to augment or replace the usual externally applied magnetic field. The particular compositions under study, the nickel-cobalt W compounds, have been tailored to control this internal anisotropy field from 13,000 oersteds to virtually zero oersteds. Devices based on ferromagnetic resonance can now be fabricated with only nominal externally applied magnetic fields at frequencies from X to V bands. Devices based on differential phase can use the same materials at still higher frequencies with only minimal magnetic field requirements. Sperry has made resonant isolators at V-band using applied fields of less than 1000 oersteds. At K band, isolators using other members of this new series again require less than 1000 oersteds as opposed to approximately 8000 oersteds required by conventional ferrites.

Diffused Silicon Field Effect Transistor

Texas Instruments Incorporated, P. O. Box 5012, Dallas 22, Texas, announces the availability of their developmental type TIX 690 Field Effect Transistor, an N-channel diffused silicon device featuring dual gate control. The Field Effect Transistor is a voltage-operated amplifying device which uses the depletion regions of back-biased N-P junctions to control the conductive thickness of a semiconductor layer. The result is a high-input-impedance, high-gain unit that will find unlimited usage in the input stages of audio and DC amplifiers, switching applications, voltage-controlled resistances, AGC circuits, voltage-controlled bandwidth amplifiers, analog multipliers, and a host of other distinctive applications.

Typical characteristics of the TIX 690 are a pinch-off voltage of 4 v, a drain-to-source voltage of 20 v, and a transconductance of 2500 micromhos. The unit is being packaged in a four-lead TO-5 can and is available in limited sample quantities through all TI Field Sales Offices. Individual specifications sheets will be supplied with each device.

(Continued on page 140A)

Use Your IRE Directory—It's valuable

When you need

POWER



FOR AIRCRAFT, MISSILES, ROCKETS

FOR TELEMETERING, CONSUMER PRODUCTS, CONTROLS, GUIDANCE, MICROWAVE, PORTABLE EQUIPMENT, ALARM SYSTEMS,

Depend on Reliable

NICAD® Nickel Cadmium Rechargeable Battery Cells

SEALED CELLS

VENTED CELLS



If you need battery POWER you will find a NICAD Sealed or Vented Power Cell designed to meet your most demanding and exacting specifications.

A product of intensive research and sound engineering, these NICAD cells offer a dependable, constant power supply for: Emergency Lighting, Controls and Alarms, Switchgear Operation, Toys, Hearing Aids, Dictating Equipment, Flashlights, Telemetering, Microwave, Engine Starting, Radio Transceivers, Telephone, Transmitters, Instrumentation, Computers and many, many more. Compact, lightweight, low in operating cost, requiring practically no maintenance, NICAD cells are ruggedly constructed and are virtually unaffected by temperature extremes.

To design reliable and economical power into your systems or products choose from the wide range of sizes and types in the NICAD line. *If you need more detailed information on your particular problem write . . .*



One of the main advantages of nickel cadmium batteries, as compared with other systems, is the constant voltage during discharge—even under extremely heavy loads. Shown above is a typical discharge curve.



FOR COMMUNICATIONS



FOR ELECTRONICS



FOR COMMERCIAL EQUIPMENT



FOR CONSUMER PRODUCTS

FOR INDUSTRY

GOULD-NATIONAL GN BATTERIES, INC.

NICAD BATTERY DIVISION

GOULD-NATIONAL

BATTERIES, INC./E-1409 First National Bank Bldg., St. Paul 1, Minnesota

EMERGENCY LIGHTING & POWER *Anywhere Automatically*

with ATR EMERGENCY LIGHTING & POWER UNIT

Illustrates ATR Emergency Lighting and Power Unit, Model ETS complete with lamps.

for PA SYSTEMS, INTERCOMS and SWITCHBOARDS

for TIME CLOCKS and OTHER RECORDING CLOCKS

for HOSPITAL OPERATING ROOMS

Completely Automatic Standby-Power Units Specially Designed to Permit the Instantaneous Continued Operation of Critical Lighting Equipment, PA Systems, Amplifiers, Intercom Systems, Burglar Alarms, Fire Alarms, Synchronous Electric Clocks, Electric Time and Recording Clocks, Incubators, Gas Valves, Telephone and Test Equipment, and Similar Critical Devices in the Event of 115 Volt AC Commercial Power Line Failure. For Use: In Hospitals, Banks, Hotels, Theatres, Factories, Office Buildings, Schools, Homes, and Many Other Areas of Operation.

SEE YOUR JOBBER OR WRITE FACTORY

• "A" Battery Eliminators • DC-AC Inverters • Auto Radio Vibrators

ATR ELECTRONICS, INC.
Formerly American Television & Radio Co
Quality Products Since 1931
ST. PAUL 1, MINNESOTA—U.S.A.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 138A)

Honeywell Appoints Maislinger

John Maislinger has been appointed chief development engineer for **Minneapolis-Honeywell's Precision Meter Division.**



He had previously been chief engineer for International Instruments, Inc., New Haven, Conn.

In his new position with Honeywell, Maislinger will be responsible for the development of new or improved meters and indicating instruments for aircraft, industrial and other applications.

A native of Austria, Maislinger received an electrical engineering degree in 1939 from the Engineering College of Salzburg and later graduated from the Naval Academy for Professional Engineering Officers, Flensburg and Kiel.

Following World War II he taught at the Professional School, Salzburg, and beginning in 1954 served for five years as a design engineer for the Canadian subsidiary of Westinghouse Electric Corp., Hamilton, Ontario.

AC Voltage Standard

Sensitive Research Instrument Corp., 310 Main St., New Rochelle, N. Y., has developed a portable thermocouple transfer standard designed to measure directly in percentage of reading, the influence of frequency on the indication of voltmeters, calibrators and other transfer standards. Frequency influence (or AC/DC differences) are measured to an accuracy of $\pm 0.01\%$ from 1.5 volts to 1125 volts over a frequency span of 20 to 50,000 cps. When employed in conjunction with precision DC potentiometers and their accessories, $\pm 0.013\%$ accurate absolute AC voltage measurements are made without difficulty.

Basic accuracy is derived from the flat frequency response of the multipliers employed. Long term resistor stability is of no importance. If the instrument is not physically damaged its frequency response, and therefore its accuracy, will remain fixed indefinitely. Warranty is on this basis. Supplied with National Bureau of Standards Certificate.

Additional specifications are: resolution, 0.005% minimum; case, shielded, formica with hinged cover and leather carrying strap; size, $21\frac{1}{4} \times 13 \times 6\frac{9}{16}$; price, $1,685.00 (Includes NBS certificate and type SR4 galvanometer); terms; net 30 days, f.o.b. NBS, Washington, D. C.

Inductance Bridge

Boonton Electronic Corp., Morris Plains, N. J., has announced the development of a new inductance bridge specifically designed for measurements in the audio frequency ranges between 0.4 and 20 kc.

The instrument is basically a calibrated variable frequency oscillator coupled to a modified Maxwell bridge and includes a self-contained tunable null detector which provides discrimination against unwanted distortion often generated in components under test.

A feature of the bridge is the direct reading calibration of both the inductance and resistance dials; 850 inches of calibrated dial provides resolution to 0.01%. Other specifications include: inductance range, 0.02 microhenries to 11 henries; resistance range, 0.002 ohms to 110 K ohms; accuracy in the order of 0.25%.

Excellent stability and convenient operating features make the instrument ideally suited for inductance matching, temperature coefficient and other laboratory or production applications.

Complete specifications as well as price and delivery information are available from the firm.

Solid State In-Flight Voltage Calibrators

Applied Electronics Corporation of N. J., 22 Center St., P.O. Box 43, Metuchen, N. J., announces the introduction of the VC series of solid state in-flight voltage calibrators. These equipments are packaged for missile environments and feature high accuracy with low power requirements.

Power Input is 28 volts at 0.75 watt. Reference Supply is 10 ma at 5 volts. Number of calibration steps: Zero, 25% 50%, 75% and full calibration voltage input. Calibration step period from 0.01 second to 0.2 second maximum $\pm 10\%$. (Periods to 1 second available on special order) Accuracy is ± 5 mv over temperature range -20 to $+85$°C. Output impedance is 100 ohms. Size is $2\frac{3}{4} \times 2 \times 1\frac{1}{8}$

(Continued on page 142A)

The Highest Sensitivity
and the lowest noise.....

Advanced electronic research by Hitachi technicians has now resulted in the development of a superb frame grid type twin triode (6R-HH8) with excellent high gain and low noise characteristics. As a component of the tuner, the 6R-HH8 ensures an excellent picture with a remarkable degree of definition.

fig. 1 Gain characteristics



fig. 2 Noise characteristics





Frame Grid (6R-HH8)

Hitachi also produces other receiving tubes and components for television which, when used together with the new 6R-HH8, cannot fail to earn any maker a market reputation even better than he currently enjoys.



Automatic tube testing equipment

Hitachi, Ltd.
Tokyo Japan
Cable Address: "HITACHY" TOKYO

HIGH SPEED PULSE GENERATOR

GASL MODEL PG-10

- **Frequency:** 1 mc to 20 mc
- **Pulse Width:** 15 nanosecs. to 300 nanosecs.
- **Rise and Fall Time:** Less than 6 nanosecs.
- **Maximum Amplitude: (93 ohm load)** +16 Volts −20 Volts
- **Source Impedance:** 93 ohms
- **Step Attenuator:** 6 steps from 0 to 60db and continuous amplitude adjustment
- **External Trigger:** 0 to 20 mc

Ask for detailed specification sheet.

General Applied Science Laboratories, Inc.
Merrick and Stewart Aves.
Westbury, L. I., N. Y. • EDgewood 3-6960

Engineers who know
—SPECIFY

Q-max*

A-27
SUPERFINE
LOW-LOSS RF LACQUER

• Q-max, an extremely low loss dielectric impregnating and coating composition, is formulated specifically for application to VHF and UHF components. It penetrates deeply, seals out moisture, provides a surface finish, imparts rigidity and promotes stability of the electrical constants of high frequency circuits. Its effect upon the "Q" of RF windings is practically negligible.

• Q-max applies easily by dipping or brushing, dries quickly, adheres well, meets most temperature requirements. Q-max is industry's standard RF lacquer. Engineers who know specify Q-max! Write for new catalog.

*Registered Trademark

Q-max Corporation
MARLBORO • NEW JERSEY
Telephone: HOpkins 2-3636

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 140A)

inches. Various modes of control are available on request.

More detailed information is available by writing to the firm.

Semicon Appoints House and Goldman

Semicon, Inc., of Bedford, Mass., announces the appointments of Robert E. House as Executive Vice President, and Herbert N. Goldman as Vice President of Engineering.

House

Goldman

Before joining Semicon, Inc., Mr. House and Mr. Goldman were associated with Transitron Electronic Corp., where House was Manager of Advanced Product Research and Goldman was Manager of Silicon Diode Development and Pilot Line Production.

House received his B.S. Degree in Engineering Science and Applied Physics from Harvard College and his M.S. Degree in Physics from Massachusetts Institute of Technology.

Goldman received his B.S. Degree in Electrical Engineering and his M.S. Degree in Mathematics and Physics from Northeastern University.

Both men will be active in the design and development of Semicon's expanding line of new semiconductor devices.

TWT With 5DB Noise Figure

Huggins Laboratories, Inc., 999 E. Arques Ave., Sunnyvale, Calif., introduced the HA-89 low-noise traveling-wave tube amplifier at the WESCON Show.



This TWT exhibits less than 5 db noise across selected 400 mc portions of the S-band while attaining greater than 25 db small-signal gain and 10 mw saturation power output. Operated broadband, 2.0 to 4.0 kmc, the HA-89 achieves 8 db maximum noise figure, 20 db minimum small-signal gain, and greater than 10 mw saturation output power. This relatively high output reduces troubles associated with inter- and cross-modulation effects when simultaneous reception of large and small signals is desired.

The HA-89 measures $19\frac{7}{8}$ inches long, including connectors, by $1\frac{5}{16}$ inches OD and weighs 2 lbs. 7 oz. All RF and DC connections are located at one end of the tube. The associated focusing solenoid weighs 21 lbs., and required solenoid power is 125 watts maximum.

New Electronic Laboratory Established

Burroughs Electronics, Inc., River Rd., Cos Cob, Conn., is a recently formed research and development organization founded by Gordon S. Burroughs of Greenwich, Conn. Gordon Burroughs, President, stated that the major effort of the firm will be research and development in the fields of radio direction finding, aerial navigation, infrared, reconnaissance, surveillance, analog computers, and others primarily for the military, industrial, and space agency services. Additional emphasis will be given to the fields of moon and space exploration as well as satellite applications.

Prior to the establishment of the new firm, Burroughs was Vice President for Military, Industrial and Advanced Systems of CBS Laboratories. He was ten years with the IT&T Laboratories as a research engineer, and before his association with CBS operated his own laboratory for three years where he made contributions to the infrared art. He was active in the early days of television and in 1938 developed and marketed home television receivers.

Sigmund Cohn Corp. of California is Organized

In order to provide technical advice and service to West Coast patrons **Sigmund Cohn Corp. of California,** 151 C. North Maple St., Burbank, Calif., has been organized. This West Coast organization will handle the various lines of wire, sheet and other products of Sigmund Cohn Corp. and its affiliates, Sigmund Cohn Mfg. Co., Inc. and Pyrofuze Corp. These products are all manufactured in the corporation's plant at Mount Vernon, N. Y.

Fred Karg

Among the products handled by the

(Continued on page 144A)

1962 1963 1964 1965 1966

All

LAMBDA

Power Supplies guaranteed for 5 years

Every Lambda power supply carries a written guarantee that it will perform to specifications for five full years. You can install power supplies now with complete assurance that they will still perform to design standards in 1966. *Lambda's guarantee, which covers workmanship and materials (except for tubes and fuses), has been in effect on all power supplies sold since 1953.* It is your strongest assurance of power supply performance in installations where dependability is an absolute necessity for round-the-clock, heavy-duty service.

SEND FOR NEW LAMBDA CATALOG 61



ALL-TRANSISTORIZED
LA SERIES

Nine Models Available
Voltages up to 330 VDC—Currents up to 20 Amp
Convection Cooled—Short Circuit Proof

LAMBDA ELECTRONICS CORP.

515 BROAD HOLLOW ROAD • HUNTINGTON, L.I., NEW YORK • 516 MYRTLE 4-4200

Western Regional Office: 230 North Lake Avenue, Pasadena, California • Phone: Code 213, MUrray 1-2544
New England Regional Office: 275 Boston Post Road, Marlboro, Massachusetts • Phone: Code 617, HUntley 5-7122
Middle Atlantic District Office: 515 Broad Hollow Road, Huntington, L. I., New York • Phone: Code 516, MYrtle 4-4200



WHY

MAJOR C. R. TUBE MFGRS. RECOMMEND SYNTRONIC YOKES

Exceptional manufacturing uniformity. Achieved by unique pepperpot tube testing—the most comprehensive method known for precise measurement for spot uniformity . . . to attain extremely accurate focusing. For technical details, request ELECTRONIC INDUSTRIES reprint #6-57 from Syntronic Instruments, Inc.

Call your nearest SYNTRONIC REP today

Boston-New Eng.:	NOrwood 7-3164
New York Area:	OXford 5-0255
Phila. Area:	MOhawk 4-4200
Wash.-Balt. Area:	APpleton 7-1023
Indianapolis:	Victor 6-0359
Los Angeles:	CUmberland 3-1201

syntronic

INSTRUMENTS, INC.

100 Industrial Road, Addison, Illinois

Phone: Kingswood 3-6444

The industry's broadest yoke line . . . already tooled for quantity production. Or, yokes can be custom designed to your precise requirement.



NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 142A)

California Corporation are the following: fine wires of precious and base metals made in small sizes such as those used in the semiconductor field, the potentiometer industry, and various instrument and temperature measuring devices; an unusual assortment of wires of high purity metals, held to close and unusual tolerances; wire electroplated for solderability and corrosion resistance. Included is Pyrofuze, a patented bimetallic material which is used in the pyrotechnics and explosives industry for the purpose of ignition, release and destruct mechanisms and similar applications.

Mr. Fred Karg is in charge of the California office. He received his technical training at the Newark College of Engineering and at the University of Southern California.

Direct Reading Phase Meter

Ad-Yu Electronics Lab., Inc., 249 Terhune Ave., Passaic, N. J., has a direct reading phase meter with the following features: (1) Meter reading independent of the ratio of input signal amplitudes from 1 to 700. (2) Equal accuracy for symmetrical waveforms of any shape. (3) Direct indication of phase angle in degrees from 500 kc down to 1 cps. (4) No amplitude adjustment of either signal voltage. (5) No ambiguity at zero reading. (6) Provision for identification of "LEAD" and "LAG." (7) Provision for self-calibration and self-adjustment.



The specifications of Type 405 Series are as follows: Frequency response: Type 405, 8 cps to 100 kc; Type 405H, 8 cps to 500 kc; Type 405L, 1 cps to 100 kc. Phase range: 0–12, 0–36, 0–90, and 0–180 degrees full scale. Accuracy: $\frac{1}{4}°$ relative and 1° or 2% absolute. Input voltage: Type 405 and 405L, 0.1 volt to 70 volts: Type 405H, 0.3 volt to 40 volts. Input Signal ratio: Meter reading is completely independent of ratio of signal amplitudes, ranging from ratios of 1 to 700 for Type 405 and 405L, and 1 to 130 for Type 405H. Input Impedance: Type 405 and 405H, 3 megohms shunted by 20 $\mu\mu$f on both input channels; Type 405L, 6.8 megohms shunted by 20 $\mu\mu$f. Input power: 60 watts, 50/60 cycles at 110 volts ±10% (220 volts ±10% available on request at no additional cost). Stability for measuring small phase angles: Drift is less than 0.001° for 10 hours of continuous operation at the vicinity of zero degree. An output signal is available with amplitude of 14 volts for application to an external recorder for plotting phase characteristic curve. Physical size: 19″×10½″, with mounting slots for all standard racks, chassis 17″×8¼″ ×2¼″, cabinet 12″×10″×20½″; 16-gauge, cold rolled steel; light gray wrinkle finish, rounded corners.

Microwave Power Meter

An increase in accuracy of direct-reading power measurements by an order of magnitude is now available with the new temperature-compensated Model 450 Precision Microwave Power Meter, a product of **General Microwave Corp.,** 47 Gazza Blvd., Farmingdale, N. Y. This instrument features direct-reading accuracy of ±0.5% of full scale, on all scale ranges, and a thermal stability of better than 2 microwatts/°C.

The instrument is designed to operate in conjunction with the GMC Model 402 series of temperature-compensated thermistor mounts covering the frequency range from 0.01 to 18.0 Gc. As an additional unique feature, the Model 450 will operate with *any* 100 or 200-Ohm uncompensated thermistor or barreter mount requiring maximum bias currents to 16 milliamperes.

Measurements may be made continuously over the range from 0.5 microwatt to 10 milliwatts. Five scale ranges are provided with full scale readings of 0.1, 0.3, 1.0, 3.0 and 10.0 milliwatts. Corresponding scales are in decibels referred to one milliwatt (dbm) from −30 to +10 dbm. An additional feature is the instrument's large 12-inch scale which yields a resolution of 0.1 microwatt on the lowest range.

Price: $495.00. Delivery: Available from stock.

Electronic Components Catalog

Components used in the electronics industry are fully illustrated and described in the new condensed 6-page, 2-color catalog issued by **National Tel-Tronics Corp.,** 52 St. Casimir Ave., Yonkers, N. Y.

The products covered include National's complete line of tip plugs and jacks, as well as banana plugs and jacks—

(Continued on page 146A)

New! Higher permeability, no extra cost...

in small transformer core laminations.

Pack extra performance into your miniature transformers *at no extra cost* with Magnetic Metals' new mite-size transformer core laminations. Use these carefully engineered laminations where you need high specific resistivity and low hysteresis loss, particularly where you require low core loss at high frequencies. They let you miniaturize your designs even further without sacrificing performance.

Supplied only by Magnetic Metals, these new small laminations are made of "Supermu 40"* which provides the highest permeability commercially available. Advanced manufacturing techniques now bring this premium line of laminations to you at no extra cost.

Write today for more information on our entire line of small transformer core laminations. Our engineers are ready to help you select, from the most comprehensive line of laminations in the industry, the best grade of material for the exact results you want.

MAGNETIC METALS

Hayes Avenue at 21st Street, Camden 1, New Jersey
853 Production Place, Newport Beach, California

transformer laminations • motor laminations • tape-wound cores
powdered molybdenum permalloy cores • electromagnetic shields

*79% nickel-iron molybdenum alloy

0 TO 1500 V COMPLIANCE with ELECTRONIC MEASUREMENTS



MODEL C638A

CONSTANT CURRENT POWER SUPPLIES

You'll find a whole new world of application in Electronic Measurements Constant Current Power Supplies. Take the husky Model C638A shown here. It'll deliver up to 1500 V dc at any output current from a few microamperes up to 100 ma. There are other features too . . . a modulation input, programmability, less than 0.01%+1 μa ripple . . . and the all-important voltage control that lets you set the maximum voltage compliance.

For complete information ask for Specification Sheet 3072B.

BRIEF SPECIFICATIONS

MODEL	RANGE MIN.	RANGE MAX.	VOLTAGE COMPLIANCE (MINIMUM)
C612A	1 μa	100 ma.	100 V
C631A	1 μa	100 ma.	300 V
C638A	1 μa	100 ma.	1500 V
C624A	2.2 μa	220 ma.	100 V
C632A	2.2 μa	220 ma.	300 V
C629A	2.2 μa	300 ma.	50 V
C633A	2.2 μa	300 ma.	300 V
C620A	5 μa	500 ma.	50 V
C621A	5 μa	500 ma.	100 V
C613A	10 μa	1 AMP	50 V
C614A	10 μa	1 AMP	100 V

ELECTRONIC MEASUREMENTS COMPANY, INCORPORATED
EATONTOWN · NEW JERSEY

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 144A)

both non-insulated and insulated. Also included are meter type banana and tip plugs, test prods, binding posts, alligator clips, nylon tip jacks, two- and three-conductor phone jacks and plugs.

A separate section of the catalog is devoted to the 11 types of molded push button terminal blocks.

A copy of the catalog can be secured by writing to the manufacturer.

Miniature DC Measuring Potentiometer

The Model PC "PocketPot" developed by **Sensitive Research Instrument Corp.**, 310 Main St., New Rochelle, N. Y., is a self-contained 0.05% accurate, miniature, DC Potentiometer that may be held and operated in the palm of the hand. Readout is direct and "in line." Design features a self-contained transistor amplified galvanometer and an internal battery operated reference source for standardization. (Operation does not require an external power source.) Effective resistance is infinite at null. Measuring range is 0–5.100 volts with continuous resolution over a 100 division slide wire (1 millivolt per division).

Current ranges from 0-1 ampere and additional voltage ranges to 500 volts can be obtained by using the "PocketPot" in combination with the Model PC-S, a "plug in" 0.05% accurate range extension unit of the same size and shape. Provision is made for mechanical and electrical zeroing of the galvanometer and readjustment of the reference source if necessary.

Size is $9\times4\frac{1}{4}\times1\frac{3}{4}$. Weight is 3 lbs. (each unit). Price of the Model PC is $450.00; the Model PC-S is $175.00.

Transistor Cooling Test Report

A new 48-page test report 172A which gives junction and case temperatures, power dissipation for power transistors in a variety of natural and forced air environments is available from **IERC Div., International Electronic Research Corp.**, 135 W. Magnolia Blvd., Burbank, Calif. The report evaluates an advanced dissipator design twice as efficient as conventional fin-types of equal volume.

The general compilation of data in the IREC Test Report provides the reader with one of the most complete coverages of transistor heat dissipator design and effectiveness. Coordinated with the text are graphs, charts and drawings, as well as full-page photographs of the environmental test laboratory set-ups to fully present the subject.

The report is a staple-bound, binder-drilled booklet capable of long service life under daily or library reference uses.

Copies will be sent on request by writing.

Selenium Rectifiers

To its recently announced line of flat, conduction-cooled selenium rectifiers that occupy as little as 1/14 of the space requited by conventional air-cooled selenium rectifiers of equal capacity, **Radio Receptor Co., Inc.**, 240 Wythe Ave., Brooklyn 11, N. Y., now have added a line of epoxy-sealed "power flats" with similar advantages in applications requiring power-handling capacities up to 250 volt-amperes or even higher.



Like the smaller, general-purpose flats, the new power flats utilize a unique construction that reduces forward resistance for lower IR drop, lower I^2R (heat) loss—hence less heat produced for a given load. Also, like the smaller units, the heat that is generated is conducted away efficiently by the chassis or other heat-sink—more effective than the customary "fins" and air convection. The combined result is a lower operating temperature, with attendant permissible space savings and substantially less thermal interference with adjacent components.

Currently available units include half-wave, doubler, and bridge configurations in single phase circuits, in a single package for voltages up to 130 volts RMS input, and current outputs to 10 amperes dc, based on an allowable (and conservatively rated) case-temperature of 150°F.

PNPN Switching Device

The development of the Type 2N1966 Dynaquad, a germanium, alloy junction PNPN switching device with triggered turn on and turn off at its base, has just been announced by **Tung-Sol Electric Inc., Semiconductor Div.**, 1 Summer Ave., Newark, N. J. The operation of the Dynaquad can be compared to the circuit equivalent of two complementary transistors, an NPN and a PNP, connected together. Because of its bistable nature and switching speed in the megacycle range, the Dynaquad can be used in



(Continued on page 148A)

a shocking development

The new Westrex 2101 Data Recording System withstands extreme shock, vibration, acceleration, pressure, and temperature, offers consistent recording integrity and survivability for re-use. Its predecessor, the RA-1653 Recorder, recorded data under impact shocks of 1500 g without damage.

Primary subsystems of the 2101 are: the RA-1660-A Data Recorder, a precision tape transport which records 14 channels on 650 feet of 1-inch magnetic tape driven at 30 ips; and the RA-1670-A Electronic Module Assembly which contains the signal processing components. Seven of the RA-1670-A's 14 wideband Subcarrier Oscillator Modules for converting analog signal inputs to frequency-modulated carriers are interchangeable with Analog Direct Record Amplifier Modules.

Overall System Specifications

Frequency response—FM, within 0.1 db for wideband (dc to 10 kc). Center frequency of voltage control oscillator 54 kc; other standard IRIG frequencies available. Direct analog, within ± 1 db (50 cps to 100 kc). Flutter and wow—less than 1% over frequency range from dc to 10 kc. Shock—records through 300 g's square wave. Vibration—20 g's, 20 to 2000 cps. Acceleration—150 g. Recording time—4⅓ minutes. Reels fit 3-inch standard NAB spindle. Write for data bulletin.



WESTREX 2101 DATA RECORDING SYSTEM OPERATES WITH PRECISION IN EXTREME MISSILE ENVIRONMENTS

Westrex Company

A DIVISION OF LITTON SYSTEMS, INC.
Recording Equipment Division
335 N. Maple Drive, Beverly Hills, California

Readouts that do more...

Series 80000

DISPLAY NUMBERS, WORDS, COLOR, and SYMBOLS

Features the largest readout area (7⅞ sq. in.) employing these applications. Price complete from $33.00. Your inquiry regarding readouts that do more, for you, is invited.

INDUSTRIAL ELECTRONIC ENGINEERS, Inc.
5528 Vineland Ave., North Hollywood, Calif.

Send for your FREE
1962 HEATHKIT CATALOG
The world's biggest kit catalog

- NEW KITS
- NEW STYLING
- NEW GUARANTEE
- NEW NO MONEY DOWN TERMS

Save up to 50% on Stereo Hi-Fi, Test Instruments, Amateur Radio, Marine, Educational and General Interest items that we *guarantee* you can build. Over 250 different kits illustrated with specifications, schematics and full descriptions in this new 100 page catalog. Send for your free copy today! Send your friends' names too.

HEATHKIT® by Daystrom

World's Largest Manufacturer of Electronic Kits

HEATH COMPANY
Benton Harbor 4, Michigan

Please send FREE 1962 Heathkit Catalog

NAME

ADDRESS

CITY ZONE STATE

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 146A)

computer and control circuits of whereever circuits employing digital techniques are used. In a simple flip-flop circuit, one Dynaquad can replace as many as seven conventional components.

The alloy junction design makes possible a minimum emitter-to-base breakdown rating of 20 volts. Peak collector current is 3 amperes with a minimum pulse width of 100 μsec and a maximum repetition rate of 300 pps. Collector dissipation is 120 milliwatts. With an I_c of 50 ma and R_{be} at 1K, base turn on current is 0.5 ma maximum; base turn off current is 12 ma maximum with an I_c of 20 ma and R_{be} at 10K. Both turn on and turn off times are in the 0.1 μsec range. Sustaining current is 20 ma maximum.

The Type 2N1966 is available in a standard hermetically sealed TO-5 package that has the semiconductor base element connected directly to the case to increase thermal efficiency. Operating temperature of the unit is from −65° to +75°C. For details contact the firm.

pH Analyzer System

A new Model J Industrial pH Analyzer System has been announced by the **Scientific and Process Instruments Div., Beckman Instruments, Inc.**, 2500 Harbor Blvd., Fullerton, Calif. The system includes the Model J pH Analyzer, new electrodes, and new electrode mounting chambers.



The Model J employs an Ac stabilized amplifier which provides stability of 0.01 pH/24 hours over −20°F. to +122°F. ambient temperature range. Output accuracy and meter sensitivity is ±0.02 pH for the full 0 to 14 pH range.

The analyzer is available with both milliampere and millivolt output for use with any potentiometric or current-type recorder. It is also available with millivolt output only.

Solid-state electronics, low-cost plug-in components and circuits reduce long-term maintenance costs and simplify service. The Model J chassis slides out of the case on rails for rapid, simple inspection. By disconnecting two plugs, the entire chassis can be quickly removed from the case.

New glass and reference electrodes feature short, compact bodies for added strength. Electrode cable fastens with capscrews at electrode caps for quick connection and disconnection.

New Electrode Immersion and flow Chambers are available for all application requirements. These units feature convenience of installation and maintenance.

For further information contact the firm.

Digital Data Simulator

Howard Instrument Co., Red Bank, N. J., announces two additions to its product line, the 600 Series Digital Data Simulators illustrated and the C-Series Binary-to-Decimal Converters.

The 600-Series Digital Data Simulators provide repeated serial data words up to 120 bits in length, with individual switch control for each bit position. Bit rates from 1000 to 500,000 per second are available and both the adjustable pulse duty cycle and adjustable inter-word gap are designed to track the bit rate. Models are available which provide up to 8 parallel channels.

The C-Series Binary to Decimal Converters accept 10-bit binary data, either serial or parallel, and convert the data to 12-bit BCD. The output is either serial or parallel. Maximum conversion rate is 1000 conversions per second.

Precision Potentiometers

New dual-element rectangular rectilinear potentiometers for servo control systems and instrumentation transducers in aircraft and missile applications are being offered by **Markite Corp.**, 155 Waverly Pl., New York 14, N. Y. The precision components (Type 2986) are particularly applicable in designs with limitations and high performance, continuous duty requirements. These potentiometers are distinguished from conventional types in that the resistance element embodies two electrically solid raised tracks of conductive plastic integrally co-molded, together with taps and terminals, to an insulator base of high temperature phenolic resin of matched thermal expansion coefficient. The conductive plastic tracks afford virtually infinite resolution and extraordinarily long wear-life. They can be provided with a wide range of electrical resistivities. The potentiometers are also characterized



(Continued on page 150A)

10,523 STANDARD COAXIAL COMPONENTS "ON THE SHELF"

IMMEDIATE DELIVERY FROM STOCK!

FIXED ATTENUATORS
DC to 12,000 mc
0 to 80 db
1.2 max. VSWR
2, 5, and 15 watts



VARIABLE ATTENUATORS
DC to 10,000 mc
0 to 60 db
1.25 max. VSWR
Continuous or Turret



LOW PASS FILTERS
100 to 10,000 mc
1.3 max. VSWR
10 and 500 watts
Sharp cut-off.



HIGH PASS FILTERS
200 to 6,000 mc
1.8 max. VSWR
10 and 50 watts
Sharp cut-off



COAXIAL TERMINATIONS
DC to 13,000 mc
1.1 max VSWR
2, 10, 150 watts
Fixed and Sliding



POWER DIVIDERS
DC to 10,000 mc
2 to 6 outputs
Resistive — wide band
Reactive — min. loss



DIRECTIONAL COUPLERS
200 to 4,000 mc
Full octave Bandwidth
High directivity
Uni-bidirectional



CRYSTAL MIXERS
250 to 8,000 mc
Single ended or balanced
1.5 max. VSWR
Adjustable L.O. Injection



CRYSTAL MOUNTS
DC to 13,000 mc
Untuned, fixed tuned;
Padded; Tripolar
High Sensitivity



TUNERS
Stub Stretchers
Line Stretchers
Double Slug
Single, double, triple stub



MONITOR TEES
Used to separate DC or video currents from an RF signal. Indispensable for monitoring helix intercept current in traveling wave tubes.



SIGNAL SAMPLERS
Used to monitor signals present in coaxial systems. Permits small signal to be taken from system without adding discontinuity. Coupling continuously adjustable.

PRINTED CIRCUIT CONNECTORS
Side, end launchers
N, C, BNC, TNC
Screw-on or flange mounts.



DC BLOCKS/SHORTS
Sections of constant impedance transmission line with built-in blocking capacitor or DC by-pass.



- **All MICROLAB products are available FROM STOCK with Type N, C, HN, BNC or TNC male or female connectors.**
- **Special values, connector combinations and other special design features at same low cost and quick delivery.**
- **Prototype or production quantities at lowest cost.**

NEW CATALOG AVAILABLE

A new 72 page catalog listing thousands of stock coaxial components and product application information is now available from MICROLAB. Write on company letterhead for CATALOG NO. 10.

MICROLAB

Livingston, New Jersey WYman 2-5700

1/4%
ACCURACY
WITH
DIRECT READOUT
M/I

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 148A)

by low electrical noise and an ability to resist 70g vibration at 5 to 2000 cps as well as shock loading in excess of 100g without malfunction.

Offering independent linearities of ±0.5% or better, these potentiometers are available with element resistances ranging from 250 ohms to 50K ohms. Shaft stroke is 1.300″ electrical length is 1.000″; dielectric strength: 1500v rms. Shorter electrical lengths and other element resistances can be furnished. The units are designed to military environmental specs and special requirements.

Solid State Power Pack Catalog

Electronic Research Associates, Inc., 67 Factory Pl., Cedar Grove, N. J., announces the availability of a new two page color catalog sheet covering their expanded line of Hypac Miniaturized High Voltage Solid State Power Packs. This catalog sheet provides full descriptive and specification data on miniature types with voltage outputs starting at 1,000 and up to 20,000 vdc. Regulated as well as non-regulated units operating from either ac or dc inputs are described.

Also included in the catalog is full information on the company's new subminiature series in their Micropac line with similar technical ratings. Applications of these units include microwave tube powering, oscilloscopes, radar sets, dielectric testing and all types of high voltage uses.

The catalog is designated as #124.

Audio Tone Equipment

Audio tone equipment for transfer-trip applications (Type TA) using frequency-shift audio tones for either pilot-wire or microwave channels is available from **Westinghouse Electric Corp.,** P.O. Box 2099, Pittsburgh 30, Pa. The equipment is equally adaptable to direct underreaching, permissive underreaching, or permissive overreaching transfer-trip relaying.



To insure against undesired tripping, and to allow testing of the tone channel while the equipment is in service, two tones may be used with their trip contacts in series. The tone frequencies are from 595 to 2975 cps with 340-cycle spacing. The operating time is approximately 1-cycle (60-cycle basis) pickup and dropout.

The power supply is capable of operating from 48-, 125-, or 250-volts dc, and consists of voltage-divider resistors and a filter capacitor. A 60-cycle ac power supply is available as optional equipment.

This equipment is completely transistorized and is of modular construction, using plug-in units for various combinations to meet the requirements of each specific application. Each module performs a single function, such as frequency determination, amplification, or filtering. The modules are of uniform height and plug into a chassis which is suitable for standard 19-inch rack mounting. The chassis also includes monitoring jacks for checking performance of the equipment.

3PDT High Speed Relay



A new 3PDT "Micro-Scan" high speed (600 microseconds) low level (microvolts) low thermal noise (less than 1 microvolt in 100K ohms) relay for sampling, multi-

(Continued on page 152A)

NEW
UNIVERSAL BRIDGE



Model 1313
Price $590

MEASURES:
L: ..... 1μH to 110H
C: ..... 1pF to 110μF
R: ..... 0.01Ω to 110MΩ
With ¼% Accuracy
EXCEPTIONAL RESOLUTION
5,000 divisions per range
BUILT-IN 1 AND 10Kc OSC/DET
100 cps to 20 Kc with ext. osc.
Automatic dial mechanism eliminates multiplying factors, giving surprising ease of use.

ASK FOR FULL DESCRIPTION NOW

MARCONI
INSTRUMENTS
DIVISION OF ENGLISH ELECTRIC CORPORATION
111 CEDAR LANE ● ENGLEWOOD, NEW JERSEY
MAIN PLANT: ST. ALBAN'S, ENGLAND



with telrex
"BEAMED-POWER" ANTENNAS

NOW MAILING! PL88 — technical data, pricing bulletin describing Advanced-design commercial and citizen-band base-station antennas and accessories. Includes Tower, Rotator, "Baluns," Masting and Transmission line data, plus nice-to-have-around "info." Request your copy, today; no obligation.

WORLD RENOWNED AND RESPECTED PERFORMANCE –6 to 1500 MC.

ANTENNAS SINCE 1921
Communication and TV Antennas
telrex LABORATORIES
ASBURY PARK 46, NEW JERSEY, U.S.A.

WHY READ THE AD



when you can mail in a bingo card?

People have been grabbing free literature since the Middle Ages, when Bibles were chained to lecterns to keep people from taking them home.

The man who fills in a bingo card is primarily interested in free literature. Because he has mailed the card, he need not read your ad. He has made no decision to buy. In fact, the bingo card has given him an out—he has *put off* a decision to buy, perhaps forever.

The bingo card provides a publication with an out, too. It takes away the selling action of your ad, and transfers it to your direct mail, which is always expensive.

Proceedings of the IRE believes that the dual function of advertising is to make known and to sell. That is why *Proceedings,* almost alone among electronics publications, has no bingo card. It offers you instead:

1. far and away the largest pre-selected readership in the field; 75,727, average total paid (ABC) as of June 1961; 70,639 readers who are highly-qualified electronics engineers!
2. unmatched editorial excellence; *Proceedings* is the most highly-technical electronics journal published anywhere!

Electronics engineers know: a manufacturer dare not advertise his product in *Proceedings* unless it can stand up to the scrutiny of the nation's finest electronics minds. Manufacturers know this, too: that is why they use *Proceedings* to spell out, in precise terms, what their equipment is capable of doing and how accurate it is.

Match your advertising to *Proceedings*' editorial, and you'll never need a bingo crutch again.

For rate card, and copy of our merchandising cooperation plan, write or call today:

Proceedings of the IRE

Adv. Dept., 72 West 45th St., N. Y. 36. MU 2-6606

Unusual Shapes?

Weldable Leads?

Temperature-Stable?

Modular Size?

HIGH Capacitance?

LOW Capacitance?



MUCON

can include all in ONE

SUBMINIATURE CERAMIC CAPACITOR

MUCON can give you the capacitor for your most unusual requirements
Send your specs. in today!

MUCON CORPORATION

9 St. Francis Street, Newark 5, N. J.
Mitchell 2-1476, 7, 8

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 150A)

plexing, time sharing and control circuits is now available from **James Electronics, Inc.,** 4050 N. Rockwell St., Chicago 18, Ill. The 3PDT construction permits complete switching of low level two wire transducer data plus the associated guard shield allowing differential input isolation, low loss and high speed control. Rugged center pivot reed construction permits reliable performance under extreme military and commercial environment conditions, providing a life expectancy in excess of 1,000,000,000 operations. Prices range from $30 to $40 ea. Delivery of sample from stock, production quantities in 4 to 6 weeks.

Shaft Position Encoders

Northern Precision Laboratories, Inc., 54 Commerce St., Franklin Lakes, N. J., presents a new line of Analog-to-Digital Shaft Position Encoders based upon the Gray Code format. Units are available in ranges from 2^5 to 12^{13}. Precious metal alloy code drums are utilized in lieu of etched or plated discs. Multi-strand wipers are used on each track to increase reliability and to reduce noise. Units satisfy or exceed all applicable requirements of MIL-E-5272 and MIL-T-5422.

NEW

Important 120 page book . . . of interest to people in the

SOLID STATE FIELD

Instructions — Outline — Pre-Index for

SOLID STATE ABSTRACTS ON CARDS

Solid State Abstracts on Cards provides a cumulative reference file to the technical literature of solid state physics and electronics. The 120 page book, written by Geoffrey Knight, Jr., Ph.D. editor of *SOLID STATE ABSTRACTS JOURNAL*, completely describes the fundamental classification system used . . . together with suggestions for the effective use of Solid State Abstracts on Cards. Keep well informed . . . send for your copy today . . .

FREE

By writing direct to publisher

CAMBRIDGE COMMUNICATIONS CORPORATION

238 MAIN ST., CAMBRIDGE 42, MASS

Polarad Appoints Schindler

Appointment of Joe P. Schindler as director of marketing was recently announced by Paul H. Odessey, executive vice president of the **Polarad Electronics Corp.,** 43–20 34th St., Long Island City 1, N. Y. In this new capacity Schindler assumes the responsibility of achieving Polarad's future sales goals. The complete industrial sales complex, which includes the Industrial Sales, Advertising, and Market Research Departments, is now combined under the administration of the Director of Marketing.

Schindler joined Polarad in 1950 as a project engineer. In this position he was engaged in the development of microwave signal generators and receivers. Since then he has been closely associated with the company's equipment development efforts, in the positions of Group Leader and Section Head.

In 1957 Schindler was appointed assistant to vice president in charge of engineering, and department head of the Ground Support Equipment development.

Transistorized Microwave Spectrum Analyzer

Polarad Electronics Corp., 43–20 34th St., Long Island City 1, N. Y., has developed a mobile, transistorized, microwave spectrum analyzer. The Model SA-84T covers the frequency range from 10 to 40,880 mc.

The instrument is capable of a number of operations, including spectral measurements, detection and identification of spurious signals, countermeasures analysis, measurement of frequency difference of two RF signals, testing microwave oscillators (magnetrons, klystrons, and so forth) for pulling, double-moding, and other types of malfunctions, checking the tracking of radar components, and measurement of spectral characteristics of pulse modulated and FM signals.

This spectrum analyzer is suited to mobile operation because of its light weight (70 pounds), its extensive transistorization, and its acceptance of either standard 12-volt automobile battery power or 115 volt ac power. The SA-84T incorporates several

other features, such as a single tuning unit covering the entire frequency range, a direct-reading frequency dial, a self-contained frequency marker for measuring small frequency differences, a completely transistorized, electronically regulated power supply, adjustable frequency dispersion, single-knob UNIDIAL tuning, and low incidental frequency and amplitude modulation.

Literature further describing the SA-84T is available from the firm.

Automatic Vacuum-Tube Voltmeter

A simplified direct-reading DYNAMATIC 375 VTVM automatic vacuum-tube voltmeter that provides quick, direct, error-free readings without multiplying, is announced by **B&K Manufacturing Co.,** 1801 W. Belle Plaine Ave., Chicago 13, Ill.

In the DYNAMATIC 375 there is an individual wide-view scale for each range, and all scales are direct reading. Every scale is the same full size and only one scale is visible at any one time. Once you set the range switch properly, it is impossible to read the wrong scale.

Utilizes a single DC-AC ohms probe, anti-parallax mirror, and other features. Includes a swivel stand which permits tilting the instrument to any desired viewing angle, or swings up as a convenient carry-handle.

Ranges: DC volts—0–1.5, 5, 15, 50, 150, 500, 1500. AC Volts (rms)—0–1.5, 5, 15, 50, 150, 500, 1500. AC Volts (peak-to-peak)—0–1.5, 5, 15, 50, 150, 500, 1500. DC Current—0–5 ma, 50 ma, 500 ma. Ohms—0–500 ohms, 5 k, 50 k, 500 k, 5 meg, 50 meg, 1000 meg.

Input Resistance: 11 megohms on all DC ranges. Accuracy: ±3% full scale AC and DC. Meter Movement: Sensitive 100 microampere. Precision Multiplier Resistors: ±1% accuracy.

Includes 1½ volt battery. Operates on 117 volts 50 to 60 cycles ac. Sturdy metal case. Size $10\frac{3}{4}'' \times 6\frac{3}{4}'' \times 4''$. Net wt: 8 lbs. Net Price, $89.95.

For further information, write for catalog AP18 to the firm.

Blair President Feldmann Chairman of FXR Division

Neil M. Blair, president of the RF Products Division of Amphenol-Borg Electronics Corp., was named president of **Amphenol-Borg's FXR Division.**

Henry Feldmann, chairman and president of FXR, Inc., before it was merged May 31 with Amphenol-Borg, will continue as chairman of the FXR Division, Matthew L. Devine, president of Amphenol-Borg announced. Feldmann was recently elected to the board of directors of Amphenol-Borg. FXR, of Woodside, N. Y., is a major manufacturer of microwave test instruments and associated high-frequency equipment.

Blair

Feldmann

Blair joined Amphenol-Borg in 1959 after serving as vice president and assistant to the president of Intelex Systems, Inc., a subsidiary of ITT.

"Blair brings to FXR both an excellent technical background in electronics and a record of accomplishment in management and manufacturing," Devine said.

Thermoelectric Modules Cooling/Heating

A new line of thermoelectric modules which uses 1/10 the amount of current normally required to do an equivalent job

(Continued on page 154A)

NEW

RELIABILITY DELIVERED

SUBMINIATURE COAXIAL R F CONNECTORS

SMALLEST, LIGHTEST, MATCHED IMPEDANCE SUBMINIATURE CONNECTOR AVAILABLE

NOW . . . from MICON . . . 50 ohm connectors available in screw on . . . snap on . . . and crimp on types. Only MICON offers the most extensive line of matched impedance bulkhead, chassis, line and printed wiring board connectors.

MICON Evaluation Kit Available On Request

MICON ELECTRONICS, INC.
ROOSEVELT FIELD.
GARDEN CITY, L. I., NEW YORK
a wholly owned subsidiary of Metalcraft, Inc.

KODAK IRTRAN OPTICAL ELEMENTS

. . . for efficient transmission of infrared and microwaves despite heat and shock

Kodak has developed a new class of "optical" materials for missiles, radiometers, space vehicles, laboratory instruments, and other infrared and microwave applications. They keep much of their high transmittance when hot, 600°C and beyond. Thermal shock, humidity, abrasion, weathering, organic solvents, 0.5N HNO_3, 1N H_2SO_4, 0.5N KOH, 0.5N NH_4OH do not injure them. The curves look like this:



Irtran-1 material seems to provide the best present answer to the "dual-mode" problem. Infrared and microwave guidance can look through the same window. At 9.4 kmc its dielectric constant is around 5 and its loss tangent 10^{-4}. One untuned sample .012" thick we tested in the X-band introduced an attenuation of less than 0.3db, with a maximum standing wave ratio of 1.5. In the infrared at 1μ its refractive index is only 1.38. No need for anti-reflection coatings, you see.

Irtran-2 material, in contrast, has the relatively high infrared refractive index of 2.2.

Both of these materials we form and polish into lenses, domes, prisms, and flats. We also use them as substrates for infrared band-pass filters. Currently our limiting diameter is 6½"; the thickness limit for Irtran-1 materials is 3" and for Irtran-2, 1".

Of course, our connection with infrared technology doesn't end with Irtran optics. We also make Kodak Ektron Detectors and build complete infrared systems. Details on all these subjects from—

EASTMAN KODAK COMPANY
Apparatus and Optical Division
Rochester 4, N.Y.

Kodak TRADE MARK



Write For This Free Catalog!

6 colorful, fully illustrated pages on new, expanded applications for Phelps Dodge Styroflex®, Spirafil and Foamflex Air Dielectric coaxial cable . . .

- Delay Lines
- Custom Cut Lengths
- Special Bent Shapes
- Connector Fitting
- Electrical and Mechanical Testing
- Feed Networks

A-T ELECTRONICS, INC.

11 Lawrence Street
New Haven 8, Conn.
Fabricators-Distributors of
Phelps Dodge Coaxial Cable.



NOW WITH SPDJ*

MODEL **5015A**

SEMICONDUCTORIZED POWER SUPPLY

0-50 V.D.C. • 0-1.5 AMP

**All Silicon Small-Signal Transistor Amplifier with Planar Diffused Junction Input Stage*

High stability solid state DC power supply with adjustable current limiting, .05% regulation, 500 μv ripple, .01 Ω source impedance, 50 μs response time, .01 volts drift/24 hours, 55-440~ input.

$234.50 F.O.B. FACTORY

IMMEDIATE DELIVERY

Write For Complete Catalog

Power Designs inc.
1700 SHAMES DRIVE
WESTBURY, L. I., N. Y.
EDgewood 3-6200 Area Code 516

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 153A)

of cooling or heating has been engineered by **Jepson Thermoelectrics, Inc.,** 139 Nevada St., El Segundo, Calif.



Specifications:

	Model 615	Model 629
Operating Current (DC):	0–3.5 amps	0–3.5 amps
Operating Voltage:	0–2 VDC	0–4 VDC
Max. Heat Pumping Capacity:	4.25 watts	8.6 watts
Max. Delta T: (module mounted on +20°C sink)		
in open air:	60°C	60°C
in vacuum:	74°C	74°C
Max. Operating Temperatures:	−130°C to +125°C	−130°C to +125°C

Modules may be operated in any position and are designed to withstand military environmental conditions. They are supplied mounted on a 0.06″ thick anodized aluminum base with provision for mounting screws. Modules can be used to cool electronic components such as diodes, rectifiers, transistors, and so forth and laboratory instrumentation devices, while having possible consumer product applications since thermoelectrics eliminate the noise and bulk of motor compressor refrigerator units.

Rack & Panel Connectors



Methode Electronics, Inc., 7447 W. Wilson Ave., Chicago 31, Ill., has just announced the introduction of their "Reli-Acon" Paired Connectors for rack and panel applications. The design, employing precision stampings, provides equal or greater ruggedness and reliability at relatively lower cost than connectors using machined contacts.

The 2P-SD-600 Series receptacle and the 2P-MD-600 Series plug are suited to multi-circuit switching or re-routing applications. The glass filled "Diall" insulator provides dimensional stability and high resistance at elevated temperatures. Female contacts are designed to provide low millivolt drop after repeated insertions and assure positive contact under extreme vibration. Contacts are of spring tempered, gold-plated phosphor bronze which will neither tarnish nor corrode. They provide good solderability for an indefinite period. Mounting plates are cadmium plated steel to meet extreme environmental conditions. Optional floating mounting grommets allow for misalignment during mating. Polarizing pins provide mating.

Complete information about this connector is available from the firm.

Precision Potentiometer Winder and Tension Catalog Page

Catalog sheet, just released, illustrates and describes Model 435-AML Precision Potentiometer Winder, which has a differential action permitting a ±7% fine adjustment of nominal pitch, and Model T-435 tension, for winding very fine wire (0.010″ to 0.0004″) on round mandrels. Available from **Geo. Stevens Mfg. Co., Inc.,** Pulaski Road at Peterson, Chicago 46, Ill.

Transistorized Military Dual Display TV Monitor

Two fully transistorized MIL Spec TV Monitors on a single 10½″ high rack mounted chassis are now available from **RMS Associates, Inc.,** 805 Mamaroneck Ave., Mamaroneck, N. Y.



Type M20002 features two 5½″×5½″ presentations. Conventional 3:4 aspect ratios are also available. Two independent 5.5 Mc video amplifiers and two independent horizontal deflection amplifiers are used. The vertical deflection amplifier is common for both monitors.

Designed to meet MIL Specs, the unit is suited for installation in ground or air transportable monitoring stations, where ruggedness and reliability are important.

The Dual Display TV Monitor is packaged on a 19″W×10½″H×17″D rack mounted chassis and weighs less than 35 pounds. Power consumption of the Type M20002 is less than 150 watts. Type M20001, which consumes less than 75 watts, is the same as the M20002 but is designed to operate from a group of power supplies normally available in ground equipment.

The price of the M20001 is $5750, and the M20002 is $6350, with delivery in 60 to 90 days.

Detailed specifications are available from RMS Associates, Inc.

(Continued on page 156A)

NOW IN WAVEGUIDE ... the best way yet to measure complex impedances



Here is the first major breakthrough in the measurement of complex impedance over a band of frequencies. For speed, simplicity, and reliability, it surpasses anything yet used. It's the Smith Chart Plotter, developed by Dielectric Products Engineering Company to obtain instantaneous Smith-Chart display of reflection coefficient as a function of frequency.

Recently 50-ohm coaxial models were announced. *Now these instruments are available in waveguide as well.* Five resolver models span the range 350 to 12000 mc/s. Calibrated mismatch loads are also available.

This unique instrument — along with appropriate auxiliary equipment to form the complete plotter — eliminates the need to tie up highly skilled technical personnel during prolonged test routines that characterize slotted line measurements.

HOW IT WORKS

With Dielectric's Smith Chart Resolver, a swept-signal generator sweeps repetitively over the frequency band desired. The reflection coefficient of the unknown load is resolved into its X and Y components, which are then applied to the X and Y amplifiers of an oscilloscope equipped with a Smith Chart faceplate. A continuous trace of reflection coefficient versus frequency is thus displayed directly. The faceplate can be either a full-scale chart, or one expanded to 1.5:1 VSWR.

As load changes or adjustments are made, impedances change. Simultaneously so does the trace . . . load changes are observed immediately. When a permanent record is required, the oscilloscope trace may be directly photographed. Or, if preferred, an X-Y chart recorder may be used.

If you're looking for a way to speed up impedance measurements on antennas, filters, load resistors, transformers and other r-f networks, the Smith Chart Plotter is the essential tool. It's more accurate, too.

And there is more to come. For the measurement of r-f impedance in systems at any power level to the highest that can be generated, in either waveguide or coaxial line, other forms of the plotter will soon be available to supply a Smith Chart display. These will be particularly useful as system monitors.

SPECIFICATIONS

Nominal impedance ..... Z_o (Waveguide)
RF input voltage ..... 0.35 volts, rms
Oscilloscope signal voltage ... 0.2 volts input required for full scale deflection on expanded Smith Chart (1.5 VSWR max) for DC oscilloscope having 1 centimeter/millivolt sensitivity
Accuracy of reflection coefficient measurement see graph below
Sweep rate (maximum) ..... 60 sps
Spot rotation rate (maximum for full accuracy) ... 1000 rev/sec
RF input-output terminals ..... Optional
Automatic level control terminals ..... BNC (where required*)

*ALC information supplied with unit.

For complete description, ask for Bulletin 60-3. You'll get the latest revision and supplement which include both waveguide and coaxial units.



Other areas of **DIELECTRIC** capability in coaxial, waveguide and open wire techniques . . .
TRANSMISSION LINE & COMPONENTS • NETWORKS • SWITCHES • TEST EQUIPMENT • R&D ENGINEERING

dial DIELECTRIC for solutions to communications problems.

DIELECTRIC PRODUCTS ENGINEERING CO., INC.

RAYMOND, MAINE

SPECTRUM TRANSLATOR



600 CPS to 18 KC

Variable positioning and/or inversion of audio spectrums for use with spectrum analyzer systems. Accommodates the translation of an input audio frequency baseband of zero to 60kc through an output spectrum window from 600 cps to 10kc with variable frequency positioning and selective channel inversion of the input signal. Provides spectrum processing for real time spectrum analysis equipment or other applications. *Write for complete information.*

RIXON

ELECTRONICS, INC.
2121 Industrial Parkway
Montgomery Industrial Park
Silver Spring, Md. Phone 622-2121



BROAD BAND CAVITY WAVEMETERS

—gas filled for sustained accuracy

Accuracy is so high these instruments may be used as secondary standards. Units are unaffected by changes in humidity, altitude or barometric pressure. Only 12 sizes serve from 2.6 KMC to 140 KMC. You save budget money on the number of sizes needed. Literature on request.

DE MORNAY BONARDI

DE MORNAY–BONARDI
780 SOUTH ARROYO PARKWAY • PASADENA, CALIF.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 154A)

Edgewise Meters

A line of long-scale, three-inch edgewise DC and AC meters has been developed by **Minneapolis-Honeywell Regulator Co.,** Precision Meter Division, Grenier Field, Manchester, N.H., for use in control console and equipment applications where reliable indication is required under severe environmental conditions.



The new instrument, hermetically sealed, is available in a broad selection of DC current (200 micro-amperes and up) and voltage ranges, as well as in rectifier-type AC styles.

The mechanism is shielded so that the panel material has no influence on calibration.

The instrument, known as MDE-3, may be mounted horizontally or vertically. Its case size (3.7 by 6.1 by 1.3 inches) makes it possible to mount the meters close together and to obtain in-line readout.

The company reports that availability of the meters is within 60 days.

For further information contact the firm.

Transistorized Modular Instruments



Completely solid state, the 1800 Series instruments designed by **Burr-Brown Research Corp.,** Box 6444, Tucson, Ariz., employ standard sub-modules including differential and chopper stabilized operational amplifiers to provide a variety of gain ranges, gain steps, frequency responses and outputs. A typical instrument provides variable gain of 0 to 1000 over 0 to 20,000 cps with an input impedance greater than 1 megohm and an output impedance suitable for driving to 100 ma galvanometer. The 1800 Series features a plug-in modular package with up to 8 units accommodated in a $5\frac{1}{4}'' \times 19''$ standard rack.

Price and availability: Prices range from $225 to $575 for the various models. Delivery is from stock to 60 days after receipt of order.

Low-Power Tube Handbook

A handbook published for design engineers with complete descriptions of low-power tubes for industrial, military and communications applications, has been made available by **Raytheon Co., Industrial Components Div.,** 55 Chapel St., Newton 58, Mass.

Besides charting all specifications, the eight-page booklet also diagrams each tube's base and envelope connections.

Low-power transmitting tubes, series regulators, rectifiers and clipper tubes are included in the three-color handbook, which also discusses military specifications and quality control techniques Raytheon tubes are required to meet.

A free handbook may be obtained from William Weed at the firm.

Stabilization Networks

Line stabilization networks for use in making radio frequency interference measurements have been added to the series of standard interference control components available from the **Sprague Electric Co.,** 235 Marshall St., North Adams, Mass.



Networks now available include Type JN17-852 to meet the requirements of Military Specification MIL-1-6181, Type JN17-586 to meet MIL-1-16910, and Type JN17-853 to meet MIL-1-26600. All three of these military specifications require the use of stabilization networks in order to assure co-relation of data between measurements made in different laboratories, it was said by Frederick S. Scarborough, manager of Sprague's interference control field measurement service.

The new Sprague line stabilization networks are described in detail in Engineering Bulletin No. 8490, available upon letter head request from the Technical Literature Section, Sprague Electric Co.

(Continued on page 158A)



WHY CHASE GHOSTS?

That's exactly what some IRE member-engineers are doing —chasing the ghosts that haunt your TV screen. For years, they've been avidly studying what causes these ghost images, and what to do about them. Their researches have led to quiet but tangible improvements in TV equipment, including antennas, and in your final enjoyment as you watch your home screen.

Last year, outstanding contributions to the theory and technology of antennas were made by Helmut L. Brueckmann, of Fort Monmouth, N. J. The IRE proudly awards him the Harry Diamond Memorial Prize, 1961, saluting him along with countless others who are perfecting the art of radio and television.

The researches and findings of electronics engineers like Mr. Brueckmann are published each month in *Proceedings of the IRE*. Advertise your electronics product in *Proceedings*, and you make your firm a partner in this worthwhile publishing enterprise.

Proceedings of the IRE

gives to the nation
man's finest research in electronics

Adv. Dept., 72 West 45th Street, New York 36 • MUrray Hill 2-6606

ANTENNA PEDESTAL SCR 584—MP 61B

Full azimuth and elevation sweeps 360 degrees in azimuth. 210 degrees in elevation. Accurate to 1 mil. or better over system. Complete for full tracking response. Angle acceleration rate: AZ, 9 degrees per second squared EL, 4 degrees per second squared. Angle slewing rate: AZ 20 degrees per sec. EL. 10 degrees per sec. Can mount up to a 20 ft. dish. Angle tracking rate: 10 degrees per sec. Includes pedestal drives, selsyns, potentiometers, drive motors, control amplidynes. Excellent condition. Quantity in stock for immediate shipment. Ideal for missile & satellite tracking, antenna pattern ranges, radar systems, radio astronomy, any project requiring accurate response in elevation and azimuth.

Complete description in McGraw-Hill Radiation Laboratory Series, Volume I, page 284 and page 209, and Volume 26, page 233.

MIT MODEL 3 PULSER

Output: 144kv (12kv at 12 amp). Duty ratio: .001 max. Pulse duration. .5 1 and 2 micro sec. Input: 115v 400 to 2000 cps and 24vdc. $325 ea. Full desc. Vol. 5 MIT Rad. Lab. series pg. 140.

AN/TPS—10D HEIGHT FINDER

250 KW X-Band. 60 & 120 mile ranges to 60,000 feet. Complete.

500 KW PULSER

5C22 Hydrogen Thyratron Modulator. 22KV at 28 Amps. W/HV & Fil supplies. 3 pulse length rep rates: 2.25 μsec 300 pps. 1.75 μsec 550 pps. .4 μsec 2500 pps. 115V 60cy AC input.

60 MC I.F. STRIP

—95 DBM sensitivity. 130 DB gain. 1 MC & 5 MC band widths. Mfg. Texas Instruments. $125 each w/tubes.

AN/TPS-1D RADAR

500kw. 1220-1359mcs. 160 nautical mile search range P.P.I. and A Scopes. MTI. thyratron mod. 5J26 magnetron. Like new. Complete system incl. spare parts and gas generator field supply.

225 KW X-BAND RF

4J50 Magentron RF Generator with dummy load & Dir. Cplr. Variable rep rates. Variable power output. 115V 60-cycle AC input. New. $2400 complete.

WESTINGHOUSE 3CM RADAR

Complete X band system oper. from 115v 60cy ac with 40 kw power output 2J55 magnetron. Ranges 0-1.5, 4, 16, 40 miles. Includes installation waveguide. An ideal system for lab school, demonstration or shipboard. $1800. New with spares.

10 CM. WEATHER RADAR SYSTEM

US Navy Raytheon. 275 KW peak output S band. Rotating yoke Plan position Indicator. Magnetron supplied for any S band frequency specified, incl. Weather Band. 4, 20 and 80 mile range 360 degree azimuth scan. Senslitve rcvr usink 2K28/707B and 1N21B. Supplied brand new complete with instruction books and installation drawings. Can be supplied to operate from 32VDC or 115 volts. Price $975. Ideal for weather work. Has picked up clouds at 50 miles. Wight 488 lbs.

10KW 3 CM. X BAND RADAR

Complete RF head including transmitter, receiver, modulator. Uses 2J42 magnetron. Fully described in MIT Rad. Lab. Series Vol. I, pps. 616-625 and Vol. II, pps. 171-185, $375. Complete X band radar system also avail. inclu. 360-deg antenna, PPI, syn pwr supply. Similar to $17,000 weather radar now in use by airlines, $750 complete.

AN/APS-15B 3 CM RADAR

Airborne radar. 40kw output using 725A magnetron. Model 3 pulser. 30 in. parabola stabilized antenna. PPI scope. Complete system. $1200 each. new.

SCR 584 RADARS

AUTOMATIC TRACKING RADAR

Our 584s in like new condition, ready to go, and in stock for immediate delivery. Ideal for research and development, airway control, GCA, missile tracking, balloon tracking, weather forecasting, antiaircraft defense tactical air support. Write us. Fully Desc. MIT Rad. Lab. Series. Vol. 1, pps. 207-210, 228, 284-286.

RADIO RESEARCH INSTRUMENT CO.

550 FIFTH AVE. NEW YORK JUDSON 6-4691

PROBING THE "TRANSPROBE" WAVEGUIDE SWITCH



The only moving parts of the "Transprobe" are solenoid plunger and a light weight, dielectrically supported metal probe. Result... greater flexibility, longer life, ability to switch under full waveguide power. The design can be applied to any waveguide size. Unit shown is a single-pole-double-throw, X-band switch. The design is equally successful for adaptation to SPDT, SP3T, transfer switch or special configurations. Typical specifications: Frequency... 8.2-12.4 KMC, VSWR... 1.20, Insertion Loss... 0.2 db, Crosstalk... 35 db, Life... 2,000,000 operations. To probe more thoroughly the unusual advantages in this new approach to waveguide switching write Transco Products, Inc., 12210 Nebraska Avenue, Los Angeles 25, California.

TRANSCO

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 156A)

Laboratory-Standard Antenna Set



Presently available from **Empire Devices, Inc.,** Amsterdam, N. Y., is a Standard Antenna Set, Model SA-301, which permits laboratory standardization of field strength from 10 kc to 300 mc. This set is used for the accurate calibration of field intensity meters. The ability of these units to generate an accurately-known field from 10 kc to 30 mc and to measure accurately an unknown field from 30 mc to 300 mc suggests a wide variety of applications. The set, when used with an RF signal source, is complete with all items needed to perform calibration. Components furnished include all necessary loop and dipole antennas, baluns, tripods, precision meters, cables and other accessory items.

All components correspond to a set developed by Empire Devices and certified by the National Bureau of Standards; a copy of the certification report is available from the firm upon request.

Further details, including a description of the calibration techniques with appropriate formulas, are available from Empire.

Tuned Amplifier-Null Detector

A low-noise, transistor amplifier with 1-microvolt full-scale sensitivity, which tunes continuously from 20 cps to 20 kc, with additional fixed-tuned frequencies of 50 kc and 100 kc, has been announced by the **General Radio Co.,** West Concord, Mass.



Known as the Type 1232-A Tuned Amplifier and Null Detector, it is intended primarily as a bridge detector, but has other applications, among them the detection of high-frequency modulated signals (with a crystal demodulator), approximate wave analysis at audio frequencies and as a preamplifier for transducers.

(Continued on page 160A)

THE ONLY SIMPLE FORMULA FOR

COMPLETE INTERFERENCE MEASUREMENTS



Through years of hard field use Model NF-105 has acquired an outstanding reputation as a noise and field intensity meter for the frequency range from 150 kilocycles to 1000 megacycles. The versatility of this instrument has now been expanded through the introduction of a new tuning unit extending its coverage down to 14 kilocycles. What is more, this unique measuring equipment has been joined by Model NF-112 which covers the frequency range from 1000 to 10,000 megacycles. The same simplicity, accuracy and speed of operation and reliability of performance which made Model NF-105 so successful have been designed into Model NF-112. Each instrument uses an impulse generator as its calibrator; each combines in one basic unit the components common to all frequency ranges, including the power supply, calibrator, attenuators and metering circuits. All frequency determining components and circuits are contained in plug-in tuning units. Model NF-112, incidentally, uses one single antenna for the entire range from 1000 to 10,000 megacycles.

You save considerably in SIZE, WEIGHT and COST by letting these two instruments do your entire interference measuring job from 14 KC all the way up to 10,000 MC.

For complete technical information, send for Catalog 614.

Plan to attend our next seminar on interference instrumentation. Details upon request.

ed EMPIRE DEVICES, Inc.
AMSTERDAM, NEW YORK • VICTOR 2-8400

MANUFACTURERS OF: FIELD INTENSITY METERS • DISTORTION ANALYZERS • IMPULSE GENERATORS • COAXIAL ATTENUATORS • CRYSTAL MIXERS

PROFESSIONAL CONSULTING SERVICES

Advertising rates

Professional Consulting Service Cards.

1 insertion $ 30.00
12 insertions $240.00
50% discount to IRE members on 3 or more consecutive insertions.

In IRE DIRECTORY $30.00 flat rate

New rate effective January 1962
1 insertion $35.00
12 insertions $300.00
50% discount to IRE members on 3 or more consecutive insertions.
In IRE DIRECTORY $35.00 flat rate
1 inch only, no cuts or display type.

Advertising restricted to professional engineering and consulting services by individuals only. No product may be offered for sale, and firm names may not be mentioned in cards.

Prof. D. S. BUGNOLO, Sc.D.
Consultant
Satellite & Space Communication
Propagation, Antennas, Information Theory
61 Lillian Place Red Bank, N.J.
SHadyside 7-1549

M. D. ERCOLINO
Antenna Laboratories and Engineering Staff
Consultation and Development
Antennas, Systems, Baluns, Rotators, Rotatable Antenna Masts
Asbury Park, N.J. PRospect 5-7252

SIDNEY FRANKEL, Ph.D.
& associates
Engineering Research • Technical Consultation
Feasibility Studies
Communication and Control Systems
Radio and Radar Techniques
1165 Saxon Way Menlo Park, Calif.
DAvenport 6-9166

Proposals Research Development
Reports Prototype Units
DR. A. W. FRIEND, P. E.
CONSULTING ENGINEER
AND PHYSICIST
5903 City Avenue TEnnyson 9-3098
Philadelphia 31, Pa. MOhawk 4-0275

Consultation • Development • Product Planning
STEVEN GALAGAN
Consulting Engineer
Antennas—Microwave Components & Devices—Interference Control & Reduction—Propagation Studies—Microwave Relay—Feasibility Studies
30 Whittier Road . . . Wellesley Hills 81, Mass.
CEdar 5-6530

EARL GREENBERG & associates
TRANSISTOR CIRCUITS and CONTROLS
Digital and Analog Devices
Design - Development - Prototype Construction
11-16 154th Street Whitestone, New York
HIckory 5-2459

LEON HILLMAN
Engineering Staff and Laboratory
• Instrumentation • Control Systems
• Electronic Research and Development
255 County Rd., Tenafly, N.J. LOwell 7-3232

Engineering • Consulting • Proposal Assistance
S. HIMMELSTEIN
and staff
Magnetic Recording Systems
Computer Peripheral Equipments
Transports, Drums, Discs, Photoreaders, Circuitry
3300 West Peterson, Chicago 45 • IRving 8-9850

LEONARD R. KAHN
Consultant in Communications and Electronics
Single-Sideband and Frequency-Shift Systems
Diversity Reception - Stereophonic Systems
Television Systems
81 South Bergen Place, Freeport, L.I., N.Y.
FReeport 9-8800

(Continued from page 158A)

Continuous tuning is provided by an RC null circuit. Unlike conventional null circuits, this RC combination has only a single variable element, a potentiometer with a total range of 40 db.

The amplifier is frequency-selective and consists of three stages with negative feedback through a null network, which has its null at the desired operating frequency. Since there is negative feedback at all frequencies but the desired one, the overall response peaks at this frequency and is roughly equivalent to that of a tuned circuit with a Q of about 20 (5% bandwidth).

The amplifier can be switched to have either linear or logarithmic amplitude characteristics. Logarithmic response is desirable in bridge measurements, since it eliminates the need for adjustments in generator level during the bridge-balancing process. In audio spectrum analysis and in general amplifier applications, the linear response is preferable.

The gain of the amplifier is about 40 db and another 40 db of gain is supplied by an amplifier compressor, making the total gain of the amplifier about 120 db.

A full-wave rectifier is used in the meter circuit to double the ripple frequency that passes through the meter and thus to prevent the needle from vibrating visibly at 20 cps.

With the G-R Type 1632-A Inductance Bridge, this null detector makes possible inductance balances to a resolution of 1 part in 10^6.

The assembly is housed in a rack-bench cabinet 8″w×6″h×7½″d and is normally supplied for bench use. Panel extensions are available for relay-rack mounting.

Price of the Type 1232-A Tuned Amplifier and Null Detector is $360.00 f.o.b. West Concord, Mass.

THIN FILM and other MICROCIRCUITS
designed & developed
Distributed Parameter Networks; Deposition Tech.
2414 Reedie Drive, Silver Spring, Md.
M. A. KARP
staff and associates
Phone: 565-2896, Silver Spring, Md.

LEONARD J. LYONS
Consulting Mechanical Engineer
COOLING—HEATING—FLUID FLOW
Analysis and Testing.
Heat Transfer & Thermodynamic Problems
3710 Crestway Dr. AXminster 1-5446
Los Angeles 43, California

LEN MAYBERRY
ELECTRONICS CONSULTING ENGINEER
Laboratories and Staff
Transistorized Modular Equipment
Product Design • Test Equipment Design
111 South Oak Street ORegon 8-4847
Inglewood, California

E. M. OSTLUND & associates
Electronic Engineers
Radio—Microwave—Carrier—Communication—Control—Systems and Equipment
Consulting—Research—Development
ANDOVER, NEW JERSEY
Tel: PArkway 9-6635 P.E.N.J.

NATHAN GRIER PARKE
and staff
Consulting Applied Mathematicians
Research • Analysis • Computation
Bedford Road • Carlisle, Massachusetts
Area Code 617 • EMerson 9-3818

PAUL ROSENBERG
& associates
Established 1945
Consultation, Research & Development in Applied Physics
100 Stevens Ave., Mt. Vernon, New York
MOunt Vernon 7-8040 Cable: PHYSICIST

MYRON M. ROSENTHAL
& staff
Microwave & Electronic Systems
19 Brookline Dr., North Massapequa, N.Y.
PErshing 5-2501

Analysis—Research—Design
Electronics and Automation
GARDNER H. SLOAN
R & D Consultant
Electrical Engineer, Physicist
One Story Street Harvard Square
Cambridge 38, Mass. Eliot 4-0766

HAROLD A. WHEELER
Laboratories and Engineering Staff
Consultation—Research—Development
Radar and Communication Antennas
Microwave Assemblies and Components
Main office: Great Neck, N. Y. HUnter 2-7876
Antenna Laboratory: Smithtown, N. Y.

Advertising Index

IRE News and Radio Notes 14A
IRE People 44A
Industrial Engineering Notes 35A
Meetings with Exhibits 8A
Membership 92A
News—New Products 96A
Positions Open 99A
Positions Wanted by Armed Forces Veterans 106A
Professional Group Meetings 32A
Section Meetings 36A
Table of Contents 1A-2A

DISPLAY ADVERTISERS

ACF Industries, Inc., ACF Electronics Div. 110A, 125A
AC Spark Plug Div., General Motors Corp. 131A
A-T Electronics, Inc. 154A
ATR Electronics, Inc. 140A
Abbott's Employment Specialists 118A
Academic Press 138A
Accredited Personnel Service 106A
Ad-Yu Electronics Lab., Inc. 162A
Airborne Instruments Laboratory, Div. of Cutler-Hammer, Inc. 4A
Alden Products Company 44A
Alfred Electronics 63A
Allen-Bradley Company 33A-34A
American Machine & Foundry Co., Automatic Equipment Div. 116A
Andrew Corporation 86A
Angelica Uniform Company 36A
Armed Forces Communications & Electronics Association 32A
Armour Research Foundation, Illinois Institute of Technology 109A, 114A, 125A
Arnold Engineering Company 57A

Ballantine Laboratories, Inc. 82A
Bausch & Lomb, Inc. 48A
Bell Telephone Laboratories 6A
Bendix Corp., Scintilla Div. 27A
Binswanger Associates, Charles A. 110A
Boeing Company 128A
Boonton Electronics Corporation 161A
Bourns, Inc. 89A
Brew & Company, Inc., Richard D. 54A
Buckbee Mears Company 71A
Bugnolo, D. S. 160A
Bussmann Mfg. Div., McGraw-Edison Co. 133A

Cambridge Communications Corp. 152A
Capitol Radio Engineering Institute 62A
Cinch Mfg. Co., Howard B. Jones Div. 92A
Cohn Mfg. Co., Inc., Sigmund 53A
Columbian Carbon Co., Mapico Iron Oxides Unit 70A
Computer Diode Corp. 93A
Consolidated Reactive Metals, Inc. 136A
Cornell Aeronautical Lab., Inc. 100A, 113A, 130A
Corning Glass Works 83A
Cross Country Consultants 122A

Davies-Shea, Inc. 100A
Del Electronics Corporation 74A
Delco Radio Div., General Motors Corp. 21A, 135A
DeMornay-Bonardi 156A
Dialight Corporation 70A
Dielectric Products Engineering Co., Inc. 155A
Dikewood Corporation 108A

Eastman Kodak Company 153A

READ .0002 μμf

PRECISION 3-TERMINAL

(INSENSITIVE TO GROUNDED CAPACITANCE)

CAPACITANCE BRIDGES

MODEL 74C

- 100 KC Test Frequency
- 0.0002-11,000 μμf Generally 0.25%
- 1000 ohms to 1000 megohms Shunt Resistance
- 0.001 to 1000 μmhos Conductance

Price $935

MODEL 75A

- 1 Mc Test Frequency MIL SPEC. TESTING
- 0.0002 to 1000 μμf Generally 0.25%
- 1000 ohms to 100 megohms Shunt Resistance
- 0.01 to 1000 μmhos Conductance

Price $990

MODEL 74C-S8 (Shown)

- With −5 to +100V DC Bias for Diode Testing

Price $995

MODEL 75A-S8

- With −5 to +100 VDC Bias for Diode Testing

Price $1050

Boonton ELECTRONICS Corp.

MORRIS PLAINS, N. J. • Phone JEFFERSON 9-4210

NEW–DIGITAL PHASE METER

type 524

Features: Reading directly in degrees independent of ratio of signal amplitude. No frequency adjustment, no amplitude adjustment.

Specifications:

FREQUENCY RESPONSE: 50 cps to 40 kc.
ACCURACY: Relative ±0.1°, absolute ±0.5°.
PHASE RANGE: 0 to 360.0°, without range switching.
INPUT VOLTAGE: 0.3 volt to 50 volts rms.
PHASE INDICATION: Digital readout, with numerals 1" high, displayed in four digits.



Block Diagram



Plotting Phase Curve

AD-YU ELECTRONICS LAB., INC.
249 Terhune Avenue, Passaic, New Jersey

Advertising Index

Electro-International 74A
Electro-Mechanical Research, Inc. 113A
Electro Motive Mfg. Co., Inc. 78A
Electronic Measurements Co., Inc. 146A
Empire Devices, Inc. 159A
Engineering-Physics Company 100A
Epsco, Inc. 112A
Erco Radio Laboratories, Inc. 40A
Ercolino, M. D. 160A

FXR, Div. of Amphenol-Borg Electronics Corp. 90A
Fairchild Semiconductor Corp. 81A, 102A
Federation Nationale des Industries Electroniques 64A
Ferrotec, Inc. 60A
Ferroxcube Corp. of America 75A
Frankel, Sidney 160A
Freed Transformer Co., Inc. 134A
Friend, A. W. 160A

Galagan, Steven 160A
General Applied Science Laboratories, Inc. 142A
General Dynamics/Electronics, Div. of General Dynamics Corp. 116A
General Electric Co., Defense Systems Dept. 105A
General Electric Co., Heavy Military Electronics Dept. 118A
General Electric Co., Semiconductor Products Dept. 38A-39A
General Radio Company ..... Cover 4
Goodyear Aircraft Corp., Arizona Div. 110A

Lenkurt Electric's engineers create unique telecommunications systems for industrial, telephone, and defense requirements. Working in an independent and creative atmosphere, they have every opportunity to further their formal education, live in the West's outstanding climate, and enjoy unlimited cultural pursuits. Qualified *communications engineers* are now being added to the staff in the specialized fields of:



solid state circuitry • data transmission
sales • mobile radio • data transmission

Qualified specialists in these fields should send a resume or call collect to: *E. Jack Shannahan, Employment Manager · Lenkurt Electric Co., Inc. · 1105 County Road · San Carlos, California. LY 1-8461, Ext 281*

LENKURT ELECTRIC
Subsidiary of
GENERAL TELEPHONE & ELECTRONICS
GENERAL SYSTEM

Advertising Index

Gould-National Batteries, Inc., Nicad Battery Div. 139A
Greenberg, Earl 160A
Guilford Personnel Service 120A

HRB-Singer, Inc. 122A
Heath Company 148A
Hewlett-Packard Company 51A-52A
Hillman, Leon 160A
Himmelstein, S. 160A
Hitachi, Ltd. 141A
Huggins Laboratories, Inc. 87A
Hughes Aircraft Company, Aerospace Engineering Div. 98A
Hughes Aircraft Company, Market Development Div. 94A-95A

Industrial Electronic Engineers, Inc. 148A
Inland Motor Corporation of Virginia 47A
Institute of Radio Engineers 58A-59A, 120A, 137A, 151A, 157A
International Business Machines Corp. 85A

James Electronics, Inc. 68A
Jet Propulsion Laboratory, Calif. Inst. of Technology 107A
Johns Hopkins University, Applied Physics Lab. 114A

Kahn, Leonard R. 160A
Karp, M. A. 160A
Kay Electric Company 9A
Kearfott Div., General Precision, Inc. 127A
Keithley Instruments, Inc. 163A
Kepco, Inc. 53A
Kin Tel, Div. of Cohu Electronics, Inc. 35A
Kollsman Instrument Corp. 124A

Lambda Electronics Corp. 143A
Lenkurt Electric 162A
Lindberg Engineering Company 132A
Litton Industries, Inc., Electron Tube Div. 97A
Lockheed-California Company, Div. of Lockheed Aircraft Corp. 103A
Lockheed Missiles & Space Co., Div. of Lockheed Aircraft Corp. 123A
Lyons, Leonard J. 160A

Machlett Laboratories, Inc. 41A
Magnetic Metals Company 145A
Mallory & Co., Inc., P. R. 102A, 124A
Marconi Instruments 150A
Marconi's Wireless Telegraph Co., Ltd. 50A
Massachusetts Institute of Technology, Instrumentation Lab. 109A
Massachusetts Institute of Technology, Lincoln Lab. 120A
Mayberry, Len 160A
McDonnell Aircraft Corp. 101A
Measurements, McGraw-Edison Div. 164A
Micon Electronics, Inc. 153A
Microlab 149A
Microtran Company, Inc. 10A
Microwave Associates, Inc. 23A
Millen Mfg. Co., Inc., James 96A
Minneapolis-Honeywell Reg. Co., Precision Meter Div. 77A
Mitre Corporation 115A
Molecular Research, Inc. 118A
Monmouth County Planning Board 78A
Motorola, Inc., Military Electronics Div. 104A
Motorola Semiconductor Products, Inc. 88A
Mucon Corporation 152A
Mycalex Corp. of America 12A-13A

Narda Microwave Corporation 19A
National Cash Register Company 102A
Northrop Corporation 119A

Ohmite Manufacturing Co. 37A
Ostlund, E. M. 160A

NEW KEITHLEY AC AMPLIFIER

can increase scope sensitivity 1000 times!

The Keithley Model 103 gives you the best attainable signal-to-noise ratio for source impedances from 3000 ohms to over 10 megohms. (The equivalent input noise resistance on the low noise position is only 3 k ohms.) Bandwidth of .1 cps to 100 kc covers a wide range of uses; eleven high and low frequency cuts permit restricted bandwidths for minimum noise.

Applications include Hall Effect studies, bridge null detection, and semi-conductor investigations, as well as such biophysical applications as recording nerve action potentials.

The usefulness of the Model 103 is enhanced by its versatility:

NOISE can be improved by changing input impedance with a "Normal" and "Low Noise" switch. Chart below indicates noise levels with input shorted, gain 1000x, 10 cps to indicated cutoff:

Frequency of high cutoff point	Maximum noise, microvolts RMS referred to input	
	Normal (10 meg impedance)	Low Noise (100 k impedance)
100 kc	3.0	1.9
30 kc	1.9	1.1
10 kc	1.4	0.8
3 kc	0.9	0.6
1 kc	0.7	0.4
300 cps	0.5	0.3
100 cps	0.4	0.25

BANDWIDTH can be selected by using 11 high and low frequency cutoffs between .1 cps and 100 kc.

INPUT IMPEDANCE in the "Normal" mode is 10 megohms; in the "Low Noise" mode, 100 k ohms.

AMPLIFIER GAIN may be set at either 100 or 1000 and adjusted to precise values.

INPUT CONNECTIONS can be made single-ended or differential.

DIFFERENTIAL REJECTION is at least 80 db permitting increased signal-to-noise ratios in many applications.

POWER can be furnished by batteries or the Keithley Model 1031, a separate, solid state power supply with noise characteristics equivalent to battery operation.

PRICE: $245.00. Rack-mounted: $255.00

This oscillograph shows a 2 kc square wave of 5 microvolts peak-to-peak amplitude at input with the amplifier in "Low Noise" position. Horizontal calibration equals 200 μv per division; vertical equals 2 μv per division. Low cut is 10 cps, high cut 1 kc. The unusually low noise levels in the 103 are achieved through the use of ceramic tubes in cascode circuitry.



send for complete specifications in latest engineering note . . .

KEITHLEY INSTRUMENTS
12415 EUCLID AVENUE CLEVELAND 6, OHIO

electrometers • micro-microammeters • microvoltmeters • milliohmmeters

MEASUREMENTS' MODEL 139 I. F. TEST OSCILLATOR

A compact, versatile, portable instrument for rapid and accurate alignment of I-F circuits in all types of radio receivers. An ideal companion instrument for Measurements' Model 560-FM Signal Generator.

FEATURES

- **Four direct reading, individually calibrated frequency scales.**
- **Two independent crystal oscillators.**
- **Self-contained, regulated power supply.**
- **Wide range of output voltage.**

SPECIFICATIONS

Frequency Ranges:
A — 3-5 Mcs. C — 8-12 Mcs.
B — 5-8 Mcs. D — 12-20 Mcs.
Crystal 1 — 455 Kc (standard)
Crystal 2 — Optional

Frequency Accuracy:
±1% (Bands A-D) Crystal accuracy (Bands 1-2).

Output Voltage:
Minimum .5 volt into a 50 ohm resistive load.
May be attenuated at least 50 to 1 by means of a front panel control.

Power Supply:
117 volts, 50/60 cycles, 10 watts.

Dimensions:
6" wide x 8" high x 6" deep.

Weight:
7 pounds.

Recommended Accessories:
Terminated 50-ohm cable. (Part No. H-5626).

Price:
$165.00 with one 455 Kc crystal installed, F.O.B. Boonton, New Jersey. Second crystal optional.

Advertising Index

Panoramic Electronics, Inc. 11A
Parke, Nathan Grier 160A
Perfection Mica Company, Magnetic Shield Div. 76A
Pergamon Press, Inc. 56A
Perkin Electronics Corp. 8A
Permanent Employment Agency, Professional and Technical Recruiting Associates 112A
Phelps Dodge Copper Products Corporation 42A-43A
Philco Corporation, Lansdale Div. ..... Cover 3
Philco Corporation, Research Center 130A
Philco Corporation, Western Development Labs. 111A
Power Designs, Inc. 154A

Q-max Corporation 142A

Radio Corp. of America, Defense Electronic Products 73A
Radio Corp. of America, Semiconductor & Materials Div. 84A
Radio Materials Company, Div. of P. R. Mallory & Co., Inc. 61A
Radio Research Instrument Co. 158A
Ramo-Wooldridge Corporation 121A
Rantec Corporation 66A-67A
Raytheon Company, Microwave & Power Tube Div. 25A
Rixon Electronics, Inc. 156A
Ron Electronics Corporation 88A
Rosenberg, Paul 160A
Rosenthal, Myron M. 160A

Sanborn Company 69A
Sanders Associates, Inc. 108A
Scientific-Atlanta, Inc. 49A
Selenia S.P.A. 80A
Sensitive Research Instrument Corp. 7A
Simplex Wire & Cable Company 91A
Sloan, Gardner H. 160A
Space Technology Labs., Inc. 126A
Sprague Electric Company 3A, 5A, 45A
Stanford Research Institute 104A
Sylvania Electric Products Inc., Amherst Laboratories 99A
Sylvania Electric Products Inc., Applied Research Laboratory 117A
Sylvania Electric Products Inc., Electronic Systems Div. 129A
Syntronic Instruments, Inc. 144A

Technical Materiel Corporation 90A
Tektronix, Inc. 30A-31A
Telrex Laboratories 150A
Texas Instruments Incorporated, Apparatus Div. 29A
Texas Instruments Incorporated, Transistor Products Div. 55A
Topping Electronics, Ltd. 72A
Transco Products, Inc. 158A

U. S. Information Agency 128A
U. S. Stoneware Co., Alite Div. 79A
United Transformer Corp. ..... Cover 2
Universal Electronics 136A

Varian Associates, Tube Div. 17A
Vitro Electronics Div., Vitro Corp. of America 127A

Weinschel Engineering Co. 46A
Western Electric Company, Inc. 65A
Westinghouse Electric Corp., Baltimore Div. 117A
Westinghouse Electric Corp., Electronic Tube Div. 126A
Westrex Co., Div. of Litton Systems, Inc. 147A
Wheeler, Harold A. 160A
Wind Turbine Company 92A
Wollensak Optical Company 62A

NEW MEASUREMENTS Standard Signal Generator for mobile communications . . .

The Model 560-FM Standard Signal Generator is specifically designed to meet the exacting requirements of the Mobile Communications industry.

Model **560-FM**
Price - $640.00

- **Frequency ranges 25-54, 140-175, 400-470, 890-960 Mc.**
- **Fine tuning control shifts carrier ±8 Kc.**
- **Peak deviation to ±16 Kc. read directly on meter.**
- **Residual FM less than 100 cycles at 460 Mc.**
- **Output 0.1 to 100,000 microvolts accurate ±10% across 50 ohm termination.**
- **Excellent stability.**
- **Modulation by 1000 cycle internal or by external source.**

Laboratory Standards

WRITE FOR BULLETIN

MEASUREMENTS A McGraw-Edison Division
BOONTON, NEW JERSEY

PHILCO EPITAXIAL SILICON MESA



FIRST TO COMBINE

120 V (BV_{CBO})
0.5 V(*SAT*)
150 mc. f_T

2N2087 NPN
CORE DRIVER
LINE DRIVER

2N2087: ABSOLUTE MAXIMUM RATINGS

Storage Temperature .....−65 to +300°C.
BV_{CER} ($R \leqq 10\Omega$) .....80 volts
BV_{CBO} .....120 volts
BV_{EBO} .....5 volts
Collector Current I_C .....500 ma
Total Device Dissipation (case 25°C.) ....2 watts
Total Device Dissipation (case 100°C.) ...1 watt
Total Device Dissipation (free air 25°C.) .0.6 watt

ELECTRICAL CHARACTERISTICS (@ 25°C.)

Characteristics	Conditions	Min.	Max.	
h_{FE}	V_{CE} = 1V. I_C = 150 ma.	40	120	
V_{BE}	I_C = 150 ma. I_B = 15 ma.		1.2	volts
V_{CE}(SAT)	I_C = 150 ma. I_B = 15 ma.		0.5	volts
f_T	I_C = 50 ma. V_{CE} = 10V.	150		mc
C_{cb}	V_{CB} = 10V. I_E = 0 ma.		12	pf
I_{CBO}	V_C = 60V. T = 25°C.		2	μa
I_{CBO}	V_C = 60V. T = 125°C.		150	μa
BV_{CER}	R ≦ 10Ω I_C = 20 ma. pulsed	80		volts
t_r			85	nsec
t_s			100	nsec
t_f			55	nsec

You would expect Philco, as inventor of industry's most capable germanium logic transistor—the MADT, to design silicon memory components with extra capability, too. And Philco has done it. 2N2087 and 2N2086 Philco epitaxial silicon mesa transistors offer incomparable combinations of parameters that may well be the special design solutions you require.

The 2N2087 combines 120 BV_{CBO}, 40 h_{FE} min., 0.5 V. max. V_{CE} (SAT), 150 mc min. f_T, 12 pf max. C_{ob}, and 100 nsec max. t_s.

The 2N2086 combines h_{FE} of 20 min., 0.7 max. V_{CE} (SAT), 120 BV_{CBO}, 150 mc min. f_T, 12 pf max. C_{ob}, and 100 nsec max. t_s.

These new Philco epitaxial silicon mesa transistors deliver optimum drive for computer memory planes, serve as medium power switches in airborne control systems, and are ideally suited to a wide variety of other applications such as small power supplies, servo amplifiers, and automation controls. For complete information, write Dept. IRE1161.

Both types 2N2087 and 2N2086 are immediately available from your Philco Industrial Semiconductor Distributor.

PHILCO®

Famous for Quality the World Over

LANSDALE DIVISION, LANSDALE, PENNSYLVANIA

TRANSISTOR CENTER U.S.A.®

1000-Mc Standard



Short-term and long-term stabilities comparable to the best crystal controlled standards available . . . at less than ⅔ the price!

Outputs from 100c to 1000 Mc at decade intervals, plus 60c, 400c, and 5 Mc . . . more outputs than any other commercial unit provides.

Two big reasons why you get so much for so little money in a G-R Frequency Standard:

1 *NO* militarization . . . why pay more for *extreme* shock and fungus protection — it doesn't make a standard more stable nor does it contribute to laboratory usefulness.

2 Years of experience . . . this standard's ancestors include the *first* commercially-available crystal-controlled primary frequency standard.

- ★5-Mc fifth-overtone crystal and two-stage oven.
- ★Short-term Stability: 1 part in 10^{10} per min., using 1-sec samples.
- ★Harmonics for measurements well beyond X-band can be produced.
- ★Outputs from 100c to 1000 Mc at decade intervals.
- ★Low Noise: pulse-type dividers give fail-safe operation and minimize phase noise below 5 Mc; phase-locked crystal oscillators provide clean signals above 5 Mc — f-m noise less than 1 part in 10^9.
- ★Long-term Stability: 5 parts in 10^{10} per day, averaged over 10 days after 60 days operation.
- ★Syncronometer resolution is better than ±0.2 msec for time comparisons consistent with stability of sky-wave signals from WWV and other stations.
- ★10-kc and 100-kc square wave available for triggering purposes.
- ★Emergency Power Supply available as an accessory.
- ★Optional Plug-In Units provide 400- and 60-cycle outputs.

Type 1120-AH 1000-MC Frequency Standard . . . $6450 complete

Includes, from top to bottom, 1103-B Syncronometer . . . $900
1113-A Standard Frequency Oscillator . . . $1550
1114-A Frequency Divider . . . $950
1112-A Standard Frequency Multiplier (1,10,100 Mc) . . . $1450
1112-B Standard Frequency Multiplier (1000 Mc) . . . $1360
plus rack and all interconnection provisions.



also available for automatic frequency measurement
1130-A Digital Time and Frequency Meter "The Counter With A Memory".

Write for information regarding a system for frequency measurements to **one part in 10^{11}.**

GENERAL RADIO COMPANY

WEST CONCORD, MASSACHUSETTS

NEW YORK, WOrth 4-2722	CHICAGO	PHILADELPHIA	WASHINGTON, D. C.	SYRACUSE	SAN FRANCISCO	LOS ANGELES	ORLANDO, FLA.	IN CANADA
District Office in Ridgefield, N. J. WHitney 3-3140	Oak Park VIllage 8-9400	Abington HAncock 4-7419	Silver Spring JUniper 5-1088	Syracuse GLenview 4-9323	Los Altos WHitecliff 8-8233	Los Angeles HOllywood 9-6201	Orlando GArden 5-4671	Toronto CHerry 6-2171